



# California Regional Water Quality Control Board Los Angeles Region



Linda S. Adams  
Agency Secretary

Recipient of the 2001 *Environmental Leadership Award* from Keep California Beautiful

Arnold Schwarzenegger  
Governor

320 W. 4th Street, Suite 200, Los Angeles, California 90013  
Phone (213) 576-6600 FAX (213) 576-6640 - Internet Address: <http://www.waterboards.ca.gov/losangeles>

Earnie Ferrer  
City of Ventura  
501 Poli Street, Room 120, P.O. Box 99  
Ventura, CA 93002

## **WATER QUALITY CERTIFICATION FOR PROPOSED CMP AND DRAINAGE INFRASTRUCTURE REPLACEMENT PROJECT (Corps' Project No. 2007-00059-AJS), VENTURA HARBOR/PACIFIC OCEAN, VENTURA, VENTURA COUNTY (File No. 07-026)**

Dear Mr. Ferrer:

Board staff has reviewed your request on behalf of City of Ventura (Applicant) for a Clean Water Act Section 401 Water Quality Certification for the above-referenced project. Your application was deemed complete January 15, 2008.

I hereby issue an order certifying that any discharge from the referenced project will comply with the applicable provisions of sections 301 (Effluent Limitations), 302 (Water Quality Related Effluent Limitations), 303 (Water Quality Standards and Implementation Plans), 306 (National Standards of Performance), and 307 (Toxic and Pretreatment Effluent Standards) of the Clean Water Act, and with other applicable requirements of State law. This discharge is also regulated under State Water Resources Control Board Order No. 2003 - 0017 - DWQ, "General Waste Discharge Requirements for Dredge and Fill Discharges that have received State Water Quality Certification" which requires compliance with all conditions of this Water Quality Certification.

The Applicant shall be liable civilly for any violations of this Certification in accordance with the California Water Code. This Certification does not eliminate the Applicant's responsibility to comply with any other applicable laws, requirements and/or permits.

Should you have questions concerning this Certification action, please contact Dana Cole, Section 401 Program, at (213) 576-5733.

\_\_\_\_\_[Original Signed By]\_\_\_\_\_  
Tracy J. Egoscue  
Executive Officer

\_\_\_\_\_  
January 28, 2008  
Date

**California Environmental Protection Agency**



*Our mission is to preserve and enhance the quality of California's water resources for the benefit of present and future generations.*

## DISTRIBUTION LIST

Oscar Balaguer  
State Water Resources Control Board  
Division of Water Quality  
P.O. Box 944213  
Sacramento, CA 94244-2130

Vicki Clark, Staff Attorney  
Environmental Defense Center  
906 Garden Street  
Santa Barbara, CA 93101

Betty Courtney  
California Department of Fish and Game  
Streambed Alteration Team  
4949 View Ridge Avenue  
San Diego, CA 92123

Jessie Altstatt  
Santa Barbara Channel Keeper  
714 Bond Street  
Santa Barbara, CA 93103

Antal Szijj  
U.S. Army Corps of Engineers  
Regulatory Branch, Ventura Field Office  
2151 Alessandro Drive, Suite 255  
Ventura, CA 93001

Aaron Setran (WTR-8)  
U.S. Environmental Protection Agency, Region 9  
75 Hawthorne Street  
San Francisco, CA 94105

Eric Raffini (by electronic copy)  
Supervisor, Wetlands Regulatory Office (WTR-8)  
US EPA, Region 9  
75 Hawthorne  
San Francisco, CA 94105

Diane Noda  
U.S. Fish and Wildlife Service  
2493 Portola Road, Suite B  
Ventura, CA 93003

# ATTACHMENT A

## Project Information File No. 07-026

1. Applicant: Ernie Ferrer  
City of Ventura  
501 Poli Street, Room 120, P.O. Box 99  
Ventura, CA 93002  
  
Phone: (805) 677-3905 Fax: (805) 641-2775
2. Applicant's Agent: None
3. Project Name: CMP and Drainage Infrastructure Replacement
4. Project Location: Ventura, Ventura County
- | <u>Longitude</u> | <u>Latitude:</u> |
|------------------|------------------|
| 119.2561         | 34.2442          |
| 119.2561         | 34.2440          |
| 119.2570         | 34.2442          |
| 119.2570         | 34.2444          |
| 119.2561         | 34.2441          |
| 119.2566         | 34.2440          |
| 119.2570         | 34.2443          |
| 119.2566         | 34.2443          |
5. Type of Project: Corrugated metal pipe replacement
6. Project Purpose: The proposed project will replace the existing deteriorating corrugated metal pipe (CMP) with a high density polyethylene pipe (HDPE).
7. Project Description: Prior to excavation, the contractor shall install temporary water diversion just upstream of the existing project inlet. The surface water collected will be routed away from the project limits and discharged into the harbor. The conditions of Attachment B, Conditions of Certification 20 will apply.

## ATTACHMENT A

### Project Information File No. 07-026

To avoid excavating the road across Harbor Blvd which could cause major traffic problems, slip lining will be the approach used to repair and replace the existing deteriorated CMP under the Harbor Blvd. Slip lining is a method in which a pipe is inserted into an existing line by either pulling or pushing continuous or short-length pipes.

The contractor shall excavate an open lead-in trench and will remove and dispose the existing 60-inch CMP drainage pipe found in the trench.

All groundwater, if encountered, will be pumped out of the trench and into a filtration tank. The groundwater will be sampled and constituents will be less than or equal to the maximum quantity levels of pollutants as set forth by the NPDES permit supplemental requirements prior to discharge into the harbor. The conditions of Attachment B, Conditions of Certification 18 will apply.

A new 48-inch diameter pipe shall then be laid in the trench and pushed upstream into the existing 60-inch diameter CMP pipe under the Harbor Blvd. Upon inserting or slip lining the total required number of pipe segments under Harbor Blvd, a low strength cement will be pumped into the space between the existing 60-inch diameter CMP pipe and the new 48-inch diameter HDPE pipe to prevent collapse or infiltration of the existing 60-inch CMP.

At the completion of pipe slip lining under the Harbor Blvd, contractor shall install a new 48-inch HDPE drainage pipe within the excavated portion of the project, then connected to the new 48-inch HDPE pipe upstream and to the existing 60-inch CMP pipe downstream. Open excavation shall then be backfilled.

The remaining 60-inch CMP pipe, not part of the project, will be protected-in-place.

- |  |  |
|--|--|
| 8. Federal Agency/Permit:                  | U.S. Army Corps of Engineers<br>NWP No. 3 (Permit No. 2007-00059-AJS)    |
| 9. Other Required<br>Regulatory Approvals: | California Department of Fish and Game<br>Streambed Alteration Agreement |

## ATTACHMENT A

### Project Information File No. 07-026

10. California Environmental Quality Act Compliance: The proposed project is Categorical Exempt from CEQA pursuant to the CEQA Guidelines, Section 15302 Replacement or Reconstruction.
11. Receiving Water: Unnamed tributary to Ventura Marina (Hydrologic Unit No. 403.11)
12. Designated Beneficial Uses: IND, NAV, REC-1, REC-2, COMM, MAR, WILD, SHELL
13. Impacted Waters of the United States: Non-wetland waters (unvegetated streambed): 0.046 temporary acres (400 linear feet)
14. Dredge Volume: None
15. Related Projects Implemented/to be Implemented by the Applicant: The Applicant has not identified any related projects carried out in the last 5 years or planned for implementation in the next 5 years.
16. Avoidance/Minimization Activities: The Applicant has proposed to implement several Best Management Practices (BMPs), including, but not limited to, the following:
- Install temporary dam upstream of the project limit and divert surface water, with a pump and flexible rubber hose, outside the project limits and discharge into the harbor.
  - Install sandbags at the upstream portion of the remaining storm drain pipe to prevent groundwater from entering the harbor.
  - Groundwater encountered within the project limit will be discharge into an NPDES approved filter tank and shall be treated and tested for metals and other pollutants prior to discharge into the harbor.

## ATTACHMENT A

### Project Information File No. 07-026

- Sandbags will be installed at the inlet end of the remaining CMP pipe to prevent surface from entering the harbor.
- Shoring will be installed within the open trench.

17. Proposed  
Compensatory  
Mitigation:

The Applicant has not proposed any compensatory mitigation due to the temporary nature of impacts associated with the project and the location of the project within a concrete lined channel.

The project activities are to replace the failing CMP which is devoid of vegetation. The channel cross-section and capacity will not be modified by the project.

18. Required  
Compensatory  
Mitigation:

Since the project impacts are temporary in nature and in a concrete-lined channel, the Regional Board will not require any additional compensatory mitigation. See *Attachment B, Conditions of Certifications, Additional Conditions* for modifications and additions to the above proposed compensatory mitigation.

## ATTACHMENT B

### Conditions of Certification File No. 07-026

#### STANDARD CONDITIONS

Pursuant to §3860 of Title 23 of the California Code of Regulations (23 CCR), the following three standard conditions shall apply to this project:

1. This Certification action is subject to modification or revocation upon administrative or judicial review, including review and amendment pursuant to §13330 of the California Water Code and Article 6 (commencing with 23 CCR §3867).
2. This Certification action is not intended and shall not be construed to apply to any activity involving a hydroelectric facility and requiring a Federal Energy Regulatory Commission (FERC) license or an amendment to a FERC license unless the pertinent Certification application was filed pursuant to 23 CCR Subsection 3855(b) and the application specifically identified that a FERC license or amendment to a FERC license for a hydroelectric facility was being sought.
3. Certification is conditioned upon total payment of any fee required pursuant to 23 CCR Chapter 28 and owed by the Applicant.

#### ADDITIONAL CONDITIONS

Pursuant to 23 CCR §3859(a), the Applicant shall comply with the following additional conditions:

1. The Applicant shall submit to this Regional Board copies of any other final permits and agreements required for this project, including, but not limited to, the U.S. Army Corps of Engineers' (ACOE) Section 404 Permit and the California Department of Fish and Game's (CDFG) Streambed Alteration Agreement. **These documents shall be submitted prior to any discharge to waters of the State.**
2. The Applicant shall adhere to the most stringent conditions indicated with either this certification, the CDFG's Streambed Alteration Agreement, or the ACOE Section 404 Permit.
3. The Applicant shall comply with all water quality objectives, prohibitions, and policies set forth in the *Water Quality Control Plan, Los Angeles Region (1994)*.
4. The Avoidance/Minimization activities proposed by the Applicant as described in Attachment A, No. **16**, are incorporated as additional conditions herein.

## **ATTACHMENT B**

### **Conditions of Certification File No. 07-026**

5. The Applicant and all contractors employed by the Applicant shall have copies of this Certification, the approved maintenance plan, and all other regulatory approvals for this project on site at all times and shall be familiar with all conditions set forth.
6. Fueling, lubrication, maintenance, operation, and storage of vehicles and equipment shall not result in a discharge or a threatened discharge to waters of the State. At no time shall the Applicant use any vehicle or equipment which leaks any substance that may impact water quality. Staging and storage areas for vehicles and equipment shall be located outside of waters of the State.
7. All excavation, construction, or maintenance activities shall follow best management practices to minimize impacts to water quality and beneficial uses. Dust control activities shall be conducted in such a manner that will not produce downstream runoff.
8. No construction material, spoils, debris, or any other substances associated with this project that may adversely impact water quality standards, shall be located in a manner which may result in a discharge or a threatened discharge to waters of the State. Designated spoil and waste areas shall be visually marked prior to any excavation and/or construction activity, and storage of the materials shall be confined to these areas.
9. All waste and/or dredged material removed shall be relocated to a legal point of disposal if applicable. A legal point of disposal is defined as one for which Waste Discharge Requirements have been established by a California Regional Water Quality Control Board, and is in full compliance therewith. Please contact Rodney Nelson, Land Disposal Unit, at (213) 620-6119 for further information.
10. The Applicant shall implement all necessary control measures to prevent the degradation of water quality from the proposed project in order to maintain compliance with the Basin Plan. The discharge shall meet all effluent limitations and toxic and effluent standards established to comply with the applicable water quality standards and other appropriate requirements, including the provisions of Sections 301, 302, 303, 306, and 307 of the Clean Water Act. This Certification does not authorize the discharge by the applicant for any other activity than specifically described in the 404 Permit.
11. The discharge shall not: a) degrade surface water communities and populations including vertebrate, invertebrate, and plant species; b) promote the breeding of mosquitoes, gnats, black flies, midges, or other pests; c) alter the color, create visual contrast with the natural appearance, nor cause aesthetically undesirable discoloration of the receiving waters; d) cause formation of sludge deposits; or e) adversely affect any designated beneficial uses.

## ATTACHMENT B

### Conditions of Certification File No. 07-026

12. The Applicant shall allow the Regional Board and its authorized representative entry to the premises, including all mitigation sites, to inspect and undertake any activity to determine compliance with this Certification, or as otherwise authorized by the California Water Code.
13. The Applicant shall not conduct any construction activities within waters of the State during a rainfall event. The Applicant shall maintain a **five-day (5-day) clear weather forecast** before conducting any operations within waters of the State.
14. The Applicant shall not conduct any maintenance activities within waters of the State during a rainfall event, or at any period when site conditions would lead to excessive erosion. If any maintenance activities are to be held within five (5) days of a predicted rainfall event, the Applicant shall stage materials necessary to prevent water degradation on site, and shall ensure that all stabilization procedures are completed prior to the rainfall event.
15. If rain is predicted after operations have begun, grading activities must cease immediately and the site must be stabilized to prevent impacts to water quality, and minimize erosion and runoff from the site.
16. Sediment removal at each phase shall not go beyond the extent as defined in the application packet.
17. The grading, stabilization and re-vegetation will be phased to limit the exposed or working face such that the graded area can be stabilized within 24 hours after the first prediction of rain during the 5-day forecast or within 24 hours after final grading of the phased area.
18. No activities shall involve wet excavations (i.e., no excavations shall occur below the seasonal high water table). A minimum **5-foot** buffer zone shall be maintained above the existing groundwater level. If construction or groundwater dewatering is proposed or anticipated, the Applicant shall file a **Report of Waste Discharge** to this Regional Board and obtain any necessary NPDES permits/Waste Discharge Requirements prior to discharging waste. Sufficient time should be allowed to obtain any such permits (generally 180 days). If groundwater is encountered without the benefit of appropriate permits, the Applicant shall cease all activities in the areas where groundwater is present, file a Report of Waste Discharge to this Regional Board, and obtain any necessary permits prior to discharging waste.
19. All project, construction or maintenance activities not included in this Certification, and which may require a permit, must be reported to the Regional Board for appropriate permitting. Bank stabilization and grading, as well as any other ground disturbances, are subject to restoration and revegetation requirements, and may require additional Certification action.

## ATTACHMENT B

### Conditions of Certification File No. 07-026

20. All surface waters, including ponded waters, shall be diverted away from areas undergoing grading, construction, excavation, vegetation removal, and/or any other activity which may result in a discharge to the receiving water. If surface water diversions are anticipated, the Applicant shall develop and submit a **Surface Water Diversion Plan** (plan) to this Regional Board. The plan shall include the proposed method and duration of diversion activities, structure configuration, construction materials, equipment, erosion and sediment controls, and a map or drawing indicating the locations of diversion and discharge points. Contingency measures shall be a part of this plan to address various flow discharge rates. The plan shall be submitted prior to any surface water diversions. If surface flows are present, then upstream and downstream monitoring for the following shall be implemented:
- pH
  - temperature
  - dissolved oxygen
  - turbidity
  - total suspended solids(TSS)
  - Downstream TSS shall be maintained at ambient levels
  - Where natural turbidity is between 0 and 50 Nephelometric Turbidity Units (NTU), increases shall not exceed 20%. Where natural turbidity is greater than 50 NTU, increases shall not exceed 10%.

Analyses must be performed using approved US Environmental Protection Agency methods, where applicable. These constituents shall be monitored for on a daily basis during the first week of diversion and/or dewatering activities, and then on a weekly basis, thereafter, until the in-stream work is complete.

Results of the analyses shall be submitted to this Regional Board by the 15th day of each subsequent sampling month. A map or drawing indicating the locations of sampling points shall be included with each submittal. Diversion activities shall not result in the degradation of beneficial uses or exceedance of water quality objectives of the receiving waters. Any such violations may result in corrective and/or enforcement actions, including increased monitoring and sample collection.

21. The Applicant shall restore the proposed **0.046 acres** of TEMPORARY IMPACTS to waters of the United States and all other areas of temporary disturbance which could result in a discharge or a threatened discharge to waters of the State. Restoration shall include grading of disturbed areas to pre-project contours and revegetation with native species. The Applicant shall implement all necessary Best Management Practices to control erosion and runoff from areas associated with this project.
22. The Applicant shall submit to this Regional Board **Annual Monitoring Reports** (Annual Reports) by **January 1<sup>st</sup>** of each year for a minimum period of **five (5) years** following this issuance of 401 Certification or until project completion has been achieved and documented.

## ATTACHMENT B

### Conditions of Certification File No. 07-026

The Annual Reports shall describe in detail all of the project/construction activities performed during the previous year and all restoration and mitigation efforts; including percent survival by plant species and percent cover. The Annual Reports shall describe the status of other agreements (e.g., mitigation banking) or any delays in the mitigation process. At a minimum the Annual Reports shall include the following documentation and answered appropriately whether or not mitigation has been performed:

- (a) Color photo documentation of the pre- and post-project and mitigation site conditions;
  - (b) Geographical Positioning System (GPS) coordinates in decimal-degrees format outlining the boundary of the project and mitigation areas;
  - (c) The overall status of project including a detailed schedule of work;
  - (d) Copies of all permits revised as required in Additional Condition 1;
  - (e) Water quality monitoring results for each reach (as required) compiled in an easy to interpret format;
  - (f) A certified Statement of “no net loss” of wetlands associated with this project;
  - (g) Discussion of any monitoring activities and exotic plant control efforts; and
  - (h) A certified Statement from the permittee or his/her representative that all conditions of this Certification have been met.
23. Prior to any subsequent maintenance activities within the subject drainages, including clearing, maintenance by-hand, and/or the application of pesticides, the Applicant shall submit to this Regional Board a NOTIFICATION of any such activity. Notification shall include: (a) the proposed schedule; (b) a description of the drainage’s existing condition; (c) the area of proposed temporary impact within waters of the State; (c) a description of any existing aquatic resources (e.g., wetland/riparian vegetation); and (d) any proposed compensatory mitigation. Notifications must be submitted a minimum of **three (3) weeks** prior to commencing work activities.
24. All applications, reports, or information submitted to the Regional Board shall be signed:
- (a) For corporations, by a principal executive officer at least of the level of vice president or his duly authorized representative, if such representative is responsible for the overall operation of the facility from which discharge originates.
  - (b) For a partnership, by a general partner.

**ATTACHMENT B**

**Conditions of Certification  
File No. 07-026**

- (c) For a sole proprietorship, by the proprietor.
  - (d) For a municipal, State, or other public facility, by either a principal executive officer, ranking elected official, or other duly authorized employee.
25. Each and any report submitted in accordance with this Certification shall contain the following completed declaration:

“I declare under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who managed the system or those directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Executed on the \_\_\_\_\_ day of \_\_\_\_\_ at \_\_\_\_\_.

\_\_\_\_\_ (Signature)  
\_\_\_\_\_ (Title)”

26. All communications regarding this project and submitted to this Regional Board shall identify the Project File Number **07-026**. Submittals shall be sent to the attention of the 401 Certification Unit.
27. Any modifications of the proposed project may require submittal of a new Clean Water Act Section 401 Water Quality Certification application and appropriate filing fee.
28. The project shall comply with the local regulations associated with the Regional Board’s **Municipal Stormwater Permit** issued to Ventura County and co-permittees under NPDES No. CAS004002 and Waste Discharge Requirements Order No. 00-108. This includes the Stormwater Quality Urban Impact Mitigation Plan (SQUIMP) and all related implementing local ordinances and regulations for the control of stormwater pollution from new development and redevelopment. The project shall also comply with all requirements of the National Pollutant Discharge Elimination System (NPDES) **General Permit** for Storm Water Discharges Associated with Construction Activity, Order No. 99-08-DWQ. All stormwater treatment systems shall be located outside of any water of the State and shall not be used as a wetland or riparian mitigation credit.
29. Coverage under this Certification may be transferred to the extent the underlying federal permit may legally be transferred and further provided that the Applicant notifies the

## ATTACHMENT B

### Conditions of Certification File No. 07-026

Executive Officer at least 30 days before the proposed transfer date, and the notice includes a written agreement between the existing and new Applicants containing a specific date of coverage, responsibility for compliance with this Certification, and liability between them.

30. The Applicant or their agents shall report any noncompliance. Any such information shall be provided verbally to the Executive Officer within 24 hours from the time the Applicant becomes aware of the circumstances. A written submission shall also be provided within five days of the time the Applicant becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected; the anticipated time it is expected to continue and steps taken or planned to reduce, eliminate and prevent recurrence of the noncompliance. The Executive Officer, or an authorized representative, may waive the written report on a case-by-case basis if the oral report has been received within 24 hours.
31. *Enforcement:*
  - (a) In the event of any violation or threatened violation of the conditions of this Certification, the violation or threatened violation shall be subject to any remedies, penalties, process or sanctions as provided for under State law. For purposes of section 401(d) of the Clean Water Act, the applicability of any State law authorizing remedies, penalties, process or sanctions for the violation or threatened violation constitutes a limitation necessary to assure compliance with the water quality standards and other pertinent requirements incorporated into this Certification.
  - (b) In response to a suspected violation of any condition of this Certification, the State Water Resources Control Board (SWRCB) or Regional Water Quality Control Board (RWQCB) may require the holder of any permit or license subject to this Certification to furnish, under penalty of perjury, any technical or monitoring reports the SWRCB deems appropriate, provided that the burden, including costs, of the reports shall be a reasonable relationship to the need for the reports and the benefits to be obtained from the reports.
  - (c) In response to any violation of the conditions of this Certification, the SWRCB or RWQCB may add to or modify the conditions of this Certification as appropriate to ensure compliance.
32. This Certification shall expire **five (5) years** from date of this Certification. The Applicant shall submit a complete application prior to termination of this Certification if renewal is requested.