

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD SAN DIEGO REGION



9174 Sky Park Court, Suite 100, San Diego, CA 92123-4340 Phone (858) 467-2952 • Fax (858) 571-6972 http://www.waterboards.ca.gov/sandiego/

TENTATIVE ORDER NO. R9-2012-0013 NPDES NO. CA0107611

WASTE DISCHARGE REQUIREMENTS FOR THE SOUTH ORANGE COUNTY WASTEWATER AUTHORITY DISCHARGE TO THE PACIFIC OCEAN THROUGH THE ALISO CREEK OCEAN OUTFALL

The following Discharger is subject to waste discharge requirements as set forth in this Order:

Table 1. Discharger Information

	1						
Discharger	South Orange County Wastewater Auth	South Orange County Wastewater Authority (SOCWA)					
Name of Facility	Aliso Creek Ocean Outfall						
	SOCWA Regional Treatment Plant	29201 La Paz Road Laguna Niguel, CA 92677 Orange County					
	SOCWA Coastal Treatment Plant	28303 Alicia Parkway Laguna Niguel, CA 92677 Orange County					
	Irvine Ranch Water District Los Alisos Water Reclamation Plant	22312 Muirlands Boulevard Lake Forest, CA 92630 Orange County					
Facility Address	El Toro Water District Water Reclamation Plant	23542 Moulton Parkway Laguna Woods, CA 92637 Orange County					
	Irvine Desalter Project Potable Water Treatment System	26 Waterworks Way Irvine, CA 92618 Orange County					
	Irvine Desalter Project Shallow Groundwater Unit	7000 Marine Way Irvine, CA 92620 Orange County					
	South Coast Water District Aliso Creek Water Harvesting Project	28303 Alicia Parkway Laguna Niguel, CA 92677 Orange County					

The U.S. Environmental Protection Agency (USEPA) and the California Regional Water Quality Control Board, San Diego Region have classified this discharge as a major discharge.

Discharges by the South Orange County Wastewater Authority from the Facilities listed in Table 1 at the discharge point identified in Table 2 are subject to waste discharge requirements as set forth in this Order:

Table 2. Discharge Location

Discharge	Effluent	Discharge Point	Discharge Point	Receiving Water
Point No.	Description	Latitude	Longitude	
001	Treated municipal wastewater, treated groundwater, and waste brine	33° 29' 53" N	117° 46' 16" W	Pacific Ocean

Table 3. Administrative Information

This Order was adopted by the California Regional Water Quality Control Board, San Diego Region on:	April 11, 2012
This Order shall become effective on:	May 31, 2012
This Order shall expire on:	May 31, 2017
The Discharger shall file a Report of Waste Discharg Regulations, not later than 180 days in advance of the new waste discharge requirements.	e in accordance with Title 23, California Code of the Order expiration date as application for issuance of

I, David W. Gibson, Executive Officer, do hereby certify that this Order with all attachments is a full, true, and correct copy of an Order adopted by the California Regional Water Quality Control Board, San Diego Region, on **April 11, 2012**.

TENTATIVE	
David W. Gibson	
Executive Officer	

Table of Contents

I.	Facility	Information	<u>5</u> 5
II.	Finding	S	<u>5</u> 5
III.	Dischar	ge Prohibitions	<u>121211</u>
IV.	Effluent	Limitations and Discharge Specifications	<u>121211</u>
	A. Effl	uent Limitations and Performance Goals – Discharge Point No. 001	<u>121211</u>
	B. Lan	d Discharge Specifications – Not Applicable	<u>222221</u>
	C. Red	clamation Specifications – Not Applicable	<u>222221</u>
V.	Receivi	ng Water Limitations	<u>222221</u>
	A. Sur	face Water Limitations	<u>222221</u>
	B. Gro	oundwater Limitations – Not Applicable	<u>2424</u> 23
VI.		ns	
		ndard Provisions	
	B. Moi	nitoring and Reporting Program (MRP) Requirements	. <u>262625</u>
	C. Spe	ecial Provisions	<u>262625</u>
		Reopener Provisions	
	2. 8	Special Studies, Technical Reports and Additional Monitoring Requiremen	
		Best Management Practices and Pollution Prevention – Not Applicable	
		Construction, Operation and Maintenance Specifications – Not Applicable.	
		Special Provisions for Wastewater Facilities (POTWs Only)	
		Other Special Provisions – Not Applicable	
		Compliance Schedules – Not Applicable	
VII.	Complia	ance Determination	<u>34</u> 34
		List of Tables	
Tabl	e 1.	Discharger Information	1
Tabl	e 2.	Discharge Location	
Tabl		Administrative Information	
Tabl	e 4.	Facility Information	5 5
Tabl	e 5.	Basin Plan Beneficial Uses of the Pacific Ocean	9 9
Tabl	e 6.	Ocean Plan Beneficial Uses of the Pacific Ocean	
Tabl	e 7.	SOCWA RTP Effluent Limitations at M-001A	<u>1212</u>
Tabl	e 8.	SOCWA CTP Effluent Limitations at M-001B	
Tabl	e 9.	Los Alisos WRP Effluent Limitations at M-001C	<u>13</u> 13
Tabl	e 10.	El Toro WRP Effluent Limitations at M-001D	<u>141413</u>
Tabl	e 11.	IDP PWTS Limitations at M-001E	
Tabl	e 12.	IDP SGU Effluent Limitations at M-001F	
Tabl	e 13.	SCWD ACWHP Limitations at M-001G	
	e 14.	ACOO Effluent Limitations at Discharge Point No. 001 (M-001)	
Tabl	e 15.	Performance Goals	<u>16</u> 16

List of Attachments

Attachment A – Definitions	<u>A-1</u> A-1
Attachment B – Map	B-1 B-1
Attachment C – Flow Schematic	
Attachment D – Standard Provisions	
Attachment E – Monitoring and Reporting Program	Ē-1 Е-1
Attachment F – Fact Sheet	
Attachment G - Discharge Prohibitions Contained in the Ocean Plan and Basin Plan.	G-1 G-1
Attachment H – Dilution Model Information	

I. FACILITY INFORMATION

The following Discharger is subject to waste discharge requirements as set forth in this Order:

Table 4. Facility Information

Table 4. Facility Informa		N the a mit		
Discharger	South Orange County Wastewater A	Authority		
Name of Facility	Aliso Creek Ocean Outfall	1		
	SOCWA Regional Treatment Plant	29201 La Paz Road Laguna Niguel, CA 92677 Orange County		
	SOCWA Coastal Treatment Plant	28303 Alicia Parkway Laguna Niguel, CA 92677 Orange County		
	Irvine Ranch Water District Los Alisos Water Reclamation Plant	22312 Muirlands Boulevard Lake Forest, CA 92630 Orange County		
Facility Address	El Toro Water District Water Reclamation Plant	23542 Moulton Parkway Laguna Woods, CA 92637 Orange County		
	Irvine Desalter Project Potable Water Treatment System	26 Waterworks Way Irvine, CA 92618 Orange County		
	Irvine Desalter Project Shallow Groundwater Unit	7000 Marine Way Irvine, CA 92620 Orange County		
	South Coast Water District Aliso Creek Water Harvesting Project	28303 Alicia Parkway Laguna Niguel, CA 92677 Orange County		
Facility Contact, Title, and Phone	Tom Rosales, General Manager, (9-	49) 234-5421		
Mailing Address	34156 Del Obispo Street, Dana Poir	nt, CA 92629		
Type of Facility	Combined ocean outfall			
Facility Flow Rate	 SOCWA Regional Treatment Plant – 12.0 million gallons per day (MGD) SOCWA Coastal Treatment Plant – 6.7 MGD Irvine Ranch Water District Los Alisos Water Reclamation Plant – 7.5 MGD El Toro Water District Water Reclamation Plant – 6.0 MGD Irvine Desalter Project Potable Water Treatment System – 1.0 MGD Irvine Desalter Project Shallow Groundwater Unit – 0.85 MGD South Coast Water District Aliso Creek Water Harvesting Project – 			

II. FINDINGS

The California Regional Water Quality Control Board, San Diego Region (hereinafter San Diego Water Board), finds:

A. Background. SOCWA, hereinafter referred to as Discharger, is currently discharging pursuant to Order No. R9-2006-0055 and National Pollutant Discharge Elimination System (NPDES) Permit No. CA0107611. The Discharger submitted a Report of Waste Discharge and two amendments (dated March 31, 2011, January 26, 2012, and January 31, 2012) and applied for a NPDES permit reissuance to discharge up to 34.37 MGD of treated municipal wastewater from four publicly owned treatment works (POTWs) and other miscellaneous wastewater/brine flows through the Aliso Creek Ocean Outfall (ACOO) to the Pacific Ocean. All of the facilities discharging to the ACOO are collectively referred to as the Facilities. The original application was deemed complete on April 30, 2011.

For the purposes of this Order, references to the "discharger" or "permittee" in applicable federal and state laws, regulations, plans, or policy are held to be equivalent to references to the Discharger herein.

B. Facility Description. SOCWA is a joint powers authority formed to reduce duplication and provide operational efficiency through consolidation. SOCWA is the legal successor to the Aliso Water Management Agency, the South East Regional Reclamation Authority, and the South Orange County Reclamation Authority. SOCWA is comprised of 10 member agencies including the City of Laguna Beach, the City of San Clemente, the City of San Juan Capistrano, El Toro Water District, Emerald Bay Service District, Irvine Ranch Water District (IRWD), Moulton Niguel Water District (MNWD), Santa Margarita Water District (SMWD), South Coast Water District (SCWD), and Trabuco Canyon Water District.

SOCWA operates the Aliso Creek Ocean Outfall (ACOO), which receives treated effluent from the following municipal wastewater treatment plants; the SOCWA Regional Treatment Plant (RTP), the SOCWA Coastal Treatment Plant (CTP), the IRWD Los Alisos Water Reclamation Plant (Los Alisos WRP), and the ETWD Water Reclamation Plant (El Toro WRP). Non-potable treated groundwater and brine discharges from the Irvine Desalter Project (IDP) are also routed to the ACOO. Finally, SCWD will discharge brine from the Aliso Creek Water Harvesting Project (ACWHP), a system designed to capture and reuse urban runoff. Facility descriptions for the Facilities that discharge to the ACOO are summarized below.

The SOCWA RTP is owned by SOCWA and treats raw wastewater generated in the MNWD service area. A portion of the secondary effluent is reclaimed for irrigation. The capacity of the existing tertiary treatment facility is 11.4 MGD. The San Diego Water Board's Order No. 97-52 establishes reclamation requirements for the reuse of effluent from the SOCWA RTP in the San Diego Region. All effluent not reclaimed at the SOCWA RTP is discharged to the Pacific Ocean through the ACOO.

The SOCWA CTP is owned and operated by SOCWA and treats raw wastewater generated in the SCWD, the City of Laguna Beach, and the Emerald Bay Services District. From Memorial Day through the end of September, the City of Laguna Beach diverts nuisance dry weather urban runoff from storm drains to the domestic sewer system, and routed to the SOCWA CTP. A portion of the secondary effluent is reclaimed for irrigation. The capacity of the existing tertiary treatment facility is 4.2 MGD. The San Diego Water Board's Order No. 97-52 establishes reclamation requirements for the reuse of effluent from the SOCWA CTP in the San Diego Region. All effluent not reclaimed at the SOCWA CTP is discharged to the Pacific Ocean through the ACOO.

The Los Alisos WRP is owned and operated by the IRWD and treats raw wastewater generated within the IRWD service area. A portion of the secondary effluent is reclaimed for irrigation. Secondary treatment capacity at the Los Alisos WRP is 7.5 mgd. The Santa Ana Regional Water Quality Control Board's Order No. 94-03 establishes reclamation requirements for the reuse of effluent from the Los Alisos WRP in the Santa Ana Region. The San Diego Water Board's Order No. 97-52 establishes reclamation requirements for the reuse of effluent from the Los Alisos WRP in the San Diego Region. All effluent not reclaimed at the Los Alisos WRP is discharged to the Pacific Ocean through the ACOO.

The El Toro WRP is owned by El Toro Water District and treats raw wastewater generated in the El Toro Water District service area. A portion of the secondary effluent is reclaimed for irrigation. The Santa Ana Water Board Order No. 94-03 establishes reclamation requirements for the reuse of effluent from the El Toro WRP in the Santa Ana Region. The San Diego Water Board's Order No. 97-52 establishes reclamation requirements for the reuse of effluent form the El Toro WRP in the San Diego Region. All effluent not reclaimed at the El Toro WRP is discharged to the Pacific Ocean through the ACOO.

The IDP is a multifaceted project operated by IRWD. The IDP includes a Potable Water Treatment System (PWTS) that generates residual brine, and a Shallow Groundwater Unit (SGU) that treats contaminated groundwater. The IDP PWTS treats up to 4.61 MGD of extracted groundwater from wells upgradient of the contaminated groundwater plume in Irvine, California. Groundwater treatment includes the addition of sulfuric acid and a threshold inhibitor; cartridge filters; reverse osmosis (RO); the addition of sodium hypochlorite (bleach); a decarbonator; and the addition of sodium hydroxide (caustic soda), bleach, and aqueous ammonia. The product water is distributed as potable water. Periodically, the RO membranes are taken off-line and cleaned and all cleaning solution is discharged to sewer. The IDP PWTS generates up to 1.0 MGD of RO concentrate, or brine, which is discharged to the ACOO.

The IDP SGU treats groundwater extracted from wells located either within or near a plume of groundwater contaminated by volatile organic compounds (VOC) on or near the former Marine Corps Air Station El Toro. As part of this operation, approximately 0.85 MGD of contaminated groundwater from extraction wells is treated using air stripping to remove VOCs and then discharged to the ACOO.

SCWD proposed the ACWHP as a means of capturing and reusing up to 0.8 MGD of urban runoff. As part of this project, captured urban runoff would be treated and blended into the SOCWA recycled water distribution system to supplement recycled water supplies. The ACWHP treatment is anticipated to include coarse screening, filtration, and RO treatment for salinity control. SCWD anticipates discharging up to 0.32 MGD of ACWHP RO reject brine to the ACOO. SCWD anticipates discharging up to 0.32 MGD of ACWHP RO reject brine to the ACOO.

The combined discharge from the ACOO enters the Pacific Ocean, a water of the United States, at Discharge Point No. 001 (see table on cover page). Attachment B provides a map of the area in the vicinity of the ACOO. Attachment C provides a flow schematic for each of the Facilities.

- **C.** Legal Authorities. This Order is issued pursuant to section 402 of the federal Clean Water Act (CWA) and implementing regulations adopted by the United States Environmental Protection Agency (USEPA) and chapter 5.5, division 7 of the California Water Code (CWC) (commencing with section 13370). It shall serve as a NPDES permit for point source discharges from the Facilities to surface waters. This Order also serves as WDRs pursuant to article 4, chapter 4, division 7 of the CWC (commencing with section 13260).
- **D. Background and Rationale for Requirements.** The San Diego Water Board developed the requirements in this Order based on information submitted as part of the application, through monitoring and reporting programs, and other available information. The Fact Sheet (Attachment F), which contains background information and rationale for Order requirements, is hereby incorporated into this Order and constitutes part of the Findings for this Order. Attachments A through E, G, and H are also incorporated into this Order.
- **E.** California Environmental Quality Act (CEQA). Under CWC section 13389, this action to adopt a NPDES permit is exempt from the provisions of CEQA, Public Resources Code sections 21100-21177.
- F. Technology-Based Effluent Limitations (TBELs). Section 301(b) of the CWA and implementing USEPA permit regulations at section 122.44, title 40 of the Code of Federal Regulations (40 CFR 122.44), require that permits include conditions meeting applicable technology-based requirements at a minimum, and any more stringent effluent limitations necessary to meet applicable water quality standards. 40 CFR Part 133 establishes the minimum weekly and monthly average level of effluent quality attainable by secondary treatment for carbonaceous biochemical oxygen demand (CBOD₅), total suspended solids (TSS), and the instantaneous minimum and maximums for pH. The POTW discharges authorized by this Order must meet minimum federal technology-based requirements based on Secondary Treatment Standards at 40 CFR Part 133. TBELs contained in Table A of the 2005 Water Quality Control Plan for Ocean Waters of California, California Ocean Plan (hereinafter Ocean Plan), which include grease and oil, TSS, settleable solids (SS), turbidity, and pH, are also applicable to discharges from the Facilities. A detailed discussion of the TBELs development is included in the Fact Sheet (Attachment F).
- **G. Water Quality-Based Effluent Limitations (WQBELs).** Section 301(b) of the CWA and 40 CFR 122.44(d) require that permits include limitations more stringent than applicable federal technology-based requirements where necessary to achieve applicable water quality standards.
 - 40 CFR 122.44(d)(1)(i) mandates that permits include effluent limitations for all pollutants that are or may be discharged at levels that have the reasonable potential to cause or contribute to an exceedance of a water quality standard, including numeric and narrative objectives within a standard. Where reasonable potential has been established for a pollutant, but there is no numeric criterion or objective for the pollutant, WQBELs must be established using: (1) USEPA criteria guidance under CWA section 304(a), supplemented where necessary by other relevant information; (2) an indicator parameter for the pollutant of concern; or (3) a calculated numeric water quality criterion, such as a proposed state criterion or policy interpreting the state's narrative criterion, supplemented with other relevant information, as provided in 40 CFR 122.44(d)(1)(vi).

H. Water Quality Control Plans. The San Diego Water Board adopted a *Water Quality Control Plan for the San Diego Region* (hereinafter Basin Plan) on September 8, 1994 that designates beneficial uses, establishes water quality objectives, and contains implementation programs and policies to achieve those objectives for the Pacific Ocean and other receiving waters addressed through the plan. The Basin Plan was subsequently approved by the State Water Resources Control Board (State Water Board) on December 13, 1994. Subsequent revisions to the Basin Plan have also been adopted by the San Diego Water Board and approved by the State Water Board. Beneficial uses applicable to the Pacific Ocean specified in the Basin Plan are as follows:

Table 5. Basin Plan Beneficial Uses of the Pacific Ocean

Discharge Point No.	Receiving Water Name	Beneficial Use(s)
001	Pacific Ocean	Industrial service supply; navigation; contact water recreation; non-contact water recreation; commercial and sport fishing; preservation of biological habitats of special significance; wildlife habitat; rare, threatened, or endangered species; marine habitat; aquaculture; migration of aquatic organisms; spawning, reproduction, and/or early development; and shellfish harvesting.

Requirements of this Order implement the Basin Plan.

I. California Ocean Plan. The State Water Board adopted the Water Quality Control Plan for Ocean Waters of California, California Ocean Plan (Ocean Plan) in 1972 and amended it in 1978, 1983, 1988, 1990, 1997, 2000, 2005, and 2009. The State Water Board adopted the latest amendment on September 15, 2009 and it became effective on March 10, 2010. The Ocean Plan is applicable, in its entirety, to point source discharges to the ocean. The Ocean Plan identifies beneficial uses of ocean waters of the State to be protected as summarized below:

Table 6. Ocean Plan Beneficial Uses of the Pacific Ocean

Discharge Point No.	Receiving Water Name	Beneficial Use
001	Pacific Ocean	Industrial water supply; water contact and non-contact recreation, including aesthetic enjoyment; navigation; commercial and sport fishing; mariculture; preservation and enhancement of designated Areas of Special Biological Significance (ASBS); rare and endangered species; marine habitat; fish spawning and shellfish harvesting.

In order to protect the beneficial uses, the Ocean Plan establishes water quality objectives and a program of implementation. Requirements of this Order implement the Ocean Plan.

- J. Alaska Rule. On March 30, 2000, USEPA revised its regulation that specifies when new and revised state and tribal water quality standards (WQS) become effective for CWA purposes. (40 CFR 131.21; 65 Fed. Reg. 24641 (April 27, 2000).) Under the revised regulation (also known as the Alaska rule), new and revised standards submitted to USEPA after May 30, 2000, must be approved by USEPA before being used for CWA purposes. The final rule also provides that standards already in effect and submitted to USEPA by May 30, 2000 may be used for CWA purposes, whether or not approved by USEPA.
- **K.** Stringency of Requirements for Individual Pollutants. This Order contains both TBELs and WQBELs for individual pollutants. The TBELs consist of restrictions on CBOD₅, TSS, pH, oil and grease, SS, and turbidity. Restrictions on these pollutants are discussed in section IV.B of the Fact Sheet (Attachment F). This Order's technology-based pollutant restrictions implement the minimum, applicable federal technology-based requirements. These limitations are not more stringent than required by the CWA.

WQBELs have been scientifically derived to implement water quality objectives that protect beneficial uses. Both the beneficial uses and the water quality objectives have been approved pursuant to federal law and are the applicable federal water quality standards. The scientific procedures for calculating the individual WQBELs are based on the Ocean Plan, which was approved by USEPA on October 8, 2010. All beneficial uses and water quality objectives contained in the Basin Plan were approved under State law and submitted to and approved by USEPA prior to May 30, 2000. Any water quality objectives and beneficial uses submitted to USEPA prior to May 30, 2000, but not approved by USEPA before that date, are nonetheless "applicable water quality standards for purposes of the CWA" pursuant to 40 CFR 131.21(c)(1). Water quality objectives contained in the Ocean Plan submitted to EPA after May 30, 2000 have subsequently been approved by EPA. Collectively, this Order's restrictions on individual pollutants are no more stringent than required to implement the requirements of the CWA.

- L. Antidegradation Policy. 40 CFR 131.12 requires that the State water quality standards include an antidegradation policy consistent with the federal policy. The State Water Board established California's antidegradation policy in State Water Board Resolution No. 68-16. Resolution No. 68-16 incorporates the federal antidegradation policy where the federal policy applies under federal law. Resolution No. 68-16 requires that existing quality of waters be maintained unless degradation is justified based on specific findings. The San Diego Water Board's Basin Plan implements, and incorporates by reference, both the State and federal antidegradation policies. As discussed in detail in the Fact Sheet (Attachment F), the permitted discharge is consistent with the antidegradation provision of 40 CFR 131.12 and State Water Board Resolution No. 68-16.
- **M.** Anti-Backsliding Requirements. Sections 402(o)(2) and 303(d)(4) of the CWA and federal regulations at 40 CFR 122.44(l) prohibit backsliding in NPDES permits. These anti-backsliding provisions require effluent limitations in a reissued permit to be as stringent as those in the previous permit, with some exceptions where limitations may be relaxed. Some effluent limitations in this Order are less stringent that those in the previous Order. As discussed in detail in the Fact Sheet (Attachment F), this relaxation of effluent limitations is consistent with the anti-backsliding requirements of the CWA and federal regulations.

- N. Endangered Species Act. This Order does not authorize any act that results in the taking of a threatened or endangered species or any act that is now prohibited, or becomes prohibited in the future, under either the California Endangered Species Act (Fish and Game Code sections 2050 to 2097) or the Federal Endangered Species Act (16 USCA sections 1531 to 1544). This Order requires compliance with effluent limits, receiving water limits, and other requirements to protect the beneficial uses of waters of the State. The Discharger is responsible for meeting all requirements of the applicable Endangered Species Act.
- O. Monitoring and Reporting. 40 CFR 122.48 requires that all NPDES permits specify requirements for recording and reporting monitoring results. CWC sections 13267 and 13383 authorizes the San Diego Water Board to require technical and monitoring reports. The Monitoring and Reporting Program (MRP) establishes monitoring and reporting requirements to implement federal and State requirements. This MRP is provided in Attachment E.
- **P. Standard and Special Provisions.** Standard Provisions, which apply to all NPDES permits in accordance with 40 CFR 122.41, and additional conditions applicable to specified categories of permits in accordance with 40 CFR 122.42, are provided in Attachment D. The San Diego Water Board has also included in this Order special provisions applicable to the Discharger. A rationale for the special provisions contained in this Order is provided in the attached Fact Sheet (Attachment F).
- **Q.** Provisions and Requirements Implementing State Law. Some of the provisions and requirements in subsections VI.C of this Order are included to implement State law only. These provisions and requirements are not required or authorized under the federal CWA; consequently, violations of these provisions and requirements are not subject to the enforcement remedies that are available for NPDES violations.
- **R.** Executive Officer Delegation of Authority. The San Diego Water Board by prior resolution has delegated all matters that may legally be delegated to its Executive Officer to act on its behalf pursuant to CWC section 13223. Therefore, the Executive Officer is authorized to act on the San Diego Water Board's behalf on any matter within this Order unless such delegation is unlawful under CWC section 13223 or this Order explicitly states otherwise.
- **S.** Notification of Interested Parties. The San Diego Water Board has notified the Discharger and interested agencies and persons of its intent to prescribe WDRs for the discharge and has provided them with an opportunity to submit their written comments and recommendations. Details of notification are provided in the Fact Sheet (Attachment F).
- **T.** Consideration of Public Comment. The San Diego Water Board, in a public meeting, heard and considered all comments pertaining to the discharge. Details of the Public Hearing are provided in the Fact Sheet (Attachment F).

THEREFORE, IT IS HEREBY ORDERED, that Order No. R9-2006-0055 is rescinded upon the effective date of this Order except for enforcement purposes, and, in order to meet the provisions contained in division 7 of the CWC (commencing with section 13000) and regulations adopted thereunder, and the provisions of the federal CWA and regulations and guidelines adopted thereunder, the Discharger shall comply with the requirements in this Order.

III. DISCHARGE PROHIBITIONS

- **A.** The discharge of waste from the SOCWA RTP, the SOCWA CTP, the Los Alisos WRP, the EI Toro WRP, IDP PWTS, IDP SGU, and the SCWD ACWHP to a location other than the ACOO (Discharge Point No. 001), unless specifically regulated by this Order or separate WDRs, is prohibited.
- **B.** The Discharger must comply with Ocean Plan Discharge Prohibitions, summarized in Attachment G, as a condition of this Order.
- **C.** The Discharger must comply with Discharge Prohibitions contained in Chapter 4 of the Basin Plan, summarized in Attachment G, as a condition of this Order.

IV. EFFLUENT LIMITATIONS AND DISCHARGE SPECIFICATIONS

A. Effluent Limitations and Performance Goals - Discharge Point No. 001

1. Final Effluent Limitations

a. The Discharger shall maintain compliance with the following effluent limitations at Monitoring Locations M-001A (for SOCWA RTP), M-001B (for SOCWA CTP), M-001C (for Los Alisos WRP), and M-001D (for El Toro WRP). Compliance shall be monitored at the same locations as described in the attached MRP (Attachment E).

Table 7. SOCWA RTP Effluent Limitations at M-001A

		Effluent Limitations					
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median
Flow	MGD	12.0					
CBOD ₅ ¹	mg/L	25	40				
	lbs/day	2,502	4,003				
TSS ¹	mg/L	30	45				
133	lbs/day	3,002	4,504				
Oil and	mg/L	25	40			75	
Grease	lbs/day	2,502	4,003			7,506	
SS	ml/L	1.0	1.5			3.0	
Turbidity	NTU	75	100			225	
рН	standard units				6.0	9.0	

The average monthly percent removal of CBOD₅ and TSS shall not be less than 85 percent.

Table 8. SOCWA CTP Effluent Limitations at M-001B

		Effluent Limitations					
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median
Flow	MGD	6.7					
CBOD ₅ ¹	mg/L	25	40				
	lbs/day	1,397	2,235				
TSS ¹	mg/L	30	45				
100	lbs/day	1,676	2,515				-
Oil and	mg/L	25	40			75	-
Grease	lbs/day	1,397	2,235			4,191	
SS	ml/L	1.0	1.5			3.0	
Turbidity	NTU	75	100			225	
рН	standard units				6.0	9.0	

The average monthly percent removal of CBOD₅ and TSS shall not be less than 85 percent.

Table 9. Los Alisos WRP Effluent Limitations at M-001C

Table 3.	LU3 Alla	003 WINI LII	iluent Linnt	ations at Wi-	0010		
		Effluent Limitations					
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median
Flow	MGD	7.5					
CBOD ₅ ¹	mg/L	25	40				
	lbs/day	1,564	2,502				
TSS ¹	mg/L	30	45				
133	lbs/day	1,877	2,815				
Oil and	mg/L	25	40			75	
Grease	lbs/day	1,564	2,502			4,691	
SS	ml/L	1.0	1.5			3.0	
Turbidity	NTU	75	100			225	
рН	standard units				6.0	9.0	

The average monthly percent removal of CBOD₅ and TSS shall not be less than 85 percent.

Table 10. El Toro WRP Effluent Limitations at M-001D

		Effluent Limitations								
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median			
Flow	MGD	6.0								
CDOD 1	mg/L	25	40							
CBOD ₅ ¹ lbs/da	lbs/day	1,251	2,002							
TSS ¹	mg/L	30	45							
155	lbs/day	1,501	2,252							
Oil and	mg/L	25	40			75				
Grease	lbs/day	1,251	2,002			3,753				
SS	ml/L	1.0	1.5			3.0				
Turbidity	NTU	75	100			225				
рН	standard units				6.0	9.0				

The average monthly percent removal of CBOD₅ and TSS shall not be less than 85 percent.

b. The Discharger shall maintain compliance with the following effluent limitations at Monitoring Locations M-001E (for IDP PWTS), M-001F (for IDP SGU), and M-001G (for SCWD ACWHP). Compliance shall be monitored at the same locations as described in the attached MRP (Attachment E).

Table 11. IDP PWTS Limitations at M-001E

			Effluent Limitations							
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median			
Flow	MGD	1.0								
TSS	mg/L	60								
133	lbs/day	500								
Oil and	mg/L	25	40			75				
Grease	lbs/day	209	334			626				
SS	ml/L	1.0	1.5			3.0				
Turbidity	NTU	75	100			225				
рН	standard units				6.0	9.0				

Table 12. IDP SGU Effluent Limitations at M-001F

		Effluent Limitations							
Parameter	The state of the s		Instantaneous Minimum	Instantaneous Maximum	6-Month Median				
Flow	MGD	0.85							
TSS	mg/L	60							
	lbs/day	425							
Oil and	mg/L	25	40			75			
Grease	lbs/day	177	284			532			
SS	ml/L	1.0	1.5			3.0			
Turbidity	NTU	75	100			225			
рН	standard units				6.0	9.0			

Table 13. SCWD ACWHP Limitations at M-001G

		Effluent Limitations							
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median		
Flow	MGD	0.32							
TSS	mg/L	60							
155	lbs/day	160							
Oil and	mg/L	25	40			75			
Grease	lbs/day	67	107			200			
SS	ml/L	1.0	1.5			3.0			
Turbidity	NTU	75	100			225			
рН	standard units				6.0	9.0			

c. The Discharger shall maintain compliance with the following effluent limitations at Discharge Point No. 001, with compliance measured at Monitoring Location M-001 as described in the attached MRP (Attachment E).

Table 14. ACOO Effluent Limitations at Discharge Point No. 001 (M-001)

		Effluent Limitations							
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median		
	BASEI	ON OBJEC	CTIVES FOR	PROTECTIO	N OF MARINE AQ	UATIC LIFE			
Flow	MGD	34.37							
Chlorine,	μg/L			1,900		14,000	480		
Total Residual	lbs/day			550		4,100	140		
Chronic Toxicity ¹	TUc			238					
Hontochlor	μg/L	1.2E-02							
Heptachlor	lbs/day	3.4E-03							
TCDD	μg/L	9.3E-07							
Equivalents ²	lbs/day	2.7E-07							

Chronic toxicity expressed as Chronic Toxicity Units (TUc) = 100/NOEL, where NOEL (No Observed Effect Level) is expressed as the maximum percent effluent or receiving water that causes no observable effect on a test organism.

TCDD Equivalents shall mean the sum of concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors, as shown by the table below:

Isomer Group	Toxicity Equivalence Factor
2,3,7,8 - tetra CDD	1.0
2,3,7,8 - penta CDD	0.5
2,3,7,8 - hexa CDD	0.1
2,3,7,8 - hepta CDD	0.01
octa CDD	0.001
2,3,7,8 - tetra CDF	0.1
1,2,3,7,8 - penta CDF	0.05
2,3,4,7,8 - penta CDF	0.5
2,3,7,8 - hexa CDFs	0.1
2,3,7,8 - hepta CDFs	0.01
octa CDF	0.001

2. Performance Goals

a. Constituents that do not have reasonable potential to cause or contribute to an exceedance of water quality objectives, or for which reasonable potential to cause or contribute to an exceedance of water quality objectives cannot be determined, are referred to as performance goal constituents and are assigned the performance goals listed in the following table. Performance goal constituents shall be monitored at M-001, but the results will be used for informational purposes only, not compliance determination.

Table 15. Performance Goals

			Performar	ice Goals ¹	
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average
OB	JECTIVES	FOR PROTECTION	ON OF MARINE AQ	UATIC LIFE	
Arsenic, Total Recoverable	μg/L	1.2E+03	6.9E+03	1.8E+04	
Arseriic, Total Recoverable	lbs/day	3.4E+02	2.0E+03	5.3E+03	

			Performar	nce Goals ¹	
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average
Cadmium, Total	μg/L	2.4E+02	9.5E+02	2.4E+03	
Recoverable	lbs/day	6.8E+01	2.7E+02	6.8E+02	
Chromium VI, Total	μg/L	4.8E+02	1.9E+03	4.8E+03	
Recoverable ²	lbs/day	1.4E+02	5.5E+02	1.4E+03	
Copper, Total Recoverable	μg/L	2.4E+02	2.4E+03	6.7E+03	
	lbs/day	6.9E+01	6.8E+02	1.9E+03	
Lond Total December	μg/L	4.8E+02	1.9E+03	4.8E+03	
Lead, Total Recoverable	lbs/day	1.4E+02	5.5E+02	1.4E+03	
	μg/L	9.4E+00	3.8E+01	9.5E+01	
Mercury, Total Recoverable	lbs/day	2.7E+00	1.1E+01	2.7E+01	
N: 1 T / 15	μg/L	1.2E+03	4.8E+03	1.2E+04	
Nickel, Total Recoverable	lbs/day	3.4E+02	1.4E+03	3.4E+03	
Selenium, Total	μg/L	3.6E+03	1.4E+04	3.6E+04	
Recoverable	lbs/day	1.0E+03	4.1E+03	1.0E+04	
	μg/L	1.3E+02	6.3E+02	1.6E+03	
Silver, Total Recoverable	lbs/day	3.7E+01	1.8E+02	4.7E+02	
7' T.I.D. II	μg/L	2.9E+03	1.7E+04	4.6E+04	
Zinc, Total Recoverable	lbs/day	8.2E+02	4.9E+03	1.3E+04	
Cyanide, Total	μg/L	2.4E+02	9.5E+02	2.4E+03	
Recoverable	lbs/day	6.8E+01	2.7E+02	6.8E+02	
Ammonia	μg/L	1.4E+05	5.7E+05	1.4E+06	
(expressed as nitrogen)	lbs/day	4.1E+04	1.6E+05	4.1E+05	
Acute Toxicity ³	TUa		7.1E+01		
Phenolic Compounds	μg/L	7.1E+03	2.9E+04	7.1E+04	
(non-chlorinated) ⁴	lbs/day	2.0E+03	8.2E+03	2.0E+04	
Chlorinated Dhamalica ⁵	μg/L	2.4E+02	9.5E+02	2.4E+03	
Chlorinated Phenolics ⁵	lbs/day	6.8E+01	2.7E+02	6.8E+02	
Fundamentan 6	μg/L	2.1E+00	4.3E+00	6.4E+00	
Endosulfan ⁶	lbs/day	6.1E-01	1.2E+00	1.8E+00	
Fodein	μg/L	4.8E-01	9.5E-01	1.4E+00	
Endrin	lbs/day	1.4E-01	2.7E-01	4.1E-01	
110117	μg/L	9.5E-01	1.9E+00	2.9E+00	
HCH ⁷	lbs/day	2.7E-01	5.5E-01	8.2E-01	

			Performa	nce Goals ¹						
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average					
Radioactivity	pCi/L	Not to exceed limits specified in Title 17, Division 1, Chapter 5, Subchapter 4, Group 3, Article 3, Section 30253 of the California Code of Regulations, Reference to Section 30253 is prospective, including future changes to any incorporated provisions of federal law, as the changes take effect.								
OBJECTIVI	OBJECTIVES FOR PROTECTION OF HUMAN HEALTH – NONCARCINOGENS									
Acrolein	μg/L				5.2E+04					
	lbs/day				1.5E+04					
Antimony	μg/L				2.9E+05					
Antimony	lbs/day				8.2E+04					
Bis(2-chloroethoxy)	μg/L				1.0E+03					
Methane	lbs/day				3.0E+02					
Bis(2-chloroisopropyl)	μg/L				2.9E+05					
Ether	lbs/day				8.2E+04					
Chlarahannana	μg/L				1.4E+05					
Chlorobenzene	lbs/day				3.9E+04					
Chromium (III), Total	μg/L				4.5E+07					
Recoverable	lbs/day				1.3E+07					
Dire but d Dhtholoto	μg/L				8.3E+05					
Di-n-butyl Phthalate	lbs/day				2.4E+05					
Dichlorobenzenes ⁸	μg/L				1.2E+06					
Dichlorobenzenes	lbs/day				3.5E+05					
Diethyd Dhthelete	μg/L				7.9E+06					
Diethyl Phthalate	lbs/day				2.3E+06					
Discontinui Diata alata	μg/L				2.0E+08					
Dimethyl Phthalate	lbs/day				5.6E+07					
4.0 distinct O modification and	μg/L				5.2E+04					
4,6-dinitro-2-methylphenol	lbs/day				1.5E+04					
O. A. dimitmon bases I	μg/L				9.5E+02					
2,4-dinitrophenol	lbs/day				2.7E+02					
Ether the common of	μg/L				9.8E+05					
Ethylbenzene	lbs/day				2.8E+05					
Eliza gantha a ga	μg/L				3.6E+03					
Fluoranthene	lbs/day				1.0E+03					

			Performar	nce Goals ¹	
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average
Hexachlorocyclopentadiene	μg/L				1.4E+04
riexaciliorocycloperitadierie	lbs/day				4.0E+03
Nitrohones	μg/L				1.2E+03
Nitrobenzene	lbs/day				3.3E+02
Thallium, Total	μg/L				4.8E+02
Recoverable	lbs/day				1.4E+02
Talvana	μg/L				2.0E+07
Toluene	lbs/day				5.8E+06
T 2	μg/L				3.3E-01
Tributyltin	lbs/day				9.6E-02
4.4.4.1.1.1.11	μg/L				1.3E+08
1,1,1-trichloroethane	lbs/day				3.7E+07
OBJECTI	VES FOR	PROTECTION OF	HUMAN HEALTH	- CARCINOGENS	-
	μg/L				2.4E+01
Acrylonitrile	lbs/day				6.8E+00
	μg/L				5.2E-03
Aldrin	lbs/day				1.5E-03
_	μg/L				1.4E+03
Benzene	lbs/day				4.0E+02
	μg/L				1.6E-02
Benzidine	lbs/day				4.7E-03
	μg/L				7.9E+00
Beryllium	lbs/day				2.3E+00
	μg/L				1.1E+01
Bis(2-chloroethyl) Ether	lbs/day				3.1E+00
	μg/L				8.3E+02
Bis(2-ethlyhexyl) Phthalate	lbs/day				2.4E+02
	μg/L				2.1E+02
Carbon Tetrachloride	lbs/day				6.1E+01
	μg/L				5.5E-03
Chlordane	lbs/day				1.6E-03
	μg/L				2.0E+03
Chlorodibromomethane	lbs/day				5.9E+02

			Performar	nce Goals ¹	
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average
Chloroform	μg/L				3.1E+04
	lbs/day				8.9E+03
DDT ⁹	μg/L				4.0E-02
	lbs/day				1.2E-02
1,4-dichlorobenzene	μg/L				4.3E+03
1,4-dicilioropenzene	lbs/day				1.2E+03
3,3'-dichlorobenzidine	μg/L				1.9E+00
3,3 -dicilioroperizidirie	lbs/day				5.5E-01
1.0 diable readbear	μg/L				6.7E+03
1,2-dichloroethane	lbs/day				1.9E+03
1.1 diable readby lene	μg/L				2.1E+02
1,1-dichloroethylene	lbs/day				6.1E+01
Dichlorobromomethane	μg/L				1.5E+03
Dichioropromomethane	lbs/day				4.2E+02
Diablasassathassa	μg/L				1.1E+05
Dichloromethane	lbs/day				3.1E+04
1.2 diable representa	μg/L				2.1E+03
1,3-dichloropropene	lbs/day				6.1E+02
Dioldrin	μg/L				9.5E-03
Dieldrin	lbs/day				2.7E-03
O. A. dimitratal cana	μg/L				6.2E+02
2,4-dinitrotoluene	lbs/day				1.8E+02
4.0 diale and leading the	μg/L				3.8E+01
1,2-diphenylhydrazine	lbs/day				1.1E+01
11-1	μg/L				3.1E+04
Halomethanes ¹⁰	lbs/day				8.9E+03
	μg/L				4.8E-03
Heptachlor Epoxide	lbs/day				1.4E-03
Have aldered	μg/L				5.0E-02
Hexachlorobenzene	lbs/day				1.4E-02
Have although (P	μg/L				3.3E+03
Hexachlorobutadiene	lbs/day				9.6E+02

			Performar	nce Goals ¹	
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average
Hexachloroethane	μg/L				6.0E+02
	lbs/day				1.7E+02
laanbarana	μg/L				1.7E+05
Isophorone	lbs/day				5.0E+04
N. nitropodimothylamino	μg/L				1.7E+03
N-nitrosodimethylamine	lbs/day				5.0E+02
NI mitmagadi NI mmanulamina	μg/L				9.0E+01
N-nitrosodi-N-propylamine	lbs/day				2.6E+01
NI without a discless of a major a	μg/L				6.0E+02
N-nitrosodiphenylamine	lbs/day				1.7E+02
PAHs ¹¹	μg/L				2.1E+00
PAHS	lbs/day				6.0E-01
PCBs ¹²	μg/L				4.5E-03
PCBS	lbs/day				1.3E-03
4.4.2.2 total chlorooth and	μg/L				5.5E+02
1,1,2,2-tetrachloroethane	lbs/day				1.6E+02
Tatrachlaracthylana	μg/L				4.8E+02
Tetrachloroethylene	lbs/day				1.4E+02
Taylankana	μg/L				5.0E-02
Toxaphene	lbs/day				1.4E-02
Triable as ether de se	μg/L				6.4E+03
Trichloroethylene	lbs/day				1.8E+03
4.4.0 Aviablana athana	μg/L				2.2E+03
1,1,2-trichloroethane	lbs/day				6.4E+02
2.4.6 triphlaranhanal	μg/L				6.9E+01
2,4,6-trichlorophenol	lbs/day				2.0E+01
Viold Oblasida	μg/L				8.6E+03
Vinyl Chloride	lbs/day				2.5E+03

Parameter	Unit	Performance Goals ¹			
		6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average

Scientific "E" notation is used to express certain values. In scientific "E" notation, the number following the "E" indicates that position of the decimal point in the value. Negative numbers after the "E" indicate that the value is less than 1, and positive numbers after the "E" indicate that the value is greater than 1. In this notation a value of 6.1E-02 represents 6.1 x 10^2 or 0.061, 6.1E+02 represents 6.1 x 10^2 or 610, and 6.1E+00 represents 6.1 x 10^0 or 6.1.

Dischargers may, at their option, apply this performance goal as a total chromium performance goal.

- Acute toxicity expressed as Acute Toxicity Units (TUa) = $100/LC_{50}$, where LC_{50} (Lethal Concentration 50%) is the percent waste giving 50% survival of test organisms.
- Non-chlorinated phenolic compounds represent the sum of 2,4-dimethylphenol, 4,6-dinitro-2-methylphenol, 2,4-dinitrophenol, 2-methylphenol, 4-methylphenol, 2-nitrophenol, 4-nitrophenol, and phenol.
- ⁵ Chlorinated phenolic compounds represent the sum of 4-chloro-3-methylphenol, 2-chlorophenol, pentachlorophenol, 2,4,5-trichlorophenol, and 2,4,6-trichlorophenol.
- ⁶ Endosulfan represents the sum of alpha-endosulfan, beta-endosulfan, and endosulfan sulfate.
- HCH (hexachlorocyclohexane) represents the sum of the alpha, beta, gamma (Lindane), and delta isomers of hexachlorocyclohexane.
- ⁸ Dichlorobenzenes represent the sum of 1.2- and 1.3-dichlorobenzene.
- DDT represents the sum of 4.4'DDT: 2.4'DDT: 4.4'DDE: 2.4'DDE: 4.4'DDD: and 2.4'DDD.
- Halomethanes represent the sum of bromoform, bromomethane (methyl bromide), and chloromethane (methyl chloride).
- PAHs (polynuclear aromatic hydrocarbons) represent the sum of acenaphthylene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo[k]fluoranthene; 1,12-benzoperylene; benzo[a]pyrene; chrysene; dibenzo[a,h]anthracene; fluorene; indeno[1,2,3-cd]pyrene; phenanthrene; and pyrene.
- PCBs (polychlorinated biphenyls) represent the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Arollor-1254, and Arcolor-1260.
 - 3. Interim Effluent Limitations Not Applicable
 - B. Land Discharge Specifications Not Applicable
 - C. Reclamation Specifications Not Applicable

V. RECEIVING WATER LIMITATIONS

A. Surface Water Limitations

The receiving water limitations set forth below for ocean waters are based on water quality objectives contained in the Basin Plan and Ocean Plan and are a required part of this Order. The discharge of waste shall not cause violation of these limitations in the Pacific Ocean. Compliance with these limitations shall be determined from samples collected at stations representative of the area within the waste field where initial dilution is completed.

1. Bacterial Characteristics

a. Within a zone bounded by the shoreline and a distance of three nautical miles from the shoreline, including all kelp beds, the following bacterial objectives shall be maintained throughout the water column. The zone of initial dilution for the ocean outfall is excluded.

30-day Geometric Mean – The following standards are based on the geometric mean of the five most recent samples from each site:

i. Total coliform density shall not exceed 1,000 per 100 ml;

- ii. Fecal coliform density shall not exceed 200 per 100 ml; and
- iii. Enterococcus density shall not exceed 35 per 100 ml.

Single Sample Maximum:

- i. Total coliform density shall not exceed 10,000 per 100 ml;
- ii. Fecal coliform density shall not exceed 400 per 100 ml;
- iii. Enterococcus density shall not exceed 104 per 100 ml; and
- iv. Total coliform density shall not exceed 1,000 per 100 ml when the fecal coliform/total coliform ratio exceeds 0.1.
- b. The Initial Dilution Zone for any wastewater outfall shall be excluded from designation as kelp beds for purposes of bacterial standards. Adventitious assemblages of kelp plants on waste discharge structures (e.g., outfall pipes and diffusers) do not constitute kelp beds for purposes of bacterial standards.
- **c.** At all areas where shellfish may be harvested for human consumption, as determined by the San Diego Water Board, the median total coliform density shall not exceed 70 per 100 ml throughout the water column, and not more than 10 percent of the samples shall exceed 230 per 100 ml.

2. Physical Characteristics

- **a.** Floating particulates and grease and oils shall not be visible.
- **b.** The discharge of waste shall not cause aesthetically undesirable discoloration of the ocean surface.
- **c.** Natural light shall not be significantly reduced at any point outside the initial dilution zone as a result of the discharge of waste.
- **d.** The rate of deposition of inert solids and the characteristics of inert solids in the ocean sediments shall not be changed such that benthic communities are degraded.

3. Chemical Characteristics

- **a.** The dissolved oxygen concentration shall not at any time be depressed more than 10 percent from that which occurs naturally, as the result of the discharge of oxygen demanding waste materials.
- **b.** The pH shall not be changed at any time more than 0.2 units from that which occurs naturally.
- **c.** The dissolved sulfide concentration of waters in and near sediments shall not be significantly increased above that present under natural conditions.

- **d.** The concentration of substances set forth in Chapter II, Table B of the Ocean Plan, shall not be increased in marine sediments to levels that would degrade indigenous biota.
- **e.** The concentration of organic materials in marine sediments shall not be increased to levels that would degrade marine life.
- **f.** Nutrient materials shall not cause objectionable aquatic growths or degrade indigenous biota.
- **g.** Numerical water quality objectives established in Chapter II, Table B of the California Ocean Plan shall not be exceeded outside of the zone of initial dilution as a result of the discharges from the Facilities.

4. Biological Characteristics

- **a.** Marine communities, including vertebrate, invertebrate, and plant species, shall not be degraded.
- **b.** The natural taste, odor, color of fish, shellfish, or other marine resources used for human consumption shall not be altered.
- **c.** The concentration of organic materials in fish, shellfish, or other marine resources used for human consumption shall not bioaccumulate to levels that are harmful to human health.

5. Radioactivity

a. Discharge of radioactive waste shall not degrade marine life.

B. Groundwater Limitations – Not Applicable

VI. PROVISIONS

A. Standard Provisions

- **1. Federal Standard Provisions.** The Discharger shall comply with all Standard Provisions included in Attachment D of this Order.
- **2.** San Diego Water Board Standard Provisions. The Discharger shall comply with the following provisions:
 - **a.** The Facilities shall be supervised and operated by persons possessing certificates of appropriate grade pursuant to Title 23, Division 3, Chapter 26 of the California Code of Regulations (CCR).

- b. All proposed new treatment facilities and expansions of existing treatment facilities shall be completely constructed and operable prior to initiation of the discharge from the new or expanded facilities. The Discharger shall submit a certification report for each new treatment facility, expansion of an existing treatment facility, and re-ratings, the certification report shall be prepared by the design engineer. For re-ratings, the certification report shall be prepared by the engineer who evaluated the treatment facility capacity. The certification report shall:
 - i. Identify the design capacity of the treatment facility, including the daily and 30-day design capacity,
 - ii. Certify the adequacy of each component of the treatment facility, and
 - **iii.** Contain a requirement-by-requirement analysis, based on acceptable engineering practices, of the process and physical design of the facility to ensure compliance with this Order.
 - iv. Contain the signature and engineering license number of the engineer preparing the certification report affixed to the report. If reasonable, the certification report shall be submitted prior to beginning construction. The Discharger shall not initiate a discharge from an existing treatment facility at a daily flow rate in excess of its previously approved design capacity until:
 - (a) The certification report is received by the San Diego Water Board,
 - **(b)** The San Diego Water Board has received written notification of completion of construction (new treatment facilities and expansions only),
 - **(c)** An inspection of the facility has been made by staff of the San Diego Water Board or their designated representatives (new treatment facilities and expansions only), and
 - (d) The San Diego Water Board has provided the Discharger with written authorization to discharge at a daily flow rate in excess of its previously approved design capacity.
- **c.** All waste treatment, containment, and disposal facilities shall be protected against 100-year peak stream flows as defined by the San Diego County flood control agency.
- **d.** All waste treatment, containment, and disposal facilities shall be protected against erosion, overland runoff, and other impacts resulting from a 100-year, 24-hour storm event.
- **e.** This Order expires on May 31, 2017, after which, the terms and conditions of this permit are automatically continued pending issuance of a new permit, provided that all requirements of USEPA's NPDES regulations at 40 CFR 122.6 and the State's regulations at Title 23, section 2235.4 of the CCR regarding the continuation of expired permits and waste discharge requirements are met.
- **f.** A copy of this Order shall be posted at a prominent location at or near the treatment and disposal facilities and shall be available to operating personnel at all times.

B. Monitoring and Reporting Program (MRP) Requirements

The Discharger shall comply with the MRP, and future revisions thereto, in Attachment E of this Order.

C. Special Provisions

1. Reopener Provisions

- **a.** This Order may be reopened for modification to include an effluent limitation if monitoring establishes that the discharge causes, has the reasonable potential to cause, or contributes to an excursion above an Ocean Plan Table B water quality objective.
- **b.** This Order may be reopened for modification of the receiving waters monitoring requirements, as the San Diego Water Board determines. The modification(s) can include, but is (are) not limited to, recommendations from Southern California Coastal Water Research Project (SCCWRP) or creation of a Regional Monitoring Program.
- **c.** This Order may be modified, revoked and reissued, or terminated for cause including, but not limited to, the following;
 - i. Violation of any terms or conditions of this Order.
 - ii. Obtaining this Order by misrepresentation or failure to disclose fully all relevant fact.
 - **iii.** A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.

The filing of a request by the Discharger for modifications, revocation and reissuance, or termination of this Order does not stay any condition of this Order. Notification by the Discharger of planned operational or facility changes, or anticipated noncompliance with this Order does not stay any condition of this Order.

- **d.** If any applicable toxic effluent standard or prohibition (including any schedule of compliance specified in such effluent standard or prohibition) is promulgated under section 307 (a) of the CWA for a toxic pollutant and that standard or prohibition is more stringent than any limitation on the pollutant in this Order, the San Diego Water Board may institute proceedings under these regulations to modify or revoke and reissue the Order to conform to the toxic effluent standard or prohibition.
- **e.** This Order may be re-opened and modified, to incorporate in accordance with the provisions set forth in 40 CFR Parts 122 and 124, to include requirements for the implementation of the watershed management approach.
- **f.** This Order may be reopened and modified, in accordance with the provisions set forth in 40 CFR Parts 122 and 124, to include new Minimum Levels (MLs).
- **g.** This Order may be re-opened and modified to revise effluent limitations as a result of future Basin Plan Amendments, or the adoption of a total maximum daily load (TMDL) for the receiving water.

- **h.** This Order may be re-opened upon submission by the Discharger of adequate information, as determined by this San Diego Water Board, to provide for dilution credits or a mixing zone, as may be appropriate.
- **i.** This Order may be re-opened and modified to revise the toxicity language once that language becomes standardized.
- j. This Order may also be re-opened and modified, revoked and, reissued or terminated in accordance with the provisions of 40 CFR 122.44, 122.62 to 122.64, 125.62, and 125.62. Causes for taking such actions include, but are not limited to, failure to comply with any condition of this Order and permit, and endangerment to human health or the environment resulting from the permitted activity.

2. Special Studies, Technical Reports and Additional Monitoring Requirements

a. Spill Prevention and Response Plans

- i. For purposes of this section, a spill is a discharge of treated or untreated wastewater that occurs at or downstream of the SOCWA RTP, SOCWA CTP, Los Alisos WRP or El Toro WRP headworks, or influent intake location(s) at the IDP PWTS, IDP SGU, and SCWD ACWHP, in violation of Discharge Prohibitions III.A of this Order, or a discharge of other materials related to the Facilities. This section does not include sanitary sewer overflows from the sewage collection system that are reportable under separate waste discharge requirements.
- ii. The Discharger shall maintain a Spill Prevention Plan (SPP) for the Facilities in an up-to-date condition and shall amend the SPP whenever there is a change (e.g., in the design, construction, operation, or maintenance of the sewerage system or sewerage facilities) which materially affects the potential for spills. The Discharger shall review and amend the SPP as appropriate after each spill from the Facilities. The SPP and any amendments thereto shall be subject to the approval of the San Diego Water Board and shall be modified as directed by the San Diego Water Board. The Discharger shall submit the SPP and any amendments thereto to the San Diego Water Board upon request of the San Diego Water Board. The Discharger shall ensure that the up-to-date SPP is readily available to the sewerage system personnel at all times and that the sewerage system personnel are familiar with it.
- iii. The Discharger shall maintain a Spill Response Plan (SRP) for the Facilities in an up-to-date condition and shall amend the SRP, as necessary. The Discharger shall review and amend the SRP as appropriate after each spill from the Facilities. The SRP and any amendments thereto shall be subject to the approval of the San Diego Water Board and shall be modified as directed by the San Diego Water Board. The Discharger shall submit the SRP and any amendments thereto to the San Diego Water Board upon request of the San Diego Water Board. The Discharger shall ensure that the up-to-date SRP is readily available to the sewerage system personnel at all times and that the sewerage system personnel are familiar with it.

b. Spill Reporting Requirements

The Discharger shall report spills as defined in Section VI.C.2.a.i above in accordance with the following procedures:

- i. If a spill results in a discharge of treated or untreated wastewater that is equal to or exceeds 1,000 gallons, and/or results in a discharge to a drainage channel and/or surface water; or results in a discharge to a storm drain that was not fully captured and returned to the sanitary sewer system, the Discharger shall:
 - (a) Report the spill to the San Diego Water Board by telephone, by voice mail, or by FAX within 24 hours from the time the Discharger becomes aware of the spill. The Discharger shall inform the San Diego Water Board of the date of the spill, spill location and its final destination, time the spill began and ended, estimated total spill volume, and type of spill material.
 - **(b)** Submit a written report, as well as any additional pertinent information, to the San Diego Water Board no later than 5 days from the time the Discharger becomes aware of the spill.
 - **(c)** The San Diego Water Board may waive the above-required written report under this provision on a case-by-case basis if an oral report has been received within 24 hours.
- ii. If a spill results in a discharge of treated or untreated wastewater under 1,000 gallons and the discharge does not reach a drainage channel, surface waters, or storm drain, the Discharger is not required to notify the San Diego Water Board within 24 hours, or provide a 5-day written report.
- iii. For spills of material other than treated or untreated wastewater that cause, may cause, or are caused by significant operational failure, or endangers or may endanger human health or the environment, the Discharger shall notify the San Diego Water Board by telephone, by voice mail, or by FAX within 24 hours from the time the Discharger becomes aware of the spill. The Discharger shall inform the San Diego Water Board of the date of the spill, spill location and its final destination, time the spill began and ended, estimated total spill volume, and type of spill material.
- **iv.** For all spills, the Discharger shall include a detailed summary of spills in the monthly self-monitoring report for the month in which the spill occurred.
- v. The spill reporting requirements contained in this Order do not relieve the Discharger of responsibilities to report to other agencies, such as the California Emergency Management Agency (EMA) and the County of Orange County Health Care Agency, Environmental Health.

c. Toxicity Reduction Requirements

If the effluent limitation for chronic toxicity or the performance goal for acute toxicity is exceeded in any one test, then within 15 days of the exceedance, the Discharger shall begin conducting six additional tests, bi-weekly, over a 12-week period.

If the toxicity performance goal/effluent limitation is exceeded in any of these six additional tests, then the Discharger shall notify the San Diego Water Board. If the San Diego Water Board determines that the discharge consistently exceeds a performance goal/toxicity effluent limitation, then the Discharger shall initiate a TRE/TIE in accordance with the TRE workplan, *Toxicity Reduction Evaluation Guidance for Municipal Wastewater Treatment Plants* (USEPA 833-B-99-002, 1999), and USEPA TIE guidance

documents (Phase I, EPA/600/6-91/005F, 1992; Phase II, EPA/600/R-92/080, 1993; and Phase III, EPA/600/R-92/081, 1993). Once the source of toxicity is identified, the Discharger shall take all reasonable steps to reduce the toxicity to meet the chronic toxicity effluent limitation and/or the acute toxicity performance goal identified in section IV.A.2 of this Order.

Within 30 days of completion of the TRE/TIE, the Discharger shall submit the results of the TRE/TIE, including a summary of the findings, data generated, a list of corrective actions necessary to achieve consistent compliance with all the toxicity limitations/performance goals of this Order and prevent recurrence of exceedances of those limitations/performance goals, and a time schedule for implementation of such corrective actions. The corrective actions and time schedule shall be modified at the direction of the San Diego Water Board.

If no toxicity is detected in any of these additional six tests, then the Discharger may return to the testing frequency specified in the MRP.

d. Toxicity Reduction Evaluation (TRE)

The Discharger shall develop a TRE workplan in accordance with TRE procedures established by USEPA in the following guidance manuals.

- i. Generalized Methodology for Conducting Industrial Toxicity Reduction Evaluations (EPA/600/2-88/070).
- ii. Toxicity Identification Evaluation, Phase I (EPA/600/6-91/005F).
- iii. Methods for Aquatic Toxicity Identification Evaluations, Phase II (EPA/600/R-92/080).
- iv. Methods for Aquatic Toxicity Identification Evaluations, Phase III (EPA/600/R-92/081).

The Discharger shall submit the TRE workplan to the San Diego Water Board within 180 days of the adoption of this Order. The TRE workplan shall be subject to the approval of the San Diego Water Board and shall be modified as directed by the San Diego Water Board.

- 3. Best Management Practices and Pollution Prevention Not Applicable
- 4. Construction, Operation and Maintenance Specifications Not Applicable
- 5. Special Provisions for Wastewater Facilities (POTWs Only)

a. Aliso Creek Ocean Outfall Capacity

No later than 180 days prior to this Order's expiration date, the Discharger shall submit a written report to the San Diego Water Board regarding capacity of the ACOO that addresses the following items:

i. Most current report on the ACOO capacity conducted within 1 year of the expiration date of this Order:

- **ii.** The Discharger's best estimate of when the average daily flow will equal or exceed the ACOO capacity;
- **iii.** The Discharger's intended schedule for studies, design, and other steps needed to provide additional capacity for the ACOO and/or to control the flow rate before the flow rate is equal to the current outfall capacity;
- **iv.** A certified statement signed by a California Licensed Engineer that states that the capacity of the ACOO is at least 34.37 MGD;
- v. Report on the physical condition of the ACOO; and
- **vi.** The report must be signed and agreed upon by each of the parties discharging through the ACOO.

b. Treatment Plant Capacity

For each POTW regulated under this Order and four years prior to reaching plant design capacity, the Discharger shall submit a Treatment Plant Capacity report to the San Diego Water Board showing how flow volumes will be prevented from exceeding existing capacity or how capacity will be increased. A notification and copy of the report shall be sent to appropriate local elected officials, local permitting agencies, and the press. The required technical report shall be reviewed, approved, and jointly submitted by all planning and building departments having jurisdiction in the area served by the POTW. Opportunities for public participation and involvement are required during the preparation and development of the technical report. The report shall be accompanied by a statement outlining how interested persons were involved in the preparation of the technical report.

c. Pretreatment Program

- i. The Discharger shall be responsible for the performance of all pretreatment requirements contained in 40 CFR Part 403, including any subsequent revisions in 40 CFR Part 403. Where 40 CFR Part 403 or subsequent revisions place mandatory actions upon the Discharger but do not specify a timetable for completion, the Discharger shall complete the mandatory actions within 6 months of the issuance date of this Order, or the effective date of the revisions to 40 CFR Part 403, whichever comes later. For violations of pretreatment requirements, the Discharger shall be subject to enforcement actions, penalties, fines, and other remedies imposed by the USEPA and/or the San Diego Water Board, as provided in the CWA and/or the CWC.
- ii. The Discharger shall implement and enforce its approved pretreatment program, and all subsequent revisions, which are hereby made enforceable conditions of this Order. The Discharger shall enforce the requirements promulgated pursuant to Sections 307(b), 307 (c), 307 (d), and 402 (b) of the CWA with timely, appropriate, and effective enforcement actions. The Discharger shall cause industrial users subject to federal categorical standards to achieve compliance no later than the date specified in those requirements, or in the case of a new industrial user, upon commencement of the discharge.

- **iii.** The Discharger shall perform the pretreatment functions required by 40 CFR 403, including, but not limited to:
 - (a) Implement the necessary legal authorities as required by 40 CFR 403.8 (f) (1);
 - **(b)** Enforce the pretreatment requirements under 40 CFR 403.5 and 403.6;
 - (c) Implement the programmatic functions as required by 40 CFR 403.8 (f) (2); and
 - (d) Provide the requisite funding and personnel to implement the pretreatment program, as required by 40 CFR 403.8 (f) (3).
- iv. By March 1 of each year, the Discharger shall submit an annual report to the San Diego Water Board; USEPA Region 9; the State Water Board, Division of Public Water Quality, Regulations Unit; and the Orange County Health Care Agency, Environmental Health, Hazardous Materials Division, describing its pretreatment activities over the previous calendar year. In the event the Discharger is not in compliance with any condition or requirement of this Order, or any pretreatment compliance inspection/audit requirements, the Discharger shall include the reasons for noncompliance and state how and when it will comply with such conditions and requirements. The annual report shall contain, but not be limited to, the following information:
 - (a) A summary of analytical results from representative flow-proportioned 24-hour composite sampling of the Discharger's influent and effluent for those pollutants known or suspected to be discharged by industrial users that the USEPA has identified under Section 307 (d) of the CWA. This will include an annual full priority pollutant scan. Wastewater sampling and analysis shall be performed in accordance with the minimum frequency of analysis required by the Monitoring and Reporting program of this Order (Attachment E of this Order). The Discharger shall also provide influent and effluent monitoring data for non-priority pollutants, which the Discharger believes may be causing or contributing to interference or pass through. The Discharger is not required to sample and analyze for asbestos. Sludge sampling and analysis is addressed in Attachment E of this Order. Wastewater sampling and analysis shall be performed in accordance with 40 CFR Part 136.
 - (b) A discussion of upset, interference, or pass through, if any, at the Facilities, which the Discharger knows or suspects were caused by industrial users. The discussion shall include the reasons why the incidents occurred, any corrective actions taken, and, if known, the name and address of the responsible industrial user(s). The discussion shall also include a review of the applicable local pollutant limitations to determine whether any additional limitations or changes to existing limitations, are necessary to prevent pass-through, interference, or non-compliance with effluent limitations and/or sludge disposal requirements.
 - **(c)** The Discharger shall characterize the compliance status of each significant industrial user (SIU) by providing a list or table for the following:
 - (1) Name of SIU and category, if subject to categorical standards;
 - (2) Type of wastewater treatment or control processes in place;

- (3) Number of samples taken by SIU during the year;
- (4) Number of samples and inspections by Discharger during the year;
- **(5)** For an SIU subject to discharge requirements for total toxic organics (TTO), whether all required certifications were provided;
- **(6)** A list of pretreatment standards (categorical or local) violated during the year, or any other violations;
- (7) Industries in significant non-compliance as defined at 40 CFR 403.12 (f) (2)(vii), at any time during the year;
- (8) A summary of enforcement actions or any other actions taken against SIUs during the year. Describe the type of action, final compliance date, and the amount of fines and/or penalties collected, if any. Describe any proposed actions for bringing SIUs into compliance; and
- **(9)** The name(s) of any SIU(s) required to submit a baseline monitoring report and any SIUs currently discharging under a baseline monitoring report.
- (d) A brief description of any programs the Discharger implements to reduce pollutants from industrial users not classified as SIUs.
- **(e)** A brief description of any significant changes in operating the pretreatment program which differ from the previous year, including, but not limited to, changes in the program's administrative structure, local limits, monitoring program, legal authority, enforcement policy, funding, and staffing levels;
- **(f)** A summary of the annual pretreatment program budget, including the cost of pretreatment program functions and equipment purchases;
- **(g)** A summary of activities to involve and inform the public of the pretreatment program, including a copy of the newspaper notice, if any, required by 40 CFR 403.8 (f) (2) (vii);
- (h) A description of any changes in sludge disposal methods; and
- (i) A discussion of any concerns not described elsewhere in the annual report.
- v. The Discharger shall submit a semiannual SIU compliance status report to the San Diego Water Board, the State Water Board, and the USEPA. The reports shall cover the periods of January 1 through June 30, and July 1 through December 31 and shall be submitted no later than September 1 and March 1, respectively. The report shall identify:
 - (a) The names and addresses of all SIUs which violated any discharge or reporting requirements during the semi-annual reporting period;
 - **(b)** A description of the violations, including whether the discharge violations were for categorical standards or local limits;

- **(c)** A description of the enforcement actions or other actions taken to remedy the non-compliance; and
- (d) The status of enforcement actions or other actions taken in response to SIU noncompliance identified in previous reports.
- (e) The Discharger shall provide a written technical evaluation of the need to revise local limits under 40 CFR 403.5(c)(1) following permit reissuance (40 CFR 122.44(j)(2)(ii)).

d. Sludge (Biosolids) Disposal Requirements

- i. The handling, treatment, use, management, and disposal of sludge and solids derived from wastewater treatment must comply with applicable provisions of CWA section 405 and USEPA regulations at 40 CFR Parts 257, 258, 501, and 503, including all monitoring, record keeping, and reporting requirements.
- ii. Sludge and wastewater solids must be disposed of in a municipal solid waste landfill, reused by land application, disposed of in a sludge-only landfill, or used in an application approved by the San Diego Water Board in accordance with 40 CFR Parts 258 and 503 and Title 23, Chapter 15 of the CCR. If the Discharger desires to dispose of solids and/or sludge in a different manner, a request for permit modification must be submitted to the USEPA and to this San Diego Water Board at least 180 days prior to beginning the alternative means of disposal.
- iii. Sludge that is disposed of in a municipal solid waste landfill must meet the requirements of 40 CFR Part 258 pertaining to providing information to the public. In the annual self-monitoring report, the Discharger shall include the amount of sludge placed in the landfill as well as the landfill to which it was sent.
- **iv.** All requirements of 40 CFR Part 503 and Title 23 Chapter 15 of the CCR are enforceable whether or not the requirements of those regulations are stated in a NPDES permit or any other permit issued to the Discharger.
- v. The Discharger shall take all reasonable steps to prevent and minimize any sludge use or disposal in violation of this Order that has a likelihood of adversely affecting human health or the environment.
- vi. Solids and sludge treatment, storage, and disposal or reuse shall not create a nuisance, such as objectionable odors or flies, and shall not result in groundwater contamination.
- vii. The solids and sludge treatment and storage site shall have adequate facilities to divert surface water runoff from adjacent areas to protect the boundaries of the site from erosion, and to prevent drainage from the treatment and storage site. Adequate protection is defined as protection, at the minimum, from a 100-year storm and protection from the highest possible tidal stage that may occur.
- viii. The discharge of sewage sludge and solids shall not cause waste material to be in position where it is, or can be, conveyed from the treatment and storage sites and deposited in waters of the State.

ix. The Discharger shall submit an annual report to the USEPA and the San Diego Water Board containing monitoring results and pathogen and vector attraction reduction requirements, as specified by 40 CFR Part 503. The Discharger shall also report the quantity of sludge removed from the Facilities and the disposal method. This self-monitoring report shall be submitted by February 19 of each year and report for the period of the previous calendar year as required by 40 CFR Part 503.

e. Collection System

On May 2, 2006, the State Water Board adopted State Water Board Order No. 2006-0003-DWQ, a Statewide General WDR for Sanitary Sewer Systems. SOCWA's member agencies shall be subject to all applicable requirements of Order No. 2006-0003-DWQ and any future revisions thereto. Order No. 2006-0003-DWQ requires that all public agencies that currently own or operate sanitary sewer systems apply for coverage under the General WDR.

Regardless of the coverage obtained under Order No. 2006-0003-DWQ, SOCWA's member agencies' collection system is part of the treatment system that is subject to this Order. As such, pursuant to federal regulations, SOCWA's member agencies must properly operate and maintain their respective collection system [40 CFR 122.41(e)], report any non-compliance [40 CFR 122.41(l)(6) and (7)], and mitigate any discharge from the collection system in violation of this Order [40 CFR 122.41(d)].

- 6. Other Special Provisions Not Applicable
- 7. Compliance Schedules Not Applicable

VII. COMPLIANCE DETERMINATION

Compliance with the effluent limitations contained in section IV of this Order will be determined as specified below:

A. Compliance with Average Monthly Effluent Limitation (AMEL)

If the average of daily discharges over a calendar month exceeds the AMEL for a given parameter, an alleged violation will be flagged and the Discharger will be considered out of compliance for each day of that month for that parameter (e.g., resulting in 31 days of noncompliance in a 31-day month). The average of daily discharges over the calendar month that exceeds the AMEL for a parameter will be considered out of compliance for the month only. If only a single sample is taken during the calendar month and the analytical result for that sample exceeds the AMEL, the Discharger will be considered out of compliance for that calendar month. For any one calendar month during which no sample (daily discharge) is taken, no compliance determination can be made for that calendar month.

B. Compliance with Average Weekly Effluent Limitation (AWEL)

If the average of daily discharges over a calendar week (Sunday through Saturday) exceeds the AWEL for a given parameter, an alleged violation will be flagged and the Discharger will be considered out of compliance for each day of that week for that parameter, resulting in 7 days of noncompliance. The average of daily discharges over the calendar week that exceeds the AWEL for a parameter will be considered out of compliance for that week only. If only a single sample is taken during the calendar week and the analytical result for that sample exceeds the AWEL, the Discharger will be considered out of compliance for that calendar week. For any one calendar week during which no sample (daily discharge) is taken, no compliance determination can be made for that calendar week.

C. Compliance with Maximum Daily Effluent Limitation (MDEL)

The MDEL shall apply to flow weighted 24-hour composite samples, or grab, as specified in the MRP (Attachment E). If a daily discharge exceeds the MDEL for a given parameter, an alleged violation will be flagged and the Discharger will be considered out of compliance for that parameter for that one day only within the reporting period. For any one day during which no sample is taken, no compliance determination can be made for that day.

D. Compliance with Instantaneous Minimum Effluent Limitation

The instantaneous minimum effluent concentration limitation shall apply to grab sample determinations. If the analytical result of a single grab sample is lower than the instantaneous minimum effluent limitation for a parameter, a violation will be flagged and the Discharger will be considered out of compliance for that parameter for that single sample. Non-compliance for each sample will be considered separately (e.g., the results of two grab samples taken within a calendar day that both are lower than the instantaneous minimum effluent limitation would result in two instances of noncompliance with the instantaneous minimum effluent limitation.)

E. Compliance with Instantaneous Maximum Effluent Limitation

The instantaneous maximum effluent concentration limitation shall apply to grab sample determinations. If the analytical result of a single grab sample is higher than the instantaneous maximum effluent limitation for a parameter, a violation will be flagged and the Discharger will be considered out of compliance for that parameter for that single sample. Non-compliance for each sample will be considered separately (e.g., the results of two grab samples taken within a calendar day that both exceed the instantaneous maximum effluent limitation would result in two instances of noncompliance with the instantaneous maximum effluent limitation).

F. Compliance with 6-Month Median Effluent Limitation

If the median of daily discharges over any 180-day period exceeds the 6-month median effluent limitation for a given parameter, an alleged violation will be flagged and the Discharger will be considered out of compliance for each day of that 180-day period for that parameter. The next assessment of compliance will occur after the next sample is taken. If only a single sample is taken during a given 180-day period and the analytical result for that sample exceeds the 6-month median, the Discharger will be considered out of compliance for the 180-day period. For any 180-day period during which no sample is taken, no compliance determination can be made for the 6-month median limitation.

G. Mass and Concentration Limitations

Compliance with mass and concentration effluent limitations for the same parameter shall be determined separately with their respective limitations. When the concentration of a constituent in an effluent sample is determined to be "Not Detected" (ND) or "Detectable but not quantifiable" (DNQ), the corresponding mass emission rate (MER) determined from that sample concentration shall also be reported as "ND" or "DNQ".

H. Percent Removal

Compliance with percent removal requirements for monthly average percent removal of biochemical oxygen demand and TSS shall be determined separately for each wastewater treatment facility discharging through an outfall. For each wastewater treatment facility, the monthly average percent removal is the average of the calculated daily discharge percent removals only for days on which the constituent concentration is monitored in both the influent and effluent of the wastewater treatment facility at location specified in the MRP (Attachment E) within a calendar month.

The percent removal for each day shall be calculated according to the following equation:

Daily discharge percent removal =
$$\frac{\textit{Influent concentration} - \textit{Effluent concentration}}{\textit{Influent concentration}} \times 100\%$$

I. Ocean Plan Provisions for Table B Constituents

1. Sampling Reporting Protocols

- **a.** The Discharger must report with each sample result the reported Minimum Level (ML) and the laboratory's current Method Detection Limit (MDL).
- **b.** The Discharger must also report results of analytical determinations for the presence of chemical constituents in a sample using the following reporting protocols:
 - i. Sample results greater than or equal to the reported ML must be reported "as measured" by the laboratory (i.e., the measured chemical concentration in the sample).
 - ii. Sample results less than the reported ML, but greater than or equal to the laboratory's MDL, must be reported as "Detected, but Not Quantified", or DNQ. The laboratory must write the estimated chemical concentration of the sample next to DNQ as well as the words "Estimated Concentration" (may be shorted to Est. Conc.").
 - iii. Sample results less than the laboratory's MDL must be reported as "Not Detected", or ND.

2. Compliance Determination

Sufficient sampling and analysis shall be required to determine compliance with the effluent limitation.

a. Compliance with Single-constituent Effluent Limitations

The Discharger shall be deemed out of compliance with an effluent limitation or discharge specification if the concentration of the constituent in the monitoring sample is greater than the effluent limitation or discharge specification and greater than or equal to the ML.

b. Compliance with Effluent Limitations Expressed as a Sum of Several Constituents

The Discharger is out of compliance with an effluent limitation that applies to the sum of a group of chemicals (e.g., PCBs) if the sum of the individual pollutant concentrations is greater than the effluent limitation. Individual pollutants of the group will be considered to have a concentration of zero if the constituent is reported as ND or DNQ.

c. Multiple Sample Data Reduction.

The concentration of the pollutant in the effluent may be estimated from the result of a single sample analysis or by a measure of central tendency (arithmetic mean, geometric mean, median, etc.) of multiple sample analyses when all sample results are quantifiable (i.e., greater than or equal to the reported ML). When one or more sample results are reported as ND or DNQ, the central tendency concentration of the pollutant shall be the median (middle) value of the multiple samples. If, in an even number of samples, one or both of the middle values are ND or DNQ, the median will be the lower of the two middle values.

d. Mass Emission Rate

The mass emission rate (MER), in pounds per day, shall be obtained from the following calculation for any calendar day:

Mass Emission Rate (lbs/day) = 8.34 x Q x C

In which Q and C are the flow rate in million gallons per day and the constituent concentration in mg/L, respectively, and 8.34 is a conversion factor (lbs/gallon of water). If a composite sample is taken, then C is the concentration measured in the composite sample and Q is the average flow rate occurring during the period over which the samples are composited.

e. Bacterial Standards and Analysis

i. The geometric mean used for determining compliance with bacterial standards is calculated with the following equation:

Geometric Mean =
$$(C_1 \times C_2 \times ... \times C_n)^{1/n}$$

Where n is the number of days samples were collected during the period and C is the concentration of bacteria (CFU/100 mL) found on each day of sampling.

ii. For all bacterial analyses, sample dilutions should be performed so the range of values extends from 2 to 16,000 CFU (colony-forming units). The detection methods used for each analysis shall be reported with the results of the analysis. Detection methods used for coliforms (total and fecal) shall be those listed in 40 CFR Part 136 or any improved method determined by the San Diego Water Board (and approved by USEPA) to be appropriate. Detection methods used for enterococcus shall be those presented in USEPA publication USEPA 600/4-85/076, Test Methods for Escherichia coli and Enterococci in Water by Membrane Filter Procedure, listed under 40 CFR Part 136, and any other method approved by the San Diego Water Board.

f. Single Operational Upset

A single operational upset (SOU) that leads to simultaneous violations or more than one pollutant parameter shall be treated as a single violation and limits the Discharger's liability in accordance with the following conditions:

- i. A SOU is broadly defined as a single unusual event that temporarily disrupts the usually satisfactory operation of a system in such a way that it results in violation of multiple pollutant parameters.
- **ii.** A Discharger may assert SOU to limit liability only for those violations which the Discharger submitted notice of the upset as required in Section I.H of Attachment D.
- iii. For purposes outside of CWC section 13385(h) and (i), determination of compliance and civil liability (including any more specific definition of SOU), the requirements for Dischargers to assert the SOU limitation of liability, and the manner of counting violations, shall be in accordance with the USEPA Memorandum "Issuance of Guidance Interpreting Single Operational Upset" (September 27, 1989).
- iv. For purposes of CWC section 13385(h) and (i), determination of compliance and civil liability (including any more specific definition of SOU), the requirements for Dischargers to assert the SOU limitation of liability, and the manner of counting violations shall be in accordance with CWC section 13385(f)(2).

J. Chronic Toxicity

Chronic toxicity is used to measure the acceptability of waters for supporting a healthy marine biota until approved methods are developed to evaluate biological response. Compliance with the chronic toxicity effluent limit established in section IV.A.1.c of this Order for Discharge Point No. 001 shall be determined using critical life stage toxicity tests in accordance with procedures prescribed by the Ocean Plan (2009) and restated in the MRP (Attachment E). Chronic toxicity shall be expressed as Toxic Units Chronic (TUc), where:

TUc = 100 / NOEL

where NOEL is the No Observed Effect Level and is expressed as the maximum percent of effluent that causes no observable effect on a test organism, as determined by the result of a critical life stage toxicity test.

ATTACHMENT A - DEFINITIONS

Acute Toxicity

a. Acute Toxicity (TUa)Expressed in Toxic Units Acute (TUa)

TUa =
$$\frac{100}{96 - \text{hr LC}_{50}}$$

b. Lethal Concentration 50% (LC₅₀)

 LC_{50} (percent waste giving 50% survival of test organisms) shall be determined by static or continuous flow bioassay techniques using standard marine test species as specified in Ocean Plan Appendix III. If specific identifiable substances in wastewater can be demonstrated by the discharger as being rapidly rendered harmless upon discharge to the marine environment, but not as a result of dilution, the LC_{50} may be determined after the test samples are adjusted to remove the influence of those substances.

When it is not possible to measure the 96-hour LC_{50} due to greater than 50 percent survival of the test species in 100 percent waste, the toxicity concentration shall be calculated by the expression:

TUa =
$$\frac{\log (100 - S)}{1.7}$$

where:

S = percentage survival in 100% waste. If S > 99, TUa shall be reported as zero.

Antidegradation.

Policies which ensure protection of water quality for a particular body where the water quality exceeds levels necessary to protect fish and wildlife propagation and recreation on and in the water. This also includes special protection of waters designated as outstanding natural resource waters. Antidegradation plans are adopted by the State to minimize adverse effects on water.

Areas of Special Biological Significance (ASBS)

Those areas designated by the State Water Board as ocean areas requiring protection of species or biological communities to the extent that alteration of natural water quality is undesirable. All Areas of Special Biological Significance are also classified as a subset of STATE WATER QUALITY PROTECTION AREAS.

Average Monthly Effluent Limitation (AMEL)

The highest allowable average of daily discharges over a calendar month, calculated as the sum of all daily discharges measured during a calendar month divided by the number of daily discharges measured during that month.

Average Weekly Effluent Limitation (AWEL)

The highest allowable average of daily discharges over a calendar week (Sunday through Saturday), calculated as the sum of all daily discharges measured during a calendar week divided by the number of daily discharges measured during that week.

Beneficial Uses of waters of the State may be protected against quality degradation include, but are not limited to, domestic, municipal, agricultural and industrial supply; power generation; recreation; aesthetic enjoyment; navigation; and preservation and enhancement of fish, wildlife, and other aquatic resources or preserves.

Best Management Practices (BMPs)

Schedules of activities, prohibitions of practices, maintenance procedures, and other management practices to prevent or reduce the pollution of waters of the United States. BMPs also include treatment requirements, operating procedures, and practices to control plant site runoff, spillage or leaks, sludge or waste disposal, or drainage from raw material storage.

Best Professional Judgment (BPJ)

The method used by permit writers to develop technology-based NPDES permit conditions on a case-by-case basis using all reasonably available and relevant data.

Bioaccumulative Pollutants

Those substances taken up by an organism from its surrounding medium through gill membranes, epithelial tissue, or from food and subsequently concentrated and retained in the body of the organism.

Bioassay

A test used to evaluate the relative potency of a chemical or a mixture of chemicals by comparing its effect on a living organism with the effect of a standard preparation on the same type of organism.

Biochemical Oxygen Demand (BOD)

A measurement of the amount of oxygen utilized by the decomposition of organic material, over a specified time period (usually 5 days) in a wastewater sample; it is used as a measurement of the readily decomposable organic content of a wastewater.

Biosolids

Sewage sludge that is used or disposed through land application, surface disposal, incineration, or disposal in a municipal solid waste landfill. Sewage sludge is defined as solid, semi-solid, or liquid untreated residue generated during the treatment of domestic sewage in a treatment facility.

Carbonaceous Biochemical Oxygen Demand (CBOD)

The measurement of oxygen required for carbonaceous oxidation of a nonspecific mixture of organic compounds. Interference caused by nitrifying bacteria in the standard 5-day BOD test is eliminated by suppressing the nitrification reaction.

Certifying Official

All applications, including notices of intent (NOIs), must be signed as follows:

For a corporation: By a responsible corporate officer, which means: (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

For a partnership or sole proprietorship: By a general partner or the proprietor, respectively; or

For a municipality, state, federal, or other public agency: By either a principal executive officer or ranking elected official. A principal executive officer of a federal agency includes (i) the chief executive officer of the agency, or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.

Chemical Oxygen Demand (COD)

A measure of the oxygen-consuming capacity of inorganic and organic matter present in wastewater. COD is expressed as the amount of oxygen consumed in mg/L. Results do not necessarily correlate to the biochemical oxygen demand (BOD) because the chemical oxidant may react with substances that bacteria do not stabilize.

Chlordane

Shall mean the sum of chlordane-alpha, chlordane-gamma, chlordene-alpha, chlordene-gamma, nonachlor-alpha, nonachlor-gamma, and oxychlordane.

Chronic Toxicity

This parameter shall be used to measure the acceptability of waters for supporting a healthy marine biota until improved methods are developed to evaluate biological response.

a. Chronic Toxicity (TUc)

Expressed as Toxic Units Chronic (TUc)

$$TUc = \frac{100}{NOEL}$$

b. No Observed Effect Level (NOEL)

The NOEL is expressed as the maximum percent effluent or receiving water that causes no observable effect on a test organism, as determined by the result of a critical life stage toxicity test listed in Ocean Plan Appendix III.

Composite Sample

Sample composed of two or more discrete samples of at least 100 milliliters collected at periodic intervals during the operating hours of a facility over a 24-hour period. The aggregate sample will reflect the average water quality covering the compositing or sample period. For volatile pollutants, aliquots must be combined in the laboratory immediately before analysis. The composite must be flow proportional; either the time interval between each aliquot or the volume of each aliquot must be proportional to either stream flow at the time of sampling or the total stream flow since the collection of the previous aliquot. Aliquots may be collected manually or automatically.

Conventional Pollutants

Pollutants typical of municipal sewage, and for which municipal secondary treatment plants are typically designed; defined at 40 CFR 401.16 as BOD, Total Suspended Solids (TSS), fecal coliform bacteria, oil and grease, and pH.

Daily Discharge

Daily Discharge is defined as either: (1) the total mass of the constituent discharged over the calendar day (12:00 am through 11:59 pm) or any 24-hour period that reasonably represents a calendar day for purposes of sampling (as specified in the permit), for a constituent with limitations expressed in units of mass or; (2) the unweighted arithmetic mean measurement of the constituent over the day for a constituent with limitations expressed in other units of measurement (e.g., concentration).

The daily discharge may be determined by the analytical results of a composite sample taken over the course of one day (a calendar day or other 24-hour period defined as a day) or by the arithmetic mean of analytical results from one or more grab samples taken over the course of the day.

For composite sampling, if 1 day is defined as a 24-hour period other than a calendar day, the analytical result for the 24-hour period will be considered as the result for the calendar day in which the 24-hour period ends.

Daily Maximum Limit

The maximum allowable daily discharge of pollutant. Where daily maximum limitations are expressed in units of mass, the daily discharge is the total mass discharged over the course of the 24-hour period. Where daily maximum limitations are expressed in terms of a concentration, the daily discharge is the arithmetic average measurement of the pollutant concentration derived from all measurements taken that 24-hour period.

DDT

Shall mean the sum of 4,4'DDT, 2,4'DDT, 4,4'DDE, 2,4'DDE, 4,4'DDD, and 2,4'DDD.

Degrade (Degradation)

Degradation shall be determined by comparison of the waste field and reference site(s) for characteristic species diversity, population density, contamination, growth anomalies, debility, or supplanting of normal species by undesirable plant and animal species. Degradation occurs if there are significant differences in any of three major biotic groups, namely, demersal fish, benthic invertebrates, or attached algae. Other groups may be evaluated where benthic species are not affected, or are not the only ones affected.

Detected, but Not Quantified (DNQ)

Sample results that are less than the reported Minimum Level, but greater than or equal to the laboratory's Method Detection Limit (MDL).

Dilution Credit

The amount of dilution granted to a discharge in the calculation of a water quality-based effluent limitation, based on the allowance of a specified mixing zone. It is calculated from the dilution ratio or determined through conducting a mixing zone study or modeling of the discharge and receiving water.

Dilution Ratio T

The critical low flow of the upstream receiving water divided by the flow of the effluent discharged.

Dichlorobenzenes

Shall mean the sum of 1,2- and 1,3-dichlorobenzene.

Discharge when used without qualification means the discharge of a pollutant. Discharge of a pollutant means:

- 1. Any addition of any pollutant or combination of pollutants to waters of the United States from any point source, or
- 2. Any addition of any pollutant or combination of pollutants to the waters of the contiguous zone or the ocean from any point source other than a vessel or other floating craft that is being used as a means of transportation.

This definition includes additions of pollutants into waters of the United States from: surface runoff which is collected or channelled by man; discharges through pipes, sewers, or other conveyances owned by a state, municipality, or other person which do not lead to a treatment works; and discharges through pipes, sewers, or other conveyances, leading into privately owned treatment works. This term does not include an addition of pollutants by any indirect Discharger.

Discharge Monitoring Report (DMR) means the USEPA uniform form, including any subsequent additions, revisions, or modifications for the reporting of self-monitoring results by permittees. DMRs must be used by approved states as well as by USEPA. The USEPA will supply DMRs to any approved state upon request. The USEPA national forms may be modified to substitute the state agency name, address, logo, and other similar information, as appropriate, in place of USEPA's.

Downstream Ocean Waters

Waters downstream with respect to ocean currents.

Dredged Material

Any material excavated or dredged from the navigable waters of the United States, including material otherwise referred to as "spoil".

Effluent Limitation

Any restriction imposed by an Order on quantities, discharge rates, and concentrations of pollutants that are discharged from point sources into waters of the United States, the waters of the contiguous zone, or the ocean.

Enclosed Bays

Indentations along the coast that enclose an area of oceanic water within distinct headlands or harbor works. Enclosed bays include all bays where the narrowest distance between headlands or outermost harbor works is less than 75 percent of the greatest dimension of the enclosed portion of the bay. This definition includes but is not limited to: Humboldt Bay, Bodega Harbor, Tomales Bay, Drakes Estero, San Francisco Bay, Morro Bay, Los Angeles Harbor, Upper and Lower Newport Bay, Mission Bay, and San Diego Bay.

Endosulfan

The sum of endosulfan-alpha and -beta and endosulfan sulfate.

Estuaries and Coastal Lagoons are waters at the mouths of streams that serve as mixing zones for fresh and ocean waters during a major portion of the year. Mouths of streams that are temporarily separated from the ocean by sandbars shall be considered as estuaries. Estuarine waters will generally be considered to extend from a bay or the open ocean to the upstream limit of tidal action but may be considered to extend seaward if significant mixing of fresh and salt water occurs in the open coastal waters. The waters described by this definition include but are not limited to the Sacramento-San Joaquin Delta as defined by section 12220 of the CWC, Suisun Bay, Carquinez Strait downstream to Carquinez Bridge, and appropriate areas of the Smith, Klamath, Mad, Eel, Noyo, and Russian Rivers.

Grab Sample

An individual sample of at least 100 milliliters collected at a randomly selected time over a period not exceeding 15 minutes. The sample is taken from a waste stream on a one-time basis without consideration of the flow rate of the waste stream and without consideration of time of day.

Halomethanes shall mean the sum of bromoform, bromomethane (methyl bromide) and chloromethane (methyl chloride).

HCH shall mean the sum of the alpha, beta, gamma (Lindane) and delta isomers of hexachlorocyclohexane.

Initial Dilution

The process that results in the rapid and irreversible turbulent mixing of wastewater with ocean water around the point of discharge.

For a submerged buoyant discharge, characteristic of most municipal and industrial wastes that are released from the submarine outfalls, the momentum of the discharge and its initial buoyancy act together to produce turbulent mixing. Initial dilution in this case is completed when the diluting wastewater ceases to rise in the water column and first begins to spread horizontally.

For shallow water submerged discharges, surface discharges, and non-buoyant discharges, characteristic of cooling water wastes and some individual discharges, turbulent mixing results primarily from the momentum of discharge. Initial dilution, in these cases, is considered to be completed when the momentum induced velocity of the discharge ceases to produce significant mixing of the waste, or the diluting plume reaches a fixed distance from the discharge to be specified by the San Diego Water Board, whichever results in the lower estimate for initial dilution.

Instantaneous Maximum Effluent Limitation

The highest allowable value for any single grab sample or aliquot (i.e., each grab sample or aliquot is independently compared to the instantaneous maximum limitation).

Instantaneous Minimum Effluent Limitation

The lowest allowable value for any single grab sample or aliquot (i.e., each grab sample or aliquot is independently compared to the instantaneous minimum limitation).

Kelp Beds

For purposes of the bacteriological standards of the Ocean Plan, are significant aggregations of marine algae of the genera <u>Macrocystis</u> and <u>Nereocystis</u>. Kelp beds include the total foliage canopy of <u>Macrocystis</u> and <u>Nereocystis</u> plants throughout the water column.

Mariculture

The culture of plants and animals in marine waters independent of any pollution source.

Material

(a) In common usage: (1) the substance or substances of which a thing is made or composed (2) substantial; (b) For purposes of the Ocean Plan relating to waste disposal, dredging and the disposal of dredged material and fill, MATERIAL means matter of any kind or description which is subject to regulation as waste, or any material dredged from the navigable waters of the United States. See also, DREDGED MATERIAL.

Maximum Daily Effluent Limitation (MDEL)

The highest allowable daily discharge of a pollutant.

Method Detection Limit (MDL)

The minimum concentration of a substance that can be measured and reported with 99 percent confidence that the analyte concentration is greater than zero, as defined in Title 40 of the CFR, Part 136, Attachment B.

Minimum Level (ML)

The concentration at which the entire analytical system must give a recognizable signal and acceptable calibration point. The ML is the concentration in a sample that is equivalent to the concentration of the lowest calibration standard analyzed by a specific analytical procedure, assuming that all the method specified sample weights, volumes, and processing steps have been followed.

Natural Light

Reduction of natural light may be determined by the San Diego Water Board by measurement of light transmissivity or total irradiance, or both, according to the monitoring needs of the San Diego Water Board.

Not Detected (ND)

Those sample results less than the laboratory's MDL.

Nuisance

CWC section 13050, subdivision (m), defines nuisance as anything which meets all of the following requirements:

- 1. Is injurious to health, or is indecent or offensive to the senses, or an obstruction to the free use of property, so as to interfere with the comfortable enjoyment of life or property.
- 2. Affects at the same time an entire community or neighborhood, or any considerable number of persons, although the extent of the annoyance or damage inflicted upon individuals may be unequal.
- 3. Occurs during, or as a result of, the treatment or disposal of wastes.

Ocean Waters

The territorial marine waters of the State as defined by California law to the extent these waters are outside of enclosed bays, estuaries, and coastal lagoons. If a discharge outside the territorial waters of the State could affect the quality of the waters of the State, the discharge may be regulated to assure no violation of the Ocean Plan will occur in ocean waters.

PAHs (polynuclear aromatic hydrocarbons)

The sum of acenaphthylene, anthracene, 1,2-benzanthracene, 3,4-benzofluoranthene, benzo[k]fluoranthene, 1,12-benzoperylene, benzo[a]pyrene, chrysene, dibenzo[ah]anthracene, fluorene, indeno[1,2,3-cd]pyrene, phenanthrene, and pyrene.

PCBs (polychlorinated biphenyls)

The sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254, and Aroclor-1260.

Pollutant Minimization Program (PMP)

PMP means waste minimization and pollution prevention actions that include, but are not limited to, product substitution, waste stream recycling, alternative waste management methods, and education of the public and businesses. The goal of the PMP shall be to reduce all potential sources of Ocean Plan Table B pollutants through pollutant minimization (control) strategies, including pollution prevention measures as appropriate, to maintain the effluent concentration at or below the water quality-based effluent limitation. Pollution prevention measures may be particularly appropriate for persistent bioaccumulative priority pollutants where there is evidence that beneficial uses are being impacted. The San Diego Water Board may consider cost effectiveness when establishing the requirements of a PMP. The completion and implementation of a Pollution Prevention Plan, if required pursuant to CWC section 13263.3(d), shall be considered to fulfill the PMP requirements.

Reported Minimum Level

The ML (and its associated analytical method) chosen by the Discharger for reporting and compliance determination from the MLs included in this Order. The MLs included in this Order correspond to approved analytical methods for reporting a sample result that are selected by the San Diego Water Board either from Appendix II of the Ocean Plan in accordance with section III.C.5.a of the Ocean Plan or established in accordance with section III.C.5.b of the Ocean Plan. The ML is based on the proper application of method-based analytical procedures for sample preparation and the absence of any matrix interferences. Other factors may be applied to the ML depending on the specific sample preparation steps employed. For example, the treatment typically applied in cases where there are matrix-effects is to dilute the sample or sample aliquot by a factor of ten. In such cases, this additional factor must be applied to the ML in the computation of the reported ML.

Sanitary Sewer Overflow (SSO)

Any overflow, spill, release, discharge or diversion of untreated or partially treated wastewater from a sanitary sewer system. SSOs include:

- 1. Overflows or releases of untreated or partially treated wastewater that reach waters of the United States:
- 2. Overflows or releases of untreated or partially treated wastewater that do not reach waters of the United States: and
- **3.** Wastewater backups into buildings and on private property that are caused by blockages or flow conditions within the publicly/federally-owned portion of a sanitary sewer system.

SSO Categories

- **1. Category 1** All discharges of sewage resulting from a failure in the Discharger's sanitary sewer system that:
 - a. Equal or exceed 1000 gallons, or
 - **b.** Result in a discharge to a drainage channel and/or surface water; or
 - **c.** Discharge to a storm drainpipe that was not fully captured and returned to the sanitary sewer system.
- **2.** Category 2 All other discharges of sewage resulting from a failure in the Discharger's sanitary sewer system.
- **3. Private Lateral Sewage Discharges** Sewage discharges that are caused by blockages or other problems within a privately owned lateral.

SSO Reporting System

Online spill reporting system that is hosted, controlled, and maintained by the State Water Board. The web address for this site is http://ciwqs.waterboards.ca.gov. This online database is maintained on a secure site and is controlled by unique usernames and passwords.

Sanitary Sewer System

Any system of pipes, pump stations, sewer lines, or other conveyances, upstream of a wastewater treatment plant headworks used to collect and convey wastewater to the wastewater treatment facility. Temporary storage and conveyance facilities (such as vaults, temporary piping, construction trenches, wet wells, impoundments, tanks, etc.) are considered to be part of the sanitary sewer system, and discharges into these temporary storage facilities are not considered to be SSOs.

Satellite Collection System

The portion, if any, of a sanitary sewer system owned or operated by a different public agency than the agency that owns and operates the wastewater treatment facility that a sanitary sewer system is tributary to.

Secondary Treatment Standards

Technology-based requirements for direct discharging municipal sewage treatment facilities. Standards are based on a combination of physical and biological processes typical for the treatment of pollutants in municipal sewage. Standards are expressed as a minimum level of effluent quality in terms of: BOD₅, TSS, and pH (except as provided for special considerations and treatment equivalent to secondary treatment).

Shellfish

Organisms identified by the State of California Department of Public Health as shellfish for public health purposes (i.e., mussels, clams, and oysters).

Significant Difference

Defined as a statistically significant difference in the means of two distributions of sampling results at the 95 percent confidence level.

Six-month Median Effluent Limitation

The highest allowable moving median of all daily discharges for any 180-day period.

State Water Quality Protection Areas (SWQPAs)

Non-terrestrial marine or estuarine areas designated to protect marine species or biological communities from an undesirable alteration in natural water quality. All AREAS OF SPECIAL BIOLOGICAL SIGNIFICANCE (ASBS) that were previously designated by the State Water Board in Resolution Nos. 74-28, 74-32, and 75-61 are now also classified as a subset of State Water Quality Protection Areas and require special protections afforded by the Ocean Plan.

Technology-Based Effluent Limit

A permit limit for a pollutant that is based on the capability of a treatment method to reduce the pollutant to a certain concentration.

Toxic Pollutant

Pollutants or combinations of pollutants, including disease-causing agents, which after discharge and upon exposure, ingestion, inhalation, or assimilation into any organism, either directly from the environment or indirectly by ingestion through food chains, will, on the basis of information available to the Administrator of USEPA, cause death, disease, behavioral abnormalities, cancer, genetic mutations, physiological malfunctions, (including malfunctions in reproduction), or physical deformations, in such organisms or their offspring. Toxic pollutants also include those pollutants listed by the Administrator under CWA section 307(a)(1) or any pollutant listed under section 405 (d) which relates to sludge management.

Toxicity Reduction Evaluation (TRE)

A study conducted in a step-wise process designed to identify the causative agents of effluent or ambient toxicity, isolate the sources of toxicity, evaluate the effectiveness of toxicity control options, and then confirm the reduction in toxicity. The first steps of the TRE consist of the collection of data relevant to the toxicity, including additional toxicity testing, and an evaluation of facility operations and maintenance practices, and best management practices. A Toxicity Identification Evaluation (TIE) may be required as part of the TRE, if appropriate. (A TIE is a set of procedures to identify the specific chemical(s) responsible for toxicity. These procedures are performed in three phases (characterization, identification, and confirmation using aquatic organism toxicity tests).

Untreated or Partially Treated Wastewater

Any volume of waste discharged from the sanitary sewer system upstream of a wastewater treatment plant headworks.

Waste

As used in the Ocean Plan, waste includes a Discharger's total discharge, of whatever origin (i.e., gross, not net, discharge).

Water Quality Control Plan

Consists of a designation or establishment for the waters within a specified area of all of the following:

- **1.** Beneficial uses to be protected.
- 2. Water quality objectives.
- 3. A program of implementation needed for achieving water quality objectives.

Water Quality Objectives means the limits or levels of water quality constituents or characteristics which are established for the reasonable protection of beneficial uses of water or the prevention of nuisance within a specific area.


Water Reclamation

The treatment of wastewater to render it suitable for reuse, the transportation of treated wastewater to the place of use, and the actual use of treated wastewater for a direct beneficial use or controlled use that would not otherwise occur.

Whole Effluent Toxicity (WET)


The total toxic effect of an effluent measured directly with a toxicity test.


ATTACHMENT B - MAP





Attachment B –Map B-1


ATTACHMENT C - FLOW SCHEMATIC











STREAM	System	CHEMICAL	INITIAL DOSAGE (gpd)	ULTIMATE DOSAGE (gpd)
₩	POT	93% SULFURIC ACID	27.6	20.4
	POT	100% THRESHOLD INHIBITOR	12,5	19.7
6	POT	12.5% SODIUM HYPOCHLORITE	63,6	115.1
6	POT	25% SODIUM HYDROXIDE	62.2	112.7
6	POT	12.5% SODIUM HYPOCHLORITE	31.8	57.6
(F)	POT	30% AQUEOUS AMMONIA	11.9	21.6

STREAM	FLOW DESCRIPTION	>	INITIAL FLOW (gprti)	ULTIMATE FLOW (gpm)
0	POTABLE WELLS FEED		4100	5700
2	POTABLE BYPASS	7	164D .	2678
3	POTABLE RO TRAIN FEED		2460	3022
4	POTABLE RO CONCENTRATE		558	732
(5)	POTABLE RO PERMEATE		1902	2290
6	POTABLE DECARBONATOR PRODUCT	<u> </u>	3543	4969
0	FINAL PRODUCT WATER		3543	4969

						SCALE NO SCALE
						DATE JANUARY 2005
						FILENAME WITLOS
						DESIGNED BY BSE
REV	DESCRIPTION	ENGR	DATE	APPD	DATE	DRAWN BY JLR CHECKED BY RSA



PLANS PREPARED BY:

TETRA TECH
16241 Lagyina Carryon Road
Suite 200
Suite 207
(349) 727-7039
FAX

SEPARATION
PROCESSES, INC.
2386 Foratov Avenue, Suite 100
cortabad, California 92008
(760) 804–5777

STEVEN D. TEDESCO RCE 39281 DATE
STEVEN L. MALLOY RCE 31926 DATE

PT 979

RYBHE RANCH
HAYER DISTRICT

IRVINE RANCH

WATER DISTRICT

IRVINE


DESALTER

PROJECT

POTABLE TREATMENT PLANT

PROCESS FLOW DIAGRAM

G-6
PROJECT NO.
0928.0070
SHT. NO. 6 of 171



ATTACHMENT D - STANDARD PROVISIONS

I. STANDARD PROVISIONS - PERMIT COMPLIANCE

A. Duty to Comply

- 1. The Discharger must comply with all of the conditions of this Order. Any noncompliance constitutes a violation of the Clean Water Act (CWA) and the California Water Code (CWC) and is grounds for enforcement action, for permit termination, revocation and reissuance, or modification; or denial of a permit reissuance application. (section 122.41(a), title 40 of the Code of Federal Regulations, 40 CFR 122.41(a))
- 2. The Discharger shall comply with effluent standards or prohibitions established under section 307(a) of the CWA for toxic pollutants and with standards for sewage sludge use or disposal established under section 405(d) of the CWA within the time provided in the regulations that establish these standards or prohibitions, even if this Order has not yet been modified to incorporate the requirement. (40 CFR 122.41(a)(1))

B. Need to Halt or Reduce Activity Not a Defense

It shall not be a defense for a Discharger in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this Order. (40 CFR 122.41(c))

C. Duty to Mitigate

The Discharger shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this Order that has a reasonable likelihood of adversely affecting human health or the environment. (40 CFR 122.41(d))

D. Proper Operation and Maintenance

The Discharger shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the Discharger to achieve compliance with the conditions of this Order. Proper operation and maintenance also includes adequate laboratory controls and appropriate quality assurance procedures. This provision requires the operation of backup or auxiliary facilities or similar systems that are installed by a Discharger only when necessary to achieve compliance with the conditions of this Order. (40 CFR 122.41(e))

E. Property Rights

- **1.** This Order does not convey any property rights of any sort or any exclusive privileges. (40 CFR 122.41(g))
- 2. The issuance of this Order does not authorize any injury to persons or property or invasion of other private rights, or any infringement of State or local law or regulations. (40 CFR 122.5(c))

F. Inspection and Entry

The Discharger shall allow the California Regional Water Quality Control Board, San Diego Region (San Diego Water Board), State Water Resources Control Board (State Water Board), United States Environmental Protection Agency (USEPA), and/or their authorized representatives (including an authorized contractor acting as their representative), upon the presentation of credentials and other documents, as may be required by law, to (40 CFR 122.41(i); CWC, § 13383):

- Enter upon the Discharger's premises where a regulated facility or activity is located or conducted, or where records are kept under the conditions of this Order (40 CFR 122.41(i)(1));
- 2. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this Order (40 CFR 122.41(i)(2));
- **3.** Inspect and photograph, at reasonable times, any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this Order (40 CFR 122.41(i)(3)); and
- **4.** Sample or monitor, at reasonable times, for the purposes of assuring Order compliance or as otherwise authorized by the CWA or the CWC, any substances or parameters at any location. (40 CFR 122.41(i)(4))

G. Bypass

1. Definitions

- **a.** "Bypass" means the intentional diversion of waste streams from any portion of a treatment facility. (40 CFR 122.41(m)(1)(i))
- **b.** "Severe property damage" means substantial physical damage to property, damage to the treatment facilities, which causes them to become inoperable, or substantial and permanent loss of natural resources that can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production. (40 CFR 122.41(m)(1)(ii))
- 2. Bypass not exceeding limitations. The Discharger may allow any bypass to occur which does not cause exceedances of effluent limitations, but only if it is for essential maintenance to assure efficient operation. These bypasses are not subject to the provisions listed in Standard Provisions Permit Compliance I.G.3, I.G.4, and I.G.5 below. (40 CFR 122.41(m)(2))
- **3.** Prohibition of bypass. Bypass is prohibited, and the San Diego Water Board may take enforcement action against a Discharger for bypass, unless (40 CFR 122.41(m)(4)(i)):
 - **a.** Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage (40 CFR 122.41(m)(4)(i)(A));

- **b.** There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass that occurred during normal periods of equipment downtime or preventive maintenance (40 CFR 122.41(m)(4)(i)(B)); and
- **c.** The Discharger submitted notice to the San Diego Water Board as required under Standard Provisions Permit Compliance I.G.5 below. (40 CFR 122.41(m)(4)(i)(C))
- **4.** The San Diego Water Board may approve an anticipated bypass, after considering its adverse effects, if the San Diego Water Board determines that it will meet the three conditions listed in Standard Provisions Permit Compliance I.G.3 above. (40 CFR 122.41(m)(4)(ii))

5. Notice

- **a.** Anticipated bypass. If the Discharger knows in advance of the need for a bypass, it shall submit a notice, if possible at least 10 days before the date of the bypass. (40 CFR 122.41(m)(3)(i))
- **b.** Unanticipated bypass. The Discharger shall submit notice of an unanticipated bypass as required in Standard Provisions Reporting V.E below (24-hour notice). (40 CFR 122.41(m)(3)(ii))

H. Upset

Upset means an exceptional incident in which there is unintentional and temporary noncompliance with technology based permit effluent limitations because of factors beyond the reasonable control of the Discharger. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation. (40 CFR 122.41(n)(1))

- 1. Effect of an upset. An upset constitutes an affirmative defense to an action brought for noncompliance with such technology based permit effluent limitations if the requirements of Standard Provisions Permit Compliance I.H.2 below are met. No determination made during administrative review of claims that noncompliance was caused by upset, and before an action for noncompliance, is final administrative action subject to judicial review. (40 CFR 122.41(n)(2))
- 2. Conditions necessary for a demonstration of upset. A Discharger who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs or other relevant evidence that (40 CFR 122.41(n)(3)):
 - **a.** An upset occurred and that the Discharger can identify the cause(s) of the upset (40 CFR 122.41(n)(3)(i));
 - **b.** The permitted facility was, at the time, being properly operated (40 CFR 122.41(n)(3)(ii));

- **c.** The Discharger submitted notice of the upset as required in Standard Provisions Reporting V.E.2.b below (24-hour notice) (40 CFR 122.41(n)(3)(iii)); and
- **d.** The Discharger complied with any remedial measures required under Standard Provisions Permit Compliance I.C above. (40 CFR 122.41(n)(3)(iv))
- **3.** Burden of proof. In any enforcement proceeding, the Discharger seeking to establish the occurrence of an upset has the burden of proof. (40 CFR 122.41(n)(4))

II. STANDARD PROVISIONS - PERMIT ACTION

A. General

This Order may be modified, revoked and reissued, or terminated for cause. The filing of a request by the Discharger for modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any Order condition. (40 CFR 122.41(f))

B. Duty to Reapply

If the Discharger wishes to continue an activity regulated by this Order after the expiration date of this Order, the Discharger must apply for and obtain a new permit. (40 CFR 122.41(b))

C. Transfers

This Order is not transferable to any person except after notice to the San Diego Water Board. The San Diego Water Board may require modification or revocation and reissuance of the Order to change the name of the Discharger and incorporate such other requirements as may be necessary under the CWA and the CWC. (40 CFR 122.41(I)(3); 122.61)

III. STANDARD PROVISIONS - MONITORING

- **A.** Samples and measurements taken for the purpose of monitoring shall be representative of the monitored activity. (40 CFR 122.41(j)(1))
- **B.** Monitoring results must be conducted according to test procedures under 40 CFR Part 136 or, in the case of sludge use or disposal, approved under 40 CFR Part 136 unless otherwise specified in 40 CFR Part 503 unless other test procedures have been specified in this Order. (40 CFR 122.41(j)(4); 122.44(i)(1)(iv))

IV. STANDARD PROVISIONS - RECORDS

A. Except for records of monitoring information required by this Order related to the Discharger's sewage sludge use and disposal activities, which shall be retained for a period of at least five years (or longer as required by 40 CFR Part 503), the Discharger shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by this Order, and records of all data used to complete the application for this Order, for a period of at least three (3) years from the date of the sample, measurement, report or application. This period may be extended by request of the San Diego Water Board at any time. (40 CFR 122.41(j)(2))

B. Records of monitoring information shall include:

- 1. The date, exact place, and time of sampling or measurements (40 CFR 122.41(j)(3)(i));
- 2. The individual(s) who performed the sampling or measurements (40 CFR 122.41(j)(3)(ii));
- 3. The date(s) analyses were performed (40 CFR 122.41(j)(3)(iii));
- **4.** The individual(s) who performed the analyses (40 CFR 122.41(j)(3)(iv));
- **5.** The analytical techniques or methods used (40 CFR 122.41(j)(3)(v)); and
- **6.** The results of such analyses. (40 CFR 122.41(j)(3)(vi))

C. Claims of confidentiality for the following information will be denied (40 CFR 122.7(b)):

- 1. The name and address of any permit applicant or Discharger (40 CFR 122.7(b)(1)); and
- 2. Permit applications and attachments, permits, and effluent data. (40 CFR 122.7(b)(2))

V. STANDARD PROVISIONS – REPORTING

A. Duty to Provide Information

The Discharger shall furnish to the San Diego Water Board, State Water Board, or USEPA within a reasonable time, any information which the San Diego Water Board, State Water Board, or USEPA may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this Order or to determine compliance with this Order. Upon request, the Discharger shall also furnish to the San Diego Water Board, State Water Board, or USEPA copies of records required to be kept by this Order. (40 CFR 122.41(h); CWC, § 13267)

B. Signatory and Certification Requirements

- 1. All applications, reports, or information submitted to the San Diego Water Board, State Water Board, and/or USEPA shall be signed and certified in accordance with Standard Provisions Reporting V.B.2, V.B.3, V.B.4, and V.B.5 below. (40 CFR 122.41(k))
- 2. All permit applications shall be signed by either a principal executive officer or ranking elected official. For purposes of this provision, a principal executive officer of a federal agency includes: (i) the chief executive officer of the agency, or (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrators of USEPA). (40 CFR 122.22(a)(3)).
- 3. All reports required by this Order and other information requested by the San Diego Water Board, State Water Board, or USEPA shall be signed by a person described in Standard Provisions Reporting V.B.2 above, or by a duly authorized representative of that person. A person is a duly authorized representative only if:
 - **a.** The authorization is made in writing by a person described in Standard Provisions Reporting V.B.2 above (40 CFR 122.22(b)(1));

- **b.** The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity such as the position of plant manager, operator of a well or a well field, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters for the company. (A duly authorized representative may thus be either a named individual or any individual occupying a named position.) (40 CFR 122.22(b)(2)); and
- **c.** The written authorization is submitted to the San Diego Water Board and State Water Board. (40 CFR 122.22(b)(3))
- 4. If an authorization under Standard Provisions Reporting V.B.3 above is no longer accurate because a different individual or position has responsibility for the overall operation of the facility, a new authorization satisfying the requirements of Standard Provisions Reporting V.B.3 above must be submitted to the San Diego Water Board and State Water Board prior to or together with any reports, information, or applications, to be signed by an authorized representative. (40 CFR 122.22(c))
- **5.** Any person signing a document under Standard Provisions Reporting V.B.2 or V.B.3 above shall make the following certification:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations." (40 CFR 122.22(d))

C. Monitoring Reports

- **1.** Monitoring results shall be reported at the intervals specified in the Monitoring and Reporting Program (Attachment E) in this Order. (40 CFR 122.41(I)(4))
- 2. Monitoring results must be reported on a Discharge Monitoring Report (DMR) form or forms provided or specified by the San Diego Water Board or State Water Board for reporting results of monitoring of sludge use or disposal practices. (40 CFR 122.41(I)(4)(i))
- 3. If the Discharger monitors any pollutant more frequently than required by this Order using test procedures approved under 40 CFR Part 136 or, in the case of sludge use or disposal, approved under 40 CFR Part 136 unless otherwise specified in 40 CFR Part 503, or as specified in this Order, the results of this monitoring shall be included in the calculation and reporting of the data submitted in the DMR or sludge reporting form specified by the San Diego Water Board. (40 CFR 122.41(I)(4)(ii))
- **4.** Calculations for all limitations, which require averaging of measurements, shall utilize an arithmetic mean unless otherwise specified in this Order. (40 CFR 122.41(I)(4)(iii))

D. Compliance Schedules

Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this Order, shall be submitted no later than 14 days following each schedule date. (40 CFR 122.41(I)(5))

E. Twenty Four-Hour Reporting

- 1. The Discharger shall report any noncompliance that may endanger health or the environment. Any information shall be provided orally within 24 hours from the time the Discharger becomes aware of the circumstances. A written submission shall also be provided within five (5) days of the time the Discharger becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. (40 CFR 122.41(I)(6)(i))
- 2. The following shall be included as information that must be reported within 24 hours under this paragraph (40 CFR 122.41(I)(6)(ii)):
 - **a.** Any unanticipated bypass that exceeds any effluent limitation in this Order. (40 CFR 122.41(I)(6)(ii)(A))
 - **b.** Any upset that exceeds any effluent limitation in this Order. (40 CFR 122.41(I)(6)(ii)(B))
- **3.** The San Diego Water Board may waive the above-required written report under this provision on a case-by-case basis if an oral report has been received within 24 hours. (40 CFR 122.41(l)(6)(iii))

F. Planned Changes

The Discharger shall give notice to the San Diego Water Board as soon as possible of any planned physical alterations or additions to the permitted facility. Notice is required under this provision only when (40 CFR 122.41(I)(1)):

- 1. The alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in 40 CFR 122.29(b) (40 CFR 122.41(I)(1)(i)); or
- 2. The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants that are not subject to effluent limitations in this Order. (40 CFR 122.41(l)(1)(ii))
- **3.** The alteration or addition results in a significant change in the Discharger's sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan. (40 CFR 122.41(I)(1)(iii))

G. Anticipated Noncompliance

The Discharger shall give advance notice to the San Diego Water Board or State Water Board of any planned changes in the permitted facility or activity that may result in noncompliance with General Order requirements. (40 CFR 122.41(I)(2))

H. Other Noncompliance

The Discharger shall report all instances of noncompliance not reported under Standard Provisions – Reporting V.C, V.D, and V.E above at the time monitoring reports are submitted. The reports shall contain the information listed in Standard Provision – Reporting V.E above. (40 CFR 122.41(I)(7))

I. Other Information

When the Discharger becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to the San Diego Water Board, State Water Board, or USEPA, the Discharger shall promptly submit such facts or information. (40 CFR 122.41(I)(8))

VI. STANDARD PROVISIONS - ENFORCEMENT

A. The San Diego Water Board is authorized to enforce the terms of this permit under several provisions of the CWC, including, but not limited to, sections 13385, 13386, and 13387

VII. ADDITIONAL PROVISIONS – NOTIFICATION LEVELS

A. Publicly-Owned Treatment Works (POTWs)

All POTWs shall provide adequate notice to the San Diego Water Board of the following (40 CFR 122.42(b)):

- 1. Any new introduction of pollutants into the POTW from an indirect discharger that would be subject to sections 301 or 306 of the CWA if it were directly discharging those pollutants (40 CFR 122.42(b)(1)); and
- 2. Any substantial change in the volume or character of pollutants being introduced into that POTW by a source introducing pollutants into the POTW at the time of adoption of the Order. (40 CFR 122.42(b)(2))
- **3.** Adequate notice shall include information on the quality and quantity of effluent introduced into the POTW as well as any anticipated impact of the change on the quantity or quality of effluent to be discharged from the POTW. (40 CFR 122.42(b)(3)).

ATTACHMENT E - MONITORING AND REPORTING PROGRAM

Table of Contents

l.	Genera	Monitoring Provisions	E-2
II.	Monitor	ing Locations	<u>E-3</u> E-3
III.	Influent	Monitoring Requirements	<u>E-5</u> E-5
	A. Mo	nitoring Locations M-INFA, M-INFB, M-INFC, and M-INFD	<u>E-5</u> E-5
IV.		Monitoring Requirements	
	A. Mo	nitoring Locations M-001A, M-001B, M-001C, and M-001D	<u>E-5</u> E-5
		nitoring Location M-001	
	C. Moi	nitoring Locations M-001E, M001F, and M-001G	<u>E-9</u> E-9
V.	Whole E	Effluent Toxicity (WET)Testing Requirements	<u>E-10</u> E-10
VI.	Land Di	scharge Monitoring Requirements – Not Applicable	<u>E-11</u> E-11
VII.	Reclam	ation Monitoring Requirements – Not Applicable	<u>E-11</u> E-11
VIII.	Receivi	ng Water Monitoring Requirements – Surface Water	<u>E-12E-12</u>
	A. Sur	f Zone Water Quality Monitoring	<u>E-12</u> E-12
	B. Nea	ar Shore Water Quality Monitoring	<u>E-13</u> E -13
	C. Off	Shore Water Quality Monitoring	<u>E-14</u> E-14
	D. Ber	nthic Monitoring	<u>E-15</u> E-15
IX.	Other M	Ionitoring Requirements	<u>E-16</u> E-16
	A. Kel	p Bed Canopy	<u>E-16</u> E -16
	B. Reg	gional Monitoring	<u>E-16</u> E -16
	C. Sol	ids Monitoring	<u>E-16</u> E -16
Χ.	Reportii	ng Requirements	<u>E-16</u> E-16
	A. Gei	neral Monitoring and Reporting Requirements	<u>E-16</u> E-16
		f Monitoring Reports (SMRs)	
	C. Dis	charge Monitoring Reports (DMRs)	<u>E-20</u> E-20
	D. Oth	er Reports	<u>E-20</u> E-20
		List of Tables	
		List of Tables	
Tabl	e E-1.	Monitoring Station Locations	<u>E-3</u> E-3
Tabl	e E-2.	Influent Monitoring	<u>E-5</u> E-5
Tabl	e E-3.	Effluent Monitoring at M-001A, M-001B, M-001C, and M-001D	<u>E-5</u> E-5
Tabl	e E-4.	Effluent Monitoring at M-001	<u>E-6</u> E-6
Tabl	e E-6.	Effluent Monitoring at M-001E, M001F, and M-001G	<u>E-9</u> E-9
Tabl	e E-7.	Whole Effluent Toxicity Testing	<u>E-10E-10</u>
Tabl	e E-8.	Approved Test for Chronic Toxicity	<u>E-10</u> E-10
Tabl	e E-9.	Near Shore Water Quality Reduced Monitoring Requirements	<u>E-13</u> E-13
Tabl	e E-10.	Near Shore Water Quality Intensive Monitoring Requirements	
Tabl	e E-11.	Off Shore Water Quality Reduced Monitoring Requirements	<u>E-14</u> E -14
Tabl	e E-12.	Off Shore Water Quality Intensive Monitoring Requirements	<u>E-14</u> E-14
Tabl	e E-13.	Sediment Monitoring Requirements	
Tabl	e E-14.	Infauna Monitoring Requirements	<u>E-15</u> E-15
Tabl	e E-15.	Monitoring Periods and Reporting Schedule	<u>E-18</u> E-18

ATTACHMENT E – MONITORING AND REPORTING PROGRAM (MRP)

Regulations at section 122.48, title 40 of the Code of Federal Regulations (40 CFR 122.48) require that all National Pollutant Discharge Elimination System (NPDES) permits specify monitoring and reporting requirements. Sections 13267 and 13383 of the California Water Code (CWC) also authorize the California Regional Water Quality Control Board, San Diego Region (San Diego Water Board) to require technical and monitoring reports. This MRP establishes monitoring and reporting requirements, which implement the federal and State regulations.

I. GENERAL MONITORING PROVISIONS

- **A.** Samples and measurements taken as required herein shall be representative of the volume and nature of the monitoring discharge. All samples shall be taken at the monitoring points specified below and, unless otherwise specified, before the monitored flow joins or is diluted by any other waste stream, body of water, or substance. Monitoring points shall not be changed without notification to and the approval of the San Diego Water Board. Samples shall be collected at times representative of "worst case" conditions with respect to compliance with the requirement of Order No. R9-2012-0013.
- **B.** Appropriate flow measurement devices and methods consistent with accepted scientific practices shall be selected and used to ensure the accuracy and reliability of measurements of the volume of monitored discharges. The devices shall be installed, calibrated and maintained to ensure that the accuracy of the measurement is consistent with the accepted capability of that type of device. Devices selected shall be capable of measuring flows with a maximum deviation of less than ±5 percent from true discharge rates throughout the range of expected discharge volumes.
- **C.** Monitoring must be conducted according to U.S. Environmental Protection Agency (USEPA) test procedures approved at 40 CFR Part 136, *Guidelines Establishing Test Procedures for the Analysis of Pollutants Under the Clean Water Act* as amended, or unless other test procedures are specified in Order No. R9-2012-0013 and/or in this MRP and/or by the San Diego Water Board.
- **D.** All analyses shall be performed in a laboratory certified to perform such analyses by the California Department of Public Health (DPH) or a laboratory approved by the San Diego Water Board.
- **E.** Records of monitoring information shall include information required under Standard Provision, Attachment D, section IV.
- **F.** All monitoring instruments and devices used by the Discharger to fulfill the prescribed monitoring program shall be properly maintained and calibrated as necessary to ensure their continued accuracy. All flow measurement devices shall be calibrated at least once per year, or more frequently, to ensure continued accuracy of the devices.
- **G.** The Discharger shall have, and implement, an acceptable written quality assurance (QA) plan for laboratory analyses. Duplicate chemical analyses must be conducted on a minimum of 10 percent of the samples or at least one sample per month, whichever is greater. A similar frequency shall be maintained for analyzing spiked samples. When requested by USEPA or the San Diego Water Board, the Discharger will participate in the NPDES discharge monitoring

report QA performance study. The Discharger should have a success rate equal or greater than 80 percent.

- **H.** Analysis for toxic pollutants, including chronic toxicity, with effluent limits or performance goals based on water quality objectives of the California Ocean Plan shall be conducted in accordance with procedures described in the California Ocean Plan and restated in this MRP.
- I. This permit may be modified in accordance with the requirements set forth at 40 CFR Parts 122 and 124, to include appropriate conditions or limits to address demonstrated effluent toxicity based on newly available information, or to implement any USEPA approved, new, State water quality standards applicable to effluent toxicity.

II. MONITORING LOCATIONS

A. The Discharger shall establish the following monitoring locations to demonstrate compliance with the effluent limitations, discharge specifications, and other requirements in this Order:

Table E-1. Monitoring Station Locations

		ig Station Locations
Discharge	Monitoring	Manitarian Lagatian Description
Point	Location	Monitoring Location Description
Name	Name	
		At the South Orange County Wastewater Authority (SOCWA) Regional Treatment
	M-INFA	Plant (RTP) and at a location where all influent flows to the treatment plant are
	101 11 41 7 4	accounted for in monitoring events; upstream of any in-plant return flows; and where
		representative samples of influent can be collected.
		At the SOCWA Coastal Treatment Plant (CTP) and at a location where all influent
	M-INFB	flows to the treatment plant are accounted for in monitoring events; upstream of any
		in-plant return flows; and where representative samples of influent can be collected
		At the Los Alisos Water Reclamation Plant (WRP) and at a location where all influent
	M-INFC	flows to the treatment plant are accounted for in monitoring events; upstream of any
		in-plant return flows; and where representative samples of influent can be collected.
		At the El Toro Water Recycling Plant (WRP) and at a location where all influent flows
	M-INFD	to the treatment plant are accounted for in monitoring events; upstream of any in-plant
	W II W	return flows; and where representative samples of influent can be collected
		Sampling will not physically occur at this monitoring location. This monitoring location
		represents a combined sample from all contributors to the ACOO. Samples shall be
001	M-001	taken from Monitoring Locations M-001A, M-001B, M-001C, M-001D, M-001E, M-
		001F, and M-001G as described further below.
		Final effluent from the SOCWA RTP and downstream of any in-plant return flows and
	NA 001A	
	M-001A	disinfection units where representative samples of effluent treated solely at the
		treatment plant can be collected.
		Final effluent from the SOCWA CTP and downstream of any inplant
	M-001B	return flows and disinfection units where representative samples of effluent treated
		solely at the treatment plant can be collected.
		Final effluent from the Los Alisos WRP and downstream of any in-plant return flows
	M-001C	and disinfection units where representative samples of effluent treated solely at the
		treatment plant can be collected.
		Final effluent from the El Toro WRP and downstream of any in-plant return flows and
	M-001D	disinfection units where representative samples of effluent treated solely at the
		treatment plant can be collected.
	M 001E	Brine discharge from the Irvine Desalter Project (IDP) Potable Water Treatment
	M-001E	System (PWTS) prior to mixing with any other flows directed to the ACOO.
	NA 004E	Non-potable treated groundwater from the IDP Shallow Groundwater Unit (SGU) prior
	M-001F	to mixing with any other flows directed to the ACOO.

Point Name Name Name Received Re	Discharge	Monitoring						
## Brine discharge from the South Coast Water District (SCWD) ## Aliso Creek Water Harvesting Project (ACWHP) prior to mixing with any other flows directed to the ACOO. ## SURF ZONE STATONS	Point	Location	Monitoring Location Description					
M-001G	Name	Name						
SURF ZONE STATONS		M 001C						
SURF ZONE STATONS		IVI-001G						
S2								
S3 Surf 10,000 feet south of the outfall S4 Surf 5,000 feet south of the outfall S5 Surf 4,000 feet south of the outfall S6 Surf 3,000 feet south of the outfall S7 Surf 2,000 feet south of the outfall S8 Surf 1,000 feet south of the outfall S8 Surf 1,000 feet south of the outfall S9 Surf at outfall S10 Surf 1,000 feet north of outfall S11 Surf 2,000 feet north of outfall S12 Surf 3,000 feet north of outfall S13 Surf 4,000 feet north of outfall S14 Surf 3,000 feet north of outfall S15 Surf 1,000 feet north of outfall S16 Surf 10,000 feet north of outfall N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, 500 feet south of the outfall N5 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall offuser section Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		S1	Surf 20,000 feet south of the outfall					
S4 Surf 5,000 feet south of the outfall S5 Surf 4,000 feet south of the outfall S6 Surf 3,000 feet south of the outfall S7 Surf 2,000 feet south of the outfall S8 Surf 1,000 feet south of the outfall S9 Surf 1,000 feet south of the outfall S9 Surf 1,000 feet north of outfall S10 Surf 1,000 feet north of outfall S11 Surf 2,000 feet north of outfall S12 Surf 3,000 feet north of outfall S13 Surf 4,000 feet north of outfall S14 Surf 5,000 feet north of outfall S15 Surf 10,000 feet north of outfall S16 Surf 15,000 feet north of outfall N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, at the outfall N4 1,000 feet offshore, 500 feet south of the outfall N5 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall offshore, 2,500 feet south of the outfall offshore and the intersection of its diagonal located at the center of the outfall officer section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction.		S2	Surf 15,000 feet south of the outfall					
S5		S3	Surf 10,000 feet south of the outfall					
S6 Surf 3,000 feet south of the outfall S7 Surf 2,000 feet south of the outfall S8 Surf 1,000 feet south of the outfall S9 Surf at outfall S10 Surf 1,000 feet north of outfall S11 Surf 2,000 feet north of outfall S12 Surf 3,000 feet north of outfall S13 Surf 4,000 feet north of outfall S13 Surf 4,000 feet north of outfall S14 Surf 5,000 feet north of outfall S15 Surf 10,000 feet north of outfall S16 Surf 10,000 feet north of outfall S16 Surf 15,000 feet north of outfall N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, 500 feet south of the outfall N5 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall		S4	Surf 5,000 feet south of the outfall					
S7 Surf 2,000 feet south of the outfall S8 Surf 1,000 feet south of the outfall S9 Surf at outfall S10 Surf 1,000 feet north of outfall S11 Surf 2,000 feet north of outfall S12 Surf 3,000 feet north of outfall S13 Surf 4,000 feet north of outfall S14 Surf 5,000 feet north of outfall S15 Surf 10,000 feet north of outfall S16 Surf 15,000 feet north of outfall S16 Surf 15,000 feet north of outfall NA 1,000 feet offshore, 2,500 feet south of the outfall NA 1,000 feet offshore, 1,000 feet south of the outfall NA 1,000 feet offshore, 500 feet south of the outfall NA 1,000 feet offshore, 500 feet south of the outfall NA 1,000 feet offshore, 1,000 feet south of the outfall NA 1,000 feet offshore, 500 feet south of the outfall NA 1,000 feet offshore, 500 feet south of the outfall NA 1,000 feet offshore, 2,500 feet south of the outfall NA 1,000 feet offshore, 500 feet south of the outfall NA 1,000 feet offshore, 500 feet south of the outfall NA 1,000 feet offshore, 2,500 feet south of the outfall NA 1,000 feet offshore, 2,500 feet south of the outfall NA 1,000 feet offshore, 2,500 feet south of the outfall NA 1,000 feet offshore, 2,500 feet south of the outfall NA 1,000 feet offshore, 2,500 feet south of the outfall NA 1,000 feet offshore, 2,500 feet south of the outfall NA 1,000 feet offshore, 2,500 feet south of the outfall NA 1,000 feet offshore, 2,500 feet south of the outfall offshore, 2,500 fee		S5	Surf 4,000 feet south of the outfall					
S8 Surf 1,000 feet south of the outfall S9 Surf at outfall S10 Surf 1,000 feet north of outfall S11 Surf 2,000 feet north of outfall S12 Surf 3,000 feet north of outfall S13 Surf 4,000 feet north of outfall S14 Surf 5,000 feet north of outfall S15 Surf 10,000 feet north of outfall S16 Surf 15,000 feet north of outfall N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 500 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, 500 feet south of the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall offsuer section Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		S6	Surf 3,000 feet south of the outfall					
Sysurf at outfall Surf 1,000 feet north of outfall Surf 2,000 feet north of outfall Surf 2,000 feet north of outfall Surf 3,000 feet north of outfall Surf 4,000 feet north of outfall Surf 5,000 feet north of outfall Surf 5,000 feet north of outfall Surf 15,000 feet south of the outfall Surf 15,000 feet offshore, 2,500 feet south of the outfall Surf 15,000 feet offshore, 1,000 feet south of the outfall Surf 15,000 feet offshore, 1,000 feet south of the outfall Surf 15,000 feet offshore, 1,000 feet south of the outfall Surf 15,000 feet offshore, 500 feet south of the outfall Surf 15,000 feet offshore, 2,500 feet south of the outfall Surf 15,000 feet offshore, 2,500 feet south of the outfall Surf 15,000 feet offshore, 2,500 feet south of the outfall Surf 15,000 feet offshore, 2,500 feet south of the outfall Surf 15,000 feet offshore, 2,500 feet south of the outfall offshore offshore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. At the intersection of the diagonals of the above square		S7	Surf 2,000 feet south of the outfall					
S10 Surf 1,000 feet north of outfall S11 Surf 2,000 feet north of outfall S12 Surf 3,000 feet north of outfall S13 Surf 4,000 feet north of outfall S14 Surf 5,000 feet north of outfall S15 Surf 10,000 feet north of outfall S16 Surf 15,000 feet north of outfall S16 Surf 15,000 feet north of outfall N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, at the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall Station A1 shall be located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. At the intersection of the diagonals of the above square		S8	Surf 1,000 feet south of the outfall					
S11 Surf 2,000 feet north of outfall S12 Surf 3,000 feet north of outfall S13 Surf 4,000 feet north of outfall S14 Surf 5,000 feet north of outfall S15 Surf 10,000 feet north of outfall S16 Surf 15,000 feet north of outfall S16 NEAR SHORE STATIONS N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, 500 feet south of the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall STATIONS A1 - A4 At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction A5 At the intersection of the diagonals of the above square		S9	Surf at outfall					
S12 Surf 3,000 feet north of outfall S13 Surf 4,000 feet north of outfall S14 Surf 5,000 feet north of outfall S15 Surf 10,000 feet north of outfall S16 Surf 15,000 feet north of outfall NEAR SHORE STATIONS N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, 500 feet south of the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		S10	Surf 1,000 feet north of outfall					
S13 Surf 4,000 feet north of outfall S14 Surf 5,000 feet north of outfall S15 Surf 10,000 feet north of outfall S16 Surf 15,000 feet north of outfall NEAR SHORE STATIONS N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, at the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall OFFSHORE STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. At the intersection of the diagonals of the above square		S11	Surf 2,000 feet north of outfall					
S14 Surf 5,000 feet north of outfall S15 Surf 10,000 feet north of outfall S16 Surf 15,000 feet north of outfall NEAR SHORE STATIONS N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, at the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 500 feet south of the outfall N7 1,000 feet offshore, 1,000 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		S12	Surf 3,000 feet north of outfall					
S15 Surf 10,000 feet north of outfall S16 Surf 15,000 feet north of outfall NEAR SHORE STATIONS N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, at the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		S13	Surf 4,000 feet north of outfall					
S16 Surf 15,000 feet north of outfall NEAR SHORE STATIONS N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, at the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		S14	Surf 5,000 feet north of outfall					
NEAR SHORE STATIONS N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, at the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		S15	Surf 10,000 feet north of outfall					
N1 1,000 feet offshore, 2,500 feet south of the outfall N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, at the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall OFFSHORE STATIONS A1 At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction A5 At the intersection of the diagonals of the above square		S16	Surf 15,000 feet north of outfall					
N2 1,000 feet offshore, 1,000 feet south of the outfall N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, at the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall OFFSHORE STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction A5 At the intersection of the diagonals of the above square			NEAR SHORE STATIONS					
N3 1,000 feet offshore, 500 feet south of the outfall N4 1,000 feet offshore, at the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall OFFSHORE STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction A5 At the intersection of the diagonals of the above square		N1	1,000 feet offshore, 2,500 feet south of the outfall					
N4 1,000 feet offshore, at the outfall N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall OFFSHORE STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction A5 At the intersection of the diagonals of the above square		N2	1,000 feet offshore, 1,000 feet south of the outfall					
N5 1,000 feet offshore, 500 feet south of the outfall N6 1,000 feet offshore, 1,000 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall OFFSHORE STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		N3	1,000 feet offshore, 500 feet south of the outfall					
N6 1,000 feet offshore, 1,000 feet south of the outfall N7 1,000 feet offshore, 2,500 feet south of the outfall OFFSHORE STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		N4	1,000 feet offshore, at the outfall					
N7 1,000 feet offshore, 2,500 feet south of the outfall OFFSHORE STATIONS At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		N5						
At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		N6	1,000 feet offshore, 1,000 feet south of the outfall					
At the corners of a 1,000 foot by 1,000 foot square having one side parallel to shore and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		N7						
 A1 – A4 and the intersection of its diagonal located at the center of the outfall diffuser section. Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square 								
Station A1 shall be located at the northeastern corner and Stations A2 through A4 at successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square								
successive corners in a clockwise direction. A5 At the intersection of the diagonals of the above square		A1 – A4						
A5 At the intersection of the diagonals of the above square								
		A5						
Di One fille down-coast from the outrall, and over the same depth contour as station Ab		B1	One mile down-coast from the outfall, and over the same depth contour as Station A5					
B2 One mile down-coast from the outfall, and over the same depth contour as Station A5		B2	One mile down-coast from the outfall, and over the same depth contour as Station A5					

B. Monitoring station locations may be modified with the approval of the San Diego Water Board.

III. INFLUENT MONITORING REQUIREMENTS

A. Monitoring Locations M-INFA, M-INFB, M-INFC, and M-INFD

1. The Discharger shall monitor at Monitoring Locations M-INFA, M-INFB, M-INFC, and M-INFD upstream of any in-plant return flows, and where representative samples of the influent can be obtained. Influent samples shall be collected on the same day as, and shortly before the collection of effluent samples. Sampling shall be monitored as follows.

Table E-2. Influent Monitoring

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method
Flow	MGD	Recorder/Totalizer	Continuous	
Carbonaceous Biochemical Oxygen	mg/L	24-hr Composite	1/Week	1
Demand (5-day @ 20°C) (CBOD ₅)	lbs/day	Calculate ²	1/Week	
Biochemical Oxygen Demand (5-day	mg/L	24-hr Composite	1/Month	1
@ 20°C) (BOD ₅)	lbs/day	Calculate ²	1/Month	
Total Supponded Solide (TSS)	mg/L	24-hr Composite	1/Week	1
Total Suspended Solids (TSS)	lbs/day	Calculate ²	1/Week	

¹ As required under 40 CFR Part 136.

IV. EFFLUENT MONITORING REQUIREMENTS

A. Monitoring Locations M-001A, M-001B, M-001C, and M-001D

1. The Discharger shall monitor the effluent at Monitoring Locations M-001A, M-001B, M-001C, and M-001D as follows.

Table E-3. Effluent Monitoring at M-001A, M-001B, M-001C, and M-001D

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method
Flow	MGD	Recorder/Totalizer	Continuous	
	mg/L	24-hr Composite	1/Day ²	1
CBOD₅	lbs/day	Calculate ³	1/Day ²	
	% Removal	Calculate ⁴	1/Day ²	
	mg/L	24-hr composite	1/Month	1
BOD₅	lbs/day	Calculate ³	1/Month	
	% Removal	Calculate ⁴	1/Month	
	mg/L	24-hr Composite	1/Day ²	1
TSS	lbs/day	Calculate ³	1/Day ²	
	% Removal	Calculate ⁴	1/Day ²	
Settleable Solids (SS)	mL/L	Grab	1/Day ²	1
Oil and Crasss	mg/L	Grab	1/Month ²	1
Oil and Grease	lbs/day	Calculate ³	1/Month	
Turbidity	NTU	Grab	1/Week	1

The Discharger shall calculate and report the Mass Emission Rate (MER) of the constituent for each sample taken. The MER shall be calculated in accordance with section VII.I.2.d of this Order.

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method
рН	standard units	Grab	1/Day ²	1

As required under 40 CFR Part 136.

B. Monitoring Location M-001

1. The Discharger shall monitor the effluent from M-001 (Discharge Point No. 001) as follows.

Table E-4. Effluent Monitoring at M-001

Table E-4. Effluent Monito	Tilig at W-001		NA* *	Di.
Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method
Flow	MGD	Recorder/Totalizer	Continuous	
Temperature	°F	Grab	1/Week	1
Dissolved Oxygen	mg/L	Grab	1/Week	1
Conductivity	mmhos/cm	Grab	1/Month	1
TABLE B PARA	METERS FOR I	PROTECTION OF MAR	INE AQUATIC LIF	Ē
Arsenic, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Cadmium, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Chromium (VI), Total Recoverable ⁴	μg/L	24-hr Composite	2/Year ^{2,3}	1
Copper, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Lead, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Mercury, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Nickel, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Selenium, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Silver, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Zinc, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Cyanide, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1,5
Chlorine, Total Residual	μg/L	Grab	1/Day ^{2,6}	1
Ammonia Nitrogen, Total (as N)	mg/L	24-hr Composite	1/Month ^{2,3}	1
Phenolic Compounds (nonchlorinated) ⁷	μg/L	Grab	2/Year ^{2,3}	1
Phenolic Compounds (chlorinated) ⁸	μg/L	Grab	2/Year ^{2,3}	1
Endosulfan ⁹	μg/L	Grab	2/Year ^{2,3}	1
Endrin	μg/L	Grab	2/Year ^{2,3}	1
HCH ¹⁰	μg/L	Grab	2/Year ^{2,3}	1
Radioactivity	pCi/L	24-hr Composite	2/Year ^{2,3}	1

Five days per week except seven days per week for at least one week during July or August of each year.

The Discharger shall calculate and report the Mass Emission Rate (MER) of the constituent for each sample taken. The MER shall be calculated in accordance with section VII.I.2.d of this Order.

The Discharger shall calculate the daily percent average removal and report the monthly average percent removal for $CBOD_5$, BOD_5 and TSS in accordance with section VII.H of this Order.

The Discharger shall calculate the daily percent average removal and report the monthly average percent removal for CBOD₅, BOD₅ and TSS in accordance with section VII.H of this Order.

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method
TABLE B PARAMETER	S FOR PROTEC	CTION OF HUMAN HEA		L .
Acrolein	μg/L	Grab	2/Year ^{2,3}	1
Antimony, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Bis (2-chloroethoxy) Methane	μg/L	Grab	2/Year ^{2,3}	1
Bis (2-chloroisopropyl) Ether	μg/L	Grab	2/Year ^{2,3}	1
Chlorobenzene	μg/L	Grab	2/Year ^{2,3}	1
Chromium (III), Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Di-n-butyl Phthalate	μg/L	Grab	2/Year ^{2,3}	1
Dichlorobenzenes ¹¹	μg/L	Grab	2/Year ^{2,3}	1
Diethyl Phthalate	μg/L	Grab	2/Year ^{2,3}	1
Dimethyl Phthalate	μg/L	Grab	2/Year ^{2,3}	1
4,6-dinitro-2-methylphenol	μg/L	Grab	2/Year ^{2,3}	1
2,4-dinitrophenol	μg/L	Grab	2/Year ^{2,3}	1
Ethylbenzene	μg/L	Grab	2/Year ^{2,3}	1
Fluoranthene	μg/L	Grab	2/Year ^{2,3}	1
Hexachlorocyclopentadiene	μg/L	Grab	2/Year ^{2,3}	1
Nitrobenzene	μg/L	Grab	2/Year ^{2,3}	1
Thallium, Total Recoverable	μg/L	24-hr Composite	2/Year ^{2,3}	1
Toluene	μg/L	Grab	2/Year ^{2,3}	1
Tributyltin	μg/L	24-hr Composite	2/Year ^{2,3}	1
1,1,1-trichloroethane	μg/L	Grab	2/Year ^{2,3}	1
TABLE B PARAMET	ERS FOR PROT	ECTION OF HUMAN HE		OGENS
Acrylonitrile	μg/L	Grab	2/Year ^{2,3}	1
Aldrin	μg/L	Grab	2/Year ^{2,3}	1
Benzene	μg/L	Grab	2/Year ^{2,3}	1
Benzidine	μg/L	Grab	2/Year ^{2,3}	1
Beryllium, Total Recoverable	μg/L	24-hr composite	2/Year ^{2,3}	1
Bis (2-chloroethyl) Ether	μg/L	Grab	2/Year ^{2,3}	1
Bis (2-ethlyhexyl) Phthalate	μg/L	Grab	2/Year ^{2,3}	1
Carbon Tetrachloride	μg/L	Grab	2/Year ^{2,3}	1
Chlordane	μg/L	Grab	2/Year ^{2,3}	1
Chlorodibromomethane	μg/L	Grab	2/Year ^{2,3}	1
Chloroform	μg/L	Grab	2/Year ^{2,3}	1
DDT ¹²	μg/L	Grab	2/Year ^{2,3}	1
1,4-dichlorobenzene	μg/L	Grab	2/Year ^{2,3}	1
3,3'-dichlorobenzidine	μg/L	Grab	2/Year ^{2,3}	1
1,2-dichloroethane	μg/L	Grab	2/Year ^{2,3}	1
1,1-dichloroethylene	μg/L	Grab	2/Year ^{2,3}	1
Dichlorobromomethane	μg/L	Grab	2/Year ^{2,3}	1
Dichloromethane	μg/L	Grab	2/Year ^{2,3}	1
1,3-dichloropropene	μg/L	Grab	2/Year ^{2,3}	1
Dieldrin	μg/L	Grab	2/Year ^{2,3}	1

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method
2,4-dinitrotoluene	μg/L	Grab	2/Year ^{2,3}	1
1,2-diphenylhydrazine	μg/L	Grab	2/Year ^{2,3}	1
Halomethanes ¹³	μg/L	Grab	2/Year ^{2,3}	1
Heptachlor	μg/L	Grab	2/Year ^{2,3}	1
Heptachlor Epoxide	μg/L	Grab	2/Year ^{2,3}	1
Hexachlorobenzene	μg/L	Grab	2/Year ^{2,3}	1
Hexachlorobutadiene	μg/L	Grab	2/Year ^{2,3}	1
Hexachloroethane	μg/L	Grab	2/Year ^{2,3}	1
Isophorone	μg/L	Grab	2/Year ^{2,3}	1
N-nitrosodimethylamine	μg/L	Grab	2/Year ^{2,3}	1
N-nitrosodi-N-propylamine	μg/L	Grab	2/Year ^{2,3}	1
N-nitrosodiphenylamine	μg/L	Grab	2/Year ^{2,3}	1
PAHs ¹⁴	μg/L	Grab	2/Year ^{2,3}	1
PCBs ¹⁵	μg/L	Grab	2/Year ^{2,3}	1
TCDD equivalents ¹⁶	μg/L	Grab	2/Year ^{2,3}	1
1,1,2,2-tetrachloroethane	μg/L	Grab	2/Year ^{2,3}	1
Tetrachloroethylene	μg/L	Grab	2/Year ^{2,3}	1
Toxaphene	μg/L	Grab	2/Year ^{2,3}	1
Trichloroethylene	μg/L	Grab	2/Year ^{2,3}	1
1,1,2-trichloroethane	μg/L	Grab	2/Year ^{2,3}	1
2,4,6-trichlorophenol	μg/L	Grab	2/Year ^{2,3}	1
Vinyl Chloride	μg/L	Grab	2/Year ^{2,3}	1

As required under 40 CFR Part 136.

The Discharger shall calculate and report the MER of the constituent for each sample taken. The MER shall be calculated in accordance with section VII.1.2.d of this Order.

- The Discharger shall monitor quarterly, except ammonia, which shall be twice per month, if any analysis for this constituent yields a result higher than the applicable effluent limitation or performance goal specified in this Order. The increased minimum frequency of monitoring shall remain in effect until the results of a minimum of four consecutive analyses for this constituent are below all applicable effluent limitations or performance goals specified in this Order.
- The Discharger may, at their option, apply this performance goal as a total chromium performance goal.
- If a Discharger can demonstrate to the satisfaction of the San Diego Water Board (subject to USEPA approval) that an analytical method is available to reliably distinguish between strongly and weakly complexed cyanide, effluent limitations for cyanide may be met by the combined measurement of free cyanide, simple alkali metals cyanides, and weakly complexed organometallic cyanide complexes. In order for the analytical method to be acceptable, the recovery of free cyanide from metal complexes must be comparable to that achieved by the approved method in 40 CFR Part 136, as revised May 14, 1999.
- Monitoring of total chlorine residual is not required on days when none of the treatment units that are subject to this Order use chlorine for disinfection. If only one sample is collected for total chlorine residual analysis on a particular day, that sample must be collected at the time when the concentration of total chlorine residual in the discharge would be expected to be greatest. The times of chlorine discharges on the days that samples are collected, and the time at which samples are collected, shall be reported.
- Non-chlorinated phenolic compounds represent the sum of 2,4-dimethylphenol, 4,6-dinitro-2-methylphenol, 2,4-dinitrophenol, 2-methylphenol, 4-methylphenol, 2-nitrophenol, 4-nitrophenol, and phenol.
- Chlorinated phenolic compounds represent the sum of 4-chloro-3-methylphenol, 2-chlorophenol, pentachlorophenol, 2,4,5-trichlorophenol, and 2,4,6-trichlorophenol.
- ⁹ Endosulfan represents the sum of alpha-endosulfan, beta-endosulfan, and endosulfan sulfate.
- HCH (hexachlorocyclohexane) represents the sum of the alpha, beta, gamma (Lindane), and delta isomers of hexachlorocyclohexane.
- Dichlorobenzenes represent the sum of 1,2- and 1,3-dichlorobenzene.
- DDT represents the sum of 4,4'DDT; 2,4'DDT; 4,4'DDE; 2,4'DDE; 4,4'DDD; and 2,4'DDD.

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method
			rrequency	wethod

Halomethanes represent the sum of bromoform, bromomethane (methyl bromide), and chloromethane (methyl chloride).

TCDD equivalents represent the sum of concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors, as shown by the table below. USEPA Method 8280 may be used to analyze TCDD equivalents.

Isomer Group	Toxicity Equivalence Factor
2,3,7,8 – tetra CDD	1.0
2,3,7,8 – penta CDD	0.5
2,3,7,8 - hexa CDD	0.1
2,3,7,8 – hepta CDD	0.01
octa CDD	0.001
2,3,7,8 – tetra CDF	0.1
1,2,3,7,8 – penta CDF	0.05
2,4,5,7,8 - penta CDF	0.5
2,3,7,8 - hexa CDFs	0.1
2,3,7,8 – hepta CDFs	0.01
Octa CDF	0.001

C. Monitoring Locations M-001E, M001F, and M-001G

1. The Discharger shall monitor the effluent from Monitoring Locations M-001E, M001F, and M-001G as follows.

Table E-6. Effluent Monitoring at M-001E, M001F, and M-001G

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method
Flow	MGD	Recorder/Totalizer	Continuous	
TOO	mg/L	24-hr Composite	1/Month	1
TSS	lbs/day	Calculate ²	1/Month	
SS	mL/L	Grab	1/Month	1
Oil and	mg/L	Grab	1/Month	1
Grease	lbs/day	Calculate ²	1/Month	
Turbidity	NTU	Grab	1/Month	1
рН	standard units	Grab	1/Month	1
Conductivity	mmhos/cm	Grab	1/Month	1

As required under 40 CFR Part 136.

PAHs (polynuclear aromatic hydrocarbons) represent the sum of acenapthalene; anthracene; 1,2-benzanthracene; 4,5-benzofluoranthene; benzo[k]fluoranthene; 1,12-benzoperylene; benzo[a]pyrene; chrysene; dibenzo[a,h]anthracene; fluorene; indeno[1,2,3-cd]pyrene; phenanthrene; and pyrene.

PCBs (polychlorinated biphenyls) represent the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Arolclor-1254, and Arcolor-1260.

The Discharger shall calculate and report the Mass Emission Rate (MER) of the constituent for each sample taken. The MER shall be calculated in accordance with section VII.I.2.d of this Order.

V. WHOLE EFFLUENT TOXICITY (WET) TESTING REQUIREMENTS

The Discharger shall conduct chronic toxicity testing on effluent samples collected at Monitoring Location M-001, in accordance with the following schedule and requirements:

Table E-7. Whole Effluent Toxicity Testing

Test	Unit	Sample Type	Minimum Test Frequency
Acute Toxicity	TU_a	24-hr Composite	1/Quarter
Screening period for chronic toxicity	TU_c	24-hr Composite	Every other year for 3 months, beginning with the calendar year 2012
Chronic Toxicity	TU₀	24-hr Composite	1/Month

Acute toxicity testing shall be performed using either a marine fish or invertebrate species in accordance with procedures established by the USEPA guidance manual, *Methods for Measuring the Acute Toxicity of Effluents and Receiving Waters to Freshwater and Marine Organisms*, 5th Edition, October 2002 (EPA-821-R-02-012).

Critical life stage toxicity tests shall be performed to measure chronic toxicity. Testing shall be performed using methods outlined in *Short-Term Methods for Estimating the Chronic Toxicity of Effluent and Receiving Waters to West Coast Marine Estuarine Organisms* (Chapman, G.A., D.L. Denton, and J.M. Lazorchak, 1995) or *Procedures Manual for Conducting Toxicity Tests Developed by the Marine Bioassay Project* (State Water Resources Control Board, 1996).

A screening period for chronic toxicity shall be conducted every other year, beginning with the calendar year 2012. Each screening period shall consist of 3 consecutive months of WET tests, using a minimum of three test species with approved test protocols, from the following list (from the Ocean Plan). Repeat screening periods may be terminated after the first month if the most sensitive species is the same as the species previously found to be most sensitive. Other tests may be used, if they have been approved for such testing by the State Water Resources Control Board (State Water Board). The test species shall include a fish, an invertebrate, and an aquatic plant. After the screening period, the most sensitive test species shall be used for the quarterly testing. Control and dilution water should be receiving water or lab water as appropriate. If the dilution water is different from the culture water, then culture water should be used in a second control. The sensitivity of the test organisms to a reference toxicant shall be determined concurrently with each bioassay test and reported with test results.

Table E-8. Approved Test for Chronic Toxicity

Species	Test	Tier ¹	Reference ²
giant kelp, <i>Macrocystis pyrifera</i>	percent germination; germ tube length	1	a, c
red abalone, Haliotis rufescens	abnormal shell development	1	a, c
oyster, Crassostrea gigas; mussels, Mytilus spp.	abnormal shell development; percent survival	1	a, c
urchin, Strongylocentrotus purpuratus; sand dollar, Dendraster excentricus	percent normal development	1	a, c
urchin, Strongylocentrotus purpuratus; sand dollar, Dendraster excentricus	percent fertilization	1	a, c
shrimp, Homesimysis costata	percent survival; growth	1	a, c
shrimp, Mysidopsis bahia	percent survival; fecundity	2	b, d
topsmelt, Atherinops affinis	larval growth rate; percent	1	a, c

Species	Test	Tier 1	Reference ²
	survival		
Silversides, Menidia beryllina	larval growth rate; percent survival	2	b, d

- First tier methods are preferred for compliance monitoring. If first tier organisms are not available, the Discharger can use a second tier test method following approval by the San Diego Water Board.
- Protocol References:
 - a. Chapman, G.A., D.L. Denton, and J.M. Lazorchak. 1995. Short-term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to West Coast Marine and Estuarine Organisms. USEPA Report No. EPA/600/R-95/136
 - b. Klemm, D.J., G.E. Morrison, T.J. Norberg-King, W.J. Peltier, and M.A. Heber. 1994. Short-term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Water to Marine and Estuarine Organisms. USEPA Report No. EPA-600-4-91-003.
 - SWRCB 1996. Procedures Manual for Conducting Toxicity Tests Developed by the Marine Bioassay Project. 96-1WQ.
 - d. Weber, C.I., W.B. Horning, I.I., D.J. Klemm, T.W. Nieheisel, P.A. Lewis, E.L. Robinson, J. Menkedick and F. Kessler 9eds). 1998. Short-term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to Marine and Estuarine Organisms. EPA/600/4-87/028. National Information Service, Springfield, VA.

If the effluent limit for chronic toxicity is exceeded in any one test, then within 15 days of the exceedance, the Discharger shall begin conducting six additional tests, bi-weekly, over a 12-week period. If the toxicity effluent limitation is exceeded in any of these six additional tests, then the Discharger shall notify the San Diego Water Board. If the San Diego Water Board determines that the discharge consistently exceeds a toxicity limitation or performance goal, then the Discharger shall initiate a TRE/TIE in accordance with the TRE workplan, Toxicity Reduction Evaluation Guidance for Municipal Wastewater Treatment Plants (USEPA 833-B-99-002, 1999), and USEPA TIE guidance documents (Phase I, EPA/600/6-91/005F, 1992; Phase II, EPA/600/R-92/080, 1993; and Phase III, EPA/600/R-92/081, 1993). Once the source of toxicity is identified, the Discharger shall take all reasonable steps to reduce the toxicity to meet the chronic toxicity effluent limitation and the acute toxicity performance goal identified in section IV.A.2 of this Order.

Within 30 days of completion of the TRE/TIE, the Discharger shall submit the results of the TRE/TIE, including a summary of the findings, data generated, a list of corrective actions necessary to achieve consistent compliance with all the toxicity limitations/performance goals of this Order and prevent recurrence of exceedances of those limitations/performance goals, and a time schedule for implementation of such corrective actions. The corrective actions and time schedule shall be modified at the direction of the San Diego Water Board.

If no toxicity is detected in any of these additional six tests, then the Discharger may return to the testing frequency specified in the MRP.

VI. LAND DISCHARGE MONITORING REQUIREMENTS – NOT APPLICABLE

VII. RECLAMATION MONITORING REQUIREMENTS – NOT APPLICABLE

VIII. RECEIVING WATER MONITORING REQUIREMENTS – SURFACE WATER

Receiving water and sediment monitoring in the vicinity of the ACOO shall be conducted as specified below. Station location, sampling, sample preservation and analyses, when not specified, shall be by methods approved by the San Diego Water Board. The monitoring program may be modified by the San Diego Water Board at any time.

The receiving water and sediment monitoring program for the ACOO may be conducted jointly with other dischargers to the ACOO.

During monitoring events, if possible, sample stations shall be located using a land-based microwave positioning system or a satellite positioning system such as GPS. If an alternate navigation system is proposed, its accuracy should be compared to that of microwave and satellite based systems, and any compromises in accuracy shall be justified.

A. Surf Zone Water Quality Monitoring

All surf zone stations shall be monitored as follows.

1. Grab samples shall be collected and analyzed for total and fecal coliform and enterococcus bacteria at a minimum frequency of twice per week. As required by implementation procedures at section III.D of the Ocean Plan, measurement of enterococcus density shall be conducted at all stations where measurement of total and fecal coliform bacteria is required.

Samples shall be collected in accordance with the Orange County Health Care Agency, Environmental Health.

If a single sample exceeds any of the single sample bacterial standards, repeat sampling at that location shall be conducted to determine the extent and persistence of the exceedance. Repeat sampling shall be conducted within 24 hours of receiving analytical results and continued until the sample result is less than the single sample bacterial standards or until a sanitary survey is conducted to determine the source of the high bacterial densities.

Single sample bacterial standards include:

- i. Total coliform density will not exceed 10,000 per 100 ml; or
- ii. Fecal coliform density will not exceed 400 per 100 ml; or
- iii. Total coliform density will not exceed 1,000 per 100 ml when the ratio of fecal/total coliform exceeds 0.1;
- iv. Enterococcus density will not exceed 104 per 100 ml.

- 2. At the same time samples are collected from surf zone stations, the following information shall be recorded: observation of wind direction and speed; weather (cloudy, sunny, or rainy); current direction; tidal conditions; and observations of water color, discoloration, oil and grease; turbidity, odor, and materials of sewage origin in the water or on the beach; andwater temperature. The Discharger shall also record the status of the mouth of Aliso Creek (open, closed, flow, etc.).
- 3. In the event of stormy weather which makes sampling hazardous at certain surf zone stations, collection of samples at such stations can be omitted, provided that such omissions do not occur more than 5 days in any calendar year or occur at consecutive sampling times. The observations listed in (2) above shall still be recorded and reported to the San Diego Water Board for these stations at the time the sample was attempted to be collected.

B. Near Shore Water Quality Monitoring

All near shore stations shall be monitored as follows.

1. Reduced Monitoring

If the San Diego Water Board determines that the effluent at all times complies with the effluent limitations and performance goals at section IV.A of this Order and the receiving water limitations at section V.A of this Order, only reduced near shore water quality monitoring specified below is required.

Table E-9. Near Shore Water Quality Reduced Monitoring Requirements

Determination	Units	Type of Sample	Minimum Frequency
Visual Observations	1	1	1/Month
Total Coliform Organisms	Number / 100 mL	Grab ¹	1/Month
Fecal Coliform Organisms	Number / 100 mL	Grab ¹	1/Month
Enterococcus	Number / 100 mL	Grab ¹	1/Month

At the surface.

2. Intensive Monitoring

The intensive near shore water quality monitoring specified below is required during the 12-month period beginning July 1, 2013 through June 30, 2014, and must be submitted by October 1, 2016. The intensive near shore water quality monitoring specified below is also required if the San Diego Water Board determines that 1) the effluent does not at all times comply with the effluent limitations and performance goals at section IV.A of this Order, or 2) the receiving water limitations at section V.A of this Order are not being consistently achieved.

Table E-10.Near Shore Water Quality Intensive Monitoring Requirements

Determination	Units	Type of Sample	Minimum Frequency
Visual Observations	1	-	1/Month
Total Coliform Organisms	Number / 100 mL	Grab ¹	1/Month
Fecal Coliform Organisms	Number / 100 mL	Grab ¹	1/Month
Enterococcus	Number / 100 mL	Grab ¹	1/Month

At the surface and mid-depth.

C. Off Shore Water Quality Monitoring

All off shore stations shall be monitored as follows.

1. Reduced Monitoring

If the San Diego Water Board determines that the effluent at all times complies with the effluent limitations and performance goals at section IV.A of this Order and the receiving water limitations at section V.A of this Order, only reduced off shore water quality monitoring specified below is required.

Table E-11.Off Shore Water Quality Reduced Monitoring Requirements

Determination	Units	Type of Sample	Minimum Frequency
Visual Observations			1/Month
Total Coliform Organisms	Number / 100 mL	Grab ¹	1/Month
Fecal Coliform Organisms	Number / 100 mL	Grab ¹	1/Month
Enterococcus	Number / 100 mL	Grab ¹	1/Month

At surface and mid-depth.

2. Intensive Monitoring

The intensive off shore water quality monitoring specified below is required during the 12-month period beginning July 1, 2013 through June 30, 2014, and must be submitted by October 1, 2016. The intensive off shore water quality monitoring specified below may also be required if the San Diego Water Board determines that 1) the effluent does not at all times comply with the effluent limitations and performance goals at section IV.A of this Order or 2) the receiving water limitations section V.A of this Order are not being consistently achieved.

Table E-12. Off Shore Water Quality Intensive Monitoring Requirements

Determination	Units	Type of Sample	Minimum Frequency
Visual Observations			1/Month
Total Coliform Organisms	Number / 100 mL	Grab ¹	1/Month
Fecal Coliform Organisms	Number / 100 mL	Grab ¹	1/Month
Enteroccoccus	Number / 100 mL	Grab ¹	1/Month
Salinity, Temperature, and Depth	Practical Salinity Units,°F, feet	Grab ²	1/Month
Dissolved Oxygen	mg/L	Grab ³	1/Month
Light Transmittance	percent	Instrument ³	1/Month
рН	standard units	Grab⁴	1/Month

At the surface and mid-depth.

At 1-meter intervals, surface to bottom.

At the surface, mid-depth, and bottom.

⁴ At the surface.

D. Benthic Monitoring

The intensive monitoring specified below is required during the 12-month period beginning July 1, 2013 through June 30, 2014, and must be submitted by October 1, 2016. The sediment monitoring specified below may also be required if the San Diego Water Board determines that 1) the effluent does not at all times comply with Effluent Limitations and Performance Goals at section IV.A of this Order or 2) the receiving water limitations section V.A of this Order are not being consistently achieved. Benthic monitoring shall be conducted at all off shore monitoring stations.

1. Sediment Characteristics. Analyses shall be performed on the upper 2 inches of core.

Table E-13. Sediment Monitoring Requirements

Determination	Units	Type of Sample	Minimum Frequency
Sulfides	mg/kg	Core	2/Year
Total Chlorinated Hydrocarbons	mg/kg	Core	2/Year
BOD ₅	mg/kg	Core	2/Year
Chemical Oxygen Demand	mg/kg	Core	2/Year
Particle Size Distribution	mg/kg	Core	2/Year
Arsenic	mg/kg	Core	1/Year
Cadmium	mg/kg	Core	1/Year
Total Chromium	mg/kg	Core	1/Year
Copper	mg/kg	Core	1/Year
Lead	mg/kg	Core	1/Year
Mercury	mg/kg	Core	1/Year
Nickel	mg/kg	Core	1/Year
Silver	mg/kg	Core	1/Year
Zinc	mg/kg	Core	1/Year
Cyanide	mg/kg	Core	1/Year
Phenolic Compounds (non-chlorinated)	mg/kg	Core	1/Year
Chlorinated Phenolics	mg/kg	Core	1/Year
Aldrin and Dieldrin	mg/kg	Core	1/Year
Chlordane and Related Compounds	mg/kg	Core	1/Year
DDT and Derivatives	mg/kg	Core	1/Year
Endrin	mg/kg	Core	1/Year
НСН	mg/kg	Core	1/Year
PCBs	mg/kg	Core	1/Year
Toxaphene	mg/kg	Core	1/Year
Radioactivity	pCi/kg	Core	1/Year

2. Infauna. Unless authorized by the San Diego Water Board to use an alternative method, samples shall be collected with a Paterson, Smith-McIntyre, or orange-peel type dredge, having an open sampling area of not less than 124 square inches and a sediment capacity of not less than 210 cubic inches. The sediment shall be sifted through a 1-millimeter mesh screen and all organisms shall be identified to as low a taxon as possible.

Table E-14. Infauna Monitoring Requirements

Determination	Units	Sample Type	Minimum Frequency
Benthic Biota	Identification and enumeration	3 Grabs	2/Year

IX. OTHER MONITORING REQUIREMENTS

A. Kelp Bed Canopy

The Discharger shall participate with other ocean dischargers in the San Diego Region in an annual regional kelp bed photographic survey. Kelp beds shall be monitored annually by means of vertical aerial infrared photography to determine the maximum aerial extent of the region's coastal kelp beds within the calendar year. Surveys shall be conducted as close as possible to the time when kelp bed canopies cover the greatest area. The entire San Diego Region coastline, from the international boundary to the San Diego Region/Santa Ana Region boundary shall be photographed on the same day.

The images produced by the surveys shall be presented in the form of 1:24,000 scale photomosaic of the entire San Diego Region coastline. Onshore reference points, locations of all ocean outfalls and diffusers, and the 30-foot mean lower low water (MLLW) and 60-foot (MLLW) depth contours shall be shown.

The aerial extent of the various kelp beds photographed in each survey shall be compared to that noted in surveys of previous years. Any significant losses which persist for more than one year shall be investigated by divers to determine the probable reason for the loss.

B. Regional Monitoring

The Discharger shall, as directed by the San Diego Water Board, participate with other regulated entities, other interested parties, and the San Diego Water Board in development, refinement, implementation, and coordination of regional monitoring and assessment programs to:

- 1. Determine the status and trends of conditions in ocean waters with regard to beneficial uses, e.g.
 - a. Are fish and shellfish safe to eat?
 - b. Is water quality safe for swimming?
 - c. Are ecosystems healthy?
- 2. Identify the stressors causing / contributing to conditions of concern;
- 3. Identify the sources of the stressors causing / contributing to conditions of concern; and
- 4. Evaluate the effectiveness (i.e., environmental outcomes) of actions taken to address such stressors and sources.

C. Solids Monitoring

The Discharger shall report, annually, the volume of screenings, sludge [biosolids], grit, and other solids generated and/or removed during wastewater treatment and the locations where these waste materials are placed for disposal. Copies of all annual reports required by 40 CFR Part 503 shall be submitted to the San Diego Water Board at the same time they are submitted to the USEPA.

X. REPORTING REQUIREMENTS

A. General Monitoring and Reporting Requirements

1. The Discharger shall comply with all Standard Provisions (Attachment D of this Order) related to monitoring, reporting, and recordkeeping.

- **2.** Reports of marine monitoring surveys conducted to meet receiving water monitoring requirements of this MRP shall include, as a minimum, the following information:
 - **a.** A description of climatic and receiving water characteristics at the time of sampling (weather observations, floating debris, discoloration, wind speed and direction, swell or wave action, time of sampling, tide height, etc.)
 - **b.** A description of sampling stations, including differences unique to each station (e.g., station location, sediment grain size, distribution of bottom sediments, rocks, shell litter, calcareous worm tubes, etc.).
 - **c.** A description of the sample collection and preservation procedures used in the survey.
 - **d.** A description of the specific method used for laboratory analysis.
 - **e.** An in-depth discussion of the results of the survey. All tabulations and computations shall be explained.
 - **f.** Annual reports will include detailed statistical analyses of all data. Methods may include, but are not limited to, various multivariate analyses such as cluster analysis, ordination, and regression. The Discharger should also conduct additional analyses, as appropriate, to elucidate temporal and spatial trends in the data.
- **3.** The Discharger shall report all instances of noncompliance not reported under Attachment D, Sections V.E, V.G, and V.H, of this Order at the time monitoring reports are submitted.
- **4.** By March 1 of each year, the Discharger shall submit an annual report to the San Diego Water Board and USEPA Region 9 that contains tabular and graphical summaries of the monitoring data obtained during the previous year. The Discharger shall discuss the compliance record and corrective actions taken, or which may be taken, or which may be needed to bring the discharge into full compliance with the requirements of this Order and this MRP.

B. Self Monitoring Reports (SMRs)

- 1. The Discharger shall electronically submit Self-Monitoring Reports (SMRs) using the State Water Board's California Integrated Water Quality System (CIWQS) Program Web site (http://www.waterboards.ca.gov/ciwqs/index.html). The CIWQS Web site will provide additional directions for SMR submittal in the event there will be service interruption for electronic submittal.
- 2. The Discharger shall report in the SMR the results for all monitoring specified in this MRP under sections III through IX. The Discharger shall submit SMRs including the results of all required monitoring using USEPA-approved test methods or other test methods specified in this Order. If the Discharger monitors any pollutant more frequently than required by this Order, the results of this monitoring shall be included in the calculations and reporting of the data submitted in the SMR.
- **3.** Unless otherwise noted in the MRP, monitoring periods and reporting for all required monitoring shall be completed according to the following schedule:

Table E-15. Monitoring Periods and Reporting Schedule

Table E-15. Monitoring Periods and Reporting Schedule					
Sampling Frequency	Monitoring Period Begins	Monitoring Period	SMR Due Date		
Continuous	First day of the calendar month following the permit effective date or on permit effective date if that date is first day of the month.	All	First day of second calendar month following month of sampling.		
1/Day	First day of the calendar month following the permit effective date or on permit effective date if that date is first day of the month.	(Midnight through 11:59 PM) or any 24-hour period that reasonably represents a calendar day for purposes of sampling.	First day of second calendar month following month of sampling.		
1/Week	First Sunday of the calendar month following the permit effective date or on permit effective date if on a Sunday.	Sunday through Saturday	First day of second calendar month following month of sampling.		
1/Month	First day of calendar month following permit effective date or on permit effective date if that date is first day of the month.	First day of calendar month through last day of calendar month	First day of second calendar month following month of sampling.		
1/Quarter	Closest of January 1, April 1, July 1, or October 1 following (or on) permit effective date.	January 1 through March 31 April 1 through June 30 July 1 through September 30 October 1 through December 31	May 1 August 1 November 1 February 1		
2/Year	Closest of January 1 or July 1 following (or on) permit effective date.	January 1 through June 30 July 1 through December 31	September 1 March 1		
Significant Industrial User Compliance Status Report	Closest of January 1 or July 1 following (or on) permit effective date.	January 1 through June 30 July 1 through December 31	September 1 March 1		
1/Year Pretreatment Program Biosolids Report	January 1 following (or on) permit effective date.	January 1 through December 31	March 1 (Biosolids Report – February 19)		
Intensive Monitoring	July 1, 2013	June 30, 2014	October 1, 2016		

4. Reporting Protocols. The Discharger shall report with each sample result the applicable reported Minimum Level (ML) and the current Method Detection Limit (MDL), as determined by the procedure in 40 CFR Part 136. For each numeric effluent limitation or performance goal for a parameter identified in Table B of the Ocean Plan, the Discharger shall not use a ML greater than that specified in Appendix II of the Ocean Plan.

The Discharger shall report the results of analytical determinations for the presence of chemical constituents in a sample using the following reporting protocols:

- **a.** Sample results greater than or equal to the reported ML shall be reported as measured by the laboratory (i.e., the measured chemical concentration in the sample).
- **b.** Sample results less than the ML, but greater than or equal to the laboratory's MDL, shall be reported as "Detected, but Not Quantified," or DNQ. The estimated chemical concentration of the sample shall also be reported.

For the purposes of data collection, the laboratory shall write the estimated chemical concentration next to DNQ as well as the words "Estimated Concentration" (may be shortened to "Est. Conc."). The laboratory may, if such information is available, include numerical estimates of the data quality for the reported result. Numerical estimates of data quality may be percent accuracy (+ a percentage of the reported value), numerical ranges (low to high), or any other means considered appropriate by the laboratory.

- **c.** Sample results less than the laboratory's MDL shall be reported as "Not Detected," or ND.
- d. Dischargers are to instruct laboratories to establish calibration standards so that the ML value (or its equivalent if there is differential treatment of samples relative to calibration standards) is the lowest calibration standard. At no time is the Discharger to use analytical data derived from extrapolation beyond the lowest point of the calibration curve.
- 5. Compliance Determination. Compliance with effluent limitations for reportable pollutants shall be determined using sample reporting protocols defined above and Attachment A of this Order. For purposes of reporting and administrative enforcement by the San Diego Water Board and State Water Board, the Discharger shall be deemed out of compliance with effluent limitations if the concentration of the reportable pollutant in the monitoring sample is greater than the effluent limitation and greater than or equal to the reported ML.
- 6. Multiple Sample Data. When determining compliance with a measure of central tendency (arithmetic mean, geometric mean, median, etc.) of multiple sample analyses and the data set contains one or more reported determinations of DNQ or ND, the Discharger shall compute the median in place of the arithmetic mean in accordance with the following procedure:
 - **a.** The data set shall be ranked from low to high, ranking the reported ND determinations lowest, DNQ determinations next, followed by quantified values (if any). The order of the individual ND or DNQ determinations is unimportant.
 - **b.** The median value of the data set shall be determined. If the data set has an odd number of data points, then the median is the middle value. If the data set has an even number of data points, then the median is the average of the two values around the middle unless one or both of the points are ND or DNQ, in which case the median value shall be the lower of the two data points where DNQ is lower than a value and ND is lower than DNQ.

- 7. The Discharger shall submit SMRs in accordance with the following requirements:
 - a. The Discharger shall arrange all reported data in a tabular format. The data shall be summarized to clearly illustrate whether the facility is operating in compliance with interim and/or final effluent limitations. The Discharger is not required to duplicate the submittal of data that is entered in a tabular format within CIWQS. When CIWQS does not provide for entry into a tabular format within the system, the Discharger shall electronically submit the data in a tabular format as an attachment.
 - **b.** The Discharger shall attach a cover letter to the SMR.
 - **c.** The Discharger clearly identify violations of the waste discharge requirements; discuss corrective actions taken or planned; and the proposed time schedule for corrective actions within CIWQS. Identified violations must include a description of the requirement that was violated and a description of the violation.

C. Discharge Monitoring Reports (DMRs)

- 1. At any time during the term of this permit, the State or San Diego Water Board may notify the Discharger to electronically submit SMRs that will satisfy federal requirements for submittal of Discharge Monitoring Reports (DMRs). Until such notification is given, the Discharger shall submit DMRs in accordance with the requirements described below.
- 2. DMRs must be signed and certified as required by the standard provisions (Attachment D). The Discharger shall submit the original DMR and one copy of the DMR to the address listed below:

STANDARD MAIL	FEDEX/UPS/ OTHER PRIVATE CARRIERS	
State Water Resources Control Board	State Water Resources Control Board	
Division of Water Quality	Division of Water Quality	
c/o DMR Processing Center	c/o DMR Processing Center	
PO Box 100	1001 I Street, 15 th Floor	
Sacramento, CA 95812-1000	Sacramento, CA 95814	

3. All discharge monitoring results must be reported on the official USEPA pre-printed DMR forms (EPA Form 3320-1). Forms that are self-generated will not be accepted unless they follow the exact same format of USEPA Form 3320-1.

D. Other Reports

1. The Discharger shall report the results of any chronic toxicity testing, TRE/TIE, Aliso Creek Ocean Outfall Capacity Study, Treatment Plant Capacity Report (if needed), Sludge Disposal Report, Significant Industrial User Compliance Status Report, Intensive Monitoring, and Pretreatment Report, as required by Special Provisions – VI.C. of this Order. The Discharger shall submit reports with the first monthly SMR scheduled to be submitted on or immediately following the report due date.

ATTACHMENT F - FACT SHEET

Table of Contents

I.	Permit Information	<u>F-4</u> F-3
II.	Facility Description	F-6 <mark>F-5</mark>
	A. Description of Wastewater and Biosolids Treatment or Controls	<u>F-6</u> F-5
	B. Discharge Points and Receiving Waters	<u>F-9F-8F-9</u>
	C. Summary of Existing Requirements and Self-Monitoring Report (SMR)	Data <u>F-10</u> F-9
	D. Compliance Summary	
	E. Planned Changes	
III.	Applicable Plans, Policies, and Regulations	F-18F-17F-18
	A. Legal Authorities	F-18F-17F-18
	B. California Environmental Quality Act (CEQA)	F-18F-17F-18
	C. State and Federal Regulations, Policies, and Plans	
	D. Impaired Water Bodies on CWA 303(d) List	
	E. Other Plans, Policies and Regulations	
IV.	Rationale For Effluent Limitations and Discharge Specifications	
	A. Discharge Prohibitions	F-20F-19F-20
	B. Technology-Based Effluent Limitations (TBELs)	F-21F-20F-21
	C. Water Quality-Based Effluent Limitations (WQBELs)	
	1. Scope and Authority	F-23F-22F-23
	2. Applicable Beneficial Uses and Water Quality Criteria and Objective	s <u>F-24F-23</u> F-24
	Determining the need for WQBELs	F-24F-23F-24
	4. WQBEL Calculations	
	5. Whole Effluent Toxicity (WET)	F-31F-30F-31
	D. Final Effluent Limitations	
	Satisfaction of Anti-Backsliding Requirements	F-35F-34F-35
	2. Satisfaction of Antidegradation Policy	F-36F-35F-36
	3. Stringency of Requirements for Individual Pollutants	F-37F-36F-37
	E. Performance Goals	
	F. Interim Effluent Limitations – Not Applicable	F-42F-41F-42
	G. Land Discharge Specifications – Not Applicable	F-42F-41F-42
	H. Reclamation Specifications	
٧.	Rationale for Receiving Water Limitations	<u>F-43</u> F-42
VI.	Rationale for Monitoring and Reporting Requirements	<u>F-44F-43</u> F-44
	A. Influent Monitoring	<u>F-44F-43</u> F-44
	B. Effluent Monitoring	<u>F-44F-43</u> F-44
	C. Whole Effluent Toxicity Testing Requirements	<u>F-45F-44</u> F-45
	D. Receiving Water Monitoring	<u>F-45F-44</u> F-45
	E. Other Monitoring Requirements	F-46F-45F-46
VII.	Rationale for Provisions	F-47F-46F-47
	A. Standard Provisions	<u>F-47F-46</u> F-47
	B. Special Provisions	<u>F-47F-46</u> F-47
	1. Reopener Provisions	
	2. Special Studies and Additional Monitoring Requirements	F-47 F-46F-47

	Best Management Practices and Pollution Prevention – Not App 18	olicable <u>F-48F-47F-</u>
4. (Construction, Operation, and Maintenance Specifications – Not	Applicable <u>F-48F-</u>
-	1 <mark>7F-48</mark>	E 40E 47E 40
	Special Provisions for Wastewater Facilities	
	Other Special Provisions – Not Applicable	
	Compliance Schedules – Not Applicable	
	Participation	
	tification of Interested Parties	
	itten Comments	
C. Pul	olic Hearing	<u>F-31F-3UF-32</u>
	ste Discharge Requirements Petitions	
	ormation and Copying	
	gister of Interested Persons	· · · · · · · · · · · · · · · · · · ·
G. Au	ditional Information	<u>Г-ЭZГ-Э I</u> Г-ЭЭ
	List of Tables	
Table F-1.	Facility Information	F-4 F-3
Table F-2.	ACOO Land Outfall Connections	
Table F-3.	Effluent Flows Discharging to the ACOO	F-9 F-8F-9
Table F-4.	Historic Effluent Limitations and Monitoring Data at M-001 (AC	
Table F-5.	Historic Effluent Limitations and Monitoring Data at M-001A (S	
	10 F-9F-10	,
Table F-6.	Historic Effluent Limitations and Monitoring Data at M-001B (S	SOCWA CTP) <mark>F-</mark>
	11 F-10 F-11	,
Table F-7.	Historic Effluent Limitations and Monitoring Data at M-001C (L	os Alisos WRP). F-
	<u>11F-10</u> F-11	,
Table F-9.	Historic Effluent Limitations and Monitoring Data at M-001E (II	DP PWTS) <u>F-12F-</u>
	<u>11</u> F-12	
Table F-11.	Basin Plan Beneficial Uses	<u>F-18F-17F-18</u>
Table F-12.	Ocean Plan Beneficial Uses	<u>F-19F-18</u> F-19
Table F-13.	Summary of Technology-Based Effluent Limitations Based on	Secondary
	Treatment Standards	<u>F-22F-21F-22</u>
Table F-14.	Summary of Technology-Based Effluent Limitations Based on	Table A of the
	Ocean Plan	
Table F-15.	RPA Results Summary	
Table F-16.	Pollutants Having Background Concentrations	<u>F-30F-29</u> F-30
Table F-17.	Example Parameter Water Quality Objectives	
Table F-18.	Summary of Water Quality-based Effluent Limitations	<u>F-31F-30F-31</u>
Table F-19.	Technology-based Effluent Limitations for SOCWA RTP (M-00	01A). <u>F-32F-31F-32</u>
Table F-20.	Technology-based Effluent Limitations for SOCWA CTP (M-00	01B). <u>F-32F-31F-32</u>
Table F-21.	Technology-based Effluent Limitations for Los Alisos WRP (M	-001C). F-33F-32F-
	33	
Table F-22.	Technology-based Effluent Limitations for El Toro WRP (M-00	
Table F-23.	Technology-based Effluent Limitations for the IDP PWTS (M-0	
Table F-24.		

Table F-25.	Technology-based Effluent Limitations for the SCWD ACWHP (M-001G) F-34F-
Table E 26	33F-34 Effluent Limitations for Combined Flow, Based on Table B of the Ocean Plan at
Table F-20.	M-001 F-35F-34F-35
Table F-27.	Performance Goals Based on the Ocean Plan

ATTACHMENT F - FACT SHEET

As described in section II of this Order, this Fact Sheet includes the legal requirements and technical rationale that serve as the basis for the requirements of this Order.

This Order has been prepared under a standardized format to accommodate a broad range of discharge requirements for Dischargers in California. Only those sections or subsections of this Order that are specifically identified as "not applicable" have been determined not to apply to this Discharger. Sections or subsections of this Order not specifically identified as "not applicable" are fully applicable to this Discharger.

I. PERMIT INFORMATION

The following table summarizes administrative information related to the Facility.

Table F-1. Facility Information

WDID	9 0000001117				
Discharger	South Orange County Wastewater Authority (SOCWA)				
Name of Facility	Aliso Creek Ocean Outfall				
	SOCWA Regional Treatment Plant	29201 La Paz Road Laguna Niguel, CA 92677 Orange County			
	SOCWA Coastal Treatment Plant	28303 Alicia Parkway Laguna Niguel, CA 92677 Orange County			
	Irvine Ranch Water District Los Alisos Water Reclamation Plant	22312 Muirlands Boulevard Lake Forest, CA 92630 Orange County			
Facility Address	El Toro Water District Water Reclamation Plant	23542 Moulton Parkway Laguna Woods, CA 92637 Orange County			
	Irvine Desalter Project Potable Water Treatment System	26 Waterworks Way Irvine, CA 92618 Orange County			
	Irvine Desalter Project Shallow Groundwater Unit	7000 Marine Way Irvine, CA 92620 Orange County			
	South Coast Water District Aliso Creek Water Harvesting Project	28303 Alicia Parkway Laguna Niguel, CA 92677 Orange County			
Facility Contact, Title and Phone	Tom Rosales, General Manager, 94	9-234-5421			
Authorized Person to Sign and Submit Reports	Tom Rosales, General Manager				
Mailing Address	34156 Del Obispo Street Dana Point, CA 92629				
Billing Address	Same as Mailing Address				
Type of Facility	Combined ocean outfall				
Major or Minor Facility	Major				
Threat to Water Quality	1				

Complexity	A		
Pretreatment Program	Yes		
Reclamation Requirements	Producer and Distributor (regulated under separate waste discharge requirements (WDRs))		
requirements (WDRs)) SOCWA Regional Treatment Plant – 12.0 million gallons per (MGD) SOCWA Coastal Treatment Plant – 6.7 MGD Irvine Ranch Water District Los Alisos Water Reclamation For 7.5 MGD El Toro Water District Water Reclamation Plant – 6.0 MGD Irvine Desalter Project Potable Water Treatment System – Irvine Desalter Project Shallow Groundwater Unit – 0.85 Million South Coast Water District Aliso Creek Water Harvesting P			
Facility Design Flow	Ocean outfall: 50 MGD		
Watershed	Pacific Ocean		
Receiving Water	Pacific Ocean		
Receiving Water Type	Ocean		

- A. SOCWA (hereinafter Discharger) is a joint powers authority formed to reduce duplication and provide operational efficiency through consolidation. SOCWA is the legal successor to the Aliso Water Management Agency, the South East Regional Reclamation Authority, and the South Orange County Reclamation Authority. SOCWA is comprised of 10 member agencies including the City of Laguna Beach, the City of San Clemente, the City of San Juan Capistrano, El Toro Water District (ETWD), Emerald Bay Service District, Irvine Ranch Water District (IRWD), Moulton Niguel Water District (MNWD), Santa Margarita Water District (SMWD), South Coast Water District (SCWD) and Trabuco Canyon Water District.
- **B.** For the purposes of this Order, references to the "discharger" or "permittee" in applicable federal and State laws, regulations, plans, or policy are held to be equivalent to references to the Discharger herein.
- C. SOCWA operates the Aliso Creek Ocean Outfall (ACOO), which receives treated effluent from the following municipal wastewater treatment plants; the SOCWA Regional Treatment Plant (RTP), the SOCWA Coastal Treatment Plant (CTP), the IRWD Los Alisos Water Reclamation Plant (Los Alisos WRP), and the ETWD Water Reclamation Plant (El Toro WRP). Non-potable treated groundwater and brine discharges from the Irvine Desalter Project (IDP) are also routed to the ACOO. Finally, SCWD will discharge brine from the Aliso Creek Water Harvesting Project (ACWHP), a system designed to capture and reuse urban runoff. All the discharges to the ACOO are collectively referred to as the Facilities.
- **D.** The Discharger discharges effluent from a variety of sources through the ACOO to the Pacific Ocean, a water of the United States, and is currently regulated by Order No. 2006-0055, which was adopted on August 16, 2006 and expired on October 1, 2011. In accordance with section 122.6, title 40 of the Code of Federal Regulations (40 CFR 122.6), the terms of the existing Order automatically continued in effect after the permit expiration date.
- **E.** The Discharger filed a Report of Waste Discharge (ROWD) and submitted an application for reissuance of its WDRs and National Pollutant Discharge Elimination System (NPDES) permit on March 31, 2011.

II. FACILITY DESCRIPTION

A. Description of Wastewater and Biosolids Treatment or Controls

The following describes each of the facilities that discharge to the ACOO.

1. SOCWA Regional Treatment Plant

The SOCWA RTP, located at 29201 La Paz Road, Laguna Niguel, is owned by SOCWA and treats raw wastewater generated in the MNWD service area. Wastewater treatment unit operations and processes are screening, aerated grit removal, primary sedimentation, activated sludge aeration, and secondary clarification. A portion of the secondary effluent is reclaimed for irrigation and receives tertiary treatment by chemical addition, coagulation, filtration, and chlorine disinfection. The capacity of the existing tertiary treatment facility is 11.4 MGD. The California Regional Water Quality Control Board, San Diego Region's (San Diego Water Board's) Order No. 97-52 establishes reclamation requirements for the reuse of effluent from the SOCWA RTP in the San Diego Region. The SOCWA RTP treats solids produced by the SOCWA RTP, raw solids trucked to the plant from the El Toro WRP, and raw solids transported by force main from the SOCWA CTP. Solids treatment consists of dissolved air flotation thickening, anaerobic digestion, and centrifuge dewatering. Dewatered biosolids are removed from the facility by a private contractor and are either sent to a composting facility in Kern County, California or La Paz County, Arizona. Screenings and grit are transported by a private contractor to a sanitary landfill in Simi Valley.

2. SOCWA Coastal Treatment Plant

The SOCWA CTP, located at 28303 Alicia Parkway, Laguna Niguel, is owned and operated by SOCWA and treats raw wastewater generated in the SCWD, the City of Laguna Beach, and the Emerald Bay Services District. Wastewater treatment and unit operations and processes are screening, aerated grit removal, primary clarification, activated sludge aeration, and secondary clarification. A portion of the secondary effluent is reclaimed for irrigation and receives tertiary treatment by chemical addition, coagulation, filtration, and chlorine disinfection. The capacity of the existing tertiary treatment facility is 4.2 MGD. The San Diego Water Board's Order No. 97-52 establishes reclamation requirements for the reuse of effluent from the SOCWA CTP in the San Diego Region. Primary sludge and thickened waste activated sludge are combined and pumped through a force main to the SOCWA RTP for treatment and disposal. Screenings and grit are transported by a private contractor to a sanitary landfill in Simi Valley.

The SOCWA CTP also receives nuisance dry weather runoff flows diverted to the sanitary sewer system by the City of Laguna Beach during the summer period (Memorial Day through the end of September). To improve downstream receiving water quality, urban runoff flows of up to 0.235 MGD are diverted to the sewer from approximately 15 sites.

3. IRWD Los Alisos Water Reclamation Plant

IRWD Los Alisos Water Recycling Plant. The Los Alisos WRP, located at 22312 Muirlands Boulevard in Lake Forest, is owned and operated by the IRWD and treats raw wastewater generated within the IRWD service area. Secondary treatment capacity at the Los Alisos WRP is 7.5 mgd. Secondary treatment unit operation and processes include screening and aerated lagoons. Dewatered biosolids are trucked to a composting facility in La Paz County,

Arizona. Screenings and grit from the plant influent are hauled to a Class I Landfill. A portion of the Los Alisos WRP secondary effluent is reclaimed for irrigation and receives tertiary treatment by chemical addition, flash mixing, coagulation, flocculation, sedimentation, filtration, and chlorine disinfection. The capacity of the Los Alisos WRP tertiary treatment facility is 5.5 mgd. Santa Ana Regional Water Quality Control Board Order No. 94-03 establishes reclamation requirements for the reuse of effluent from the Los Alisos WRP within the Santa Ana Region. San Diego Regional Board Order No. 97-52 establishes reclamation requirements for the reuse of effluent from the Los Alisos WRP in the San Diego Region. The Los Alisos WRP tertiary treatment facility is operated seasonally to meet higher summer-time demands for recycled water in the Lake Forest area. During periods of lower demand, tertiary treated effluent from the Michelson Water Recycling Plant in Irvine is pumped to the Irvine Zone B recycled water system and supplied to the wet well of the Los Alisos WRP recycled water pump station. From the wet-well, the recycled water can be: (1) Pumped to the Lake Forest Zone A recycled water system for irrigation purposes; or (2) Gravity fed into the final series of treatment ponds, blended with secondary treated water in the pond, and pumped to ocean outfall via the SOCWA effluent pump station.

4. El Toro Water District Water Reclamation Plant

The El Toro WRP, located at 23542 Moulton Parkway, Laguna Hills, is owned by El Toro Water District and treats raw wastewater generated in the El Toro Water District service area. Wastewater treatment unit operations and processes are coarse screening, aerated grit removal, fine screening, activated sludge aeration, and secondary clarification. A portion of the secondary effluent is reclaimed for irrigation and receives filtering and chlorine disinfection. The Santa Ana Regional Water Board Order No. 94-03 establishes reclamation requirements for the reuse of effluent form the El Toro WRP in the Santa Ana Region. The San Diego Water Board's Order No. 97-52 establishes reclamation requirements for the reuse of effluent form the El Toro WRP in the San Diego Region. Waste activated sludge is thickened using dissolved air floatation and then trucked to the SOCWA RTP for treatment and disposal. Screenings and grit are transported by a private contractor to a sanitary landfill in Simi Valley.

5. Irvine Desalter Project

The IDP is a multifaceted project operated by IRWD. The IDP includes a Potable Water Treatment System (PWTS) that generates residual brine, and a Shallow Groundwater Unit (SGU) that treats contaminated groundwater.

The IDP PWTS is located approximately 4 miles southeast of the intersection of Sand Canyon Avenue and Irvine Center Drive in Irvine, California. The potable water operations involve extracting up to 4.61 MGD of groundwater from wells upgradient of the contaminated groundwater plume in Irvine, California. Groundwater treatment includes the addition of sulfuric acid and a threshold inhibitor; cartridge filters; reverse osmosis (RO); the addition of sodium hypochlorite (bleach); a decarbonator; and the addition of sodium hydroxide (caustic soda), bleach, and aqueous ammonia. The product water is distributed as potable water. Periodically, the RO membranes are taken off-line and cleaned and all cleaning solution is discharged to sewer. The IDP PWTS generates up to 1.0 MGD of RO concentrate, or brine, which is discharged to the ACOO.

The IDP SGU treats groundwater extracted from wells located either within or near a plume of groundwater contaminated by volatile organic compounds (VOC) on or near the former

Marine Corps Air Station El Toro. The primary VOC of concern in the groundwater is trichloroethylene (TCE). As part of this operation, approximately 0.85 MGD of contaminated groundwater from extraction wells is treated using air stripping to remove VOCs and then discharged to the ACOO. The IDP SGU operations addressed in Order No. R9-2006-0055 were based on the presumption that treated SGU groundwater would be discharged to the ACOO only during conditions in which extracted groundwater flows exceeded the capacity of groundwater injection facilities. Because of the uncertainty of the frequency and duration of IDP SGU discharges to the ACOO, Order No. R9-2006-0055 did not include the SGU groundwater extraction flow in the 32.86 MGD monthly average flow limit established for the ACOO. However, the IDP SGU continuously discharges to the ACOO (groundwater injection is no longer used as a means of disposing of this treated water), and SOCWA has requested and the proposed Order authorizes an increase to the ACOO monthly average flow limit include up to 0.85 MGD of treated groundwater from the IDP SGU.

6. SCWD Aliso Creek Water Harvesting Project

SCWD proposed the ACWHP as a means of capturing and reusing up to 0.8 MGD of urban runoff. As part of this project, captured urban runoff would be treated and blended into the SOCWA recycled water distribution system to supplement recycled water supplies. The ACWHP treatment is anticipated to include coarse screening, filtration, and RO treatment for salinity control. SCWD anticipates discharging up to 0.32 MGD of ACWHP RO reject brine to the ACOO. SOCWA requested and the proposed Order authorizes an increase to the ACOO monthly average flow limit to include up to 0.32 MGD of reject brine from the ACWHP.

7. Aliso Creek Ocean Outfall (ACOO)

Secondary effluent from the four wastewater treatment plants is conveyed to the ACOO via the Effluent Transmission Main. As described in Table F-2, the Effluent Transmission Main consists of five reaches (A through E) and the on-shore portion of the ACOO.

Table F-2. ACOO Land Outfall Connections

Table 1-2. A000 Land Odiran Connections						
ACOO Land Outfall Reach	Pipeline Capacity (MGD)	Reach Length (feet)	Municipal Treatment Plants Discharging to the Land Outfall Reach	Rated Capacity of Upstream Plants ¹		
Reach A	7.5	11,904	Los Alisos WRP	7.5		
Reach B	15	4,012	Los Aliso WRP	7.5		
Reach C	15	3,654	Los Aliso WRP El Toro WRP	13.5 ²		
Reach D	20	6,860	Los Aliso WRP El Toro WRP	13.5 ²		
Reach E	34.4	17,210	Los Aliso WRP El Toro WRP SOCWA RTP	25.5 ³		
Onshore Portion of ACOO	50	5,405	Los Aliso WRP EI Toro WRP SOCWA RTP SOCWA CTP	32.2 ⁴		

Combined rated capacity of SOCWA or member agency wastewater treatment plants that contribute flow to the listed land outfall reach.

² Includes the 6.0 MGD El Toro WRP and the 7.5 MGD Los Alisos WRP.

³ Includes the 6.0 MGD EI Toro WRP, the 7.5 MGD Los Alisos WRP, and the 12 MGD SOCWA RTP.

Includes the 6.0 MGD EI Toro WRP, the 7.5 MGD Los Alisos WRP, the 12 MGD SOCWA RTP, and the 6.7 MGD SOCWA CTP.

A summary of the flows from the municipal wastewater treatment plants, as reported in the ROWD, is provided in the table below. These facilities discharge wastes, or have the potential to discharge wastes, to the Pacific Ocean through the ACOO, and, as such, are subject to the requirements of Order No. R9-2012-0013.

Table F-3. Effluent Flows Discharging to the ACOO

Treatment Facility	Nature of Discharge	Existing Treatment Design Capacity (MGD)
SOCWA RTP	Secondary Effluent	12.0
SOCWA CTP	Secondary Effluent	6.7
Los Alisos WRP	Secondary Effluent	7.5
El Toro WRP	Secondary Effluent	6.0
IDP PWTS	Treated Contaminated Groundwater	1.0
IDP SGU	Waste Brine	0.85
SCWD ACWHP	Waste Brine	0.32
Total		34.37

B. Discharge Points and Receiving Waters

The ACOO has been in use since 1979. The outfall extends 7,900 feet offshore in a southwesterly direction from the mouth of Aliso Creek. The inshore end of the diffuser is located approximately 6,700 feet offshore at a depth of approximately 170 feet. The diffuser, which is collinear with the rest of the outfall, is approximately 1,200 feet long and extends to a maximum depth of 195 feet. The terminus of the diffuser is located at Latitude 33°29'53" N and Longitude 117°46'16" W.

The design capacity of the ACOO is 50 MGD. In the previous Order, the Discharger was subject to a flow limitation of 32.86 MGD. As reported in the ROWD, the average flow rate discharging through the ACOO was 12.75 MGD in 2009 and 16.48 MGD in 2010; the maximum flow reported between 2007 and 2010 was 33.9 MGD.

The San Diego Water Board determined the minimum initial dilution factor to be 237 for the discharge of up to 34.37 MGD of effluent through the ACOO using the U.S. Environmental Protection Act (USEPA) -approved computer modeling package Visual Plumes with the UM3 model. The computer modeling was performed based on characteristics of the ACOO, the effluent, and the receiving water, subject to the input limitations of Visual Plumes. The flow rate used in the computer modeling is 34.37 MGD, which allows for brine from the IDP SGU and the anticipated SCWD ACWHP. Initial dilution (Dm) factors were determined for each month during the period July 2008 through June 2009 using receiving water characteristics for each month provided by the Discharger; the minimum initial dilution factor was determined using the March 2009 receiving water data. Section IV.C of this Fact Sheet includes additional discussion on initial dilution. Additional details of the initial dilution computer modeling performed are provided in Attachment H and in the San Diego Water Board records.

C. Summary of Existing Requirements and Self-Monitoring Report (SMR) Data

Effluent limitations contained in Order No. 2006-0055 for major constituents and properties of wastewater for discharges from the ACOO, and representative monitoring data for January 2007 through December 2010 (unless otherwise noted) are provided in the tables below.

Table F-4. Historic Effluent Limitations and Monitoring Data at M-001 (ACOO)

Parameter	Units	Effluent Limitation ¹		tion ¹	Monitoring Data (January 2007 – December 2010)	
		Average Monthly	Average Weekly	Maximum Daily	Mean Maximum	
Flow	MGD			32.86	14.28	33.9
Chronic Toxicity ⁴	TUc			261	89 ²	> 1,000
TCDD Equivalents	μg/L	1.02E-06			9.98E-07 ³	9.10E-08
	lbs/day	2.79E-07			4.9E-08	< 2E-07

Concentration limits are based on Ocean Plan objectives using a dilution ratio of 260 parts of seawater to 1 part effluent.

January 2009 to December 2010 monthly data. Results below detection are assumed as ½ the detection limit for

calculation purposes. Value greater than 1,000 estimated as 1,000 in average.

Table F-5. Historic Effluent Limitations and Monitoring Data at M-001A (SOCWA RTP)

Parameter	Units	Effluent Limitation			Monitoring Data (January 2007 – December 2010)	
		Average Monthly	Average Weekly	Maximum Daily	Mean	Maximum
Flow	MGD				3.60	14.91
Total Suspended	mg/L	30	45		6.2	30.6
Solids (TSS)	% removal I ne average			ge monthly percent removal t be less than 85 percent		81.8 ¹
Carbonaceous	mg/L	25	40		4.7	24
Biochemical Oxygen Demand (5-day @ 20°C) (CBOD ₅)	% removal		The average monthly percent removal shall not be less than 85 percent			89.2 ¹
Turbidity	NTU	75	100	225 ³	3.13	14.0
рН	Standard Units			$6.0^4 - 9.0^3$	7.4	$6.9 - 7.8^2$
Settleable Solids (SS)	ml/L	1.0	1.5	3.0 ³	0.11	1.0
Oil and Grease	mg/L	25	40	75 ³	1.9	2.0

Minimum value.

Results below detection are assumed as ½ the detection limit for calculation purposes. Detection limit for July 2009 not available and not included in calculation.

Chronic toxicity expressed as Chronic Toxicity Units (TUc) = 100/NOEL, where NOEL (No Observed Effect Level) is expressed as the maximum percent effluent or receiving water that causes no observable effect on a test organism.

Minimum and maximum range of values during 2007 through 2010 (according to the March 31, 2011 ROWD).

Instantaneous maximum.

Instantaneous minimum.

Table F-6. Historic Effluent Limitations and Monitoring Data at M-001B (SOCWA CTP)

Parameter	Units	ı	Effluent Limita	Monitoring Data (January 2007 – December 2010)		
		Average Monthly	Average Weekly	Maximum Daily	Mean	Maximum
Flow	MGD				3.04	6.75
	mg/L	30	45		7.5	63.6
TSS	% removal		age monthly pe ot be less than	97.7	87.3 ¹	
CBOD ₅	mg/L	25	40		7.5	36
	% removal		age monthly pe ot be less than	97.0	86.5 ¹	
Turbidity	NTU	75	100	225 ³	5.02	30.7
pH	Standard Units			7.0	$6.2 - 7.5^2$	
SS	ml/L	1.0	1.5	3.0^{3}	0.16	32.0
Oil and Grease	mg/L	25	40	75 ³	1.9	2.0

Minimum value.

Table F-7. Historic Effluent Limitations and Monitoring Data at M-001C (Los Alisos WRP)

Parameter	Units	ı	Effluent Limita	Monitoring Data (January 2007 – December 2010)		
		Average Monthly	Average Weekly	Maximum Daily	Mean	Maximum
Flow	MGD				3.30	7.18
	mg/L	30	45		17.8	53.9
TSS	% removal		age monthly pe ot be less than	94.2	77.0 ¹	
CBOD ₅	mg/L	25	40		9.1	28
	% removal		age monthly pe ot be less than	96.3	86.9 ¹	
Turbidity	NTU	75	100	225 ³	12.8	39.0
pH	Standard Units	$6.0^4 - 9.0^3$			7.3	$6.5 - 8.6^2$
SS	ml/L	1.0	1.5	3.0^{3}	0.11	0.50
Oil and Grease	mg/L	25	40	75 ³	5.1	10.0

¹ Minimum value.

Minimum and maximum range of values during 2007 through 2010 (according to the March 31, 2011 ROWD).

³ Instantaneous maximum.

Instantaneous minimum.

Minimum and maximum range of values during 2007 through 2010 (according to the March 31, 2011 ROWD).

³ Instantaneous maximum.

⁴ Instantaneous minimum.

Table F-8. Historic Effluent Limitations and Monitoring Data at M-001D (El Toro WRP)

Parameter	Units		Effluent Limita	Monitoring Data (January 2007 – December 2010)		
		Average Monthly	Average Weekly	Maximum Daily	Mean	Maximum
Flow	MGD				3.91	7.54
	mg/L	30	45		12.4	44.3
TSS	% removal		age monthly pe ot be less than	95.7	84.7 ¹	
CBOD ₅	mg/L	25	40		5.7	24.9
	% removal		age monthly pe ot be less than	96.9	86.8 ¹	
Turbidity	NTU	75	100	225 ³	5.85	16.0
pH	Standard Units			7.1	$6.9 - 7.5^2$	
SS	ml/L	1.0	1.5	3.0^{3}	0.10	2.5
Oil and Grease	mg/L	25	40	75 ³	4.8	5.0

Minimum value.

Table F-9. Historic Effluent Limitations and Monitoring Data at M-001E (IDP PWTS)

Parameter	Units	ı	Effluent Limita	Monitoring Data (January 2007 – December 2010)		
		Average Monthly	Average Weekly	Maximum Daily	Mean	Maximum
Flow	MGD				0.69	1.1
TSS	mg/L	60			3.2	11.4
Turbidity	NTU	75	100	225 ³	0.62	1.60
рН	Standard Units	1	1	$6.0^4 - 9.0^3$	7.6	$7.2 - 8.8^2$
SS	ml/L	1.0	1.5	3.0^{3}	< 0.1	< 0.1
Oil and Grease	mg/L	25	40	75 ³	< 4.77	< 5.0

Minimum value.

Minimum and maximum range of values during 2007 through 2010 (according to the March 31, 2011 ROWD).

Instantaneous maximum.

Instantaneous minimum.

Minimum and maximum range of values during 2007 through 2010 (according to the March 31, 2011 ROWD).

Instantaneous maximum.

Instantaneous minimum.

Table F-10.	Historic Effluent Limitations and Monitoring Data at M-001F ((IDP SGU))
	Thotomo Emacine Eminerations and mornioning Bata at in com		/

Parameter	Units	ı	Effluent Limita	Monitoring Data (January 2007 – December 2010)		
		Average Monthly	Average Weekly	Maximum Daily	Mean	Maximum
Flow	MGD				0.59	0.81
TSS	mg/L	60			2.5	8.5
Turbidity	NTU	75	100	225 ³	0.84	2.9
pH	Standard Units			$6.0^4 - 9.0^3$	7.9	$7.2 - 8.4^2$
SS	ml/L	1.0	1.5	3.0 ³	< 0.1	< 0.1
Oil and Grease	mg/L	25	40	75 ³	< 4.78	< 5.0

Minimum value

D. Compliance Summary

- 1. Compliance Evaluation Inspections (CEIs) of the SOCWA RTP were conducted on five occasions between 2007 and 2011. Compliance issues noted by inspectors were as follows::
 - **a.** On January 11, 2007:
 - i. The Discharger failed to include the flow at monitoring locations M-001E and M-001F in the facility's calculation of the combined effluent flow at the ocean outfall (M-001). The excluded flow represented less than 2 percent of the total flow at M-001.
 - **b.** On February 12, 2008:
 - **i.** A flow measurement devise was not installed at the influent to the treatment plant.
 - **ii.** Staff collected oil and grease samples in a plastic container and transferred the sample to a glass container prior to transport to a contract laboratory for analysis.
 - iii. The Facility's written procedures state that composite samples collected for Part 503 (biosolids) metals analysis are to be comprised of at least four grab samples collected every 2 hour. Records were not maintained to document when the grab samples were collected and laboratory personnel were not able to confirm that the samples submitted for analysis by the operators were composite samples.
 - **iv.** The inspector was not able to verify that pH measurements were made within the specified 15-minute holding time because the time of analysis was not recorded on the analytical work sheets.

Minimum and maximum range of values during 2007 through 2010 (according to the March 31, 2011 ROWD).

Instantaneous maximum.

Instantaneous minimum.

c. On January 14, 2009:

- i. The Facility's written procedures state that composite samples collected for Part 503 (biosolids) metals analysis are to be comprised of at least four grab samples collected every 2 hours. Records were not maintained to document when the grab samples were collected and laboratory personnel were not able to confirm that the samples submitted for analysis by the operators were composite samples.
- ii. The Facility has not submitted written reports to the San Diego Water Board indicating when the monthly average influent flow rate equaled or exceeded 75 percent of the design secondary treatment capacity. The Facility representative stated that the average treatment flow at the SOCWA RTP is 10.5 MGD. The flow rate at which the Facility's monthly average influent flow would exceed 75 percent of the design capacity of 12.0 MGD is 9.0 MGD.
- **iii.** The Discharger reported several exceedances of receiving water limitation during October and November 2008.
- **iv.** The Facility was not conducting continuous flow monitoring as specified in the Monitoring and Reporting Program.
- v. The inspector found that planned process changes will require the Facility to notify the San Diego Water Board and submit the required certification report.

d. On March 2, 2010:

- **i.** The Discharger's 2009 Annual Report was not signed and certified in accordance with permit requirements.
- ii. The November 2009 SMR provided to the inspector contained a certification statement that differed with the statement required by the permit. The December 2009 and January 2010 SMRs and the 2009 Annual Report provided to the inspector did not contain a transmittal letter or a certification statement.
- iii. The Discharger was unable to produce documentation to verify that a letter had been sent to the San Diego Water Board once the Facility's monthly average influent flow rate equals or exceeds 75 percent of the design secondary treatment capacity. The Facility's average daily treatment flow was 9.44 MGD for 2009 and the design capacity is 12.0 MGD.
- iv. The Discharger failed to correctly report CBOD results on at least three occasions during the review period (November 2009 through January 2010). In addition, the TSS laboratory worksheet contained incorrect dates on a preprinted form that resulted in a discrepancy between the form and the reported results.
- v. The Discharger reported numerous exceedances of receiving water limitations during November 2009, December 2009, and January 2010.
- vi. The Facility was not conducting continuous flow monitoring as specified in the Monitoring and Reporting Program.

e. On April 29, 2011:

- i. The on-site TSS bench sheets for the period under review provided by the Laboratory Supervisor did not include the name of the person performing the analysis.
- ii. The inspector observed that SMRs during the period of review (August 2010 through January 2011) contained a certification statement that differed with the statement required by the permit. The transmittal letter for the December 2010 Discharge Monitoring Report (DMR) contained the correct certification statement. The 2010 Annual Monitoring Report transmittal letter did not contain a certification statement.
- **iii.** The Discharger failed to document calibrating the Advanced Wastewater Treatment plant applied flow and backwash flow meters at least once per year.
- **iv.** The Discharger's on-site laboratory method for TSS is based on SM Method 2540D but was not in full compliance with the 40 CFR Part 136 approved method.
- v. The Discharger has been reporting the results of ammonia tests that were performed without the preliminary distillation (specified under 40 CFR Part 136, SM 4500-NH3) and without having comparability data demonstrating that the distillation step is unnecessary.
- vi. Based on the calibration records provided to the inspector (7/2/2009, 6/29/2010, 8/24/2010, 9/20/2010, and 2/10/11), it appears that the turbidimeter was not calibrated in accordance with the required quarterly frequency (40 CFR Part 136, EPA method 180.1).
- **vii.** The Laboratory Supervisor could not find the Quality Assurance Plan (QAP) for laboratory analysis and was not sure if the Laboratory had one.
- **viii.** The calibration procedure specified in SM 4500-H, an approved method under 40 CFR Part 136 for measuring pH, requires the use of a third buffer to verify the initial calibration. The calibration procedure utilized by the laboratory did not include the required calibration check with a third buffer.
- **2.** CEIs of the SOCWA CTP were conducted on three occasions between 2007 and 2010. Compliance issues noted by inspectors were as follows:
 - **a.** On January 11, 2007:
 - i. Neither influent flow meter was operational during the inspection.
 - **ii.** The inspector noted that the current effluent flow meter location is situated so that flow variations may create inaccurate readings.
 - **iii.** The inspector found that the effluent self-monitoring location is not located so that a representative sample may be collected.

b. On February 11, 2008:

- **i.** The Facility is designed to measure influent flow for two force mains with strap-on sonic meters. One of the influent flow meters was not operational.
- **ii.** The location of the effluent flow meter is not representative of the actual discharge to the Ocean Outfall.
- **iii.** The secondary treated effluent sampling location may not provide representative samples of the discharge to the Ocean Outfall.
- **iv.** The inspector was unable to verify that pH tests were conducted within the 15-minute holding time because neither the time of sample collection nor the time of analysis was recorded in the monitoring logbook.
- c. On January 15, 2009:
 - **i.** The Facility was not conducting continuous flow monitoring as specified in the Monitoring and Reporting Program.
 - ii. The inspector found that the location of the effluent flow meter and the effluent sampling point used are not representative of the actual discharge to the ACOO. The Facility had installed, but not used, a new magnetic flow meter and effluent sampler in appropriate locations.
 - **iii.** The inspector noted large solids in the secondary clarifier effluent and the equalization retention basin near the effluent weir box. The Facility representative stated that the solids treatment process was offline and would be back on-line within one week of the inspection.
- **d.** On March 4, 2010:
 - i. The inspector did not note any major findings.
- **3.** CEIs of the Los Alisos WRP were conducted on three occasions between 2007 and 2011. Compliance issues noted by inspectors were as follows:
 - **a.** On January 11, 2007:
 - i. The inspector did not note any major findings.
 - **b.** On February 13, 2008:
 - i. The Discharger failed to obtain sufficient composite sample volume to TSS on August 29, 2007, and pH and SS data was not obtained on August 31, 2007 due to an unexpected shutdown operations. In addition, sampling was not performed during the first two weeks in September 2007 because while discharge was not expected, discharge of secondary effluent did occur due to a valve not fully seating while the SCADA system indicated that all valves were in the fully closed position.

- **c.** On January 13, 2009:
 - i. The inspector identified that the design of the Facility's new influent pipe structure is not designed to ensure adequate flow measurement during use of the structure's bypass channel.
 - **ii.** The Discharger failed to calibrate the effluent pump magnetic flow meter at the Facility's Ocean Outfall Pumping Station at least once per year.
- **d.** On March 3, 2010:
 - **i.** The Discharger changed the sample collection for grab samples from the effluent junction box to a sample spigot that is not downstream of all in-plant flows.
 - **ii.** WET samples for Monitoring Locations M-001C (final effluent from the Los Alisos WRP) and M-001E (effluent from the IDP PWTS) are collected after plant effluents are combined and therefore do not meet the permit monitoring requirements.
- **4.** CEIs of the EI Toro WRP were conducted on three occasions between 2007 and 2010. Compliance issues noted by inspectors were as follows:
 - a. On January 10, 2007:
 - i. The Facility failed to report all BOD₅ sampling results to SOCWA for monthly reporting requirements to the San Diego Water Board.
 - **b.** On February 14, 2008:
 - **i.** The inspector did not note any major findings.
 - **c.** On January 12, 2009:
 - i. The Discharger failed to calibrate the effluent pump magnetic flow meter at the ACOO at least once per year.
 - **d.** On March 23, 2010:
 - i. The Discharger exceeded the 15 minute holding time for pH on at least four occasions in January 2010 and failed to record a pH analysis time on at least one occasion in January 2010.

E. Planned Changes

The Discharger proposed the SCWD ACWHP as a means of capturing and reusing up to 0.8 MGD of urban runoff. SCWD requested and the proposed Order authorizes discharging up to 0.32 MGD of ACWHP RO reject brine to the ACOO.

III. APPLICABLE PLANS, POLICIES, AND REGULATIONS

The requirements contained in the proposed Order are based on the requirements and authorities described in this section.

A. Legal Authorities

This Order is issued pursuant to section 402 of the federal Clean Water Act (CWA) and implementing regulations adopted by the USEPA and chapter 5.5, division 7 of the California Water Code (CWC) (commencing with section 13370). It shall serve as a NPDES permit for point source discharges from the Facilities to surface waters. This Order also serves as WDRs pursuant to article 4, chapter 4, division 7 of the CWC (commencing with section 13260).

B. California Environmental Quality Act (CEQA)

Under CWC section 13389, this action to adopt a NPDES permit is exempt from the provisions of CEQA, Public Resources Code sections 21100 through 21177.

C. State and Federal Regulations, Policies, and Plans

1. Water Quality Control Plans. The San Diego Water Board adopted a Water Quality Control Plan for the San Diego Basin (hereinafter Basin Plan) on September 8, 1994 that designates beneficial uses, establishes water quality objectives, and contains implementation programs and policies to achieve those objectives for the Pacific Ocean and other receiving waters addressed in the plan. The Basin Plan was subsequently approved by the State Water Resources Control Board (State Water Board) on December 13, 1994. Subsequent revisions to the Basin Plan have also been adopted by the San Diego Water Board and approved by the State Water Board. Beneficial uses applicable to the Pacific Ocean specified in the Basin Plan are as follows:

Table F-11. Basin Plan Beneficial Uses

Discharge Point No.	Receiving Water Name	Beneficial Use(s)
001	Pacific Ocean	Industrial service supply; navigation; contact water recreation; non-contact water recreation; commercial and sport fishing; preservation of biological habitats of special significance; wildlife habitat; rare, threatened, or endangered species; marine habitat; aquaculture; migration of aquatic organisms; spawning, reproduction, and/or early development; and shellfish harvesting.

Requirements of this Order implement the Basin Plan.

2. California Ocean Plan. The State Water Board adopted the Water Quality Control Plan for Ocean Waters of California, California Ocean Plan (Ocean Plan) in 1972 and amended it in 1978, 1983, 1988, 1990, 1997, 2000, 2005, and 2009. The State Water Board adopted the latest amendment on September 15, 2009 and it became effective on March 10, 2010. The Ocean Plan is applicable, in its entirety, to point source discharges to the ocean. The Ocean Plan identifies beneficial uses of ocean waters of the State to be protected as summarized below:

Table F-12. Ocean Plan Beneficial Uses

Discharge Point No.	Receiving Water	Beneficial Uses
001	Pacific Ocean	Industrial water supply; water contact and non-contact recreation, including aesthetic enjoyment; navigation; commercial and sport fishing; mariculture; preservation and enhancement of designated Areas of Special Biological Significance (ASBS); rare and endangered species; marine habitat; fish migration, fish spawning and shellfish harvesting.

In order to protect beneficial uses, the Ocean Plan establishes water quality objectives and a program of implementation. Requirements of this Order implement the Ocean Plan.

- 3. Alaska Rule. On March 30, 2000, USEPA revised its regulation that specifies when new and revised state and tribal water quality standards (WQS) become effective for CWA purposes (40 CFR 131.21, 65 Fed. Reg. 24641 (April 27, 2000)). Under the revised regulation (also known as the Alaska Rule), new and revised standards submitted to USEPA after May 30, 2000, must be approved by USEPA before being used for CWA purposes. The final rule also provides that standards already in effect and submitted to USEPA by May 30, 2000, may be used for CWA purposes, whether or not approved by USEPA.
- 4. Antidegradation Policy. 40 CFR 131.12 requires that the State water quality standards include an antidegradation policy consistent with the federal policy. The State Water Board established California's antidegradation policy in State Water Board Resolution No. 68-16. Resolution No. 68-16 incorporates the federal antidegradation policy where the federal policy applies under federal law. Resolution No. 68-16 requires that existing water quality be maintained unless degradation is justified based on specific findings. The San Diego Water Board's Basin Plan implements, and incorporates by reference, both the State and federal antidegradation policies. The permitted discharge must be consistent with the antidegradation provision of 40 CFR 131.12 and State Water Board Resolution No. 68-16.
- **5.** Anti-Backsliding Requirements. Sections 402(o)(2) and 303(d)(4) of the CWA and 40 CFR 122.44(l) prohibit backsliding in NPDES permits. These anti-backsliding provisions require that effluent limitations in a reissued permit must be as stringent as those in the previous permit, with some exceptions in which limitations may be relaxed.

D. Impaired Water Bodies on CWA 303(d) List

On June 28, 2007, USEPA approved the list of impaired water bodies, prepared by the State Water Board pursuant to section 303(d) of the CWA, which are not expected to meet applicable water quality standards after implementation of technology-based effluent limitations (TBELs) for point sources. The 303(d) list for waters in the vicinity of the ACOO include:

- **1.** 0.03 miles of Pacific Ocean shoreline at Aliso Creek for enterococcus, total coliform, and fecal coliform.
- **2.** 0.29 acres at the mouth of Aliso Creek for indicator bacteria.

Impairment has been detected in the above waters; however, the receiving waters in the immediate vicinity of the Discharge Point No. 001 (ACOO) are not included on the current 303(d) list. An applicable total maximum daily load (TMDL) has not been adopted for this discharge.

E. Other Plans, Policies and Regulations

- 1. Secondary Treatment Regulations. 40 CFR Part 133 establishes the minimum levels of effluent quality to be achieved by secondary treatment. These limitations, established by the USEPA, are incorporated into this Order, except where more stringent limitations are required by other applicable plans, policies, or regulations.
- 2. Storm Water. Sewage treatment works with a design flow of 1.0 MGD or greater are required to comply with Water Quality Order No. 97-03-DWQ (NPDES General Permit No. CAS000001), WDRs for Dischargers of Storm Water Associated with Industrial Activity, Excluding Construction Activities.
- **3. Pretreatment.** Discharges of pollutants that may interfere with operations of a POTW are regulated by USEPA's pretreatment regulations at 40 CFR 403. These regulations require Dischargers to develop and implement pretreatment programs that impose limitations on industrial users of the POTW.

IV. RATIONALE FOR EFFLUENT LIMITATIONS AND DISCHARGE SPECIFICATIONS

The CWA requires point source dischargers to control the amount of conventional, non-conventional, and toxic pollutants that are discharged into the waters of the United States. The control of pollutants discharged is established through effluent limitations and other requirements in NPDES permits. There are two principal bases for effluent limitations in the CFR: 40 CFR 122.44(a) requires that permits include applicable technology-based limitations and standards; and 40 CFR 122.44(d) requires that permits include water quality-based effluent limits (WQBELs) to attain and maintain applicable numeric and narrative water quality criteria to protect the beneficial uses of the receiving water.

A. Discharge Prohibitions

This Order retains the discharge prohibitions from Order No. R9-2006-0055, as described below. Compliance determination language is included in section VII of this Order to accurately describe how violations of these prohibitions are determined. Discharges from the Facilities to surface waters in violation of prohibitions contained in this Order are violations of the CWA and therefore are subject to third party lawsuits. Discharges from the Facilities to land in violation of prohibitions contained in this Order are violations of the CWC and are not subject to third party lawsuits under the CWA because the CWC does not contain provisions allowing third party lawsuits.

- Prohibitions III.A of this Order is retained from Order No. R9-2006-0055. Prohibition III.A
 was included in Order No. R9-2005-0055 to clearly define what types of discharges are
 prohibited.
- 2. Order No. R9-2006-0055 included the discharge prohibitions of the Basin Plan and the Ocean Plan, all of which are now included in this Order as a Prohibition III.B and C and incorporated in Attachment G.

B. Technology-Based Effluent Limitations (TBELs)

1. Scope and Authority

Section 301(b) of the CWA and implementing USEPA permit regulations at 40 CFR 122.44 require that permits include conditions meeting applicable technology-based requirements at a minimum, and any more stringent effluent limitations necessary to meet applicable water quality standards. The discharge authorized by this Order must meet minimum federal technology-based requirements based on Secondary Treatment Standards at 40 CFR Part 133.

Regulations promulgated in 40 CFR 125.3(a)(1) require technology-based effluent limitations for municipal dischargers to be placed in NPDES permits based on Secondary Treatment Standards or Equivalent to Secondary Treatment Standards.

The Federal Water Pollution Control Act Amendments of 1972 (PL 92-500) established the minimum performance requirements for POTWs [defined in section 304(d)(1)]. Section 301(b)(1)(B) of that Act requires that such treatment works must, as a minimum, meet effluent limitations based on secondary treatment as defined by the USEPA Administrator.

Based on this statutory requirement, USEPA developed secondary treatment regulations, which are specified in 40 CFR Part 133. These technology-based regulations apply to all municipal wastewater treatment plants and identify the minimum level of effluent quality attainable by secondary treatment in terms of biochemical oxygen demand (BOD₅), TSS, and pH.

2. Applicable Technology-Based Effluent Limitations

a. Federal Regulations. 40 CFR Part 133 establishes the minimum weekly and monthly average level of effluent quality attainable by secondary treatment for BOD_5 and TSS. 40 CFR 133.102(a)(4) allows for effluent limitations for $CBOD_5$ to be applied in lieu of effluent limitations for BOD_5 where BOD_5 may not provide a reliable measure of the oxygen demand of the effluent. USEPA has determined that a 30-day average effluent limitation of 25 mg/L and a 7-day average effluent limitation of 40 mg/L are effectively equivalent to the secondary treatment standards for BOD_5 . As such, the $CBOD_5$ limitations from Order No. R9-2005-0055 are carried over to this Order.

40 CFR 133.102, in describing the minimum level of effluent quality attainable by secondary treatment, states that the 30-day average percent removal of BOD_5 and TSS shall not be less than 85 percent. This Order contains a limitation requiring an average of 85 percent removal of $CBOD_5$ and TSS over each calendar month.

The secondary treatment regulations at 40 CFR Part 133 also require that pH be maintained between 6.0 and 9.0 standard units.

As described in Section II of this Fact Sheet, SOCWA operates the ACOO, which receives treated effluent from the following municipal wastewater treatment plants; the SOCWA RTP, the SOCWA CTP, the Los Alisos WRP, and the EI Toro WRP. In accordance with the definition contained in 40 CFR 122.2, each of these wastewater treatment plants is considered a POTW. The TBELs based on secondary treatment standards are applicable to each of these facilities, prior to the commingling of their

respective effluents with any other wastewater. Thus, compliance with these effluent limitations must be determined at internal outfall locations upstream of the location where these wastewaters commingle with other wastewaters.

TBELs based on secondary treatment standards for CBOD₅, TSS, and pH are summarized in the following table.

Table F-13. Summary of Technology-Based Effluent Limitations Based on Secondary Treatment Standards

		Effluent Limitations					
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	
CBOD ₅	mg/L	25	40				
	% Removal	85					
TSS	mg/L	30	45				
155	% Removal	85					
рН	Standard units				6.0	9.0	

b. Ocean Plan. The Ocean Plan is applicable, in its entirety, to point source discharges to the ocean. Therefore, the discharge of wastewater to the Pacific Ocean at Discharge Point No. 001 is subject to the Ocean Plan.

The Ocean Plan establishes water quality objectives, general requirements for management of waste discharged to the ocean, effluent quality requirements for waste discharges, discharge prohibitions, and general provisions. Further, Table A of the Ocean Plan establishes TBELs for POTWs and industrial discharges for which Effluent Limitation Guidelines have not been established pursuant to Sections 301, 302, or 306 of the federal CWA.

Order No. R9-2005-0055, established numeric effluent limitations based on Table A of the Ocean Plan applicable to each of the contributing municipal wastewater treatment plants. As the TSS percent removal requirement and standards under 40 CFR Part 133 for POTWs are more stringent than the Ocean Plan requirement, the more stringent TSS requirements were included in Order No. R9-2006-0055 for the discharges from the SOCWA RTP, the SOCWA CTP, the Los Alisos WRP, and the El Toro WRP. These same requirements remain applicable, and the effluent limitations are carried over to this Order.

The Ocean Plan Table A effluent limitations were also applied in Order No. R9-2006-0055 to the industrial discharges to the ocean through the ACOO, including discharges from the IDP PWTS and IDP SGU. Table A effluent limitations are also applicable to the SCWD ACWHP. Table A of the Ocean Plan requires dischargers to, as a monthly average, achieve a percent removal of 75 percent for TSS from the influent stream before discharging wastewater to the Pacific Ocean, except that the effluent limitation to be met shall not be less than 60 mg/L. The discharges from the IDP PWTS, IDP SGU, and SCWD ACWHP are considered industrial discharges and are subject to Table A limits prior to commingling at the ACOO. Therefore, an effluent TSS limitation of 60 mg/L is appropriate.

Table F-14. Summary of Technology-Based Effluent Limitations Based on Table A of the Ocean Plan

		Effluent Limitations					
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	
Oil and Grease	mg/L	25	40			75	
TSS	mg/L	60 ¹					
133	% Removal	1					
SS	ml/L	1.0	1.5			3.0	
Turbidity	NTU	75	100			225	
рН	standard units				6.0	9.0	

Table A of the Ocean Plan requires that the Discharger shall, as a monthly average, remove 75 percent of TSS from the influent stream before discharging wastewater to the Pacific Ocean, except that the effluent limitation to be met shall not be less than 60 mg/L.

C. Water Quality-Based Effluent Limitations (WQBELs)

1. Scope and Authority

Section 301(b) of the CWA and 40 CFR 122.44(d) require that permits include limitations more stringent than applicable federal technology-based requirements where necessary to achieve applicable water quality standards.

40 CFR 122.44(d)(1)(i) mandates that permits include effluent limitations for all pollutants that are or may be discharged at levels that have reasonable potential to cause or contribute to an exceedance of a water quality standard, including numeric and narrative objectives within a standard. Where reasonable potential has been established for a pollutant, but there is no numeric criterion or objective for the pollutant, WQBELs must be established using: (1) USEPA criteria guidance under CWA section 304(a), supplemented where necessary by other relevant information; (2) an indicator parameter for the pollutant of concern; or (3) a calculated numeric water quality criterion, such as a proposed state criterion or policy interpreting the state's narrative criterion, supplemented with other relevant information, as provided in 40 CFR 122.44(d)(1)(vi).

The process for determining reasonable potential and calculating WQBELs is intended to protect the designated uses of the receiving water as specified in the Basin Plan and Ocean Plan and achieve applicable water quality objectives and criteria that are contained in the Ocean Plan.

2. Applicable Beneficial Uses and Water Quality Criteria and Objectives

The Basin Plan and Ocean Plan designate beneficial uses, establishes water quality objectives, and contain implementation programs and policies to achieve those objectives for all waters.

a. Basin Plan. The beneficial uses specified in the Basin Plan applicable to the Pacific Ocean are summarized in section III.C.1 of this Fact Sheet.

The Basin Plan water quality objective for dissolved oxygen applicable to ocean waters is stated as follows: "The dissolved oxygen concentration in ocean waters shall not at any time be depressed more than 10 percent from that which occurs naturally, as the result of the discharge of oxygen demanding waste materials".

The Basin Plan includes water quality objectives for pH applicable to the receiving water. The Basin Plan states, "The terms and conditions of the State Board's "Water Quality Control Plan for Ocean Waters of California" (Ocean Plan), "Water Quality Control Plan for Control of Temperature in the Coastal and Interstate Waters and Enclosed Bays and Estuaries of California" (Thermal Plan), and any revisions thereto are incorporated into this Basin Plan by reference. The terms and conditions of the Ocean Plan and Thermal Plan apply to the ocean waters within this Region."

b. Ocean Plan. The beneficial uses specified in the Ocean Plan for the Pacific Ocean are summarized in section III.C.2 of this Fact Sheet. The Ocean Plan also includes water quality objectives for the ocean receiving water for bacterial characteristics, physical characteristics, chemical characteristics, biological characteristics, and radioactivity.

Table B of the Ocean Plan includes the following water quality objectives for toxic pollutants and whole effluent toxicity:

- i. 6-month median, daily maximum, and instantaneous maximum objectives for 21 chemicals and chemical characteristics, including total residual chlorine and chronic toxicity, for the protection of marine aquatic life.
- **ii.** 30-day average objectives for 20 non-carcinogenic chemicals for the protection of human health.
- **iii.** 30-day average objectives for 42 carcinogenic chemicals for the protection of human health.
- iv. Daily maximum objectives for acute and chronic toxicity.

3. Determining the need for WQBELs

Order No. R9-2006-0055 evaluated the need for effluent limitations for non-conventional and toxic pollutant parameters in Table B of the California Ocean Plan. For this Order, the need for effluent limitations based on water quality objectives in Table B of the Ocean Plan was re-evaluated in accordance with 40 CFR 122.44(d) and guidance for statistically determining the "reasonable potential" for a discharged pollutant to exceed an objective, as outlined in the revised *Technical Support Document for Water Quality-based Toxics Control* (TSD; EPA/505/2-90-001, 1991) and the Ocean Plan Reasonable Potential Analysis (RPA) Amendment that was adopted by the State Water Board on April 21, 2005. The statistical

approach combines knowledge of effluent variability (as estimated by a coefficient of variation) with the uncertainty due to a limited amount of effluent data to estimate a maximum effluent value at a high level of confidence. This estimated maximum effluent value is based on a lognormal distribution of daily effluent values. Projected receiving water values (based on the estimated maximum effluent value or the reported maximum effluent value and minimum probably initial dilution) can then be compared to the appropriate objective to determine potential for an exceedance of that objective and the need for an effluent limitation. According to the Ocean Plan amendment, the RPA can yield three endpoints: 1) Endpoint 1, an effluent limitation is required and monitoring is required; 2) Endpoint 2, an effluent limitation is not required and the San Diego Water Board may require monitoring; 3) Endpoint 3, the RPA is inconclusive, monitoring is required, and an existing effluent limitation may be retained or a permit reopener clause may be included to allow inclusion of an effluent limitation if future monitoring warrants the inclusion. Endpoint 3 is typically the result when there are fewer than 16 data points and all are censored data (i.e., below quantitation or method detection levels for an analytical procedure).

The implementation provisions for Table B in section III.C of the Ocean Plan specify that the minimum initial dilution is the lowest average initial dilution within any single month of the year. Dilution estimates are to be based on observed waste flow characteristics, observed receiving water density structure, and the assumption that no currents of sufficient strength to influence the initial dilution process flow across the discharge structure. Before establishing a dilution credit for a discharge, it must first be determined if, and how much, receiving water is available to dilute the discharge.

As described in the fact sheet for Order No. R9-2006-0055, the San Diego Water Board, with assistance from the State Water Board, had previously determined the minimum initial dilution for the ACOO, using the computer model UMERGE, to be 260. The UMERGE initial dilution factor was based on discharge of up to 27.0 MGD of effluent through the ACOO. The San Diego Water Board reassessed the initial dilution factor in 2004 when considering authorization of brine discharge from the IDP. The result of the analysis indicated that the addition of the IDP SGU would not have a significant impact on the initial dilution factor. Therefore, the initial dilution of 260 was used for the RPA and calculating effluent limitations in Order No. R9-2006-0055. Based on the data collected by the Discharger during the term of Order No. R9-2006-0055, the San Diego Water Board recalculated the initial dilution using Visual Plumes. Based on this reevaluation, the minimum initial dilution was calculated to be 237:1 (see Attachment H). Therefore, a Dm of 237:1 will be used in the current Order and applied to WQBELs established herein.

Conventional pollutants were not considered as part of the RPA. Technology-based effluent limitations for these pollutants are included in this Order as described in section IV.B of this Fact Sheet.

Using the RPcalc 2.0 software tool developed by the State Water Board for conducting reasonable potential analyses, the San Diego Water Board has conducted the RPA for the constituents listed in Table F-15. For constituents that do not display reasonable potential, this Order includes desirable maximum effluent concentrations which were derived using the effluent limitation determination procedure described below and are referred to in this Order as "performance goals". A narrative limit statement to comply with all Ocean Plan objectives requirements is provided for those parameters not displaying reasonable potential. The Discharger is required to monitor for these constituents as stated in the MRP (Attachment E) in order to gather data for use in reasonable potential analyses for future permit reissuance.

Effluent data provided in the Discharger's monitoring reports for the Facilities from May 2007 through December 2010 were used in the RPA for the majority of parameters. For ammonia, acute toxicity, and chronic toxicity, data were available for the period January 2009 through December 2010. A minimum probable initial dilution of 237 to 1 was considered in this evaluation.

A summary of the RPA results is provided below:

Table F-15. RPA Results Summary

Parameter	Units	n¹	MEC ^{2,4}	Most Stringent Criteria	Background	RPA Endpoint ³
Arsenic	μg/L	15	< 25	8 ⁵	3 ⁶	3
Cadmium	μg/L	15	< 6.0	1 ⁵	0	3
Chromium (Hexavalent)	μg/L	15	< 10	2 ⁵	0	2
Copper	μg/L	15	< 20	3 ⁵	2 ⁶	3
Lead	μg/L	15	< 19	2 ⁵	0	3
Mercury	μg/L	15	< 3.0	0.04 ⁵	0.0005 ⁶	3
Nickel	μg/L	15	< 13	5 ⁵	0	3
Selenium	μg/L	13	18.0	15 ⁵	0	3
Silver	μg/L	15	< 10	0.7 ⁵	0.16 ⁶	3
Zinc	μg/L	15	40	20 ⁵	8 ⁶	2
Cyanide	μg/L	15	< 24	1 ⁵	0	3
Total Residual Chlorine ¹⁰	μg/L	1,521	1,959	2 ⁵	0	1
Ammonia	μg/L	24	18,100	600 ⁵	0	2
Acute Toxicity ¹¹	TUa	23	1.48	0.3 ⁷	0	2
Chronic Toxicity ¹²	TUc	24	> 1,000	1 ⁷	0	1
Phenolic Compounds ¹³	μg/L	15	< 6	30 ⁵	0	3
Chlorinated Phenolics ¹⁴	μg/L	15	< 8	1 ⁵	0	3
Endosulfan ¹⁵	μg/L	15	< 0.06	0.009 ⁵	0	3
Endrin	μg/L	15	< 1.0	0.002 ⁵	0	3
HCH ¹⁶	μg/L	15	< 0.20	0.004 ⁵	0	3
Radioactivity	pCi/L	8	28.8	8	0	
Acrolein	μg/L	8	< 10	220 ⁹	0	3
Antimony	μg/L	8	< 31	1,200 ⁹	0	3
Bis(2-chloroethoxyl)methane	μg/L	8	< 5.0	4.4 ⁹	0	3
Bis(2-chloroisopropyl)ether	μg/L	8	< 5.0	1,200 ⁹	0	3
Chlorobenzene	μg/L	8	< 1.0	570 ⁹	0	3
Chromium (III)	μg/L	8	< 10	190,000 ⁹	0	3
Di-n-butyl phthalate	μg/L	8	< 5.0	3,500 ⁹	0	3
Dichlorobenzenes ¹⁷	μg/L	8	< 1.0	5,100 ⁹	0	3
Diethyl phthalate	μg/L	8	< 5.0	33,000 ⁹	0	3
Dimethyl phthalate	μg/L	8	< 5.0	820,000 ⁹	0	3
4,6-Dinitro-2-methylphenol	μg/L	8	< 5.0	220 ⁹	0	3
2,4-Dinitrophenol	μg/L	8	< 1.0	4.0 ⁹	0	3
Ethylbenzene	μg/L	8	< 1.0	4,100 ⁹	0	3

Parameter	Units	n¹	MEC ^{2,4}	Most Stringent Criteria	Background	RPA Endpoint ³
Fluoranthene	μg/L	8	< 5.0	15 ⁹	0	3
Hexachlorocyclopentadiene	μg/L	8	< 5.0	58 ⁹	0	3
Nitrobenzene	μg/L	8	< 5.0	4.9 ⁹	0	3
Thallium	μg/L	8	< 11	2 ⁹	0	3
Toluene	μg/L	8	< 1.0	85,000 ⁹	0	3
Tributyltin	μg/L	8	< 0.005	0.0014 ⁹	0	3
1,1,1-Trichloroethane	μg/L	8	< 1.0	540,000 ⁹	0	3
Acrylonitrile	μg/L	8	< 10	0.10 ⁹	0	3
Aldrin	μg/L	8	< 0.075	0.000022 ⁹	0	3
Benzene	μg/L	8	< 1.0	5.9 ⁹	0	3
Benzidine	μg/L	8	< 5.0	0.000069 ⁹	0	3
Beryllium	μg/L	8	< 9.0	0.033 ⁹	0	3
Bis(2-chloroethyl) ether	μg/L	8	< 5.0	0.045 ⁹	0	3
Bis(2-ethylhexyl) phthalate	μg/L	8	< 5.0	3.5 ⁹	0	3
Carbon tetrachloride	μg/L	8	< 1.0	0.909	0	3
Chlordane	μg/L	8	< 0.50	0.000023 ⁹	0	3
Chlorodibromomethane	μg/L	8	< 1.0	8.6 ⁹	0	3
Chloroform	μg/L	8	5.7	130 ⁹	0	2
DDT ¹⁸	μg/L	8	< 0.020	0.00017 ⁹	0	3
1,4-Dichlorobenzene	μg/L	8	< 1.0	18 ⁹	0	3
3,3-Dichlorobenzidine	μg/L	8	< 5.0	0.0081 ⁹	0	3
1,2-Dichloroethane	μg/L	8	< 1.0	28 ⁹	0	3
1,1-Dichloroethylene	μg/L	8	< 1.0	0.9 ⁹	0	3
Dichlorobromomethane	μg/L	8	3.3	6.2 ⁹	0	3
Dichloromethane	μg/L	8	< 1.0	450 ⁹	0	3
1,3-Dichloropropene	μg/L	8	< 1.0	8.9 ⁹	0	3
Dieldrin	μg/L	7	< 0.02	0.00004 ⁹	0	3
2,4-Dinitrotoluene	μg/L	8	< 5.0	2.6 ⁹	0	3
1,2-Diphenylhydrazine	μg/L	8	< 5.0	0.16 ⁹	0	3
Halomethanes ¹⁹	μg/L	8	< 1.0	130 ⁹	0	3
Heptachlor ²⁰	μg/L	8	> 0.010	0.00005 ⁹	0	1
Heptachlor Epoxide ²¹	μg/L	8	< 0.020	0.000029	0	3
Hexachlorobenzene	μg/L	8	< 5.0	0.00021 ⁹	0	3
Hexachlorobutadiene	μg/L	8	< 5.0	14 ⁹	0	3
Hexachloroethane	μg/L	8	< 5.0	2.5 ⁹	0	3
Isophorone	μg/L	8	< 5.0	730 ⁹	0	3
N-nitrosodimethylamine	μg/L	8	< 5.0	7.3 ⁹	0	3
N-nitrosodi-N-propylamine	μg/L	8	< 5.0	0.389	0	3
N-nitrosodiphenylamine	μg/L	8	< 5.0	2.5 ⁹	0	3
PAHs ²²	μg/L	8	< 5.0	0.00889	0	3
PCBs ²³	μg/L	8	< 5.0	0.000019 ⁹	0	3
TCDD equivalents ²⁴	pg/L	8	<0.00001	0.0000000039 ⁹	0	3

Parameter	Units	n¹	MEC ^{2,4}	Most Stringent Criteria	Background	RPA Endpoint ³
1,1,2,2-Tetrachoroethane	μg/L	8	< 1.0	2.3 ⁹	0	3
Tetrachloroethylene	μg/L	8	< 1.0	2.0 ⁹	0	3
Toxaphene	μg/L	8	< 1.0	0.00021 ⁹	0	3
Trichloroethylene	μg/L	8	< 1.0	27 ⁹	0	3
1,1,2-Trichloroethane	μg/L	9	< 1.0	9.4 ⁹	0	3
2,4,6-Trichlorophenol	μg/L	8	< 1.0	0.299	0	3
Vinyl Chloride	μg/L	8	< 1.0	36 ⁹	0	3

- Number of data points available for the RPA.
- If there is a detected value, the highest reported value is summarized in the table. If there are no detected values, the lowest MDL is summarized in the table.
- End Point 1 RP determined, limit required, monitoring required.
 - End Point 2 Discharger determined not to have RP, monitoring may be established.
 - End Point 3 RPA was inconclusive, carry over previous limits if applicable, and establish monitoring.
- Note that the reported MEC does not account for dilution. The RPA does account for dilution; therefore it is possible for a parameter with an MEC in exceedance of the most stringent criteria not to present a RP (i.e. Endpoint 1).
- Based on the 6-Month Median in the Table B of the Ocean Plan.
- Background concentrations contained in Table C of the Ocean Plan.
- Based on the Daily Maximum in Table B of the Ocean Plan.
- Not to exceed limits specified in Title 17, Division 1, Chapter 5, Subchapter 4, Group 3, Article 3, Section 30253 of the California Code of Regulations. Radioactivity at levels that exceed the applicable criteria are not expected in the discharge.
- Based on 30-Day Average in Table B of the Ocean Plan.
- Although none of the contributing POTWs utilize chorine disinfection for treatment prior to discharge through the ACOO, detectable concentrations of total residual chlorine were reported by the Discharger at levels that result in End Point 1.
- One of the 24 reported acute toxicity measurements were recorded as 0 TUa. This data point was not included in the RPA since several steps require the log transformation of the reported data. Inclusion of these data points would decrease the likelihood of determining an Endpoint 1 for acute toxicity and increase the likelihood of determining Endpoint 2; therefore, there exclusion does not bias the result of the RPA.
- Chronic toxicity expressed as Chronic Toxicity Units (TUc) = 100/NOEL, where NOEL (No Observed Effect Level) is express as the maximum percent effluent of receiving water that causes no observable effect on a test organism. In one instance, where chronic toxicity measurement exceeded the maximum calibration point of the method (i.e., the measurement was reported as > 1000 TUc), the maximum calibration point was used in the RPA.
- Non-chlorinated phenolic compounds represent the sum of 2,4-dimethylphenol, 4,6-dinitro-2-methylphenol, 2,3-dinitrophenol, 2-methylphenol, 4-methylphenol, 2-nitrophenol, 4-nitrophenol, and phenol.
- Chlorinated phenolic compounds represent the sum of 4-chloro-3-methylphenol, 2-chlorophenol, pentachlorophenol, 2,4,5-trichlorophenol, and 2,4,6-trichlorophenol.
- ¹⁵ Endosulfan represents the sum of alpha-endosulfan, beta-endosulfan, and endosulfan sulfate.
- HCH (hexachlorocyclohexane) represents the sum of the alpha, beta, gamma (Lindane), and delta isomers of hexachlorocyclohexane.
- Dichlorobenzenes represent the sum of 1,2- and 1,3-dichlorobenzene.
- DDT represents the sum of 4,4'DDT; 2,4'DDE; 2,4'DDE; 4,4'DDD; and 2,4'DDD.
- Halomethanes represent the sum of bromoform, bromomethane (methyl bromide), and chloromethane (methyl chloride).
- In one instance, where the heptachlor measurement exceeded the maximum calibration point of the method (i.e., the measurement was reported as > 0.10 μg/L), the maximum calibration point was used in the RPA.
- In one instance, where the heptachlor epoxide measurement exceeded the maximum calibration point of the method (i.e., the measurement was reported as > 0.10 µg/L), the maximum calibration point was used in the RPA.
- PAHs (polynuclear aromatic hydrocarbons) represent the sum of acenapthalene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo[k]fluoranthene; 1,12-benzoperylene; benzo[a]pyrene; chrysene; dibenzo[a,h]anthracene; fluorene; indeno[1,2,3-cd]pyrene; phenanthrene; and pyrene.
- PCBs (polychlorinated biphenyls) represent the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Arolclor-1254, and Arcolor-1260.
- TCDD equivalents represent the sum of concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors, as shown by the table below. USEPA Method 8280 may be used to analyze TCDD equivalents.

Parameter	Units	n¹	MEC ^{2,4}	Most Stringent Criteria	Background	RPA Endpoint ³
	Isom	er Group	Toxicity	Equivalence Factor		
	2,3,7,8 -	tetra CDD		1.0		
	2,3,7,8 -	penta CDI)	0.5		
	2,3,7,8 -	hexa CDD)	0.1		
	2,3,7,8 – hepta CDD)	0.01		
	octa CDD)		0.001		
	2,3,7,8 -	tetra CDF		0.1		
	1,2,3,7,8	penta C	DF	0.05		
	2,3,4,7,8	penta Cl	DF	0.5		
	2,3,7,8 – hexa CDFs		S	0.1		
	2,3,7,8 – hepta CDFs		-s	0.01		
	Octa CDF			0.001		

Consistent with 40 CFR 122(I)(2)(i)(B), effluent limitations from Order No. R9-2006-0055 will not be retained for constituents for which the RPA results indicated Endpoint 2. Instead, performance goals have been assigned for these constituents. Parameters for which Endpoint 2 was concluded are determined not to have reasonable potential, thus it is inappropriate to establish effluent limitations for these parameters.

For parameters for which Endpoint 3 was concluded, reasonable potential was inconclusive. For parameters for which Endpoint 3 was concluded and previous effluent limitations had not been established, reasonable potential was not determined. For parameters for which new data is available and reasonable potential cannot be determined, effluent limitations have been retained. For this Order, the reasonable potential analysis for TCDD equivalents resulted in End Point 3. As Order No. R9-2006-0055 contained effluent limitations for TCDD equivalents, effluent limitations are retained in this Order. The monitoring and reporting program (MRP) in Attachment E of this Order is intended to facilitate collection of additional information for these constituents to determine if reasonable potential exists in future permit reissuance and/or updates.

Reasonable potential to cause or contribute to an exceedance of water quality objectives contained within the Ocean Plan (i.e. Endpoint 1) was determined for total residual chlorine, total chronic toxicity, and heptachlor. Thus, effluent limitations for these parameters have been established in this Order based on the minimum probable dilution of 237 to 1, as discussed below.

4. WQBEL Calculations

a. From the Table B water quality objectives of the Ocean Plan, effluent limitations and performance goals are calculated according to the following equation for all pollutants, except for acute toxicity (if applicable) and radioactivity:

$$Ce = Co + Dm (Co - Cs)$$
 where,

Ce = the effluent limitation (µg/L)

Co = the water quality objective to be met at the completion of initial dilution $(\mu g/L)$

Cs = background seawater concentration

Dm = minimum probable initial dilution expressed as parts seawater per part wastewater

- **b.** Initial dilution (Dm) has been determined to be 237 to 1 by the San Diego Water Board through the application of USEPA's dilution model, Visual Plumes.
- **c.** Table C of the Ocean Plan establishes background concentrations for some pollutants to be used when determining reasonable potential (represented as "Cs"). In accordance with Table B implementing procedures, Cs equals zero for all pollutants not established in Table C. The background concentrations provided in Table C are summarized below:

Table F-16. Pollutants Having Background Concentrations

	<u> </u>
Pollutant	Background Seawater Concentration
Arsenic	3 μg/L
Copper	2 μg/L
Mercury	0.0005 μg/L
Silver	0.16 μg/L
Zinc	8 μg/L

d. As an example of how effluent limitations and performance goals have been calculated, the effluent limits for heptachlor are determined as follows:

Water quality objectives from the Ocean Plan for heptachlor are:

Table F-17. Example Parameter Water Quality Objectives

Parameter	Units	30-Day Average		
Heptachlor	μg/L	5E-05		

Using the equation, Ce = Co + Dm (Co - Cs), effluent limitations/performance goals are calculated as follows.

Heptachlor

$$Ce = 5E-05 + 237 (5E-05 - 0) = 1.2E-02 (30-Day Average)$$

Based on the implementing procedures described above, effluent limitations and performance goals have been calculated for all Table B pollutants from the California Ocean Plan and incorporated into this Order.

e. 40 CFR 122.45(f)(1) requires effluent limitations be expressed in terms of mass, with some exceptions, and 40 CFR 122.45(f)(2) allows pollutants that are limited in terms of mass to additionally be limited in terms of other units of measurement. This Order includes effluent limitations expressed in terms of mass and concentration. In addition, pursuant to the exceptions to mass limitations provided in 40 CFR 122.45(f)(1), some effluent limitations are not expressed in terms of mass, such as pH and temperature, and when the applicable standards are expressed in terms of concentration (e.g., CTR criteria and Maximum Contaminant Levels or MCLs) and mass limitations are not necessary to protect the beneficial uses of the receiving water.

Mass-based effluent limitations were calculated using the following equation:

lbs/day = permitted flow (MGD) x pollutant concentration (mg/L) x 8.34

f. A summary of the WQBELs established in this Order are provided below:

Summary of Water Quality-based Effluent Limitations Discharge Point No. 001

Table F-18. Summary of Water Quality-based Effluent Limitations

			Effluent Limitations						
Parameter	Units	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average				
BAS	.IFE								
Chlorine, Total	μg/L	4.8E+02	1.9E+03	1.4E+04					
Residual	lbs/day	1.4E+02	5.4E+02	4.1E+03					
Chronic Toxicity	TUc	-	2.4E+02		-				
Hontochlor	μg/L	-			1.2E-02				
Heptachlor	lbs/day	1			3.4E-03				
TCDD Equivalents	μg/L	-			9.4E-07				
	lbs/day				2.6E-07				

g. A summary of the performance goals is provided in Table F-27 of this Fact Sheet.

5. Whole Effluent Toxicity (WET)

- a. Implementing provisions at section III.C.4.c.(3) of the Ocean Plan states that the Discharger shall conduct chronic toxicity monitoring for ocean waste discharges with minimum initial dilution factors ranging from 100:1 to 350:1. Using monthly chronic WET testing data conducted between January 2009 and December 2010, the RPA resulted in Endpoint 1, and an effluent limitation and monthly monitoring for chronic toxicity is required. Based on the methods established by the California Ocean Plan, a maximum daily effluent limitation (MDEL) of 238 TUc is established in this Order.
- **b.** Implementing provisions at section III.C.4.c.(3) of the Ocean Plan states that the San Diego Water Board may require acute toxicity testing in addition to chronic toxicity monitoring for ocean waste discharges with minimum initial dilution factors ranging from 100:1 to 350:1 as necessary for the protection of beneficial uses of ocean waters. The Discharger has been granted a dilution ratio of 237 at Discharge Point No. 001 and the results of the RPA do not indicate reasonable potential for acute toxicity; however, because the results of the RPA do indicate reasonable potential for chronic toxicity, acute toxicity is included as a performance goal and acute toxicity monitoring has been reduced from monthly to quarterly.

D. Final Effluent Limitations

The following tables list the effluent limitations established by this Order. Where this Order establishes mass emission rates (MERs), these limitations have been derived based on flows of 12.0 MGD (SOCWA RTP), 6.7 MGD (SOCWA CTP), 7.5 MGD (Los Alisos WRP), 6.0 MGD (El Toro WRP), 1.0 MGD (IDP RO), 0.85 MGD (IDP SGU), and 0.32 MGD (SCWD ACWHP). MERs for the combined flows are based on 34.37 MGD total flow through the ACOO.

Table F-19. Technology-based Effluent Limitations for SOCWA RTP (M-001A)

		Effluent Limitations									
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median				
CBOD ₅ ¹	mg/L	25	40								
	lbs/day	2,502	4,003								
TSS ¹	mg/L	30	45								
133	lbs/day	3,002	4,504								
Oil and Grease	mg/L	25	40			75					
Oil and Grease	lbs/day	2,502	4,003			7,506					
SS	ml/L	1.0	1.5			3.0					
Turbidity	NTU	75	100		-	225					
рН	standard units				6.0	9.0					

The average monthly percent removal of CBOD₅ and TSS shall not be less than 85 percent.

Table F-20. Technology-based Effluent Limitations for SOCWA CTP (M-001B)

Table F-20.	1 ECITION	ugy-baset I	Lindent		TOT SUCWA C	II (INI-OUTD)	
				,	uent Limitations	TT	
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median
CBOD₅¹	mg/L	25	40				
	lbs/day	1,397	2,235				
TSS ¹	mg/L	30	45				
133	lbs/day	1,676	2,515		-		
Oil and Grease	mg/L	25	40		1	75	
Oil and Grease	lbs/day	1,397	2,235			4,191	
SS	ml/L	1.0	1.5			3.0	
Turbidity	NTU	75	100			225	
рН	standar d units				6.0	9.0	

The average monthly percent removal of CBOD₅ and TSS shall not be less than 85 percent.

Table F-21. Technology-based Effluent Limitations for Los Alisos WRP (M-001C)

		Effluent Limitations							
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median		
CBOD₅ ¹	mg/L	25	40						
	lbs/day	1,564	2,502						
TSS ¹	mg/L	30	45						
	lbs/day	1,877	2,815						
Oil and Grease	mg/L	25	40			75			
Oli aliu Grease	lbs/day	1,564	2,502			4,691			
SS	ml/L	1.0	1.5			3.0			
Turbidity	NTU	75	100			225			
рН	standard units				6.0	9.0			

The average monthly percent removal of CBOD₅ and TSS shall not be less than 85 percent.

Table F-22. Technology-based Effluent Limitations for El Toro WRP (M-001D)

Table F-22.	reciiio	nology-based Emident Limitations for El Toro WRP (M-001D)							
		Effluent Limitations							
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median		
CBOD ₅ ¹	mg/L	25	40				1		
	lbs/day	1,251	2,002		-		1		
TSS ¹	mg/L	30	45						
133	lbs/day	1,501	2,252						
Oil and Grease	mg/L	25	40			75			
	lbs/day	1,251	2,002			3,753			
SS	ml/L	1.0	1.5			3.0			
Turbidity	NTU	75	100			225			
рН	standard units				6.0	9.0			

The average monthly percent removal of CBOD₅ and TSS shall not be less than 85 percent.

Table F-23. Technology-based Effluent Limitations for the IDP PWTS (M-001E)

		Effluent Limitations									
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median				
TSS	mg/L	60									
133	lbs/day	500									
Oil and	mg/L	25	40			75					
Grease	lbs/day	209	334			626					
SS	ml/L	1.0	1.5			3.0					
Turbidity	NTU	75	100			225					
рН	standard units				6.0	9.0					

Table F-24. Technology-based Effluent Limitations for the IPD SGU (M-001F)

		Effluent Limitations							
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median		
TOO	mg/L	60							
TSS	lbs/day	425							
Oil and	mg/L	25	40			75			
Grease	lbs/day	177	284			532			
SS	ml/L	1.0	1.5			3.0			
Turbidity	NTU	75	100			225			
рН	standard units				6.0	9.0			

Table F-25. Technology-based Effluent Limitations for the SCWD ACWHP (M-001G)

	Effluent Limitations						
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median
TSS ¹	mg/L	60					
155	lbs/day	160					
Oil and	mg/L	25	40			75	
Grease	lbs/day	67	107			200	
SS	ml/L	1.0	1.5			3.0	
Turbidity	NTU	75	100			225	
рН	standard units				6.0	9.0	

Table F-26. Effluent Limitations for Combined Flow, Based on Table B of the Ocean Plan at M-001

	IVI-O	<u> </u>							
			Effluent Limitations						
Parameter	Units	Average Monthly	Average Weekly	Maximum Daily	Instantaneous Minimum	Instantaneous Maximum	6-Month Median		
BASED ON OBJECTIVES FOR PROTECTION OF MARINE AQUATIC LIFE									
Chlorine,	μg/L			1,900		14,000	480		
Total Residual	lbs/day			550		4,100	140		
Chronic Toxicity ¹	TUc			238					
Hontochlor	μg/L	1.2E-02							
Heptachlor	lbs/day	3.4E-03							
TCDD	μg/L	9.3E-07				-			
Equivalents ²	lbs/day	2.7E-07							

Chronic toxicity expressed as Chronic Toxicity Units (TUc) = 100/NOEL, where NOEL (No Observed Effect Level) is expressed as the maximum percent effluent or receiving water that causes no observable effect on a test organism.

TCDD Equivalents shall mean the sum of concentrations of chlorinated dibenzodioxins (2,3,7,8-CDDs) and chlorinated dibenzofurans (2,3,7,8-CDFs) multiplied by their respective toxicity factors, as shown by the table below:

Isomer Group	Toxicity Equivalence Factor
2,3,7,8 - tetra CDD	1.0
2,3,7,8 - penta CDD	0.5
2,3,7,8 - hexa CDD	0.1
2,3,7,8 - hepta CDD	0.01
octa CDD	0.001
2,3,7,8 - tetra CDF	0.1
1,2,3,7,8 - penta CDF	0.05
2,3,4,7,8 - penta CDF	0.5
2,3,7,8 - hexa CDFs	0.1
2,3,7,8 - hepta CDFs	0.01
octa CDF	0.001

1. Satisfaction of Anti-Backsliding Requirements

The TBELs in this Order are at least as stringent as the effluent limitations in the previous Order.

Effluent limitations from Order No. R9-2006-0055 are not retained for constituents for which RPA results indicated Endpoint 2, or Endpoint 3 when previous effluent limitations had not been established: instead performance goals have been assigned for these constituents. Parameters for which Endpoint 2 was concluded are determined not to have reasonable potential, thus it is inappropriate to establish effluent limitations for these parameters. For parameters for which Endpoint 3 was concluded and previous effluent limitations had not been established, reasonable potential was not determined. For parameters for which new data is available, and reasonable potential cannot be determined, effluent limitations have been removed as allowed under 40 CFR 122(I)(2)(i)(B), and performance goals have been established in their place. The MRP for this Order is designed to obtain additional information for these constituents to determine if reasonable potential exists for these constituents in future permit reissuance and/or updates.

This permit complies with all applicable federal and State anti-backsliding regulations.

2. Satisfaction of Antidegradation Policy

WDRs for the Discharger must conform with federal and State antidegradation policies provided at 40 CFR 131.12 and in State Water Board Resolution No. 68-16, *Statement of Policy with Respect to Maintaining High Quality of Waters in California*. The antidegradation policies require that beneficial uses and the water quality necessary to maintain those beneficial uses in the receiving waters of the discharge shall be maintained and protected, and, if existing water quality is better than the quality required to maintain beneficial uses, the existing water quality shall be maintained and protected unless allowing a lowering of water quality is necessary to accommodate important economic and social development or consistent with maximum benefit to the people of California. When a significant lowering of water quality is allowed by the San Diego Water Board, an antidegradation analysis is required in accordance with the State Water Board's Administrative Procedures Update (July 2, 1990), *Antidegradation Policy Implementation for NPDES Permitting*.

a. Technology-based Effluent Limitations (TBELs)

The concentration-based TBELs contained in Order No. R9-2006-0055 have been retained in this Order. The TBELs are at least as stringent as the previous effluent limitations, and no degradation of the receiving water is expected.

Order No. R9-2006-0055 applied concentration-based TBELs based on secondary treatment standards to the individual discharges of secondary effluent from the SOCWA RTP, the SOCWA CTP, the Los Alisos WRP, and the El Toro WRP. Corresponding MERs, however, were not established.

Order No. R9-2006-0055 also applied concentration-based TBELs based on the Ocean Plan Table A effluent limitations to the industrial discharges to the ocean through the ACOO, including discharges from the IDP PWTS and IDP SGU. Corresponding MERs, however, were not established.

Consistent with concentration limitations, and in accordance with section III.B of the Ocean Plan, this Order applies effluent MERs, based on Table A and/or secondary treatment standards, at the individual discharges from the Facilities. Because the new MERs are applied individually, they ensure proper performance of individual treatment plants.

b. Water Quality-based Effluent Limitations

The 32.86 MGD flow restriction on the ACOO has been increased to accommodate discharges from the IDP SGU (0.85 MGD), IDP PWTS (1.0 MGD) and anticipated production from the SCWD ACWHP (0.32 MGD). Order No. R9-2006-0055 was based on the presumption that treated SGU groundwater would be discharged to the ACOO only during conditions in which extracted groundwater flows exceeded the capacity of groundwater injection facilities. The injection facilities, however, are no longer available. The total requested increase is 0.9 MGD. The San Diego Water Board does not anticipate a lowering of water quality due to the increase in the flow restriction for two reasons. First, this increase of 0.9 MGD represents only 2.7 percent of the total regulated flow from the ACOO. Second, and as described previously in section IV.C.3 of this Fact Sheet, the minimum initial dilution was calculated to be 237:1, representing a reduction in the allowable dilution used to calculate effluent limitations and performance goals. This revised initial dilution results in more stringent concentration-based effluent

limitations and performance goals as compared to those contained in Order No. R9-2006-0055. Based on the revised concentration-based effluent limitations and performance goals, and using the increased flow requested by the Discharger (34.37 MGD), the resulting MERs are also more stringent than those contained in Order No. R9-2006-0055.

As WQBELs and performance goals are at least as stringent as in Order No. R9-2006-0055, the San Diego Water Board has determined that water quality will not be lowered as a result of increasing the flow restriction for the ACOO, and an antidegradation analysis is not required.

3. Stringency of Requirements for Individual Pollutants

This Order contains both TBELs and WQBELs for individual pollutants. The TBELs consist of restrictions on CBOD₅, TSS, oil and grease, SS, turbidity, and pH. Restrictions on these constituents are discussed in section IV.B of this Fact Sheet. This Order's technology-based pollutant restrictions implement the minimum, applicable federal technology-based requirements. These limitations are not more stringent than required by the CWA.

WQBELs have been scientifically derived to implement water quality objectives that protect beneficial uses. Both the beneficial uses and the water quality objectives have been approved pursuant to federal law and are the applicable federal water quality standards. The scientific procedures for calculating the individual WQBELs are based on the Ocean Plan, which was approved by USEPA on October 8, 2010. All beneficial uses and water quality objectives contained in the Basin Plan were approved under State law and submitted to and approved by USEPA prior to May 30, 2000. Any water quality objectives and beneficial uses submitted to USEPA prior to May 30, 2000, but not approved by USEPA before that date, are nonetheless "applicable water quality standards for purposes of the CWA" pursuant to 40 CFR 131.21(c)(1). Water quality objectives contained in the Ocean Plan submitted to EPA after May 30, 2000 have subsequently been approved by EPA. Collectively, this Order's restrictions on individual pollutants are no more stringent than required to implement the requirements of the CWA.

E. Performance Goals

Constituents that do not display reasonable potential to cause or contribute to an exceedance of a water quality standard are listed as performance goals in this Order. Performance goals serve to maintain existing treatment levels and effluent quality and supports State and federal antidegradation policies. Additionally, performance goals provide all interested parties with information regarding the expected levels of pollutants in the discharge that should not be exceeded in order to maintain the water quality objectives established in the Ocean Plan. Performance goals are not limitations or standards for the regulation of the discharge. Effluent concentrations above the performance goals will not be considered as violations of the permit but serve as red flags that indicate water quality concerns. Repeated red flags may prompt the San Diego Water Board to reopen and amend the permit to replace performance goals for constituents of concern with effluent limitations, or the San Diego Water Board may coordinate such actions with the next permit reissuance.

The following table lists the performance goals established by this Order. A minimum probable initial dilution factor of 237 to 1 was used in establishing the performance goals and a flow of 34.37 MGD was used to develop the MERs.

Table F-27. Performance Goals Based on the Ocean Plan

			Performance Goals ¹					
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average			
OB	OBJECTIVES FOR PROTECTION OF MARINE AQUATIC LIFE							
Arsenic, Total Recoverable	μg/L	1.2E+03	6.9E+03	1.8E+04				
Albertic, Total Necoverable	lbs/day	3.4E+02	2.0E+03	5.3E+03				
Cadmium, Total	μg/L	2.4E+02	9.5E+02	2.4E+03				
Recoverable	lbs/day	6.8E+01	2.7E+02	6.8E+02				
Chromium VI, Total Recoverable ²	μg/L	4.8E+02	1.9E+03	4.8E+03				
Recoverable ²	lbs/day	1.4E+02	5.5E+02	1.4E+03				
Copper, Total Recoverable	μg/L	2.4E+02	2.4E+03	6.7E+03				
Copper, Total Recoverable	lbs/day	6.9E+01	6.8E+02	1.9E+03				
Load Total Description	μg/L	4.8E+02	1.9E+03	4.8E+03				
Lead, Total Recoverable	lbs/day	1.4E+02	5.5E+02	1.4E+03				
Maraum, Tatal Dagayarahla	μg/L	9.4E+00	3.8E+01	9.5E+01				
Mercury, Total Recoverable	lbs/day	2.7E+00	1.1E+01	2.7E+01				
Niekal Tatal Danassanahla	μg/L	1.2E+03	4.8E+03	1.2E+04				
Nickel, Total Recoverable	lbs/day	3.4E+02	1.4E+03	3.4E+03				
Selenium, Total	μg/L	3.6E+03	1.4E+04	3.6E+04				
Recoverable	lbs/day	1.0E+03	4.1E+03	1.0E+04				
0" T.I.D. II	μg/L	1.3E+02	6.3E+02	1.6E+03				
Silver, Total Recoverable	lbs/day	3.7E+01	1.8E+02	4.7E+02				
7 T (D	μg/L	2.9E+03	1.7E+04	4.6E+04				
Zinc, Total Recoverable	lbs/day	8.2E+02	4.9E+03	1.3E+04				
Cyanide, Total	μg/L	2.4E+02	9.5E+02	2.4E+03				
Recoverable	lbs/day	6.8E+01	2.7E+02	6.8E+02				
Ammonia	μg/L	1.4E+05	5.7E+05	1.4E+06				
(expressed as nitrogen)	lbs/day	4.1E+04	1.6E+05	4.1E+05				
Acute Toxicity ³	TUa		7.1E+01					
Phenolic Compounds	μg/L	7.1E+03	2.9E+04	7.1E+04				
(non-chlorinated) ⁴	lbs/day	2.0E+03	8.2E+03	2.0E+04				
Oblasia eta di Dhanailia a 5	μg/L	2.4E+02	9.5E+02	2.4E+03				
Chlorinated Phenolics ⁵	lbs/day	6.8E+01	2.7E+02	6.8E+02				
5 16 6	μg/L	2.1E+00	4.3E+00	6.4E+00				
Endosulfan ⁶	lbs/day	6.1E-01	1.2E+00	1.8E+00				
	μg/L	4.8E-01	9.5E-01	1.4E+00				
Endrin	lbs/day	1.4E-01	2.7E-01	4.1E-01				
7	μg/L	9.5E-01	1.9E+00	2.9E+00				
HCH ⁷	lbs/day	2.7E-01	5.5E-01	8.2E-01				

		Performance Goals ¹						
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average			
Radioactivity	pCi/L	Not to exceed limits specified in Title 17, Division 1, Chapter 5, Subchapte 4, Group 3, Article 3, Section 30253 of the California Code of Regulations, Reference to Section 30253 is prospective, including future changes to an incorporated provisions of federal law, as the changes take effect.						
OBJECTIVE	S FOR P	ROTECTION OF H	UMAN HEALTH – I	NONCARCINOGEN	IS			
Acrolein	μg/L				5.2E+04			
Toroicin	lbs/day				1.5E+04			
Antimony	μg/L				2.9E+05			
Antimony	lbs/day				8.2E+04			
Bis(2-chloroethoxy)	μg/L				1.0E+03			
Methane	lbs/day				3.0E+02			
Bis(2-chloroisopropyl)	μg/L				2.9E+05			
Ether	lbs/day				8.2E+04			
Chlorobonzono	μg/L				1.4E+05			
Chlorobenzene	lbs/day				3.9E+04			
Chromium (III), Total	μg/L				4.5E+07			
Recoverable	lbs/day				1.3E+07			
D' a back i Dhillialata	μg/L				8.3E+05			
Di-n-butyl Phthalate	lbs/day				2.4E+05			
D: 11 8	μg/L				1.2E+06			
Dichlorobenzenes ⁸	lbs/day				3.5E+05			
D: 0 1 D: 0 1 4	μg/L				7.9E+06			
Diethyl Phthalate	lbs/day				2.3E+06			
D:	μg/L				2.0E+08			
Dimethyl Phthalate	lbs/day				5.6E+07			
40 " " 0 " 11 1	μg/L				5.2E+04			
4,6-dinitro-2-methylphenol	lbs/day				1.5E+04			
	μg/L				9.5E+02			
2,4-dinitrophenol	lbs/day				2.7E+02			
	μg/L				9.8E+05			
Ethylbenzene	lbs/day				2.8E+05			
	μg/L				3.6E+03			
Fluoranthene	lbs/day				1.0E+03			
	μg/L				1.4E+04			
Hexachlorocyclopentadiene	lbs/day				4.0E+03			
	μg/L				1.2E+03			
Nitrobenzene	lbs/day				3.3E+02			
Thallium, Total	µg/L				4.8E+02			
Recoverable					1.4E+02			
Recoverable	lbs/day				1.4E+02			

			Performar	nce Goals ¹	
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average
T	μg/L				2.0E+07
Toluene	lbs/day				5.8E+06
Tributyltin	μg/L				3.3E-01
Tributyitiii	lbs/day				9.6E-02
1 1 1 triphloroothono	μg/L				1.3E+08
1,1,1-trichloroethane	lbs/day				3.7E+07
OBJECT	IVES FOR	PROTECTION OF	HUMAN HEALTH	- CARCINOGENS	
	μg/L				2.4E+01
Acrylonitrile	lbs/day				6.8E+00
	μg/L				5.2E-03
Aldrin	lbs/day				1.5E-03
_	μg/L				1.4E+03
Benzene	lbs/day				4.0E+02
D	μg/L				1.6E-02
Benzidine	lbs/day				4.7E-03
Dan III	μg/L				7.9E+00
Beryllium	lbs/day				2.3E+00
Dia/O ablamanthud) Etham	μg/L				1.1E+01
Bis(2-chloroethyl) Ether	lbs/day				3.1E+00
D'- (O - the de annul) Die the alate	μg/L				8.3E+02
Bis(2-ethlyhexyl) Phthalate	lbs/day				2.4E+02
Carban Tatraablarida	μg/L				2.1E+02
Carbon Tetrachloride	lbs/day				6.1E+01
Chlorodono	μg/L				5.5E-03
Chlorodane	lbs/day				1.6E-03
Chloradibromomothono	μg/L				2.0E+03
Chlorodibromomethane	lbs/day				5.9E+02
Chloroform	μg/L				3.1E+04
Chloroform	lbs/day				8.9E+03
DDT ⁹	μg/L				4.0E-02
ו טט	lbs/day				1.2E-02
1.4 dichlorohenzene	μg/L				4.3E+03
1,4-dichlorobenzene	lbs/day				1.2E+03
2.2' diablorobonzidino	μg/L				1.9E+00
3,3'-dichlorobenzidine	lbs/day				5.5E-01
1.2 dichloroothons	μg/L				6.7E+03
1,2-dichloroethane	lbs/day				1.9E+03

	Performance Goals ¹						
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average		
1,1-dichloroethylene	μg/L				2.1E+02		
r, r-dichioroethylene	lbs/day				6.1E+01		
Dichlorobromomethane	μg/L				1.5E+03		
Dichiorobromomethane	lbs/day				4.2E+02		
Dichloromethane	μg/L				1.1E+05		
Dictiloromethane	lbs/day				3.1E+04		
1.2 diableronrones	μg/L				2.1E+03		
1,3-dichloropropene	lbs/day				6.1E+02		
Dialdria	μg/L				9.5E-03		
Dieldrin	lbs/day				2.7E-03		
O. A. dissituated come	μg/L				6.2E+02		
2,4-dinitrotoluene	lbs/day				1.8E+02		
4.0 diabandania	μg/L				3.8E+01		
1,2-diphenylhydrazine	lbs/day				1.1E+01		
	μg/L				3.1E+04		
Halomethanes ¹⁰	lbs/day				8.9E+03		
	μg/L				4.8E-03		
Heptachlor Epoxide	lbs/day				1.4E-03		
Harrack Lands are a second	μg/L				5.0E-02		
Hexachlorobenzene	lbs/day				1.4E-02		
l lava alala na lavita di ana	μg/L				3.3E+03		
Hexachlorobutadiene	lbs/day				9.6E+02		
I lava ablana athan a	μg/L				6.0E+02		
Hexachloroethane	lbs/day				1.7E+02		
la ambanana	μg/L				1.7E+05		
Isophorone	lbs/day				5.0E+04		
NI selfano e a discontinuo de serio e	μg/L				1.7E+03		
N-nitrosodimethylamine	lbs/day				5.0E+02		
NI - Mars	μg/L				9.0E+01		
N-nitrosodi-N-propylamine	lbs/day				2.6E+01		
N 1 '4 P 1 1 1	μg/L				6.0E+02		
N-nitrosodiphenylamine	lbs/day				1.7E+02		
DALI-11	μg/L				2.1E+00		
PAHs ¹¹	lbs/day				6.0E-01		
DOD-12	μg/L				4.5E-03		
PCBs ¹²	lbs/day				1.3E-03		
440044	μg/L				5.5E+02		
1,1,2,2-tetrachloroethane	lbs/day				1.6E+02		

		Performance Goals ¹				
Parameter	Unit	6-Month Median	Maximum Daily	Instantaneous Maximum	30-Day Average	
Tetrachloroethylene	μg/L				4.8E+02	
retracilloroethylene	lbs/day				1.4E+02	
Toxaphene	μg/L				5.0E-02	
	lbs/day				1.4E-02	
Trichloroethylene	μg/L				6.4E+03	
Trichioroethylene	lbs/day				1.8E+03	
1 1 2 triphloroothono	μg/L				2.2E+03	
1,1,2-trichloroethane	lbs/day				6.4E+02	
2.4.6 triphlorophonol	μg/L				6.9E+01	
2,4,6-trichlorophenol	lbs/day				2.0E+01	
Vinyl Chlorida	μg/L				8.6E+03	
Vinyl Chloride	lbs/day				2.5E+03	

Scientific "E" notation is used to express certain values. In scientific "E" notation, the number following the "E" indicates that position of the decimal point in the value. Negative numbers after the "E" indicate that the value is less than 1, and positive numbers after the "E" indicate that the value is greater than 1. In this notation a value of 6.1E-02 represents 6.1 x 10^{-2} or 0.061, 6.1E+02 represents 6.1 x 10^{-2} or 610, and 6.1E+00 represents 6.1 x 10^{-2} or 6.1.

² Dischargers may, at their option, apply this performance goal as a total chromium performance goal.

Acute toxicity expressed as Acute Toxicity Units (TUa) = $100/LC_{50}$, where LC_{50} (Lethal Concentration 50%) is the percent waste giving 50% survival of test organisms.

Non-chlorinated phenolic compounds represent the sum of 2,4-dimethylphenol, 4,6-dinitro-2-methylphenol, 2,4-dinitrophenol, 2-methylphenol, 4-methylphenol, 2-nitrophenol, 4-nitrophenol, and phenol.

- ⁵ Chlorinated phenolic compounds represent the sum of 4-chloro-3-methylphenol, 2-chlorophenol, pentachlorophenol, 2,4,5-trichlorophenol, and 2,4,6-trichlorophenol.
- 6 Endosulfan represents the sum of alpha-endosulfan, beta-endosulfan, and endosulfan sulfate.
- HCH (hexachlorocyclohexane) represents the sum of the alpha, beta, gamma (Lindane), and delta isomers of hexachlorocyclohexane.
- Dichlorobenzenes represent the sum of 1,2- and 1,3-dichlorobenzene.
- DDT represents the sum of 4,4'DDT; 2,4'DDT; 4,4'DDE; 2,4'DDE; 4,4'DDD; and 2,4'DDD.
- Halomethanes represent the sum of bromoform, bromomethane (methyl bromide), and chloromethane (methyl chloride).
- PAHs (polynuclear aromatic hydrocarbons) represent the sum of acenapthalene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo[k]fluoranthene; 1,12-benzoperylene; benzo[a]pyrene; chrysene; dibenzo[a,h]anthracene; fluorene; indeno[1,2,3-cd]pyrene; phenanthrene; and pyrene.
- PCBs (polychlorinated biphenyls) represent the sum of chlorinated biphenyls whose analytical characteristics resemble those of Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Arolclor-1254, and Arcolor-1260.

F. Interim Effluent Limitations – Not Applicable

G. Land Discharge Specifications – Not Applicable

H. Reclamation Specifications

The SOCWA RTP, SOCWA CTP, Los Aliso WRP, and El Toro WRP shall continue to comply with reclamation requirements established in San Diego Water Board Order No. 97-52, and any applicable future revised to or reissuance WDRs.

V. RATIONALE FOR RECEIVING WATER LIMITATIONS

Receiving water limitations of this Order are derived from the water quality objectives for ocean waters established by the Basin Plan and the Ocean Plan.

Prior to this Order, the San Diego Water Board has interpreted the Bacterial Characteristics Water-contact Standards of the Ocean Plan (Receiving Water Limitations section V.A.1) to apply only in the zone bounded by the shoreline and a distance 1,000 feet from the shoreline or the 30-foot depth contour, whichever is further from the shoreline, and within kelp beds. The 2005 Ocean Plan also has language that these standards also apply in areas outside this zone used for water contact sports, as determined by the Regional Boards (i.e., waters designated as REC-1). These designations would need to be specified in the Basin Plan. Because the San Diego Water Board has not completed a process to designate specific areas where the water-contact standards apply, Ocean Plan Bacterial Standards apply throughout all ocean waters in the San Diego Region. This interpretation has been confirmed by the USEPA.

More than 1,200 total coliform samples were collected at the near shore and offshore monitoring locations during 2006 through 2010. During this 2006 through 2010 period, ACOO stations outside the zone of initial dilution (ZID) achieved 100 percent compliance with REC-1 single sample maximum standards for total coliform. Additionally, 100 percent of the monthly total coliform grab samples contained coliform concentrations less than the 30-day geometric mean REC-1 total coliform standard.

No fecal coliform samples exceeded the single sample maximum limit of 400 organisms per 100 ml. None of the monthly fecal coliform grab samples exceeded the REC-1 30-day geometric mean limit.

While 4 out of 420 enterococcus samples exceeded a concentration of 104 organisms per 100 ml (the REC-1 single sample maximum limit), only one exceedance occurred at a near-ZID station. The remaining three exceedances occurred in surface samples. According to the Discharger, these exceedances are unlikely to be related to the ACOO discharge due to thermal trapping effects on the discharge plume.

A total of six of 420 monthly enterococcus grab samples from the water surface at near shore monitoring locations exceeded a concentration of 35 organisms per 100 ml (the REC-1 30-day geometric mean limit). According to the Discharger, these exceedances also may not be related to the outfall discharge due to thermal plume trapping effects and distance from the outfall.

The Discharger assumes that they would likely have been able to reduce the geometric monthly mean concentrations to less than the REC-1 geometric mean limit had two or more enterococcus samples been collected during each month.

Receiving water data collected during the current NPDES period demonstrate that the Discharger has achieved almost 100 percent compliance with the Ocean Plan REC-1 standards in and near the ACOO ZID. As a result, the ACOO discharge does not discernibly impact bacteriological water quality or recreational beneficial uses. Thus, the 5-year compliance schedule, that was included in three recently adopted POTW Ocean Outfall NPDES Permits, is not included in this tentative Order.

VI. RATIONALE FOR MONITORING AND REPORTING REQUIREMENTS

40 CFR 122.48 requires that all NPDES permits specify requirements for recording and reporting monitoring results. CWC sections 13267 and 13383 authorize the San Diego Water Board to require technical and monitoring reports. The MRP (Attachment E) of this Order, establishes monitoring and reporting requirements to implement federal and State requirements. The following provides the rationale for the monitoring and reporting requirements contained in the MRP for the Facilities.

A. Influent Monitoring

Influent monitoring is required to assess the performance of treatment facilities and to evaluate compliance with effluent limitations. Influent monitoring frequencies and sample types for flow, CBOD $_5$, BOD $_5$, and TSS have been retained from Order No. R9-2006-0055 for the SOCWA RTP, SOCWA CTP, Los Alisos WRP, and El Toro WRP. Monitoring the influent for CBOD $_5$ and TSS is necessary for determining compliance with the secondary treatment percent removal requirements. Sampling for BOD $_5$ is required to monitor the non-carbonaceous oxygen demand of the effluent from the wastewater treatment plants.

B. Effluent Monitoring

Effluent monitoring is required to determine compliance with the permit conditions, to identify operational problems, to improve plant performance, and to conduct reasonable potential analyses for subsequent Orders. Effluent monitoring also provides information on wastewater characteristics for use in interpreting water quality and biological data. Effluent monitoring has been required for each of the discharges into the ACOO collection system, prior to commingling with other discharges contributing to the ACOO, to determine compliance with the applicable technology-based effluent limitations. Effluent monitoring to determine compliance with WQBELs is required at a location where representative samples of commingled effluent from all contributors to the ACOO can be taken (Monitoring Location M-001).

Except as described below, all effluent monitoring types and frequencies from Order No. 2006-0055 are retained this Order.

The MRP (Attachment E) of this Order includes conductivity effluent monitoring at M-001E, M-001F, and M-001G to assist the San Diego Water Board in the evaluation of the ROWD and to conduct reasonable potential analyses for subsequent Orders.

The MRP (Attachment E) of this Order modifies the sample type specified in Order No. R9-2006-0055 for turbidity, nonchlorinated and chlorinated phenolics, endosulfan, endrin, and hexachlorocyclohexane isomers (HCH), from composite to grab. The Ocean Plan Table A specifies turbidity objectives as an instantaneous maximum and a grab sample is more appropriate for the Facilities to determine compliance with this objective. For nonchlorinated and chlorinated phenolics, endosulfan, endrin, and HCH, methods approved under 40 CFR Part 136 specify amber glass containers and other specialized materials for sample containers and automatic samplers to avoid degradation and introduction of interfering analytes. As such, it may be difficult to appropriately equip automatic samplers or to manually collect composites.

The MRP (Attachment E) of this Order modifies the sample frequency specified in Order No. R9-2006-0055 for toxic metals, cyanide, phenolics, endosulfan, endrin, HCH, and radioactivity from quarterly to semiannually, as requested in the ROWD. Consistent with the findings for Order No. R9-2006-0055, there was no reasonable potential for any of these parameters to exceed Ocean Plan objectives, and monitoring during the current permit term indicates consistent compliance with the applicable performance goals.

C. Whole Effluent Toxicity Testing Requirements

As described in section IV.C.5 of the Fact Sheet, the requirement to perform acute WET testing will be retained in this Order. However, based on the acute WET testing results provided by the Discharger during the previous permit term, monitoring will be reduced from monthly to quarterly.

The existing monthly chronic WET testing requirements are being retained in this Order because the chronic WET test data provided during the previous permit term indicated reasonable potential to exceed Ocean Plan objectives. The monthly monitoring requirements will be used to determine compliance with the effluent limit based on Ocean Plan Table B water quality objectives and evaluate any potential synergistic effects in the effluent.

D. Receiving Water Monitoring

1. Surface Water

a. Microbiological (Near Shore and Off Shore)

Recognizing that significant water-contact recreation, such as surfing and scuba diving, occurs year-round in ocean waters that may be impacted by the discharge from the ACOO, the San Diego Water Board required surf zone monitoring twice per week in Order No R9-2006-0055. These potential impacts remain as a result of the discharge from the ACOO and therefore this Order retains the requirements of Order No. 2006-0055 for surf zone water quality monitoring.

In the ROWD, the Discharger requested that the surf zone monitoring frequency be reduced from twice per week to once a week. This same request was made for the previous permit reissuance. In response to this request, Order No. R9-2006-0055 required the Discharger to prepare and submit a special study to properly asses the opportunity for more equitable distribution of surf zone monitoring requirements. The Discharger submitted this report on April 30, 2007; however, a final collaborative beach water quality monitoring program to equitably distribute surf zone monitoring has not been put in place. Until the collaborative effort is in place and the Discharger obtains approval from the San Diego Water Board through a monitoring program revision, the Discharger is still required to monitoring the surf zone twice per week.

In the ROWD, the Discharger requested the elimination of bacteriological monitoring at Station S15 and S16. They report that these stations are well beyond the influence of the SJCOO. Their requests, however, is denied at this time until, as stated in the previous paragraph, the collaborative effort is in place and the Discharger obtains approval from the San Diego Water Board through a monitoring program revision.

b. Near and Off Shore Water Quality Monitoring

The near shore and off shore water quality sampling program is designed to help evaluate the fate of the wastewater plume under various conditions and to determine if the Ocean Plan standards are being negatively impacted by the discharge. Further, bacterial sampling is required to provide data to help track the wastewater plume in the offshore waters, to evaluate compliance with recreational water standards in the kelp beds, and to address issues of beach water quality at the shoreline stations. Monitoring requirements for total coliform organisms, fecal coliform organisms, and enterococcus bacteria have been established in this Order, consistent with Order No. R9-2006-0055

c. Benthic Monitoring

Sediment and infauna monitoring is required to help evaluate the potential effects of the discharge on the physical and chemical properties of the sediment and biological communities in the vicinity of the discharge, consistent with Order No. R9-2006-0055.

E. Other Monitoring Requirements

- 1. Kelp Bed Monitoring. Kelp bed monitoring is intended to assess the extent to which the discharge of wastes may affect the aerial extent and health of coastal kelp beds. The aerial extent of the various kelp beds photographed in each survey will provide a baseline for future monitoring to help evaluate any significant and persistent losses to the kelp beds. This Order specifically requires the Discharger to participate with other ocean Dischargers in the San Diego Region in an annual regional kelp bed photographic survey.
- 2. Regional Monitoring. The purpose of regional monitoring programs (such as the Southern California Bight Regional Monitoring Program, which is coordinated by the Southern California Coastal Water Research Project) is to address questions about conditions in and influences on water bodies with regard to beneficial uses. This is done using scientifically sound and cost-effective monitoring designs and coordinating the efforts of various parties involved in monitoring. The Discharger is required to participate in regional monitoring programs pursuant to 40 CFR 122.48 and CWC sections 13225, 13267, and 13383.

The Discharger may request to reduce the level of effort devoted to other monitoring so that resources can be reallocated to regional monitoring by submitting a proposal to the San Diego Water Board and USEPA for such changes (including sampling, analytical, and/or reporting work).

3. Solids Monitoring. The Discharger is required to monitor solids generated at the Facilities pursuant to 40 CFR Part 503. The Discharger shall report, annually, the volume of screenings, sludges, grit, and other solids generated and/or removed during wastewater treatment and the locations where these waste materials are placed for disposal.

VII. RATIONALE FOR PROVISIONS

A. Standard Provisions

Standard Provisions, which apply to all NPDES permits in accordance with 40 CFR 122.41, and additional conditions applicable to specified categories of permits in accordance with 40 CFR 122.42, are provided in Attachment D to the Order.

40 CFR 122.41(a)(1) and (b) through (n) establish conditions that apply to all State-issued NPDES permits. These conditions must be incorporated into the permits either expressly or by reference. If incorporated by reference, a specific citation to the regulations must be included in the Order. 40 CFR 123.25(a)(12) allows the State to omit or modify conditions to impose more stringent requirements. In accordance with 40 CFR 123.25, this Order omits federal conditions that address enforcement authority specified in 40 CFR 122.41(j)(5) and (k)(2) because the enforcement authority under the CWC is more stringent. In lieu of these conditions, this Order incorporates by reference CWC section 13387(e).

B. Special Provisions

1. Reopener Provisions

This Order may be re-opened and modified, revoked and reissued, or terminated in accordance with the provisions of 40 CFR Parts 122, 123, 124, and 125. The San Diego Water Board may reopen the permit to modify permit conditions and requirements. Causes for modifications include the promulgation of new regulations, modification in sludge use or disposal practices, or adoption of new regulations by the State Water Board or the San Diego Water Board, including revisions to the Basin Plan.

2. Special Studies and Additional Monitoring Requirements

a. Spill Prevention and Response Plans

The CWA largely prohibits any discharge of pollutants from point sources to waters of the United States except as authorized under a NPDES permit. In general, any point source discharge of sewage effluent to waters of the United States must comply with technology-based, secondary treatment standards, at a minimum, and any more stringent requirements necessary to meet applicable water quality standards and other requirements. The unpermitted discharge of wastewater to waters of the United States is illegal under the CWA. Further, the Basin Plan prohibits discharges of waste to land, except as authorized by WDRs or the terms described in CWC section 13264. The Basin Plan also prohibits the unauthorized discharge of treated or untreated sewage to waters of the State or to a storm water conveyance system. Further, Discharge Prohibition III.A of the Order prohibits the discharge of waste from the Facilities to a location other than Discharge Point No. 001.

Sanitary collection and treatment systems experience periodic failures resulting in discharges that may affect waters of the State. There are many factors which may affect the likelihood of a spill. To ensure appropriate funding, management, and planning to reduce the likelihood of a spill, and increase the spill preparedness, this Order requires the Discharger to maintain and implement Spill Prevention and Response Plans.

b. Spill Reporting Requirements

To determine compliance with Discharge Prohibition III.A and provide appropriate notification to the general public for the protection of public health, spill reporting requirements have been established in VI.C.2.b of this Order.

c. Whole Effluent Toxicity (WET)

Implementing provisions at section III.C.4.c.(3) of the Ocean Plan require chronic toxicity monitoring for ocean waste discharges with minimum initial dilution factors ranging from 100:1 to 350:1 and that the Regional Water Quality Control Boards may also require acute toxicity monitoring in addition to chronic for the protection of beneficial uses of ocean waters. Based on methods of the California Ocean Plan, a maximum daily effluent limitation of 238 TUc is established in this Order and monthly monitoring is retained from Order No. R9-2006-0055. In addition, the San Diego Water Board is including a performance goal of 72 TUa and the requirement to conduct acute toxicity monitoring.

This Order requires the Discharger to develop a Toxicity Reduction Evaluation (TRE) workplan, and submit the TRE workplan within 180 days of the effective date of this Order. The workplan shall describe steps the Discharger intends to follow if the limitation for chronic toxicity (238 TUc) is exceeded or if the performance goal for acute toxicity (72 TUa) is exceeded.

If the limitation or performance goals for chronic and/or acute toxicity is exceeded, then within 15 days of the exceedance, the Discharger shall begin conducting six additional tests, bi-weekly, over a 12-week period. If the toxicity effluent limitation/performance goal is exceeded in any of these six additional tests, then the Discharger shall notify the San Diego Water Board. If the San Diego Water Board determines that the discharge consistently exceeds a toxicity effluent limitation or performance goal, then the Discharger shall initiate a TRE/TIE in accordance with the TRE workplan, *Toxicity Reduction Evaluation Guidance for Municipal Wastewater Treatment Plants* (USEPA 833-B-99-002, 1999), and USEPA Toxicity Identification Evaluation (TIE) guidance documents (Phase I, EPA/600/6-91/005F, 1992; Phase II, EPA/600/R-92/080, 1993; and Phase III, EPA/600/R-92/081, 1993). If no toxicity is detected in any of these additional six tests, then the Discharger may return to the testing frequency specified in the MRP.

- 3. Best Management Practices and Pollution Prevention Not Applicable
- 4. Construction, Operation, and Maintenance Specifications Not Applicable
- 5. Special Provisions for Wastewater Facilities
 - a. Aliso Creek Outfall Capacity

To ensure that sufficient capacity is available to accommodate potential growth in the future, this Order requires the Discharger to evaluate the capacity of the ACOO during the term of the permit and submit their findings to the San Diego Water Board.

b. Treatment Plant Capacity

Order No. R9-2006-0055 required the Discharger to submit a written report to the Executive Officer within 90 days after the monthly average influent flow rate equals or exceeds 75 percent of the secondary treatment design capacity of each of the POTWs regulated under this Order. Wastewater flow projections for the tributary drainage area indicate that this flow rate will not be exceeded at ultimate conditions. Therefore, in lieu of a written report for each time the monthly average influent flow rate equals or exceeds 75 percent of the secondary treatment design capacity, the requirement has been changed to require the report be submitted four years prior to the time wastewater flow are projected to reach plant capacity, as stated in Title 23, section 2232 of the CCR. The revised requirement states:

For each POTW regulated under this Order and four years prior to reaching plant design capacity, the Discharger shall submit a Treatment Plant Capacity report to the San Diego Water Board showing how flow volumes will be prevented from exceeding existing capacity or how capacity will be increased. A notification and copy of the report shall be sent to appropriate local elected officials, local permitting agencies, and the press. The required technical report shall be reviewed, approved, and jointly submitted by all planning and building departments having jurisdiction in the area served by the POTW. Opportunities for public participation and involvement are required during the preparation and development of the technical report. The report shall be accompanied by a statement outlining how interested persons were involved in the preparation of the technical report.

If the San Diego Water Board finds that the technical report indicates adequate steps are not being taken to address the capacity problem, the San Diego Water Board will adopt a time schedule order or other enforcement order. Such action will be preceded by notice and a hearing.

c. Pretreatment Program

The federal CWA section 307(b), and federal regulations, 40 CFR Part 403, require POTWs to develop an acceptable industrial pretreatment program. A pretreatment program is required to prevent the introduction of pollutants, which will interfere with treatment plant operations or sludge disposal, and prevent pass through of pollutants that exceed water quality objectives, standards, or permit limitations. Pretreatment requirements are imposed pursuant to 40 CFR Part 403.

The Discharger shall implement and enforce its approved pretreatment program and is an enforceable condition of this Order. If the Discharger fails to perform the pretreatment functions, the San Diego Water Board, the State Water Board, or USEPA may take enforcement actions against the Discharger as authorized by the CWA.

In January 2011, a Pretreatment Compliance Inspection (PCI) was performed of the SOCWA pretreatment program. The inspection included SOCWA's 2008 technical review of its local limits, as required under Order No. R9-2006-0055. The PCI report concluded that the local limits are not technically based, but have provided adequate protection for the POTWs. In the ROWD, the Discharger requested that the requirement to review the local limits be removed. Based on the results of the PCI and the requirements under 40 CFR 122.44(j)(2)(ii), however, the San Diego Water Board will

require as part of this Order that the Discharger provide a written technical evaluation of the need to revise local limits under 40 CFR 403.5(c)(1).

In the ROWD, the Discharger requested the requirement to continue its implementation of a Non-Industrial Source Control Program be eliminated since it is no longer applicable, This request was granted and the requirement was not carried over to this Order.

d. Sludge (Biosolids Disposal Requirements

The use and disposal of biosolids is regulated under federal and State laws and regulations, including permitting requirements and technical standards included in 40 CFR Part 503. The Discharger is required to comply with the standards and time schedules contained in 40 CFR Part 503.

Title 27, Division 2, Subdivision 1, section 20005 of the California Code of Regulations establishes approved methods for the disposal of collected screenings, residual sludge, biosolids, and other solids removed from liquid wastes. Requirements to ensure the Discharger disposes of solids in compliance with State and federal regulations have been included in this Order.

e. Collection System

The State Water Board issued General Waste Discharge Requirements for Sanitary Sewer Systems, Water Quality Order No. 2006-0003-DWQ (General Order) on May 2, 2006. The General Order requires public agencies that own or operate sanitary sewer systems with greater than 1 mile of pipes or sewer lines to enroll for coverage under the General Order. The General Order requires agencies to develop sanitary sewer management plans (SSMPs) and report all sanitary sewer overflows (SSOs), among other requirements and prohibitions.

Furthermore, the General Order contains requirements for operation and maintenance of collection systems and for reporting and mitigating SSOs. Public agencies that are discharging wastewater into the Facilities were required to obtain enrollment for regulation under the General Order by December 1, 2006.

At this time, the Discharger does not own or operate the collection systems from which it receives wastewater.

6. Other Special Provisions – Not Applicable

7. Compliance Schedules – Not Applicable

VIII. PUBLIC PARTICIPATION

The San Diego Water Board is considering the issuance of WDRs that will serve as a NPDES permit for the Facilities. As a step in the WDR adoption process, the San Diego Water Board staff has developed tentative WDRs. The San Diego Water Board encourages public participation in the WDR adoption process.

A. Notification of Interested Parties

The San Diego Water Board has notified the Discharger and interested agencies and persons of its intent to prescribe WDRs for the discharge and has provided them with an opportunity to submit their written comments and recommendations. Notification was published in the Orange County Registry on January 23, 2012 and posted on the San Diego Water Board web site on January 23, 2012.

B. Written Comments

The staff determinations are tentative. Interested persons are invited to submit written comments concerning these tentative WDRs. Comments must be submitted either in person or by mail to the San Diego Water Board at the address above on the cover page of this Order.

To be fully responded to by staff and considered by the San Diego Water Board, written comments must be received at the San Diego Water Board offices by 5:00 p.m. on February 20, 2012.

C. Public Hearing

The San Diego Water Board will hold a public hearing on the tentative WDRs during its regular board meeting on the following date and time and at the following location:

Date: April 11, 2012 Time: 9:00 AM

Location: Mission Viejo City Council Chambers

200 Civic Center

Mission Viejo, CA 92691

Interested persons are invited to attend. At the public hearing, the San Diego Water Board will hear testimony, if any, pertinent to the discharge, WDRs, and permit. Oral testimony will be heard; however, for accuracy of the record, important testimony should be in writing.

Please be aware that dates and venues may change. Our Web address is http://www.waterboards.ca.gov/sandiego/ board_info/agendas/ where you can access the current agenda for changes in dates and locations.

D. Waste Discharge Requirements Petitions

Any aggrieved person may petition the State Water Board to review the decision of the San Diego Water Board regarding the final WDRs. The petition must be submitted within 30 days of the San Diego Water Board's action to the following address:

State Water Resources Control Board Office of Chief Counsel P.O. Box 100, 1001 I Street Sacramento, CA 95812-0100

E. Information and Copying

The Report of Waste Discharge (RWD), related documents, tentative effluent limitations and special provisions, comments received, and other information are on file and may be inspected at the address above on the cover page of this Order at any time between 8:30 a.m. and 4:45 p.m., Monday through Friday. Copying of documents may be arranged through the San Diego Water Board by calling (858) 467-2952.

F. Register of Interested Persons

Any person interested in being placed on the mailing list for information regarding the WDRs and NPDES permit should contact the San Diego Water Board, reference this facility, and provide a name, address, and phone number.

G. Additional Information

Requests for additional information or questions regarding this Order should be directed to Joann Lim or (858) 637-5589.

ATTACHMENT G – DISCHARGE PROHIBITIONS CONTAINED IN THE OCEAN PLAN AND BASIN PLAN

I. Ocean Plan Discharge Prohibitions

- 1. The Discharge of any radiological chemical, or biological warfare agent or high-level radioactive waste into the ocean is prohibited.
- 2. Waste shall not be discharged to designated Areas of Special Biological Significance except as provided in Chapter III.E. of the Ocean Plan.
- 3. Pipeline discharge of sludge to the ocean is prohibited by federal law; the discharge of municipal and industrial waste sludge directly to the ocean, or into a waste stream that discharges to the ocean, is prohibited. The discharge of sludge digester supernatant directly to the ocean, or to a waste stream that discharges to the ocean without further treatment, is prohibited.
- 4. The by-passing of untreated wastes containing concentrations of pollutants in excess of those of Table A or Table B [of the Ocean Plan] is prohibited.

II. Basin Plan Discharge Prohibitions

- 1. The discharge of waste to waters of the State in a manner causing, or threatening to cause a condition of pollution, contamination or nuisance as defined in CWC section 13050, is prohibited.
- 2. The discharge of waste to land, except as authorized by WDRs or the terms described in CWC section 13264 is prohibited.
- 3. The discharge of pollutants or dredged or fill material to waters of the United States except as authorized by an NPDES permit or a dredged or fill material permit (subject to the exemption described in CWC section 13376) is prohibited.
- 4. Discharges of recycled water to lakes or reservoirs used for municipal water supply or to inland surface water tributaries thereto are prohibited, unless this San Diego Water Board issues a NPDES permit authorizing such a discharge; the proposed discharge has been approved by the State of California Department of Public Health and the operating agency of the impacted reservoir; and the discharger has an approved fail-safe long-term disposal alternative.
- 5. The discharge of waste to inland surface waters, except in cases where the quality of the discharge complies with applicable receiving water quality objectives, is prohibited. Allowances for dilution may be made at the discretion of the San Diego Water Board. Consideration would include streamflow data, the degree of treatment provided and safety measures to ensure reliability of facility performance. As an example, discharge of secondary effluent would probably be permitted if streamflow provided 100:1 dilution capability.
- The discharge of waste in a manner causing flow, ponding, or surfacing on lands not owned or under the control of the discharger is prohibited, unless the discharge is authorized by the San Diego Water Board.

- 7. The dumping, deposition, or discharge of waste directly into waters of the State, or adjacent to such waters in any manner which may permit its being transported into the waters, is prohibited unless authorized by the San Diego Water Board.
- 8. Any discharge to a storm water conveyance system that is not composed entirely of storm water is prohibited unless authorized by the San Diego Water Board. [The federal regulations, 40 CFR 122.26(b)(13), define storm water as storm water runoff, snow melt runoff, and surface runoff and drainage. 40 CFR 122.26(b)(2) defines an illicit discharge as any discharge to a storm water conveyance system that is not composed entirely of storm water except discharges pursuant to a NPDES permit and discharges resulting from fire fighting activities.] [Section 122.26 amended at 56 FR 56553, November 5, 1991; 57 FR 11412, April 2, 1992].
- 9. The unauthorized discharge of treated or untreated sewage to waters of the State or to a storm water conveyance system is prohibited.
- 10. The discharge of industrial wastes to conventional septic tank/ subsurface disposal systems, except as authorized by the terms described in CWC section 13264, is prohibited.
- 11. The discharge of radioactive wastes amenable to alternative methods of disposal into the waters of the State is prohibited.
- 12. The discharge of any radiological, chemical, or biological warfare agent into waters of the State is prohibited.
- 13. The discharge of waste into a natural or excavated site below historic water levels is prohibited unless the discharge is authorized by the San Diego Water Board.
- 14. The discharge of sand, silt, clay, or other earthen materials from any activity, including land grading and construction, in quantities which cause deleterious bottom deposits, turbidity or discoloration in waters of the State or which unreasonably affect, or threaten to affect, beneficial uses of such waters is prohibited.

ATTACHMENT H - DILUTION MODEL INFORMATION

Initial dilution for the Aliso Creek Ocean Outfall (ACOO) was assessed using an U.S. Environmental Protection Agency (USEPA) modeling application, Visual Plumes (UM3). UM3 is an acronym for the three-dimensional Updated Merge model for simulating single and multi-port submerged discharges. The USEPA Visual Plumes website is located at http://www.epa.gov/ceampubl/swater/vplume/.

The ACOO is a diffuser, which is oriented collinear with the outfall. Offshore, the outfall extends 7,900 feet from the shoreline to the end of the diffuser. The length of diffuser is 1,200 feet (collinear to the outfall in its entirety). The diffuser has 200 discharge ports, which are spaced in 12 feet intervals on alternating sides. Port diameters are constant at 2.0 inches for the length of the diffuser.

A. Dilution

Initial dilution is defined in the Ocean Plan as follows:

"The process which results in the rapid and irreversible turbulent mixing of wastewater with ocean water around the point of discharge.

For a submerged buoyant discharge, characteristic of most municipal and industrial wastes that are released from the submarine outfalls, the momentum of the discharge and its initial buoyancy act together to produce turbulent mixing. Initial dilution in this case is completed when the diluting wastewater ceases to rise in the water column and first begins to spread horizontally."

Initial dilution, as defined by the Ocean Plan, is interpreted to be when the effluent plume either surfaces or reaches its initial trapping level (level at which the density of the effluent equals that of the ambient background and the effluent no longer has upward momentum based solely on buoyancy).

Dilution is a function of various characteristics of the diffuser, effluent, and ambient background. Dilution of an effluent plume into a receiving water is dependent on the flow of effluent, the momentum of the effluent flow into the receiving water (highly dependent on the effluent flow, shape, size, and number of diffuser ports), the buoyancy of the effluent within the receiving water (highly dependent between the delta between effluent and the ambient background of salinity and temperature), the placement of diffuser ports (space between diffuser ports and directional settings of each port), and the available volume and boundaries of the receiving water.

To effectively model dilution, Visual Plumes breaks data entry into the modeling system into three main components:

- 1. Diffuser and Effluent Characteristics
- 2. An Ambient Profile
- 3. Special Settings

NPDES NO. CA0107611

A summary of each of these components and the assumptions for each of these components while conducting the modeling effort is provided below.

B. Diffuser and Effluent Characteristics

Diffuser and effluent characteristics are necessary to determine the momentum of the effluent as it enters the receiving water and the density of the effluent (which will affect its buoyancy in the receiving water).

The input fields for the model are listed below with applicable explanations for the input into each field:

1. Port Diameter

In the Report of Waste Discharge (ROWD), the Discharger provided a summary of the diffuser geometry, including the number of ports and their respective diameters. Visual Plumes data entry limitations include only allowing a single input for "Port Diameter". Thus, a single port diameter must be determined. In cases where the port diameter varies along the length of the diffuser, an average port diameter is used in the modeling effort. In the case of the ACOO, all ports along the length of the diffuser possess a diameter of 2.0 inches. Therefore, a port diameter of 2.0 inches was input to Visual Plumes.

2. Port Elevation

The port elevation (or height of the port from the seabed) was not specified in the ROWD. On October 25, 2011, the Discharger provided supplementary information indicating that the elevation of the ports was 32 inches. Based on this information, a port elevation of 32 inches was used in the model.

3. Vertical Angle

The vertical angle is defined in the Visual Plumes manual (4th Edition) as the discharge angle relative to the horizontal with zero being horizontal, 90 being vertical upward, and -90 being vertically downward. The ROWD indicates that the ports are located at -5 degrees from the horizontal on either side of the diffuser. A data entry limitation of Visual Plumes is that only one vertical angle may be entered. In cases where there is potential for two plumes emitted from different angles on the diffuser to merge within the water column, the Visual Plumes manual suggests modeling the diffuser as if all ports are on one side of the diffuser and with half the spacing. In situations where the potential for plume merging is considered to be negligible, an alternative approach is to model one-half of the diffuser (i.e., one plume) and assume no cross-merging of plumes.

Because the plumes from each side of the diffuser are assumed to have the potential to merge, both sides of the diffuser have been included in the simulation (i.e., all ports are treated as if they are on one side of the diffuser and with half the spacing). An effluent flow of 34.37 MGD and a single vertical angle of -5 degrees were used in the model.

NPDES NO. CA0107611

4. Horizontal Angle

The horizontal angle is defined in the Visual Plumes manual as the angle of the diffuser relative to the x-coordinate. Assuming that the default units (degrees) are used, zero is in the direction of the x-coordinate (flow towards the east) and 90 in the direction of the y-coordinate (flow towards the north).

A data entry limitation of Visual Plumes is that only one vertical angle may be entered. This field is important when considering currents and stream flow, both of which are not considered when modeling for discharges to which the Ocean Plan is applicable. Since these elements are not being considered in this simulation and since the horizontal angle entry field does not have an impact on the final initial dilution, an angle of 0 degrees was entered into this field.

5. Number of Ports

The number of ports specified in the ROWD (and summarized in the Port Diameter portion of this Attachment) is 200 ports. These ports alternate on each side of the diffuser.

6. Port Spacing

The ROWD indicated that the ports were approximately 12 feet apart. Since both sides of the diffuser are being modeled on one side of the diffuser, a value of 6 feet was entered into the model.

7. Acute Mix Zone/Chronic Mix Zone

This value is not relevant to the final initial dilution calculations and has no impact on model output. The Visual Plumes software requires that a value be entered into these fields. Therefore, 1 m was entered into each field.

8. Port Depth

The ROWD indicates that the diffuser discharge depth is 170 feet at the inshore end of the diffuser and 195 feet at the offshore end of the diffuser. An average depth of 182.5 feet was computed and was used in the model.

9. Effluent Flow

The maximum monthly average flow permitted for the Discharger is 32.20 million gallons per day (MGD) The Discharger has requested an increase to 34.37 MGD in order to accommodate discharges from the Irvine Desalter Project (IDP) and the Aliso Creek Water Harvesting Project (ACWHP). The Discharger currently discharges a monthly average flow significantly below the proposed permitted flow, which would result in a greater (and less conservative) dilution value. Because the Discharger will continue to be capable of discharging up to 34.37 MGD, and this is the most conservative value to use when modeling dilution, 34.37 MGD was considered to be the applicable discharge volume through the outfall and this value was entered into the effluent flow field.

10. Effluent Conductivity

The Discharger provided monthly average effluent conductivity data for the period January 2009 through May 2011. In order to provide consistency with the available temperature data, discussed in section 11, monthly average conductivities were computed for each month across the span of the available data (i.e., the mean conductivity value for January was computed using the January 2009, January 2010, and January 2011 data). Higher levels of salinity in the effluent result in a less buoyant effluent and provide a conservative estimate of dilution. The highest average monthly conductivity observed was 1.790 mmhos/cm.

As discussed in section 9, the Discharger is requesting a 0.9 MGD increase in permitted flow to accommodate the IDP and ACWHP. Additional brine and treated groundwater from these facilities will be substantially more saline than the existing outfall discharge. Therefore, the San Diego Water Board developed an estimated post-expansion outfall conductivity using a mass balance approach. Based on supplementary information provided by the Discharger, the San Diego Water Board has assumed an average effluent conductivity value of 2.850 mmhos/cm at the IDP SGU and 8 mmhos/cm at the ACWHP. Estimated effluent conductivity at the outfall was estimated using the following equation:

$$C_0 = ((Q_{IDP} \times C_{IDP}) + (Q_{ACWHP} \times C_{ACWHP}) + (Q_{ex} \times C_{ex})) / (Q_{IDP} + Q_{ACWHP} + Q_{ex})$$

Where.

C_o = Estimated Outfall Conductivity (mmhos/cm)

C_{IDP} = IDP Conductivity (2.850 mmhos/cm) C_{ACWHP} = IDP Conductivity (8.0 mmhos/cm)

C_{ex} = Conductivity of Existing Discharge (1.790 mmhos/cm)

 Q_{IDP} = IDP SGU Flow (0.85 MGD) Q_{ACWHP} = ACWHP Flow (0.32 MGD)

Q_{ex} = Existing Discharge Permitted Flow (33.20 MGD)

An estimated outfall conductivity of 1.874 mmhos/cm was computed and used in the model.

11. Effluent Temperature

The Discharger provided average Monthly temperature data from 2007 through 2010 (i.e., January data for 2007-2010 was averaged to provide a mean January temperature). The density of water is a function of temperature. Therefore, a smaller difference in temperature between the effluent and receiving waters (i.e., Δ) will produce a relatively smaller difference between the densities of the effluent and receiving waters and less dilution is likely to occur. Receiving water temperatures are significantly lower than the temperature of the effluent discharged from the ACOO. Thus, a lower effluent temperature is likely to result in lower dilution. The lowest monthly average temperature of 69°F was entered into the data field.

12. Effluent Concentration

This data field is for calculating "effective dilution" and does not have an effect on the final initial dilution calculated. However a value must be entered into this field for the model to run, so "20 ppm" was chosen.

C. Ambient Profile

1. An ambient profile is a conservative profile of the receiving water. This profile includes components of density (temperature and salinity), current (which is always set to zero when running models for the Ocean Plan), and a far-field diffusion coefficient. The ambient profile takes into consideration the natural stratification of the receiving waters, allowing for the entry of various data points at varying depths. The model is capable (and this feature was utilized during the modeling effort for Point Loma Ocean Outfall) of extrapolating data for the depths that were not entered based on the data that is entered. The extrapolation feature was utilized for this modeling effort.

Receiving water monitoring of temperature and salinity was established during the current permit term at the following monitoring locations, which are representative of the receiving water at the point of discharge:

- Monitoring Location A1
- Monitoring Location A2
- Monitoring Location A3
- Monitoring Location A4
- Monitoring Location A5

The Monitoring and Reporting Program for Order No. R9-2006-0055 states that the monitoring locations are arranged at the corners of a 1,000 ft x 1,000 ft square having one side parallel to shore and the intersection of its diagonals located at the center of the outfall diffuser sections.. Monitoring Location A1 is located on the northeastern corner of the square and Monitoring Locations A2 – A4 at successive corners in a clockwise direction. Monitoring Location A5 is located at the intersection of the diagonals over the diffuser.

Ambient monitoring data was provided by the Discharger for Monitoring Locations A1 – A5. The ACOO is located near Dana Point and is under the influence of the California Counter, which flows from the northwest to the southeast. Currents near the outfall are expected to in general push the plume to the southeast. Monthly ambient profiles for Monitoring Location A3 were selected for use in the modeling effort because Monitoring Location A3 is likely to be the least influenced by the existing discharge plume from the outfall.

Part C.3.d of the California Ocean Plan states:

"For the purpose of this Plan, minimum initial dilution is the lowest average initial dilution within any single month of the year."

Using data from July 2008 through June 2009, the ambient profile providing the most conservative estimate of initial dilution was the March 2009 profile. Dilution estimates developed on the basis of the provided ambient profiles at Monitoring Location A3 are provided in section E, below.

Based on the Discharger's results, the ambient profile for March 2009 provided the most conservative estimate of dilution. The following ambient profile for March 2009 was used to calculate the final initial dilution by the San Diego Water Board using Visual Plumes:

Depth (m)	Temperature (°C)	Salinity (psu)
0	14.2966	33.3504
1	14.2896	33.3502
2	14.3001	33.3507
3	14.2955	33.3509
4	14.297	33.3499
5	14.3076	33.3497
6	14.305	33.3508
7	14.3139	33.3495
8	14.3096	33.3507
9	14.3085	33.3509
10	14.3076	33.3498
11	14.2318	33.3533
12	14.1846	33.3556
13	14.0948	33.3593
14	14.0503	33.3626
15	14.012	33.3619
16	13.8526	33.3711
17	13.7556	33.3757
18	13.6701	33.3782
19	13.4942	33.3954
20	12.9965	33.4202
21	12.9187	33.4196
22	12.7226	33.4255
23	12.6462	33.4367
24	12.5471	33.435
25	12.4153	33.4607
26	12.3003	33.472
27	12.1475	33.472
28	12.0563	33.4924
29	12.0014	33.4991
30	11.9947	33.5076
31	11.9909	33.5109
32	11.9268	33.5222
33	11.8046	33.5273
34	11.7363	33.5308
35	11.7118	33.5409
36	11.6942	33.5608
37	11.6834	33.5654
38	11.6704	33.5668
39	11.5795	33.5899

Depth (m)	Temperature (°C)	Salinity (psu)
40	11.4368	33.6052
41	11.406	33.5957
42	11.373	33.5929
43	11.3529	33.5999
44	11.2821	33.6082
45	11.2315	33.5966
46	11.2697	33.6112
47	11.3104	33.6269
48	11.2635	33.6277
49	11.2273	33.6207
50	11.2176	33.632
51	11.1533	33.6219
52	10.9804	33.6147
53	10.8709	33.6227
54	10.8066	33.6444
55	10.8082	33.6458
56	10.8233	33.6714
57	10.8434	33.6811
58	10.8647	33.6997
59	10.8804	33.7148
60	10.8175	33.7342
61	10.6691	33.7952

Data was extrapolated for depths at which no data was available.

2. Far-field Diffusion Coefficient

The Visual Plumes manual recommends the use of $0.0003 \, \text{m}^{0.67}/\text{s}^2$. This value was used in the data field as a constant (not extrapolated as the ambient temperature and density were).

D. Special Settings

1. UM3 Tidal Pollutant Buildup Parameters

This field is used to calculate "effective dilution", which was irrelevant to the ACOO modeling effort.

2. Diffuser Port Contraction Coefficient

The shape of the diffuser ports was not specified in the ROWD. Upon request, the Discharger indicated that the diffuser ports are sharp-edged cylinders. Thus, a diffuser port contraction coefficient of 0.61 was used as recommended in the Visual Plumes manual.

3. Standard Light Adsorption Coefficient

The value of 0.16 is recommended in the Visual Plumes manual as a conservative value. This is not relevant to final initial dilution, and is for the Mancini bacteria model applications of the model.

4. Far-field Increment (m)

This value controls the number of lines output by the Brooks far-field algorithm. A small value produces more lines and graphic output than large values. A value between 100 to 1000 m is recommended by the Visual Plumes manual. This field has little effect on the final calculated initial dilution, a value of 100 m was used in the data field.

5. UM3 Aspiration Coefficient

This is the rate at which ambient fluid is entrained (diluted) into the plume. The default value of 0.1 is an average that is rarely changed. A larger value causes more rapid plume spreading and affects other characteristics, like plume rise. The default value of 0.1 was used in the data field.

E. Final Results

Twelve model runs were conducted using the data input specified above, one for each available monthly ambient profile. This provided dilution values (expressed at the second trapping level or at the point where the plume reaches the surface of the water column) when considering worst case scenarios (most conservative – high flow, high effluent salinity, low effluent temperature, etc.).

Table H-1. Initial Dilution

Date	Dilution
July 2008	317
August 2008	245
September 2008	237
October 2008	281
November 2008	245
December 2008	240
January 2009	266
February 2009	244
March 2009	237
April 2009	245
May 2009	316
June 2009	281

Model output has been included below and has been copied directly from the Visual Plumes text output.

The minimum initial dilution for March 2009 was calculated to be 237:1. The previous modeling effort used in the previous Order Nos. 2001-08 and R9-2006-0055 utilized an estimated minimum initial dilution value of 260:1.

March 2009

ambient file C:\My Documents\Desktop\ACOO Profiles\acoo.003.db; Diffuser table record 1: ------

Depth	Amb-cur	Amb-	-dir A	mb-sal A	mb-tem	Amb-po	l De	cay	Far-spd	Far-dir	Disprsn	Density
m	m/s	deg	ps	u C	kg/kg	s-1	m/s	d€	eg m0.67.	/s2 sign	na-T	
0.0	0.0	0.0	33.35	5 14.3	0.0	0.0	-	-	0.0003	24.87		
1.0	0.0	0.0	33.35	14.29	0.0	0.0	-	-	0.0003	24.88		
2.0	0.0	0.0	33.35	5 14.3	0.0	0.0	-	-	0.0003	24.87		
3.0	0.0	0.0	33.35	5 14.3	0.0	0.0	-	-	0.0003	24.88		
4.0	0.0	0.0	33.35	5 14.3	0.0	0.0	-	-	0.0003	24.87		
5.0	0.0	0.0	33.35	5 14.31	0.0	0.0	-	-	0.0003	24.87		
6.0	0.0	0.0	33.35	5 14.3	0.0	0.0	-	-	0.0003	24.87		
7.0	0.0	0.0	33.35	5 14.31	0.0	0.0	-	-	0.0003	24.87		
8.0	0.0	0.0	33.35	5 14.31	0.0	0.0	-	-	0.0003	24.87		
9.0	0.0	0.0	33.35	5 14.31	0.0	0.0	-	-	0.0003	24.87		
10.0	0.0	0.0	33.3	5 14.31	0.0	0.0	-	-	0.0003	24.87		
11.0	0.0	0.0	33.3	5 14.23	0.0	0.0	-	-	0.0003	24.89		
12.0	0.0	0.0	33.3	6 14.18	0.0	0.0	-	-	0.0003	24.9		
13.0	0.0	0.0	33.3	6 14.09	0.0	0.0	-	-	0.0003	24.92		
14.0	0.0	0.0	33.3	6 14.05	0.0	0.0	-	-	0.0003	24.94		
15.0	0.0	0.0	33.3	6 14.01	0.0	0.0	-	-	0.0003	24.94		
16.0	0.0	0.0	33.3	7 13.85	0.0	0.0	-	-	0.0003	24.98		
17.0	0.0	0.0	33.3	8 13.76	0.0	0.0	-	-	0.0003	25.01		
18.0	0.0	0.0	33.3	8 13.67	0.0	0.0	-	-	0.0003	25.03		
19.0	0.0	0.0	33.4	13.49	0.0	0.0	-	_	0.0003	25.07		

Diffuser table:

P-dia P-elev V-angle H-angle Ports Spacing AcuteMZ ChrncMZ P-depth Ttl-flo Eff-con Temp Polutnt

```
(in) (in) (deg) (deg) () (ft) (m) (m) (ft) (MGD)(mmho/cm) (F) (ppm) 2.0 32.0 -5.0 0.0 200.0 6.0 1.0 1.0 182.5 34.37 1.874 69.0 20.0
```

Simulation:

Froude number: 59.68; effleunt density (sigma-T) -0.948; effleunt velocity 6.09(m/s); Depth Amb-cur P-dia Polutnt Dilutn x-posn y-posn

_						• • • • • • • • • • • • • • • • • • • •	, i
Step	(ft)	(m/s)	(in) (p	pm)	() (ft)	(ft)	
0	182.5	0.0	1.562	20.0	1.0	0.0	0; stream limit reached;
100	182.7	7 0.0	11.09	2.761	7.081	1.971	0.0;
123	182.7	7 0.0	17.48	1.751	11.15	3.298	0.0; chronic zone, acute zone;
141	182.8	0.0	24.97	1.226	15.92	4.854	0.0; local maximum rise or fall;
200	180.8	0.0	63.61	0.454	42.89	13.22	0.0;
215	179.5	0.0	72.24	0.382	51.01	15.28	0.0; merging;
293	136.0	0.0	206.7	0.12	162.8	35.56	0.0; trap level;
300	123.4	1 0.0	288.4	0.105	186.1	39.69	0.0;
311	117.1	0.0	447.6	0.0999	195.0	42.34	0.0; begin overlap;
400	112.6	0.0	1035.5	0.0991	196.6	46.37	0.0;
420	112.5	5 0.0	1060.2	0.0991	196.6	46.8	0.0; local maximum rise or fall;
500	113.6	0.0	757.2	0.0991	196.6	48.95	0.0;
539	119.3	0.0	442.9	0.0975	199.9	52.19	0.0; end overlap;
557	144.6	0.0	383.0	0.0821	237.2	59.76	0.0; trap level;

SOUTH ORANGE COUNTY WASTEWATER AUTHORITY 2012-0013 ALISO CREEK OCEAN OUTFALL

TENTATIVE ORDER NO. R9-NPDES NO. CA0107611

.