TABLE OF CONTENTS

Section 13 Building Block 3.1: Suisun Marsh Tidal Wetland Restoration and Managed Wetland Enhancements 13-1

13.1 Introduction 13-1
13.1.1 Background: Suisun Marsh and Bay 13-1
13.1.2 Purpose and Scope of Building Block 13-2
13.1.3 Objective and Approach 13-2
13.2 Conceptual Development of Improvement 13-4
13.2.1 Existing Conditions 13-4
13.2.2 Selection of Conceptual Restoration Sites 13-4
13.2.3 Identification of Exterior Levees and Potential Breaches for Tidal Restoration 13-6
13.2.4 Identification of Conceptual Areas for Managed Wetlands Enhancement 13-6
13.2.5 Analysis Results and Design Layouts 13-7
13.3 Geometric Description of Improvements 13-8
13.3.1 Assumptions 13-8
13.3.2 Description of Values, Benefits, and Constraints 13-10
13.4 Cost Estimate 13-15
13.5 Risk Reduction 13-16
13.6 Findings and Conclusions 13-16
13.6.1 Findings 13-16
13.6.2 Conclusion and Recommendations 13-17

Tables

13-1 List of Special-Status Sensitive Species in Suisun Marsh

13-2 Key Agencies and Groups Managing Suisun Marsh

13-3 Significant Policies Affecting Marsh Actions

13-4 Suisun Marsh Existing Habitat Composition by Planning Region

13-5 Target Acreages for Tidal Restoration

13-6 Total Area and Levee Lengths for Conceptual Restoration Areas

13-7 Total Area and Planned Improvements in Conceptual Managed Wetland Enhancement Areas

13-8 Tidal Datum for Montezuma Slough at Suisun Slough Cut

13-9 Existing Elevations (LiDAR 2006)

13-10 Conceptual-Level Capital Costs of Building Block 3.1: Suisun Marsh Tidal Wetland Restoration

13B-1 Infrastructure and Assets in Suisun Marsh

Table 13-8 Tidal Datum for Montezuma Slough at Suisun Slough Cut

Tide	Feet (NAVD88)
Mean higher high water (MHHW)	5.58
Mean high water (MHW)	5.02
Mean sea level (MSL)	3.03
Mean low water (MLW)	1.15
Mean lower low water (MLLW)	0.56

Source: DWR 2004.