

STATE OF CALIFORNIA
CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
SAN FRANCISCO BAY REGION

STAFF SUMMARY REPORT (Tahsa Sturgis)
MEETING DATE: December 13, 2017

ITEM: 7

SUBJECT: **U.S. Army Corps of Engineers, State Coastal Conservancy, and Santa Clara Valley Water District, South San Francisco Bay Shoreline Project, Santa Clara County** – Adoption of Waste Discharge Requirements and Water Quality Certification

CHRONOLOGY: The Board has not considered this item before.

DISCUSSION: The Revised Tentative Order (Appendix A) would issue waste discharge requirements and water quality certification to the U.S. Army Corps of Engineers (Corps), the State Coastal Conservancy (Coastal Conservancy), and the Santa Clara Valley Water District (District) to implement the South San Francisco Bay Shoreline Project (Project). This Project is a significant multi-benefit project that provides both flood protection and environmental restoration and addresses anticipated future sea level rise. The Project would construct a levee that will reduce the risk of tidal flooding to homes, schools, and businesses along Santa Clara County's Bay shoreline, including Alviso and the San Jose/Santa Clara Regional Wastewater Facility (RWF). In addition, it will allow for restoration and enhancement of tidal marsh and related habitat that was lost due to past diking for salt production. The restoration component of the Project includes former salt ponds, currently managed ponds, that are a portion of the larger South Bay Salt Pond Restoration Project. Restoration of these managed ponds cannot occur unless there is adequate flood protection provided prior to breaching the ponds to allow full tidal action.

The Revised Tentative Order would conditionally authorize full Project construction, which is expected to occur over the next 14 years, even though only the initial phase is funded. Given funding availability, it is appropriate to consider Project approval now, so that flood protection can be provided to Alviso as soon as possible.

The Project would be built in three phases, shown with projected dates of construction:

Phase I (2018-2022)

- Construct a 3.8-mile long levee along five reaches, including creation of approximately 91.52 acres of shallowly sloped ecotone habitat along the levee alignment by 2022
- Restore tidal action to Ponds A12 and A18 (1,120 acres)

Phase II (2027)

- Restore tidal action to Ponds A9, A10, and A11 (900 acres)

Phase III (2032)

- Restore tidal action to Ponds A13, A14, and A15 (880 acres)

The Project would result in initial impacts to waters of the State and U.S. associated with the levee and ecotone construction—placement of fill into about 132.2 acres of waters of the U.S. Those impacts are substantially addressed by the Project’s significant restoration components, but, because there is uncertainty regarding aspects of Project design and timing, the Order establishes a mechanism for further evaluation and approval as Project details are finalized.

Board staff has worked with the Project proponents on the proposed alignment of the levee and significant progress has been made to resolve issues identified as early as during our review of the Project’s Environmental Impact Report. The Order requires, and the Discharger is completing, an evaluation of more-landward alignments for a portion of the levee adjacent to the RWF. Such alignments have the potential to increase wetland acreage, thereby significantly reducing the Project’s Bay fill, while also reducing Project costs and facilitating cleanup of inactive sludge lagoons at the RWF.

The Order attempts to balance the short-term impacts from Project construction with recognition that its longer-term benefits support long-term restoration and shoreline resiliency on a spatially significant scale.

A tentative order for the Project was circulated for a 30-day public comment period in October. Staff received comments from the Corps, Conservancy, District, and the U.S. Fish and Wildlife Service (Appendix B). Some of the comments received reflect a misunderstanding that the tentative order would have required all proposed restoration acreage (2900 acres) to be completed and, if not, compensatory mitigation would be required. As described the Response to Comments (Appendix C), we have revised the tentative order to clarify that the tentative order’s intent and requirements to mitigate only for fill impacts. Staff also incorporated minor, self-initiated editorial revisions during this process.

**RECOMMEN-
DATION:**

Adoption of the Revised Tentative Order

**CIWQS Place
Number:**

813084

APPENDICES:

- A. Revised Tentative Order
- B. Comments on Tentative Order
- C. Response to Comments

**Appendix A:
Revised Tentative Order**

**401 Water Quality Certification and
Waste Discharge Requirements**

**South San Francisco Bay
Shoreline Project**

**City of San Jose
Santa Clara County**

December 2017

**CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD
SAN FRANCISCO BAY REGION**

REVISED TENTATIVE ORDER

WATER QUALITY CERTIFICATION AND WASTE DISCHARGE REQUIREMENTS for:

**U.S. ARMY CORPS OF ENGINEERS
STATE COASTAL CONSERVANCY
SANTA CLARA VALLEY WATER DISTRICT**

**SOUTH SAN FRANCISCO BAY SHORELINE PROJECT
SANTA CLARA COUNTY**

The California Regional Water Quality Control Board, San Francisco Bay Region (Regional Water Board), finds that:

1. The U.S. Army Corps of Engineers (Corps) has applied to the Regional Water Board for approval to construct the South San Francisco Bay Shoreline Project (Project). The Corps intends to build the Project in three phases over approximately 14 years.
2. **Application.** On June 16, 2017, the Corps filed an application for CWA section 401 Water Quality Certification with the Regional Water Board for authorization to implement the Project (33 U.S.C. section 1341). The Regional Water Board used this information to determine compliance with California Water Code (Water Code or CWC) section 13360, which requires a Report of Waste Discharge for issuance of Waste Discharge Requirements (WDRs).
3. **Order Authorization.** This Order authorizes, subject to the requirements herein, Project Reaches 1 through 3 and mitigation and monitoring activities, including ecosystem restoration and adaptive management actions. Additionally, it conditionally authorizes the remaining parts of the Project (Reaches 4 and 5) by setting forth a process by which the Project's remaining construction events and phases may be authorized, subject to applicable public, Regional Water Board, and Regional Water Board Executive Officer review. Authorization of Reaches 4 and 5 is conditioned on additional submittals, including acceptable design plans and supporting documentation, and associated review, as described herein. This Order identifies potential Project impacts to water quality and beneficial uses and requires necessary measures, including the successful implementation of compensatory mitigation, to address them.
4. **Local-Federal Partnership.** The Corps is partnering with the State Coastal Conservancy (Coastal Conservancy) and the Santa Clara Valley Water District (District) to increase flood protection and provide shoreline resiliency against projected sea level rise (SLR) to protect the community of Alviso and valuable shoreline infrastructure and restore tidal action to about 2,900 acres of historically diked baylands. The Water Resources Development Act (WRDA) of 1986, Public Law 99-662, as amended (33 U.S.C. section 2213) stipulates that the Non-Federal Sponsors (the Coastal Conservancy and District) will contribute 35 to 50 percent of the total Project cost. The Corps and Non-Federal Sponsors are each funding Project costs and are coordinating the division and/or various shared roles and responsibilities, such as design, construction, and post-construction operations, which arrangements will be formalized in accordance with the Project Partnership Agreement (PPA) that will be signed by the Corps, Coastal Conservancy, and District when Congress appropriates funds in the Construction General account. The cost-sharing schedule specifically requires the Corps to conduct (and/or

oversee) construction contracting and activities and the Non-Federal Sponsors to provide all lands, easements, rights-of-way, relocations, and disposal areas (LERRD). A design agreement between the Corps, Coastal Conservancy, and District has been used to move the Project forward until the PPA is signed. The design agreement was signed on July 11, 2016, and states the Non-Federal Sponsors shall contribute 35 percent of the total design costs, in accordance with the WRDA of 1986, Public Law 99-662, as amended. The WRDA also requires the Corps to prepare an operations and maintenance manual for the Project.

5. **Discharger.** The Regional Water Board is issuing this Order to the Corps, the Coastal Conservancy, and the District, collectively referred to as the Discharger, because Project activities will cause or contribute to a discharge of waste that will affect the quality of waters of the U.S.¹ The nature of WDRAs projects is that the partnership between the Corps and the Non-Federal Sponsors is inextricable, and the Project could not occur without each sponsor. Therefore, the Regional Water Board is naming the Corps and the Non-Federal Sponsors, who are the Project co-sponsors, as dischargers. As appropriate, this Order notes which partner has agreed to be responsible for certain requirements based on WRDA requirements, as well as the Regional Water Board's understanding of the agreements the Corps, Conservancy, and District have made with each other.

The Discharger will implement the Project as described in the application materials and herein. As described in the agreement among the Corps and Non-Federal Sponsors, the Corps will be responsible for construction of flood protection, ecosystem restoration, and some recreational elements. Once the flood risk management levee is constructed and fully functional, the Corps will transfer the levee's operation, maintenance, and management responsibility to the District. The Corps and the Non-Federal Sponsors will share financial responsibility for the ecosystem restoration monitoring and adaptive management. However, the Corps' ecosystem restoration cost sharing obligation is restricted to ten years following each pond-breaching event. Once the Corps' cost-sharing obligation ends, the Non-Federal Sponsors will assume the total cost for each pond's long-term operation, maintenance, and management. Responsibilities for costs, which will also include operation and maintenance costs, will be allocated pursuant to the PPA, when it is finalized. Currently, the Non-Federal Sponsors are negotiating how their respective roles and responsibilities, including cost sharing, will be divided during the ecosystem restoration's long-term operation, maintenance, and management.

6. **Project Purpose.** The Project's overall purpose is to safeguard homes, schools, and businesses along Santa Clara County's South Bay shoreline, including Alviso and the San Jose/Santa Clara Regional Wastewater Treatment Facility (RWF), from the risk of tidal flooding by constructing a levee and restoring and enhancing tidal marsh and related habitat that was lost due to former salt production activities. The Project's overall purpose will be achieved through implementation of a flood risk management levee and ecosystem restoration. The Project's objectives are to:
 - Reduce the risk to public health, human safety, and the environment due to tidal flooding along the South Bay shoreline in Santa Clara County, by providing protection from the 1

¹ Waters of the United States are subsumed within waters of the State. All of the surface waters discussed in the Order are both waters of the State and United States. For ease of reference, these WDRs refer to both as waters of the U.S. Groundwater, a water of the State only, is addressed separately, where applicable.

percent annual chance of exceedance flood (i.e., the 100-year event), taking into account anticipated SLR through 2067;

- Reduce potential economic damages due to tidal flooding in areas near the South Bay shoreline in Santa Clara County;
- Increase contiguous tidal marsh to restore ecological function and habitat quantity, quality, and connectivity in the Project Area; and
- Provide opportunities for public access, environmental education, and recreation in the Project Area.

7. **Site Description and Background.** The Project site is located between Alviso Slough/ Guadalupe River and Coyote Creek and includes the community of Alviso and the RWF. The Alviso pond complex is within the Project site, and the RWF is located to the southeast (Att. A, Figures 1 to 3). The Alviso pond complex consists of 25 ponds of former salt production ponds over approximately 9,000 acres along 15 miles of shoreline between Palo Alto and Fremont. The United States Fish and Wildlife Service (USFWS) owns and manages about 8,000 acres of former salt ponds within the Alviso pond complex. The approximately 820-acre Pond A18, just outside the Alviso pond complex, is owned by the City of San Jose and located within the Project site.

The community of Alviso has over 2,500 residents, 1,100 structures, and 3,000 commuters who work and travel through the area each day. The surrounding low-lying terrain is mostly urban and contains portions of Silicon Valley, transportation corridors, and other critical infrastructure.

Low-lying terrain within the area is the result of widespread overdraft of groundwater for agricultural and urban uses during the early and middle decades of the 20th century. This overdraft led to severe ground subsidence under most of the Santa Clara Valley and portions of the South Bay, including many of the Project site's former salt ponds. Salt pond dikes were raised by their owners, and outboard tidal marshes accumulated sediment quickly enough to maintain their elevation. However, without tidal flows, the floors of the salt ponds and adjacent alluvial plains had no way to compensate for the previous loss in elevation. In addition, the non-engineered berms protecting these areas from tidal flooding are dikes that were created as early as the 1920s and generally maintained to protect the ponds from tidal flooding when they were used for salt production. These dikes were not engineered or intended to reduce flood risk for urban areas. While groundwater overdraft has ceased and the water table has recovered considerably, the previous loss of elevation is permanent.

Due to this subsidence, many areas landward of the former salt ponds have become vulnerable to tidal flooding. Alviso is at or below an elevation of 5 feet NAVD88, which is lower than the mean higher high tides in the area. During a 1983 flood event, floodwaters from Coyote Creek reached a depth of 6 feet in Alviso, and more than 1,700 residents were flooded.

The Project site's flood risk is exacerbated by the substantial SLR that is expected during the Project's fifty-year planning horizon (2017-2067). The Discharger has estimated that regional SLR will be between 0.51 feet and 2.59 feet. This increase in sea level will put the community

of Alviso and surrounding area at a greater risk of flooding than currently present. The Project will provide flood protection to Alviso by constructing a flood risk management (FRM) levee and restoring tidal action to Ponds A9 to A15, within the Alviso pond complex, and Pond A18. Project construction will occur in three phases that will be completed in about 2032, but monitoring and adaptive management will continue until about 2047.

8. **Project Construction Phasing.** The Project will be constructed in three phases through six total construction events, as described below. All phases are authorized or conditionally-authorized by this Order. Phase I is expected to result in fill and non-fill Project impacts for which ecosystem restoration work, integral to the Project in Phases I, II, and III, provides mitigation. However, monitoring data for the Phase I ecosystem restoration Project component may indicate breaching the ponds in Phases II and III would not facilitate tidal marsh restoration or result in other environmental benefits. In that event, Project Phases II and III may not be constructed and the ecosystem restoration benefits of these phases would not be realized. If Phase I is successfully implemented and the Discharger does not move forward with Phases II and III, the Discharger will submit supplemental information on Project impacts as described in the Provisions and, specifically, as part of a Contingency Monitoring and Mitigation Plan.

Phase I: Phase I activities include the FRM levee construction, ecotone creation, and restoration of Ponds A12 and A18 to tidal action. The levee length has been divided into five reaches. The FRM levee will be constructed first along those five reaches to provide immediate flood protection by increasing the levee height. While the FRM levee is being constructed, fill for Project construction may be stockpiled in the ecotone footprint, as described elsewhere herein.

Transitional wetland habitat (ecotone) will be created along the bayward side of the FRM levee within three of the ponds. The first two ecotones will be created in Ponds A12 and A13 once the FRM levee construction has been completed along Reaches 1 through 3. The third and final ecotone will be created in Pond A18 once the FRM levee construction has been completed along Reaches 4 and 5. Once the FRM levee has been completed and tied in to existing levees, tidal action will be restored to Ponds A12 and A18 by breaching their respective outboard dikes.

Additional Phase I activities that are authorized by this Order, but are not expected to result in the placement of fill into waters of the U.S. beyond that otherwise described in the Order, include the following:

- Construction of a pedestrian bridge over Artesian Slough to link multi-use trails;
- Completion of public access improvements that will create multi-use trails, mostly on the tops of the FRM levees, to connect to the Bay Trail network; and
- Appropriate infrastructure construction where the Project crosses the Union Pacific railroad tracks to ensure the Project can provide effective flood protection while still allowing the railroad to function effectively. This Order does not authorize a separate project to modify the railroad line to address the effects of anticipated SLR.

After Phase I activities have been completed, additional ponds will be breached in specific locations to restore tidal action to the ponds, allow sediment carried by the tides into the breached ponds, and allow for the reactivation of remnant channels in the pond bottom. Once the

salt ponds have been restored to tidal action, the anticipated result is large-scale tidal marsh restoration from sediment accretion, marsh vegetation colonization, and ongoing adaptive management actions.

Phase II: Phase II will restore Ponds A9, A10, and A11 to tidal action in generally the same manner as for the ponds breached in Phase I. Ongoing monitoring data from the previous Project phase will be used to inform restoration strategies for Ponds A9, A10, and A11.

Phase III: This final Project phase will restore Ponds A13, A14, and A15 to tidal action in generally the same manner as for the ponds in Phase I. Similar to Phase II, ongoing monitoring data from previous Project phases will be used to inform restoration strategies for Ponds A13, A14, and A15.

Project Phasing: Phasing the Project is necessary because the levee and ecotone components must be completed prior to restoring the salt ponds to tidal action to ensure that landward flood protection is maintained. The phasing also allows the anticipated ecosystem restoration to have a higher likelihood of success by allowing the Discharger to implement lessons learned from monitoring salt ponds that will be restored in earlier phases. Additionally, the phasing will allow material that will be used for the FRM levee and ecotone construction to be acquired from various sources. The Project will be constructed over approximately 14 years (see Table 1).

Table 1: The Project phases and anticipated construction timeline (Att. A, Figure 4).

Phase	FRM Levee Construction (Reach No.)	Tidal Marsh Restoration (Ponds)	Ecotone Creation (Ponds)	Anticipated Construction (Year)
I	1	--	--	2018
	2 and 3	--	A12 and A13	2019
	4 and 5	--	A18	2020-2021
II	--	A12 and A18	--	2022
	--	A9, A10, and A11	--	2027
III	--	A13, A14, and A15	--	2032

- Related Projects.** The Project is closely related to, and implements a portion of, the South Bay Salt Pond Restoration Project (SBSPRP) (Order No. R2-2004-0018, as reissued and amended [R2-2008-0078; R2-2012-0014]). The SBSPRP is located in South San Francisco Bay and consists of three former salt pond complexes and adjacent habitats: the Alviso Ponds,

Ravenswood Ponds, and Eden Landing Ponds. The SBSPRP is similarly phased to allow prior construction and restoration activities to inform future phases, and the same conceptual ecological model used in the SBSPRP will be implemented in the Project’s adaptive management strategy. The planning process for the Project is being coordinated with SBSPRP actions, as both efforts have similar flood protection, ecosystem restoration, and recreation objectives.

The Coastal Conservancy, District, and USFWS are currently collaborating to implement the SBSPRP, which encompasses 15,100 acres in the South Bay. As part of the SBSPRP, a range of potential implementation and habitat outcomes were identified, with the endpoint to be determined through phased implementation guided by adaptive management. A “staircase” analogy was used in the SBSPRP to describe the proposed project, with each step on the staircase representing one phase of tidal restoration implementation. Adaptive implementation determines how far “up the staircase” the project proceeds.

The following Findings present a more-detailed discussion of aspects of the Project and are organized into four sections: (I) South San Francisco Bay Shoreline Project (Project); (II) Reaches 1 to 3; (III) Maintenance and Management; and (IV) Other Findings.

I. South San Francisco Bay Shoreline Project (Project)

10. **Phase I (2018-2022):** Phase I of the Project consists of the construction of approximately 3.8 miles (19,775 ft.) of new levee from the Alviso Marina northeastward to the northeastern corner of the RWF property; ecotone creation; and pond preparation, breaching, and restoration. The entire FRM levee is divided into five reaches (Reaches 1 to 5) that are grouped into two segments, as shown in Table 2. Phase I activities are further divided into four construction events, as summarized in Table 3.

Table 2: Summary of FRM levee construction by Reach (Att. A, Figure 4).

Phase	Reach No.	Segment	Adjacent Ponds	Anticipated Start of Construction (Year)
I	1	Alviso	A12 and A13	2018
	2		A16	2019
	3		A16	2019
	4	RWF	A18	2020-2021
	5		A18	2020-2021

Table 3: Summary of Phase I’s construction events and activities (Att. A, Figure 4).

Phase	Construction Event	Activity	Anticipated Construction (Year)
I	First	Construct FRM levee Alviso segment (Reach 1); stockpile fill material in Ponds A12, A13, and A18	2018
	Second	Finish FRM levee Alviso segment (Reaches 2 and 3); create two ecotones in Ponds A12 and A13; stockpile material in Pond A18 as needed	2019
	Third	Complete FRM levee by starting and finishing RWF segment (Reaches 4 and 5); create third and final ecotone in Pond A18	2020-2021
	Fourth	Breach Ponds A12 and A18	2022

The first two construction events in Phase I include construction of the FRM levee’s Alviso segment (Reaches 1 to 3), creation of new upland/marsh transitional habitat (ecotone) in Ponds A12 and A13, and stockpiling construction material. The FRM levee’s Alviso segment is approximately 1.7 miles long and follows the eastern border of Pond A12 and the southern borders of Ponds A13 and A16. Ecotones will be created along approximately 3,600 linear feet of Reach 1 on the east side of Pond A12 and along approximately 600 linear feet of Reach 1 on the southern side of Pond A13 during Phase I’s second construction event. Approximately 28.79 acres of ecotone will be created in Ponds A12 and A13. Following construction of the ecotone, it will be seeded with native grasses, forbs, and low non-woody shrubs.

The third construction event in Phase I includes completion of the entire FRM levee, from construction of the RWF segment (Reaches 4 and 5), and creation of the third ecotone in Pond A18. The FRM levee’s proposed conceptual alignment for the remaining 2.1-mile RWF segment follows the southern border of Pond A18. Connecting the Alviso and RWF segments requires crossing Artesian Slough. The Discharger’s conceptual levee design is currently proposed to run west to east in a stair step pattern along the southern border of Pond A18, from the southwest corner of the pond to its northeast corner. However, the Discharger has not finalized the FRM levee’s RWF segment because a cheaper landward alignment is under evaluation (see Finding 13) (Att. C). The landward alignment under evaluation would require less fill and maximize the Project’s ecosystem restoration by utilizing landward elevations that are higher than Pond A18’s bottom elevation to support quicker colonization of wetland vegetation. The ecotone created in Pond A18 using the proposed conceptual alignment would be approximately 62.73 acres.

The fourth and final construction event in Phase I will consist of breaching the outboard dikes for Ponds A12 and A18. Monitoring and adaptive management of the Ponds A12 and A18 after breaching is necessary to inform future pond breaches.

FRM Levee: The earthen FRM levee will increase the existing levee height by approximately 10 feet to a design elevation of 15.2 feet NAVD88, after settlement. To accommodate the increase in levee height, the FRM levee's width will be 16 feet at its crest, about twice as wide as the existing levee's width. The FRM levee's design elevation of 15.2 feet corresponds to the levee height that will provide flood protection from a one percent annual chance of exceedance (ACE) flood that includes SLR estimates used by the Discharger (see Finding 17). The flood protection against a one percent ACE flood in 2067 meets Federal Emergency Management Agency (FEMA) criteria. The proposed levee height was requested by the District and Coastal Conservancy to allow for continued FEMA accreditation at the end of 2067 and meet local FRM requirements in Santa Clara County. The one percent ACE level of flood risk protection is consistent with FEMA requirements for eligibility in the National Flood Insurance Program.

The existing dike material along Ponds A12, A13, and A18 has relatively high plasticity and contains organics that make it unsuitable to remain in place or serve as fill for the new FRM levee, but the dike material may be suitable for future ecotone construction. Fill for the FRM levee construction will be imported from local sources and delivered by truck. The Discharger plans to use some fill material from nearby creek dredging projects to reduce Project costs. All imported dredged material must meet established screening criteria for reuse based upon the Regional Water Board's beneficial reuse guidelines for dredged material. Other elements, such as geotextile fabric, stone foundation columns, and foundation over-excavation may be included in the final levee design.

Vegetation is included in the levee design as erosion protection on the bayward and landward side slopes. The vegetation is anticipated to be continuous and serve as erosion protection. Marsh vegetation may be seeded or planted at the toe of the levee following construction. Peripheral halophytes such as 12- to 18-inch tall pickleweed (*Salicornia pacifica*) may be planted at the toe of the levee, if necessary. Upland grasses will be seeded at higher elevations on the side slopes between the levee crest and the pickleweed. Combinations of buried stone protection and buried gravel may be necessary to provide erosion protection in areas where the vegetation cannot be supported or to stunt the growth of native vegetation to reduce the frequency of vegetation maintenance activities, such as mowing, near the levee crest.

Certain locations may require special structures or treatment, as follows:

- The new FRM levee will diverge from the existing levee alignment by cutting across Pond A12 in the southwestern area. The divergence from the existing alignment will make construction easier by avoiding two 90-degree bends in the levee. This divergence will shorten the levee length, thereby requiring less fill material.
- Where the levee crosses an existing water feature, such as a slough, structures will be installed to allow flow during normal conditions and during flood conditions. This Order requires that the design for the Artesian Slough crossing not adversely alter the adjacent RWF's discharge quality and hydraulics.
- Where the levee crosses below-ground infrastructure (e.g., utilities), load-bearing structures may be needed to support the weight of levee materials over the infrastructure.

- Floodgates will be installed where the Reach 1 FRM levee crosses the active Union Pacific Railroad (UPRR) tracks.

Ecotone Creation: Ecotone creation will occur along the bayward sides of Reach 1 (Ponds A12 and A13), Reach 4 (Pond A18), and Reach 5 (Pond A18). The ecotones will be constructed with an average 30:1 horizontal to vertical slope. The ecotones' gradual slope will add up to 345 feet to the width of the Bay side of the levee footprints at these locations. The first two ecotones will be created along 3,600 linear feet of the levee on the east side of Pond A12 and approximately 600 feet on the south side of A13. In Ponds A12 and A13, approximately 28.79 acres of ecotone will be created in total. The third ecotone will be created bayward of the FRM levee through Reaches 4 and 5. Approximately 62.73 acres of ecotone will be constructed along approximately 14,000 linear feet of levee along Pond A18. In total, approximately 91.52 acres of ecotone will be created.

The new ecotones will provide substantial benefits for wildlife in the Project site and nearby areas because this type of habitat is not well represented in the South Bay. Further, the ecotone slopes will allow the transgression of estuarine marsh habitats over uplands as sea level rises, maintaining over time the Bay-adjacent estuarine-terrestrial transition zone (Att. A, Figure 5). Vegetation in the upland transitional areas will be limited to herbaceous, low non-woody and semi-woody plants, and possibly shallow-rooted shrubs; it will be otherwise unmanaged, except to control invasive plants from establishing.

Ponds A12 and A18 Tidal Restoration: Ponds A12 and A18 are proposed for the first phase of restoration because they have experienced the greatest degree of subsidence, and Pond A12's bottom elevation is too low to support intertidal marsh vegetation. Restoring tidal action to Ponds A12 and A18 maximizes the potential for the sites to accrete sediment transported from the Bay on flood tides. Pond A12's bottom elevation is so low that, after it is restored to tidal action, several feet of sediment deposition from sediment transported on flood tides will be needed before the pond bottom reaches a sufficient elevation to support colonization by marsh vegetation. The sedimentation process is expected to proceed at rates determined in part by suspended solids concentrations in the South Bay as well as factors causing re-suspension of sediment, such as wave action and tidal currents, in the South Bay and breached pond (ESA PWA 2012; HTH 2012). After Pond A12 is breached, the anticipated sediment deposition is expected to raise its bottom elevation sufficiently to support colonization by intertidal marsh vegetation. Internal pond dike breaches will be conducted to reconnect historical channels and restore hydrologic connections to the innermost ponds in the Project footprint. Breach sizes will be consistent with *Design Guidelines for Tidal Wetland Restoration in San Francisco Bay* (PWA 2004).

Pilot channels will be constructed on the outboard side of the pond dikes, where the breaches will occur, to facilitate and concentrate flow into the pond when the dikes are breached. Each pilot channel will be located along the locations of historical tidal channels (Att. A, Diagrams 2 and 3).

Ditch blocks will be constructed in areas within the inboard edge of the pond to direct flow away from undesirable locations and towards desired locations. The blocks will be constructed within borrow ditches along the inboard perimeter of the ponds. Once the dikes are breached, the

ditch blocks will be located in strategic areas around the inboard edge of the pond to inhibit incoming flow through the existing borrow ditches and redirect flow towards the remnant historical channels to promote scour and restore their form and function. The ditch blocks are also expected to provide some initial pickleweed habitat in locations where elevations are suitable for such growth. Without the ditch blocks, the incoming flow from the breached dikes would take a preferential path through the borrow ditches around the inboard perimeter and reduce the likelihood that historical tidal channels would be restored to form complex dendritic channels. Complex dendritic channels in the ponds are a critical hydrodynamic component and serve ecological functions such as foraging by special-status species.

To prepare Pond A12 for breaching, berms will be constructed between Pond A12 and Ponds A11 and A13. These berms will be temporarily (i.e., until tidal action is restored to Ponds A11 and A13) raised to provide flood protection for ponds A11 and A13 when Pond A12 is breached. Starter channels will then be excavated within Pond A12 to facilitate restoration of the historical tidal channels within the pond. This will improve water and sediment circulation in the pond and help accelerate marsh restoration. If determined to be suitable, surplus material excavated from pond preparation would be used to contribute to other in-pond construction activities that require material, such as raising of internal dikes. Pond A18 will be prepared for breaching by using a procedure similar to Pond A12's breaching preparation.

Following restoration of tidal flows to Ponds A12 and A18, monitoring will be conducted to measure physical and ecological processes and conditions, such as tidal exchange, sediment accretion, and vegetation establishment. If necessary, corrective measures will be implemented, consistent with the procedure described in the Monitoring and Adaptive Management Plan (MAMP). A period of approximately ten years has been planned for monitoring and adaptive management of the pond areas, but monitoring and adaptive management will continue until at least 2048.

11. **Phase II (2027):** Phase II is the fifth construction event and consists of restoring Ponds A9, A10, and A11 to tidal action. Ponds A9, A10, and A11 will be prepared for breaching in a similar fashion as Ponds A12 and A18 during Phase I, with the application of lessons learned from monitoring Ponds A12 and A18 after they were restored to tidal action. The decision to breach these ponds will be based on the MAMP and the most up-to-date version of the Ecotone and Pond Monitoring Plan (EPMP) (see Provision 35) prior to commencement of Phase II, and the decision framework in the SBSRP MAMP. These decisions involve monitoring populations of pond-associated birds and monitoring of sediment accretion in the South Bay, among other factors.

Preparing the Phase II ponds for breaching will be conducted in a similar manner as Phase I, but lessons learned from Phase I will be incorporated into the pond preparation sequence to improve the restoration of tidal action. Pond A11 will be connected to Ponds A10 and A12 with inboard berm breaches, but it will not be breached directly to Alviso Slough. Two breaches to Alviso Slough are planned in Pond A10, and one breach each to Alviso Slough and Coyote slough are planned for Pond A9. Internal berms between Ponds A9 and A11 and Ponds A13 and A14 will be temporarily raised (i.e., until breaching of ponds A13 and A14 in 2032) to provide flood protection for Ponds A13 and A14.

12. **Phase III (2032):** Phase III is the sixth construction event and consists of restoring Ponds A13, A14, and A15 to tidal action. Pond preparation for Ponds A13, A14, and A15 will be implemented based on the lessons learned from the mitigation and monitoring conducted for previously restored ponds. Similar to the Phase II breaching, the data collected, as described in MAMP and supporting documentation, from post-construction monitoring of previous phases will be used to decide if these ponds should be breached and restored to tidal marsh, subject to public and Regional Water Board review as described herein.

Prior to breaching the ponds restoring them to tidal action, a single pilot channel will be excavated and ditch blocks will be constructed. Only one outboard breach is planned for tidal restoration in these three ponds; this breach will connect Pond A15 to Coyote Creek along a major historical channel. Inboard berm breaches at the locations of historical sloughs will provide connections to Ponds A13 and A14 from the surrounding ponds (A9, A11, A15, and A12).

Future Project Considerations and Permitting

13. **Future Project Design Decisions.** The Discharger has identified a conceptual FRM levee alignment for the levee beyond Reaches 1 to 3, from Artesian Slough to its terminus at Coyote Creek. All future Project components require additional investigation by the Discharger, including supplemental analysis for each reach, collection of monitoring and maintenance data, and collection of monitoring and maintenance data to the Project area. This Order sets forth a process by which an acceptable levee alignment and other design details can be determined. The following are significant alignment and design issues to be considered:

Artesian Slough Crossing: The FRM levee will need to cross Artesian Slough in order to connect the Alviso (Reach 3) and RWF (Reach 4) segments. Artesian Slough is currently used by the RWF to discharge treated wastewater and meet its effluent requirements under its Regional Water Board-issued National Pollution Elimination Discharge System (NPDES) permit. The mixing and dilution for the RWF's discharges cannot be affected in a way that would cause non-compliance with the RWF's current NPDES permit, and the design must address the RWF's need to discharge treated wastewater to the Bay.

The Discharger's proposed Artesian Slough crossing design is intended to protect the RWF from stormwaters and tidal surges that flood the Slough and back up into the RWF during extreme storm events. The proposed location of the tide gate would be at least 300 feet bayward of the existing RWF outfall for treated water at the Slough. The gates would only be closed during extreme storm events. When the gates are closed, the RWF would need to pump treated wastewater over the proposed tide gate or provide internal excess water storage during a storm event. With or without the Project, the RWF will develop a plan to pump or store waters during such events because of increases in Bay water levels that correspond with future SLR scenarios. To best meet the general operation requirements for the RWF and allow for discharge during storm events, the tide gate will be designed in coordination with RWF engineers. This Order requires the Discharger to submit additional information regarding the crossing's proposed design and to obtain Executive Officer approval prior to constructing that component.

Reach 4 to 5 FRM Levee Alignment (RWF Segment): The Discharger's proposed levee alignment east of Artesian Slough along the RWF segment would result in a net loss of waters of the U.S. That proposed alignment would follow, in part, the Pond A18 levee that runs west to east in a stair-step pattern.

Landward Levee Alignment East of Artesian Slough: Regional Water Board staff provided feedback to the Discharger, prior to its application submittal, about opportunities to reduce Project impacts to waters of the U.S. Regional Water Board staff described a potential levee alignment east of Artesian Slough (Reaches 4 and 5) that is landward of both (a) existing mitigation wetlands north of the RWF and (b) approximately 100 acres of the RWF's legacy biosolid ponds. Regional Water Board staff provided the Discharger with technical evidence (Att. C) that this or a similar landward levee alignment east of Artesian Slough likely would reduce the volume of earthwork, be cheaper and easier to construct, reduce or potentially eliminate the immediate net loss of waters of the U.S., increase the acreage, function, and value of tidal wetlands in the area, and provide an opportunity for the City of San Jose to close the legacy biosolid ponds at the RWF. The Discharger described this proposed alignment in its application as the Pond A18 Alternative.

Material Stockpiling: Two of the largest constraints to success of the Project are the need to secure a sufficient amount of suitable fill at an acceptable cost and the need for sufficient area to stockpile the millions of cubic yards of soil required to construct all reaches of the FRM levee and the A12, A13, and A18 ecotones. Phase I, Reach 1 addresses the need for a suitable stockpiling area by allowing stockpiling in the future ecotone footprints in Ponds A12, A13, and the easternmost portion of A18, adjacent to the existing berm along the active biosolids ponds, during the initial construction activities (Att. A, Figures 7a and 7b). Material stockpiling in Ponds A12, A13, and A18 may be restricted to the future ecotone footprint within the ponds. Prior to stockpiling fill material, Ponds A12, A13, and A18 may be dewatered to facilitate dry stockpiling conditions. Water in Ponds A12 and A13 may be pumped out of the ponds to lower the water levels temporarily. Pond A18 may be passively dewatered by gravity flow through existing water control structures on Artesian Slough as much as possible, but the pond may also be pumped to reduce water levels to an appropriate height in areas where passive dewatering will not be effective (e.g., borrow ditches, former marsh channels). The stockpiling is limited to a maximum height of 17 feet, which is approximately the height of the City's sludge pond berm.

- 14. Project Alternatives Analysis:** While the overall Project design for the FRM levee along Reaches 1 to 5 has not been finalized, the Discharger has demonstrated that the currently proposed alignment along Reaches 1 to 3 is the least environmentally damaging practicable alternative along those reaches, and the Reach 1 to 3 alignment is not expected to change. The Discharger evaluated overall Project alternatives, including specific reach alignments for the FRM levee, in the *Clean Water Act Section 404(b)(1) Determination, South San Francisco Bay Shoreline Phase I Study, Santa Clara County, California* (HDR, July 1, 2015) (404(b)(1) Determination) as an appendix to the FEIR. The Discharger submitted a brief discussion of the alternatives considered in the FEIR and the Regional Water Board-proposed landward levee alignment in Reaches 4 and 5 in the application with an emphasis on the FRM levee alignment across Artesian Slough and along the RWF segment. This Order acknowledges the need to fully evaluate and reevaluate alternative levee alignments east of Reach 3 (i.e., for the crossing of Artesian Slough and Reaches 4 and 5) as designs are finalized, in order to optimize the tidal

marsh restoration opportunities while further reducing impacts to waters of the U.S., while acknowledging (in Attachment C) some of the constraints of that alternative alignment (including various departments and the City of San Jose).

15. **Authorization Process for Future Project Phases.** This Order requires supplemental applications that contain additional or revised information, including supplemental analysis and design plans for future Project work with supporting documentation that demonstrates the Project maximizes ecosystem restoration and minimizes the net fill of waters of the U.S., before construction of future Project components may commence. The future submittals will be subject to public review and approval by the Regional Water Board or the Executive Officer (see below). In addition, depending on overall Project impacts and tidal restoration success, this Order may be modified to require compensatory mitigation beyond that now required herein.

This Order requires that the supplemental analysis for Reaches 4 and 5 quantitatively address the impacts of alternative levee alignments on (a) anticipated rates and extent of post-breach establishment of vegetated tidal marsh; (b) long-term water management operations, water quality, and habitat functions/values in the City and landfill mitigation marshes given anticipated SLR (Att. C, Figures 1 and 3); and (c) anticipated attenuation of wave energy by vegetated tidal marsh bayward of the ecotone.

Supplemental analysis will also include additional information and designs for the Artesian Slough crossing, ecotones in Ponds A12, A13, and A18, and pond breaching. The current Pond breaching approach is generally suitable. If initial post-construction monitoring data indicate a high likelihood of success, the Pond breaches may be authorized by the Executive Officer, subject to applicable public review (see below).

Executive Officer Approval: This Order requires that supplemental applications provide supporting documentation to refine the Project as presented herein, including a range of alternative landward alignments along Reaches 4 and 5 that maximize ecosystem restoration opportunities and reduce overall Project cost. Those supplemental applications must be submitted to the Executive Officer for review and approval. Supporting documentation includes 30, 60, 90, and 100 percent design plans and the supplemental analysis described above (see Table 4).

Table 4: Summary of the subsequent Project work and information needed for approval.

Phase	Construction Event	Construction Activity	Supplemental Application Requirements
I	Second	FRM Levee, Reaches 2 and 3	Engineering Designs
	Third	FRM Levee, Reaches 4 and 5	Engineering Designs and Supplemental Analysis
	Fourth	Tidal Action Restoration to Ponds A12 and A18	Engineering Designs and Supplemental Analysis
II	Fifth	Tidal Action Restoration to Ponds A9, A10, and A11	Engineering Designs and Supplemental Analysis
III	Sixth	Tidal Action Restoration to Ponds A13, A14, and A15	Engineering Designs and Supplemental Analysis

Any Project changes that deviate from the Project described herein, not including the landward alignment along Reaches 4 and 5, or a similar alignment that would reduce the Project’s impacts, are considered significant and will be presented to the Regional Water Board for review and approval prior to implementation. Significant changes include, but are not limited to, any increase in net fill of waters of the U.S., failure to complete the Project as described herein, and any Artesian Slough crossing design that may alter the RWF’s ability to meet mixing requirements described in its NPDES permit.

In addition to supplemental applications, any changes to the Project that reduces the ecosystem restoration amount, thereby reducing the Project’s compensatory mitigation amount, must be approved by the Executive Officer before those changes can be implemented (see Findings 21 and 22).

Habitat and Pond Breaching Considerations

16. Ecosystem Restoration and Benefits of Tidal Marsh Restoration and Ecotones:

Implementation of the proposed ecosystem restoration is expected to result in a significant contribution to tidal wetland restoration in the San Francisco Bay region. Tidal marsh restoration was recommended in multiple regional reports, including, but not limited to, *The Baylands and Climate Change: What We Can Do. Baylands Ecosystem Habitat Goals Science Update 2015*, prepared by the San Francisco Bay Area Wetlands Ecosystem Goals Project, California State Coastal Conservancy, 2015 (Goals Project), and the San Francisco Estuary Partnership’s *Comprehensive Conservation and Management Plan (CCMP)* (1993; updated 2007 and 2016); both reports encourage the restoration of salt ponds to tidal marsh where feasible.

Restoring tidal wetland functions to former salt ponds will improve water quality in the South San Francisco Bay Estuary on a spatially significant scale with large contiguous habitat to maximize ecotonal or estuarine-terrestrial transitional habitat and minimize non-native vegetation (if appropriate management efforts are taken to control non-native species) (Goals Project). In addition to habitat and water quality benefits, tidal marsh restoration will also help protect communities from floods, storms, and SLR by attenuating wave energy and buffering storm surges. Marsh systems that are tidally-connected to the estuary improve water quality by filtering, fixing, and transforming pollutants. Marsh systems also protect beneficial uses by: providing nursery habitat and protection from predation for native fish species; creating significant biological productivity in estuarine and pelagic waters; and providing habitat for rare and endangered species such as the salt marsh harvest mouse (*Reithrodontomys raviventris*) and the California Ridgway's rail (*Rallus obsoletus*). Successful Project restoration would provide shallow open-water habitat for resident and migrating shorebirds such as Forster's terns, American avocets, Caspian terns, black-necked stilts, and the federally-threatened western snowy plovers, and resident and migratory waterfowl such as mallards, greater and lesser scaup, northern shovelers, pintail, canvasback, and others.

Broadly speaking, tidal salt marshes in San Francisco Bay are currently in dynamic equilibrium with water levels in the Bay. The surfaces of these marshes can keep pace with rising sea levels if the Bay's suspended sediment supply remains relatively high, subsidence rates remain low, and restoration activities begin soon. While suspended sediment concentrations in the South Bay are relatively high, there has been an observed decrease in suspended sediment concentrations estuary-wide, beginning in 1999. At the same time, rates of SLR along the California coast are projected to increase in the future. This purpose of the Project is to help address the uncertainty surrounding the future resiliency of vegetal tidal wetlands in the Estuary and provide the necessary flood protection to support an acceleration of tidal wetland restoration.

The proposed opening of salt ponds to tidal action is expected to restore tidal marsh on a large scale. Larger marshes tend to develop much more extensive networks of tidal channels, which provide habitat for fish and aquatic birds. These tidal channels also allow for the development of more diverse vegetative communities due to accumulation of sediment, and thus higher ground, along larger channels. Such diverse habitat with abundant internal high tide refugia will support much larger and more resilient populations of species such as the State and federally-endangered Ridgway's rail and salt marsh harvest mouse, and these animals are expected to have higher reproductive success and survivorship in larger, more heterogeneous marshes. In addition, having an established marsh in front of the FRM infrastructure will increase the resiliency of the shoreline to SLR.

The restoration will also provide more and higher quality estuarine-upland transitional habitat (ecotone) along the proposed levees in Ponds A12, A13, and A18. This habitat, located where tidal marshes transition into uplands with increasing elevation, provides habitat for a broad range of special-status plant species, increases habitat resiliency by providing space for marshes to retreat inland in the face of SLR and provides refugia for animals such as the California Ridgway's rail and salt marsh harvest mouse when the marsh plain is inundated during very high tides.

Consistent with the above, the tidal marsh restoration and ecotone creation require the conversion of existing managed pond habitat. If undesired impacts are observed during the monitoring and adaptive management period, Phases II and III may be modified by adaptive management recommendations or conversion of pond habitat to tidal marsh may stop. This Order requires any modifications to Phase II and III implementation to be submitted to the Executive Officer for review and approval (see Finding 15 and Provision 1).

17. **Sea Level Rise (SLR):** Climate change is expected to have dramatic effects on the regional sea level in San Francisco Bay. The National Research Council projects regional SLR in San Francisco Bay to reach 0.92 ± 0.30 feet (range of 0.4 to 2.0 feet) by mid-century (2050) and 3.02 ± 0.83 feet² (range of 1.39 to 5.46 feet) by the end of the century (2100) (Goals Report). Under even the most modest projections, rising seas will likely change the existing coastal habitat by flooding lower elevation habitat, such as mudflats and marshes, while occupying higher elevation terrain landward (Goals Report). SLR will also reduce drainage opportunities for tidally-controlled water management infrastructure (e.g., tide gates) by raising the elevation of the lowest tides.
18. **Pond Restoration:** Ponds will be breached in specific locations to facilitate flow of water into and through the ponds, allow the tides to carry sediment into the breached ponds, and allow for the restoration of remnant channels in the pond bottoms. The following ground preparation actions will be involved in converting ponds to tidal marsh:
 - Drain the pond to the extent feasible. Each pond will be drained passively, so it may take several months to dry out; pumping would expedite the process and may be considered. Due to historic pond subsidence, some pond areas cannot be drained completely passively. This step is also dependent on temporal proximity to the western snowy plover nesting season and/or if access to the area can be obtained without impacts to plovers, as dried pond areas may invite snowy plover nesting. This Order identifies potential impacts to wildlife, including special status species such as the snowy plover, and requires the Discharger to implement appropriate protective measures.
 - Construct wetland-upland transitional habitat (described in Findings 10 and 16).
 - Remove vegetation where needed (i.e., around the breach locations) to discourage salt marsh harvest mice from using the impact areas.
 - Excavate pilot channels on the outboard side of the pond dikes.
 - Construct ditch blocks.
 - Breach the outboard dikes.
19. **Ponds A9-A15 Internal Pond Breaching:** Tidal restoration activities in Ponds A9-A15 are similar to those described for Pond A18 in Phase II. However, the internal berms in Ponds A9 to A15 require the reconnection of historical channels and restoration of hydraulic connections to

² Projections include one standard deviation (85% confidence interval)

the innermost ponds in the Project footprint. The breaches in Ponds A9 to A15 will be sized in a similar manner to those applied to the outboard dikes and will extend beyond the dike into the remnant historical channels. Existing internal berms may be lowered in some areas during the breach excavation to create wave breaks to limit wave action, enhance sedimentation, and create vegetated marsh habitat on the berm crests in the short term, while the ponds develop from mudflat to vegetated marsh. As Ponds A9-A15 are breached during Phases II and III, berms in adjacent ponds that have not been breached yet will be temporarily raised to provide increased flood protection inboard of the ongoing pond breaching actions. Assuming no slowdown between phases based on the MAMP, the current schedule will see the internal pond dikes breached throughout A9-A15 by the end of 2032.

Impacts and Mitigation

20. **Project’s Fill of Waters of the U.S.** The Project area contains approximately 2,916 acres of waters of the U.S., comprised of tidal salt marsh, tidal brackish marsh, muted tidal/diked marsh, tidal freshwater marsh, seasonal wetland, tidal open water, batch pond, managed pond, mud flat, and former salt ponds. In total, approximately 132.2 acres of permanent, fill-based impacts to waters of the U.S. will occur from the Project’s construction activities. The permanent fill impacts include the FRM levee construction, ecotone creation, and ditch block placement (see Table 5).

Table 5: Summary of the Permanent Fill-Based Impacts by Project Component.

Feature	Permanent Impacts		
	Area (Acres)	Length (Feet)	Fill (CY)
FRM Levee and Artesian Slough Bridge	39.53	19,775	326,000
Stockpile Area within Future Ecotone Footprint (Ponds A12, A13, and A18)	41.61	5,980	702,000 ³
Ecotone Creation, Outside of Stockpile Area (A12, A13, and A18)⁴	49.91	5,747	1,232,000
Ditch Blocks	1.15	--	8,000
Total	132.2	19,775	2,268,000

The Project work will also modify waters of the U.S. without permanent placement of fill, including berm excavation, outboard dike breaches and lowering, anticipated habitat conversion

³ This amount is the maximum volume anticipated by the Discharger. The final volume may be less than what is stated in this Order, depending on available suitable material.

⁴ This is the future ecotone area not accounted for within the stockpile footprint. Since the ecotone will run parallel to the FRM levee, the stockpile impact length overlaps with the FRM levee impact length.

from former salt ponds to tidal marsh after tidal action is restored to the ponds, and establishment of a permanent FRM levee maintenance area (see Table 6).

Table 6: Summary of the Project’s Non-Fill-Based Impacts, Including Restoration Actions.

Feature	Permanent Non-Fill Impacts		
	Area (Acres)	Length (Linear Feet)	Fill (Cubic Yards)
Phase I: Pond A12 southeastern berm excavation	0.740	19,607	0
Phase I: Pilot Channel	7.8	4,373	-62,920
Phase I: Pond A12 and A18 outboard dike breaches and internal berm lowering	18.5	16,050	-89,105
Phase I: Restoration of tidal action to Ponds A12 and A18	1,120	--	--
Phase II: Ponds A9-A11 outboard dike breaches and internal berm lowering	20.0	--	0
Phase II: Restoration of tidal action to Ponds A9-A11	900	--	--
Phase III: Ponds A13-A15 outboard dike breaches and internal berm lowering	20.0	--	0
Phase III: Restoration of tidal action to Ponds A13-A15	880	--	--
Phases I to III: Permanent FRM Maintenance Easement	5.32	19,451	0
Total	2,972.36⁵	35,657⁶	-152,025

Excavation activity in Pond A12 is necessary to eliminate two 90-degree bends in the levee and results in less FRM levee fill. This excavation work will permanently impact Pond A12 because approximately 0.74 acre of the existing levee will be removed. The inboard and outboard berm breaches during ecosystem restoration construction will cause permanent impacts, but these impacts will facilitate the return of tidal action to the former salt ponds. Additionally, a 5.32-acre area along the landward side of the new levee will be used as a permanent maintenance easement for the FRM levee following Project construction.

⁵ This amount includes overlapping areas.

⁶ Since the ecotone will run parallel to the FRM levee, the stockpile impact length overlaps with the FRM levee impact length.

21. **Project’s Net Loss of Waters of the U.S.** As stated previously, constructing the FRM levee prior to breaching the ponds is necessary to provide adequate flood protection before tidal action is restored to the ponds. In addition, sequenced pond breaching will facilitate tidal restoration by maximizing sediment accretion and hydraulic connectivity at strategic pond locations. The phasing will result in a net loss of waters starting in Phase I due to the lag time between the initiation of construction activities and the eventual return of tidal action to the ponds, ecotone creation, and anticipated tidal marsh restoration. After Phase I is completed, including Ponds A12 and A18 breaching, there will be an approximate 76.96-acre net loss of waters of the U.S., not including SLR mitigation credit. After the 14-year Project is completed, there will be an approximate 8.76-acre net loss of waters of the U.S., with the currently proposed FRM levee alignment, although the currently projected loss could turn into a net gain of waters of the U.S. with an alternative landward alignment along Reaches 4 and 5 (see Att. C) (see Table 7).

Table 7: Summary of the Total Net Loss of Waters of the U.S. by Project Phase.

Created waters of the U.S.		Total Net Loss of waters of the U.S. after creation (acres) ⁷
Description	Area (Acres)	
Pond A12 southeastern berm excavation	0.740	131.5
Ecotones below high tide line ⁸	36.0	95.46
Phase I Pond A12 and A18 outboard dike breaches and berm lowering	18.5	76.96
Phase II Ponds A9-A11 outboard dike breaches and berm lowering	20.0	56.96
Phase III Ponds A13-A15 outboard dike breaches and berm lowering	20.0	36.96
50 years of SLR	28.2	8.76
Total	123	8.76⁹
Total with landward alignment		-61.24¹⁰

This Order specifies minimum required mitigation the Discharger is required to complete to compensate for Project impacts and deadlines for completing the mitigation (see Finding 22). Due to the need to phase construction activities and the uncertainty in the final levee alignment and associated impacts, final mitigation amounts may be greater or less than the minimum specified herein. To facilitate Project construction, the Order sets forth a process to determine final mitigation requirements as plans for future Project phases are further developed.

⁷ The values in this column reflect the running net loss total starting with 132.2 acres of fill-based impacts.

⁸ This area is being counted as new created waters because it has not historically existed in this area.

⁹ This is the current total net loss estimate. Further investigation during future Project phase development may yield a larger or smaller amount.

¹⁰ This amount reflects approximately 70 acres of vegetation marsh that would be restored within the footprint of the former inactive sludge ponds (see Att. C). The negative shows there would be net gain of waters of the U.S.

If there is a minimal net loss of waters of the U.S. from the final FRM levee alignment, then the tidal restoration and ecotone creation, if fully implemented consistent with the deadlines in this Order, will serve as sufficient compensatory mitigation for the impacts from Project construction activities. If there is a net loss of waters of the U.S. from the final FRM levee alignment that is greater than the amount described above in Table 7, the Order requires the Discharger to update the Project's impact quantities, and propose and implement additional compensatory mitigation as described in the Provisions (see Provisions 17, 35, and 36). Pursuant to an agreement between the Corps, District, and Conservancy, the Coastal Conservancy is responsible for complying for the requirements of Provision 17, regarding preparation and implementation of a Contingency Mitigation and Monitoring Plan.

When the Discharger submits supplemental applications for future Project work, total Project impacts will be taken into account to calculate the impacts to waters of the U.S., including temporary and permanent losses.

22. **Project Mitigation.** The Discharger will mitigate the Project's fill-based impacts by restoration actions that include creating jurisdictional waters of the U.S. and restoring tidal action to existing jurisdictional waters. As detailed in Finding 21 and summarized below, the Project will create approximately 59 acres of new jurisdictional waters from lowering and removing berms, and 36 acres of created ecotone habitat will be immediately below the high tide line, while another 28 acres of created ecotone will become jurisdictional by 2067 from estimated SLR. The anticipated restoration of tidal action to the Project's ponds is expected to provide water quality improvements, habitat for rare and endangered species and resident and migratory shorebirds and waterfowl, more and higher-quality estuarine-upland transitional habitat (ecotone) along the proposed levees in Ponds A12, A13, and A18 than is currently available, protect beneficial uses, and increase shoreline resiliency. In addition, restoring tidal marsh and creating estuarine-upland transitional habitat is consistent with the Goals Report and CCMP.

However, the mitigation requirement may change as designs for the FRM levee alignment east of Artesian Slough are further developed, which may reduce the Project's fill-based impacts. As discussed in Findings 13 to 15, the Discharger is evaluating an alternative FRM levee alignment east of Artesian Slough that would reduce the Project cost and maximize ecosystem restoration opportunities. The other uncertainty in the final mitigation requirement is the ecosystem restoration's degree of success. The anticipated tidal marsh habitat acreage may not be successful if observed sediment accretion rates in the South Bay are significantly less than anticipated rates, or mitigation and monitoring results from the first set of breached ponds do not lead to a recommendation to breach Ponds A9-A15. Since berm lowering and removal in Phases II and III are expected to create jurisdictional features that will reduce the Project's net fill amount to the currently projected 8.76 acres, there is uncertainty associated with future tidal marsh restoration and its sufficiency as mitigation for Project impacts. Therefore, the mitigation for the Project's total impacts will become more certain as the designs for future Phases are further developed and the monitoring results provide more information about the likelihood of success for the restoration activities. To account for the uncertainty in the Project's ecosystem restoration success and FRM levee alignment east of Artesian Slough, the Order sets forth a mechanism to account for, and, as needed, adjust the Project's impacts and compensatory mitigation amounts authorized by this Order (see Provisions 17, 31, 35, and 36).

Mitigation for Fill-Based Impacts and Habitat Conversion: The Project's impacts that cause a net loss of waters of the U.S. will be mitigated by the Discharger as required in this Order and described in the Findings and Provisions. The Project will create new waters of the U.S. and convert the existing ponds to restored tidal marsh and created ecotones in Phases I, II, and III (Att. A, Figures 8 and 9).

The new waters of the U.S. created by the Project will mitigate the Project's permanent fill-based impacts. Removal of the existing berm at the southeast corner of Pond A12 will create approximately 0.74 acre of new open waters that will eventually be restored to tidal marsh. Approximately 18.5 acres of new wetlands will be created from breaching Ponds A12 and A18. The created ecotones will result in approximately 28 acres of new waters of the U.S. based on the high SLR estimates calculated by the Discharger. In addition, pond breaching and berm lowering in Phases II and III will create approximately 40 acres of waters of the U.S. that are expected to become colonized with wetland vegetation. These non-fill-based impacts reduce the Project's overall net loss of waters of the U.S. as described in Findings 20 and 21.

In addition, the Project will restore up to 2,900 acres of tidal marsh by 2032 and create approximately 91.52 acres of ecotone by 2022, if the proposed restoration is successfully implemented. The anticipated tidal marsh and ecotone habitat are regionally scarce, and their restoration and creation, respectively, are recommended in the Habitat Goals report (see Finding 16). The ecotone area will convert approximately 91.52 acres of current salt pond habitat to wetland-upland transitional habitat. The conversion will facilitate a tidal wetlands restoration that mimics historical San Francisco Bay landforms. The net benefit is an increase in tidal marsh habitat and its associated beneficial uses and functions and a corresponding decrease in salt ponds. This habitat conversion is consistent with the Regional Water Board's Basin Plan Wetland Fill Policy and California Wetlands Conservation Policy (see Findings 32 and 33). However, the habitat conversion's success and consistency with these policies is contingent upon the completion of all three Project phases, including the Project's ecosystem restoration components. The remaining temporal loss of waters of the U.S. from fill-based impacts will be mitigated by the anticipated 1,120 acres of converted habitat (i.e., tidal marsh and ecotone) in Ponds A12 and A18 at the end of Phase I (see Table 8).

Table 8: Summary of Restored Tidal Marsh and Ecotone Creation by Project Phase.

Phase	Maximum Anticipated Tidal Marsh Habitat Restored (Acres)¹¹	Ecotone Created (Acres)	Anticipated Construction (Year)
I	1,120 ¹²	91.52 ¹³	2022
II	900	0	2027
III	880	0	2032
Total	2,900	91.52	--

Mitigation for Non-Fill-Based Impacts: The Project’s non-fill-based impacts will be mitigated by the corresponding conversion of pond habitat to restored tidal marsh and created ecotone, similar to the mitigation for the remaining fill-based temporal impacts (see above). The restored tidal marsh and created ecotones will mitigate the Project’s non-fill based impacts because the habitat’s expected quality and associated benefits are sufficient to offset non-fill based impacts that may result from loss of managed pond habitat and any temporal loss of functions and values that will occur from the time fill-based impacts occur to when the restoration is implemented and becomes fully established. Similar to the fill-based impact mitigation, the non-fill-based mitigation in each phase is associated with and contingent upon completion of the respective Project phase, including the proposed tidal and wetland restoration (i.e., Phase I pond conversion impacts are mitigated by the anticipated tidal and wetland restoration in the Phase I ponds, and similarly, impacts associated with the restoration in Phases II and III are mitigated by the restoration in Phases II and III).

II. Reaches 1 to 3.

The following sections discuss three of the five FRM levee reaches. The FRM levee alignment along Reaches 1 to 3 is generally acceptable, and additional design plans and documentation will be submitted to the Regional Water Board for approval prior to the initiation of construction (see Finding 15). In addition to the FRM levee alignment along Reaches 1 to 3, the stockpiling locations in Ponds A12, A13, and A18 are generally acceptable. Conceptual drawings for the FRM levee alignment along Reaches 1 to 3 and the stockpiling areas have been submitted to the Regional Water Board (Att. A).

23. **Reaches 1 to 3 Project Site.** Reach 1 is located in the southwestern corner of the Project site. Reach 2 continues at the end of Reach 1 where the levee reaches the southern portion of Pond A13 and turns east. Reach 3 continues east until Alviso Slough. Reaches 1 to 3 make up the Alviso FRM levee segment.

¹¹ These amounts are for the converted habitat onsite, not created jurisdictional waters. Mitigation credit for this conversion is only being given for the temporal loss of waters of the U.S. and functions and values of existing beneficial uses that result from the Project’s fill-based impacts.

¹² Under the FRM levee landward alignment for Reaches 4 and 5, this amount would be increased by a maximum of 70 acres to approximately 1,190 acres, which would bring the total anticipated tidal marsh restoration amount to 2,970 acres.

¹³ Approximately 55.52 acres of the created ecotone will initially be above the high tide line after construction. After 50 years of SLR, about 27.32 acres will be above the high tide line. The ecotone above the high tide line will enhance beneficial uses associated with tidal marshes by providing high tide refugia for special-status species.

24. **Reaches 1 to 3 Construction Activities.** This Order authorizes levee construction, including excavation, dewatering, and fill placement, and the creation of ecotones in Ponds A12, A13, and A18, including the use of the ecotones’ footprints in these ponds as staging/stockpiling areas.

Levee Construction: Levee construction timing and duration are constrained by weather conditions and listed species construction windows. The FRM levee will be constructed along approximately 9,345 linear feet of Reaches 1 to 3 (see Table 9).

Table 9: Summary of Reaches 1 to 3 Impacts Related to FRM Levee Construction.

Phase	Reach	Length (Linear Feet)	Description	Construction Event	Anticipated Construction (Year)
I	1	4,250	Alviso Marina to UPRR (Pond A13)	First	2018
	2	2,120	UPRR to Artesian Slough (Pond A16 & New Chicago Marsh)	Second	2019
	3	2,975			
Total		9,345		--	--

The design elevation for the new levee is 15.2 feet NAVD after settlement. The earthen levee will increase the existing dike’s height by approximately 10 feet (after settlement) and double the existing width. Upland fill material, or dredge material, will be used to construct the FRM levee and will originate from locations outside the Project area. Any dredge material used onsite will meet established screening criteria. Where the levee crosses the active UPRR line between Ponds A13 and A16, railroad floodgates will be installed. Concrete barriers will be installed on either side of the railroad right-of-way and tied into the earthen levees. Metal floodgates will be connected to the barriers and remain open during normal conditions and closed during flood conditions.

Ecotone Creation and Staging Area/Fill Stockpiling in Ponds A12, A13, and A18: The staging area and stockpiling area for fill material will be located in the future ecotone footprints in Ponds A12, A13, and A18. The fill used to construct the FRM levee will be imported from local sources and delivered by truck to the staging area. The water level in Pond A12 will be temporarily lowered during one construction season to dewater the stockpile footprint. Existing dike roads will be used as ingress and egress truck routes for the stockpiling areas. Any additional stockpile locations will be proposed in future permit applications.

The ecotones in Ponds A12 and A13 will be constructed after the adjacent FRM levee along Reaches 1 and 2 are completed. Under the current construction timeline, the ecotones in Ponds A12 and A13 will be constructed during Phase I’s second and third construction event. The

future ecotone in Pond A18 will not be created until the adjacent FRM levee along Reaches 4 and 5 is completed during the fourth construction event.

Dewatering: It is anticipated that the work area will need to be temporarily dewatered to construct the levee. If dewatering is necessary, dredge-locks or cofferdams may be constructed using earth levees or sheet piling. When possible, amphibious excavators, vibratory pile drivers, and other less-impactful equipment will be used.

Excavation: The existing dikes will be excavated below the mudline to meet FEMA levee standards. The excavator will place excavated dike and other fill material on both sides of the future Reach 1 alignment to create temporary dikes for dewatering the entire Reach 1 levee footprint. The excavator will proceed along the top of the dike for the entire length of Reach 1.

III. Maintenance and Management

25. **Replace and Realign Selected Utilities Infrastructure.** The only known utility crossing near the Reach 1 FRM levee alignment was identified as a storm drain. The storm drain is owned and operated by the City of San Jose. The storm drain's depth, diameter, and material are currently unknown. Prior to construction, the storm drain's location and condition will be identified. The storm drain will be protected in place during construction.

26. **Operation and Maintenance Plan.** The Discharger will prepare an Operation, Maintenance, Repair, Replacement, and Rehabilitation (O&M) Plan to describe ongoing activities that will be implemented along the entire FRM levee and ecotones. The District will be responsible for implementing the O&M Plan for the FRM levee after the levee construction is complete. The O&M Plan will include FRM levee O&M activities that will be performed in order to meet the Corps' levee safety program standards and FEMA certification requirements. The following O&M activities will be performed on the FRM levees:

- Trash and anthropogenic debris removal along levee slopes and where it is causing obstruction in culverts or other problems
- Repairs on levees due to damage by small burrowing mammals, runoff/erosion, storm activities, or other factors
- Repairs along concrete flood wall structures (if included in the plan) and other features, such as bridges and culverts
- Levee inspections
- Graffiti removal
- Access improvements and upkeep
- Vector monitoring (presence of mosquitos and their larvae)
- Vegetation management—the levee design will include vegetation to control erosion on the bayward and landward side slopes, but some mowing will be needed on the levee side slopes

within 12 to 15 feet of the levee crown. In addition, within a narrow 15-foot or less strip of ecotone fill along the edge of the exposed levee crest, vegetation will be managed on the ecotone in a similar manner as on the FRM levee. The following vegetation management activities will be performed by the Discharger on the FRM levee and ecotones:

- a) Regular mowing of the levee side slopes. Regular mowing will be performed annually. Mowing will proceed from the top, close to the crown, where habitat is of lowest quality, downward toward high-quality habitat so that wildlife that may be using the mowed area are encouraged to move downslope from the noise and movement of the mower.
- b) No woody plant species greater than two inches in diameter will be allowed to become established on the levees, to prevent roots from damaging the structural integrity of the levee and prevent mature woody plants from serving as raptor perches. Any woody vegetation that germinates in the higher-elevation mowing zone will be managed by mowing. Below the mowing zone, any wood plant removal that becomes necessary will be performed by hand; such hand-removal is expected to be necessary about once every few years.

27. **Monitoring and Adaptive Management Plan (MAMP).** The *South San Francisco Bay Shoreline Study, Monitoring and Adaptive Management Plan for Ecosystem Restoration* (Corps, September 2015) (MAMP) provides a feasibility-level monitoring and adaptive management plan for the Project. The MAMP identifies potential monitoring activities, outlines generally how results from the monitoring will be used to assess Project success, provides estimated costs, and recommends adaptive management actions, if such actions are necessary to achieve the desired ecosystem restoration objectives. The MAMP also specifies the parties responsible for monitoring and adaptive management activities. The MAMP is presented in four steps that capture the iterative adaptive management process:

- 1) Adaptive management planning;
- 2) Monitoring;
- 3) Regular assessments; and
- 4) Decision-making.

The adaptive management process outlined in the MAMP incorporates all four of these steps to arrive at a decision that increases the likelihood of achieving the desired habitat restoration success given Project uncertainties. The iterative process that will be used in adaptive management is shown graphically in the MAMP (Att. C, Figure 2). The MAMP used the SBSPRP's Adaptive Management Plan conceptual ecological model that provided a linkage between Project actions and expected system response.

Adaptive Management Planning: The MAMP lists the Project objectives, known constraints and considerations, and identifies related uncertainties in future conditions. The Project uses the SBSPRP tidal habitat conceptual model, which is directly relevant to the Project's desired habitat type and ecosystem restoration objectives.

Monitoring: The purposes of monitoring are to assess progress towards Project objectives, detect early signs of potential problems, and reduce uncertainties. The following primary monitoring topics were developed to address the Project's key uncertainties that were identified in the

MAMP: 1) Sediment dynamics; 2) Bird use of changing habitats; 3) Non-avian species; 4) Invasive and nuisance species; and 5) Ecotones. For each key uncertainty, restoration targets (success criteria) were also developed to identify the desirable outcome. Monitoring metrics were then defined to measure each restoration target. A complete list and description of the monitoring topics, targets, and metrics associated with ecosystem restoration objectives are shown in Appendix B, Table 2. In addition, each monitoring metric is detailed in terms of monitoring methods, locations, frequency, and duration in order to develop a cost estimate, as shown in Appendix B, Table 3. The MAMP acknowledges that the monitoring method summaries were intended to provide reasonable cost estimates but do not fully describe the monitoring regime. Consistent with MAMP Sections 3.1 and 3.3, this Order requires the Discharger to develop a monitoring plan with detailed triggers, metrics, methods, protocols, timing, and responsible parties prior to the start of monitoring (see Provision 35). This Order also requires the Discharger to monitor and adaptively manage the ponds that are restored to tidal action to ensure the Project's ecosystem restoration component is successful and mitigates the Project's permanent impacts to waters of the U.S. and to submit reports to the Executive Officer for approval.

To guide long-term management of the ponds, this Order requires that the Discharger continue to implement and report on applied studies. These studies will focus on the sources of uncertainty associated with ecosystem restoration, flood risk management, and public access that were identified in the MAMP (Att. B, Section 2.4). These sources of uncertainty were previously identified so that monitoring could be targeted to reduce these uncertainties and guide future actions, including adaptive management. This Order requires the Discharger to submit monitoring reports to the Executive Officer for the following monitoring topics and categories identified in the MAMP.

Regular assessments will be used to compare the results of the monitoring efforts to the desired Project performance targets to the corresponding management trigger. Each management trigger is a threshold that indicates, when reached, that the Project may be diverging from a restoration target. The triggers are intended to act as a warning signal before significant impacts to the system occur. This advance notice will provide the time needed to investigate the causes of the divergence and take action, as necessary, to put the system back on track. The management triggers and restoration targets will be reviewed and updated regularly as additional information becomes available during the monitoring period.

The MAMP outlines the assessment process, acceptable variances between monitoring results and targets, the frequency and timing for comparison of monitoring results to the selected targets, and assessment documentation. If the regular assessments indicate the ecosystem restoration system is not performing well, as defined by the restoration targets, then the corresponding management trigger may lead to adaptive management action. This Order requires revisions to the regular assessments and management triggers to be submitted to and approved by the Executive Officer.

Adaptive management actions will be implemented when the ecosystem restoration areas are not progressing towards the restoration targets and a management trigger has been reached. The first action will typically be to assess available monitoring data and consult with external and internal experts to inform subsequent management actions. Potential management actions are

categorized in the MAMP as the following: 1) as-needed assessments; 2) construction (adjustments to the design); and 3) changes to operations and maintenance. Changes to the restoration phasing (adaptive implementation) are also a potential outcome, but those actions are not included as cost-shared activities; and 4) additional data and analysis. This Order requires any adaptive management actions to be clearly detailed and presented with relevant supporting documentation, including monitoring data, restoration targets, management triggers, and a detailed description of the proposed actions, to the Executive Officer for review and acceptance prior to implementation (see Provisions 1 and 35).

28. **Construction General Permit.** The Discharger is required to seek coverage under and comply with, or oversee that its contractors seek coverage and comply with, the statewide General Permit for Discharges of Storm Water Associated with Construction Activities (Order No. DWQ-2009-0009, as amended, and as may subsequently be reissued) (Construction General Permit).
29. **Monitoring and Technical Reports.** All monitoring and technical reports required in this Order are required pursuant to CWC section 13267. The burden of preparing these reports, including costs, bears a reasonable relationship to the benefits to be obtained from the reports and monitoring. Specifically, the monitoring and technical reports will demonstrate protection of beneficial uses during construction and maintenance projects and verify the success of efforts to mitigate impacts. The technical reports will be used in combination with the MAMP to inform future actions and opportunities to maximize tidal restoration acreage and likelihood of restoration success.

IV. Other Findings

Laws, Regulations, and Policies

30. **California Environmental Quality Act (CEQA).** CEQA requires all discretionary projects approved by public agencies to be in full compliance with CEQA and requires a lead agency to prepare an appropriate environmental document for such projects. The District, as the lead agency, certified a combined Interim Feasibility Study and Environmental Impact Statement (EIS)/Environmental Impact Report (EIR) (Joint EIS/EIR) (HDR, July 2015) for the Project on March 22, 2016.

The Joint EIS/EIR found several potential impacts that are under the Regional Water Board's purview and jurisdiction. These include potential impacts to: (1) geology and soils; (2) hydrology and water quality; (3) aquatic biological resources; (4) terrestrial biological resources; and (5) hazardous materials. The Joint EIS/EIR also found that significant impacts identified therein, including FRM levee O&M activities and ecosystem restoration monitoring and adaptive management, would be reduced to less than significant levels by implementing the mitigation measures, with the exception of the Project's pond conversion impact. When the District certified the Joint EIS/EIR, it identified the Project's pond conversion as a significant unmitigated impact. Significant impacts that were identified in the Joint EIS/EIR include the following:

- HYD-01: Alter existing drainage patterns in a manner that would result in scour that could cause substantial erosion or siltation.

- WAT-01: Result in a violation of any water quality standard or WDRs.
- TBR-2: Have an effect on candidate, sensitive, or special-status species.
- HAZ-1: Create a significant hazard to the public or environment through transport, use, or disposal of hazardous materials or through reasonably foreseeable upset and accident conditions involving the release of hazardous materials into the environment.
- HAZ-3: Be located on a site that is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, create a significant hazard to the public or the environment.

The Regional Water Board, as a responsible agency under CEQA, has considered the Joint EIS/EIR and finds that, in combination with the requirements of this Order, impacts during the construction, post-FRM levee construction O&M activities, and post-pond breaching monitoring and adaptive management actions of the Project, including any potential FRM levee alignment changes along Reaches 4 and 5 that are landward of the currently proposed alignment, that are within the Regional Water Board's purview and jurisdiction have been identified and will be mitigated to less-than-significant levels. This Order includes conditions and mitigation measures that will substantially lessen the Project's impacts on the environment. The need to provide compensatory mitigation for impacts from the Project design is addressed in this Order.

31. **Water Quality Control Plans.** The Water Quality Control Plan for the San Francisco Bay Basin (Basin Plan) was duly adopted by the Regional Water Board and approved by the State Water Resources Control Board (State Water Board), U.S. EPA, and the Office of Administrative Law where required. The Basin Plan is the Regional Water Board's master water quality control planning document. It designates beneficial uses of receiving waters, establishes water quality objectives, and contains implementation programs and policies to achieve those objectives for all waters addressed by the Plan.

Existing and potential beneficial uses of waters within the Project area include the following:

- **Alviso Slough:** Estuarine Habitat (EST), Fish Migration (MIGR), Preservation of Rare and Endangered Species (RARE), Water Contact Recreation (REC-1), Noncontact Water Recreation (REC-2), and Wildlife Habitat (WILD);
- **Artesian Slough:** EST, RARE, REC-1, REC-2, and WILD;
- **San Francisco Bay:** Section 2.2.1 of the Basin Plan indicates that the beneficial uses of any specifically identified water body generally apply to its tributary streams. Because the former salt ponds are hydrologically connected to San Francisco Bay, the beneficial uses that are identified for San Francisco Bay also apply to the former salt ponds. These beneficial uses are: Commercial and Sport Fishing (COMM), EST, Industrial Service Supply (IND), MIGR, Navigation (NAV), RARE, REC-1, REC-2, Shellfish Harvesting (SHELL), Fish Spawning (SPWN), and WILD; and

- **Tidal Wetlands:** COMM, EST, MIGR, RARE, REC-1, REC-2, SPWN, and WILD.

32. **Basin Plan Wetland Fill Policy.** The Basin Plan Wetland Fill Policy (Fill Policy) establishes that there is to be no net loss of wetland acreage and value, and a long-term net gain, when a project and any proposed mitigation are evaluated together, and that mitigation for wetland fill projects is to be located in the same area of the region, whenever possible, as the project. The Fill Policy further establishes that wetland disturbance should be avoided whenever possible and, if not possible, should be minimized and only after avoidance and minimization of impacts should mitigation for lost wetlands be considered. The Regional Water Board incorporated U.S. EPA's Section 404(b)(1) Guidelines into the Basin Plan for determining the circumstances under which dredging or filling of wetlands, streams, or other waters of the U.S. may be authorized. The Regional Water Board must ensure that all projects meet State water quality standards, including, but not limited to, water quality objectives, existing and potential beneficial uses, and the State's Anti-degradation Policy. Requirements of this Order implement the Fill Policy.

33. **California Wetlands Conservation Policy.** Requirements of this Order implement the California Wetlands Conservation Policy. The goals of the California Wetlands Conservation Policy (Executive Order W-59-93, signed August 23, 1993) include ensuring "no overall net loss" and achieving a "...long-term net gain in the quantity, quality, and permanence of wetland acreage and values... ."

Senate Concurrent Resolution No. 28 states that "[i]t is the intent of the legislature to preserve, protect, restore, and enhance California's wetlands and the multiple resources which depend on them for benefit of the people of the State." Section 13142.5 of the CWC requires that the "highest priority shall be given to improving or eliminating discharges that adversely affect...wetlands, estuaries, and other biologically sensitive areas."

The Regional Water Board applies the California Wetlands Conservation Policy to waters that have the potential to be restored or converted to tidal marsh and related tidal marsh refugia in part because 79 percent of tidal marsh (150,000 acres) and 42 percent of tidal flats (21,000 acres) in San Francisco Bay were lost to diking and filling between 1800 and 1998 (Goals Project).¹⁴

34. **California Anti-Degradation Policy.** In the Basin Plan, the Anti-Degradation Policy (State Water Board Resolution No. 68-16: Statement of Policy with Respect to Maintaining High Quality of Waters in California) is applied to cases where water quality is better than that prescribed by the Basin Plan's water quality objectives. This policy is aimed at protecting relatively uncontaminated aquatic systems where they exist and preventing further degradation. The State's Anti-Degradation Policy is consistent with the federal Anti-degradation Policy. This Order complies with the federal and State anti-degradation policies because it will enhance the water quality of waters in the Project area by creating tidal marshes (see Finding 16) and ensures protection of existing water quality by requiring compliance with Basin Plan water quality objectives.

¹⁴ The amount of tidal marsh and tidal flats lost between 1900 and 1998 are from the Goals Report.

35. **Endangered Species Acts.** This Order does not authorize any act that results in the taking of a threatened or endangered species or any act that is now prohibited, or becomes prohibited in the future, under either the California Endangered Species Act (Fish and Game Code sections 2050 to 2097) or the federal Endangered Species Act (16 U.S.C.A. sections 1531 to 1544). The Discharger is responsible for meeting all requirements of the applicable Endangered Species Acts. As applicable, the Discharger shall utilize the appropriate protocols, as approved by USFWS and stated in the USFWS Coordination Act Report and required in this Order, to ensure that Project activities do not adversely impact water quality or the beneficial uses of Alviso Slough, Artesian Slough, and other waters of the U.S. as referenced in Finding 32.
36. **Special-Status Species.** The Discharger requested formal consultation with USFWS, pursuant to section 7 of the federal Endangered Species Act (ESA), regarding the Project's impacts to the federally-endangered California clapper rail (*Rallus longirostris obsoletus*), the endangered salt marsh harvest mouse (*Reithrodontomys raviventris*), the threatened Pacific coast population of the western snowy plover (*Charadrius alexandrinus nivosus*), and the endangered California least tern (*Sternula antillarum brown*). USFWS responded to the Discharger's consultation request in the Biological Opinion on the South San Francisco Bay Shoreline Phase 1 Study in Santa Clara County, California (BO), dated April 27, 2015. The BO included Conservation Measures, Reasonable and Prudent Measures, Terms and Conditions, and an Incidental Take Statement that the Corps, Coastal Conservancy, District, and City will comply with during Project construction and adaptive management activities.

The Discharger requested written concurrence from the National Marine Fisheries Service (NMFS), pursuant to section 7 of the ESA, regarding the Project's impacts to the federally-threatened Central California Coast steelhead (*Oncorhynchus mykiss*) and North American Green Sturgeon southern Distinct Population Segment (*Acipenser medirostris*) and their critical habitat. NMFS responded to the Discharger's consultation request in the *Endangered Species Act Section 7(a)(2) Concurrence Letter and Magnuson-Stevens Fishery Conservation and Management Act Essential Fish Habitat Response for the South San Francisco Bay Shoreline Phase I Study*, dated May 19, 2015. In its response to the Discharger's concurrence request, NMFS agreed with the Discharger's assessment that the Project is not likely to adversely affect ESA-listed fish and designed critical habitat. Part of NMFS' finding is based on the proposed measures to protect listed fish and the aquatic environment.

Public Noticing, Records, and Fees

37. **Notification of Interested Parties.** In accordance with CWC sections 13263(a) and 13241, the Regional Water Board, after considering this matter at a public hearing, has prescribed requirements as to the nature of the proposed discharge. These requirements implement the Regional Water Board's relevant water quality control plans and policies and take into consideration the beneficial uses to be protected, the water quality objectives reasonably required for that purpose, other waste discharges, and the need to prevent nuisance. The Regional Water Board has notified interested parties of its intent to issue WDRs and water quality certification for this discharge.
38. **Public Review.** Upon receipt of future applications for additional Project construction activities, including additional Phase I, II, and III activities, a public notice will be provided for a 30-day

period. The public notice of the applications will be posted on the Regional Water Board's website: http://www.waterboards.ca.gov/sanfranciscobay/public_notices/

39. **Consideration of Public Comment.** The Regional Water Board, in a public meeting, heard and considered all comments pertaining to the discharge. Additional public meetings to hear and consider all comments pertaining to future discharges may be scheduled when supplemental applications for future discharges are received by the Regional Water Board (see Finding 15).
40. **Records Management.** This Project file is maintained at the Regional Water Board under CIWQS Place No. 813084 and Regulatory Measure No. 413855.
41. **Fees for Dredge and Fill Projects.** The fee amount for this Order shall be in accordance with the current fee schedule, per 23 CCR, Division 3, Chapter 9, Article 1, section 2200(a)(3). The Regional Water Board understands, based on information from the Corps and the Non-Federal Sponsors, that the Non-Federal Sponsors are responsible for the fee.
42. **Waste Discharge Requirements (WDRs).** Pursuant to 23 CCR sections 3857 and 3859, the Regional Water Board is issuing WDRs and water quality certification for the activities proposed in this Order. Pursuant to CWC section 13263 and 23 CCR section 3857, the Regional Water Board is issuing WDRs to regulate the proposed discharge of excavation, dredge, and fill into waters of the U.S. The Regional Water Board considers WDRs necessary to adequately address impacts and mitigation to beneficial uses of waters of the U.S. from the Project, to meet the objectives of the California Wetlands Conservation Policy (Executive Order W-59-93), and to accommodate and require appropriate changes over the life of the Project, including during its construction and in subsequent phases.
43. **Water Quality Certification.** Any discharge from the Project consistent with the Corps' application and as conditioned in this Order will comply with the applicable provisions of CWA sections 301 (Effluent Limitations), 302 (Water Quality Related Effluent Limitations), 303 (Water Quality Standards and Implementation Plans), 306 (National Standards of Performance), and 307 (Toxic and Pretreatment Effluent Standards) and with other applicable requirements of State law. The Project will result in discharge of dredge and fill materials into waters of the U.S. and of the State. The CWA (33 U.S.C. §§ 1251-1387) was enacted "to restore and maintain the chemical, physical, and biological integrity of the Nation's waters." (33 U.S.C. § 1251(a).) Section 401 of the CWA (33 U.S.C. §1341) requires every applicant for a federal license or permit that may result in a discharge into navigable waters to provide the licensing or permitting federal agency with certification that the Project will be in compliance with specified provisions of the CWA, including water quality standards and implementation plans promulgated pursuant to CWA section 303 (33 U.S.C. § 1313). CWA section 401 directs the agency responsible for certification to prescribe effluent limitations and other limitations necessary to ensure compliance with the CWA and with any other appropriate requirement of state law. CWA section 401 further provides that state certification conditions shall become conditions of any federal license or permit for the Project.

IT IS HEREBY ORDERED that, pursuant to the provisions of CWA 401 and Division 7 of the CWC, related regulations, and guidelines adopted thereunder, the Discharger, its agents, successors, and assigns shall comply with the following:

A. Discharge Prohibitions.

1. The discharge of wastes, including debris, rubbish, refuse, or other solid wastes into surface waters or at any place where they would contact or where they would be eventually transported to surface waters, including floodplains, is prohibited.
2. The discharge of floating oil or other floating materials from any activity in quantities sufficient to cause deleterious bottom deposits, turbidity, or discoloration in surface waters is prohibited.
3. The discharge of silt, sand, clay, or other earthen materials from any activity in quantities sufficient to cause deleterious bottom deposits, turbidity, or discoloration in surface waters is prohibited, except as otherwise described herein.
4. The fill activities subject to these requirements shall not cause a nuisance as defined in CWC section 13050(m).
5. The groundwater in the vicinity of the Project shall not be degraded as a result of the Project activities or placement of fill for the Project.
6. The discharge of materials, which are not otherwise regulated by a separate NPDES permit or allowed by this Order, to waters of the U.S. is prohibited.
7. This Order prohibits any dewatering, diversion, or discharge before the Executive Officer accepts, in writing (including via electronic mail), a Dewatering Plan that meets the requirements of this Order.
8. This Order prohibits the alignment of any utilities, or maintenance of existing utility lines in the Project area, in a manner that will create an obstacle to flow or destabilize the ponds or adjacent creeks.
9. Equipment shall only be operated within the footprint documented in the work zone described herein and as approved by the Executive Officer. No fueling, cleaning, or maintenance of vehicles or equipment shall take place within any areas where an accidental discharge to waters of the U.S. may occur, except as described in the SPCP (see Provision 11).

B. Provisions.

1. The Discharger shall comply with all Prohibitions and requirements of this Order immediately upon adoption of this Order or as otherwise provided below. The Discharger shall fully implement all requirements of this Order, including all plans accepted by the Regional Water Board or the Executive Officer. Any significant alterations to the Project, as defined in Finding 15, shall be submitted to the Executive Officer, or this Regional Water Board, for review and approval prior to their implementation. If the Regional Water Board does not accept a significant alteration to the Project prior to its implementation, the Discharger will be considered in violation of this Order and may be subject to Regional Water Board enforcement actions.

2. All plans and reports required under this Order shall be submitted and acceptable to the Executive Officer.
3. The Project shall be constructed in conformance with the description herein, the Project application materials, and the 100 percent Design Plans that shall be submitted prior to the initiation of Project construction.
4. All work performed within waters of the U.S. shall be completed in a manner that minimizes impacts to beneficial uses and habitat. Measures shall be employed to minimize disturbances that will adversely impact the water quality of waters of the U.S.
5. Disturbance or removal of vegetation shall not exceed the minimum necessary to complete Project implementation. The Project site shall be stabilized through incorporation of appropriate BMPs, including the successful establishment of native grass vegetation, to compensate for impacts to wildlife habitat values and to prevent and control erosion and sedimentation. The Discharger shall revegetate Reach 1 based on the 100 percent Design Plans and Planting Plan.
6. The discharge shall not cause a violation of any water quality standard for receiving waters adopted by the Regional Water Board or State Water Board as required by the CWA and regulations adopted thereunder. If more stringent water quality standards are promulgated or approved pursuant to CWA section 303, or amendments thereto, the Regional Water Board may revise or modify this Order in accordance with the more stringent standards. Pond dewatering discharges, accumulated groundwater or stormwater removed during dewatering of excavations, and diverted pond and stormwater flows shall not be discharged to waters of the U.S. without meeting the receiving water objectives in the Basin Plan.
7. **Construction General Permit.** The Discharger shall seek coverage under and comply with, or ensure that its contractors seek coverage and comply with, the statewide General Permit for Discharges of Storm Water Associated with Construction Activities (Order No. DWQ-2009-0009, as amended by Order Nos. 2010-0014-DWQ and 2012- 006-DWQ), and as may be subsequently amended or reissued. All work performed within waters of the U.S. shall be completed in a manner that minimizes impacts to water quality and the beneficial uses of Alviso Slough, Artesian Slough, tidal wetlands, and other waters of the U.S.
8. **Receiving Water Limitations.** Dewatering discharges, accumulated groundwater or stormwater removed during dewatering of excavations, and diverted creek and stormwater flows shall not be discharged to waters of the U.S. without meeting the following discharge and receiving water limitations. All monitoring records at the Project site shall be maintained at a location to be designated in the Dewatering Plan and shall be made available upon request by Regional Water Board staff.
 - a. pH - the instantaneous discharge pH shall be in the range of 6.5 to 8.5, and controllable water quality factors shall not cause changes greater than 0.5 units in receiving water pH levels.

- b. Discharge Dissolved Oxygen - the discharge dissolved oxygen concentration shall be no less than 5.0 milligrams per liter (mg/L).
 - c. Discharge Dissolved Sulfide - the discharge-dissolved sulfide shall not be greater than 0.1 mg/L.
 - d. Receiving Water Turbidity - the discharge turbidity shall not be greater than 10 percent more than receiving water turbidity, measured as nephelometric turbidity units (NTU), in areas where natural turbidity is greater than 50 NTU (daily average). In areas where natural turbidity is less than or equal to 50 NTU, the discharge shall not cause an increase in receiving water turbidity of greater than 5 NTU (daily average). All Project discharge plans shall identify an acceptable location or locations at which to measure background turbidity. The Discharger shall monitor receiving water and discharge turbidity at least one time every 8 hours on days when discharges from excavations or any other dewatering processes may occur.
 - e. Receiving Water Temperature - the receiving water shall not be increased by more than 5°F (2.8°C) above natural receiving water temperature.
 - f. Nutrients - the receiving waters shall not contain biostimulatory substances in concentrations that promote aquatic growths to the extent that such growths cause nuisance or adversely affect beneficial uses.
9. **Dewatering Plan.** The Discharger shall prepare a Dewatering Plan acceptable to the Executive Officer. The plan shall be submitted to the Executive Officer at least 30 days prior to each Project phase in which dewatering is proposed or may be needed. The plan shall include the area to be dewatered, timing of dewatering, and method of dewatering to be implemented. All temporary dewatering methods shall be designed to have the minimum necessary impacts to waters of the U.S. to isolate the immediate work area. All dewatering methods shall be installed such that natural flow is maintained outside the Project area. Any temporary dams or diversions shall be installed such that the diversion does not cause sedimentation, siltation, or erosion within or upstream or downstream of the Project area. All dewatering methods shall be removed immediately upon completion of Project activities. The Discharger shall implement, or ensure that its contractor implements, the Dewatering Plan and the discharge requirements throughout the Project site.
10. **Groundwater Management Plan.** The Discharger shall prepare a Groundwater Management Plan (GMP) acceptable to the Executive Officer. The GMP shall be submitted to the Executive Officer no later than 90 days prior to start of any construction event in which groundwater dewatering is planned or needed. In construction areas that have a likelihood of encountering groundwater that may be contaminated, the GMP shall meet the standards of the Regional Water Board's VOC and Fuel General NPDES Permit.
11. **Spill Prevention and Containment Plan.** The Discharger shall prepare a Spill Prevention and Containment Plan (SPCP) acceptable to the Executive Officer. The SPCP shall be submitted to the Executive Officer no later than 90 days prior to start of any construction event in which construction equipment is planned or needed. The plan shall describe the preventative spill

measures that shall be implemented, including equipment leak prevention, and what actions shall be taken in the event of a spill. In the event of a containment spill, the Discharger shall take appropriate steps, including immediately halting the construction work, containing and mitigating the spill, and immediately notifying appropriate authorities, including Regional Water Board staff. Containers for storage, transportation, and disposal of containment absorbent materials shall be provided onsite.

12. **Directional Drilling Plan.** If directional drilling is necessary at the Project site, the Discharger shall prepare a Directional Drilling Plan acceptable to the Executive Officer. The plan shall be submitted to the Executive Officer at least 30 days prior to each Project phase in which directional drilling is proposed or may be needed. The Directional Drilling Plan shall contain boring plans that include the following items: a sketch of the approximate locations of drill entry and exit points; the proposed depth of bore and a statement of waterbody conditions that supports the proposed depth of the bore; approximate length of the proposed bores; type and size of boring equipment to be used; estimated time to complete the bore; list of lubricants and muds to be used; name(s) of contractor and cell phone numbers of the construction supervisor(s) and monitor(s); name(s) of the environmental and biological monitor(s); site-specific monitoring conditions; monitoring protocols; and a containment and cleanup plan. The drill mud pressure and volume shall be monitored at all times during drilling to ensure that hydrofracture or other loss of drill muds has not occurred. In the event of a sudden loss in pressure or volume, the Discharger shall take appropriate steps, including immediately halting the drilling operation, to ensure that drilling muds are not discharged to waters of the U.S. All drilling muds, slurries, oils, oil-contaminated water, and other waste materials removed from the bore hole or otherwise used during the Project shall be disposed of at a permitted landfill, other appropriately permitted site, or at an upland site approved in advance by the Board's Executive Officer.
13. **Quality Assurance Project Plan (QAPP and Fill Quality Report).** The Discharger shall prepare and implement a Quality Assurance Project Plan (QAPP) acceptable to the Executive Officer. The QAPP shall provide procedures and screening guidelines to reuse imported soil at the Project area. Existing guidance for the beneficial reuse of sediments establishes numeric screening guidelines for the placement of sediments in direct contact with water or the burial of sediments beneath a cover layer. The QAPP shall be submitted to the Executive Officer for review and approval not later than 90 days before Phase I construction is initiated.

The Discharger shall characterize the quality of all fill material proposed for use as fill prior to placement at the Project area. The Discharger shall not import contaminated soil for use at the Project area nor reuse any contaminated soil excavated within the Project area that does not meet acceptance screening level criteria for its intended reuse (see below). Soil to be transported offsite shall be for non-hazardous or hazardous landfill disposal, as appropriate.

Not later than 60 days prior to placing any imported or excavated soil fill material at the Project area, including all placement of fill in the ecotones' footprints, on levees, and at any other location where the fill is a discharge to or has the potential to discharge to any waters of the U.S. in the Project area, the Discharger shall submit a technical report acceptable to the Executive Officer. The technical report shall demonstrate that the chemical concentrations in

the imported or excavation soil fill comply with the protocols specified in the following documents that are appropriate to each source of material:

- *Upland Soil*: If upland soil from upland borrow sites is imported for use in future Project areas, the following conditions shall apply and be subject to Executive Officer approval: (i) Imported soil from upland borrow sites must be determined suitable based on the procedures and screening guidelines contained in a QAPP approved by the Executive Officer; and (ii) if the materials are proposed for levee construction, a report characterizing the material's suitability for levee construction shall be submitted at least 30 days prior to material placement in the stockpile areas.
- *Riverine Material*: The Regional Water Board May 2000 staff report *Beneficial Reuse of Dredged Materials: Sediment Screening and Testing Guidelines*, or the most current revised version. Regional Water Board staff shall review and approve data characterizing the quality of all material proposed for use as fill prior to placement of fill at any of the levee, marsh, or channel areas at the Project site. Modifications to these procedures may be approved by the Executive Officer on a case-by-case basis, pending the Discharger's ability to demonstrate that the imported fill material is unlikely to adversely impact beneficial uses. Soil originating from non-Bay locations shall modify the toxicity tests set forth in the Guidelines for Implementing the Inland Testing Manual in the San Francisco Bay Region (DMMO Reuse Guidance) so that the measured toxicity is representative of the conditions that will be present in the areas where sediment reuse is proposed. Any proposed modifications to toxicity tests set forth in the DMMO Reuse Guidance shall be submitted to the Executive Officer for review and acceptance prior to implementation.
- *Dredged Material*: If dredged sediment is imported for use in future Project areas, the following conditions shall apply and be subject to Executive Officer approval: (i) Regional Water Board staff shall review and approve data characterizing the quality of all dredged material (Bay sediments) proposed for use as fill prior to placement at any Project area. Sediment characterization shall follow the protocols specified in the DMMO Reuse Guidance, including case-by-case modifications approved by the Executive Officer (see above); (ii) if the material is proposed for levee maintenance, a levee inspection report shall be submitted at least 30 days prior to dredge material placement; and (iii) if applicable, a work plan and schedule for making any repairs or improvements shall also be submitted prior to dredge material placement.
- *Inactive Legacy Biosolids*: If legacy biosolids from the RWF legacy ponds (where placement in ponds dates from 1962-1974) are used for the ecotone construction or stockpiling within the ecotone footprint, the following conditions shall apply and be subject to Executive Officer approval: (i) biosolids used in the ecotones shall not be exposed; (ii) biosolids used in the ecotones shall be covered with a minimum of 3 feet of suitable cover material and engineered to ensure burial; (iii) biosolids to be reused in ecotone construction shall meet or be below the "foundation material" screening levels for contaminants (e.g., metals, TPH, VOCs, SVOCS, PCBs) in the DMMO Reuse Guidance and be at or below leachability for non-landfill conditions; and (iv) any biosolids not reused in the ecotones or that do not meet screening levels shall be

consolidated and capped within the existing inactive RWF pond area, subject to the Regional Water Board action now covered by this Order.

14. **Maintenance.** Construction activities necessary for the on-going maintenance of existing levees and infrastructure may include the following activities: trash and anthropogenic debris removal; repairs on levees due to damage by small burrowing mammals, runoff/erosion, storm activities, or other factors; levee inspections; graffiti removal; access improvements and upkeep; vector monitoring (presence of mosquitos and their larvae); or vegetation management.

Mitigation and Monitoring Requirements

15. **Pond and Ecotone Monitoring.** The ponds and ecotones shall be monitored for a minimum 10-year period following each pond-breaching event, as specified in the MAMP, to ensure they are performing as anticipated, and to allow for adaptive management if necessary.
16. **Annual Monitoring Reports.** The Discharger shall prepare annual letter reports (both electronic and hard copy) acceptable to the Executive Officer. The annual reports shall be submitted to the Regional Water Board by January 31 each year over the 10-year monitoring period that follows each pond-breaching event. The reports shall document the ponds' progress towards achieving full tidal marsh restoration and meeting wetland mitigation progress towards achieving the final success criteria specified in MAMP, as revised. The report shall address any signs of insufficient hydrology, poor survival or growth of vegetation, and excessive erosion or deposition of sediment in and around the wetland and ecotone areas. If the annual report indicates the final success criteria in MAMP may not be achieved, the Discharger shall submit a Corrective Action Plan to the Regional Water Board. If an annual report indicates the recommended corrective action may be to discontinue pond breaching and future Phases, then the Discharger shall revise the CMMP to mitigate the Project's unmitigated permanent fill impacts to waters of the U.S. and submit the revised CMMP to the Executive Officer for review and acceptance;
17. **Contingency Mitigation and Monitoring Plan (CMMP).** The Coastal Conservancy shall prepare and implement a Contingency Mitigation and Monitoring Plan (CMMP) acceptable to the Executive Officer. The CMMP shall be submitted not later than January 31, 2020 (the year that construction along Reaches 4 and 5 is anticipated). If the Project is delayed and construction along Reaches 4 and 5 has not begun by 2021, the CMMP shall be submitted in the same year that construction along Reaches 4 and 5 is rescheduled to occur. The CMMP shall provide for a minimum mitigation amount sufficient to demonstrate consistency with the Basin Plan Wetland Fill Policy and the California Wetlands Conservation Policy (Findings 32 and 33). This shall include an analysis of issues such as ensuring no net loss of area and function, including temporal loss, of waters of the U.S. resulting from the Project. Updates to the CMMP shall be submitted if all or a portion of the Project's ecosystem restoration components is not implemented. Any updates to the CMMP shall be submitted to the Executive Officer no later January 31 in each year that changes to the Project described in the Order are proposed. If the Project's impacts described herein are reduced or increased, a description of the impacts and the difference in acreage from the quantities described herein shall be submitted to the Executive Officer. If the updated impacts reflect a net loss of zero

acres of jurisdictional waters, then the CMMP shall consist of the Project described herein. Otherwise, the CMMP shall include the following:

- a. An analysis of the Project's consistency with the Basin Plan Wetland Fill Policy and the California Wetlands Conservation Policy, as described above, and including a description of any changes to Project components or impacts as compared to the Project description in this Order.
- b. Consistent with the analysis, a mitigation proposal, workplan, monitoring plan, performance standards, and other information, as appropriate, sufficient to provide appropriate mitigation of permanent and temporal losses of functions and values of waters of the U.S. resulting from Project implementation.

At a minimum, the CMMP shall propose additional mitigation to address delays of greater than five years between the timing of impacts and construction of restoration from the schedules listed in the Findings in implementation of the Project's tidal restoration.

The Regional Water Board may require a lesser or greater amount of area than the currently anticipated net loss of waters of the U.S. based on changes in the factors listed in Findings 21 and 22, such that the size and scope of the mitigation project shall be appropriate for the Project's impacts.

- c. The mitigation proposal, work plan, monitoring plan, and performance standards shall contain, but are not necessarily limited to, the following:
 - i. Annual performance criteria and final success (metrics) that may be used to assess establishment of the mitigation area's vegetation and hydrology. Annual performance criteria may include, but are not limited to, the following: percent cover, maximum percent cover for non-native species, percent survival of plants, and target plant heights. Final success criteria are used to assess the mitigation project's success at the end of a monitoring period. Additional metrics may also be considered;
 - ii. A summary of maintenance activities, including irrigation, weeding, and replanting of dead or missing vegetation; a schedule for implementing maintenance activities; the plant palette selected for replanting, including pounds per acre of seeds, numbers and sizes of container plants, and sources of all plant material; and
 - iii. Contingency measures to be implemented in the event that annual performance criteria or final success criteria are not attained or mitigation wetlands do not attain jurisdictional status at the end of the initial monitoring period.

The CMMP shall incorporate the reporting requirements in Provisions 15, 16, 18, and 19 to 29.

18. **Log of Impacts.** The Discharger shall maintain an Impacts Log to track Project activities including the start dates of impacts to waters of the U.S. and the associated mitigation activities. The Discharger shall make the Impacts Log available for review by Regional Water

Board staff upon request. The Impacts Log shall include, but not be limited to, the start dates of the following Project milestones:

- a. Excavation and grading;
- b. Pond dewatering;
- c. Groundwater management;
- d. Completion of each Project component as described in Findings 10 to 12; and
- e. Hydroseeding.

Reporting Requirements

19. **Reports.** All reports pursuant to these Provisions shall be prepared under the supervision of suitable professionals registered in the State of California.
20. **Water Quality Monitoring.** The Discharger shall report any water quality monitoring data that are not in compliance with this Order to the Regional Water Board within 24 hours via telephone and shall follow up with a written report within 14 days. The written report shall provide the following:
 - a. Discharge and receiving water measurements for the water quality parameter(s) collected during the non-compliance event;
 - b. The location, duration, and likely cause of the non-compliance event;
 - c. All actions taken to remedy non-compliance immediately after identifying the non-compliance event and to mitigate for any adverse impacts caused or contributed to by the non-compliance event; and
 - d. All actions taken to prevent a similar non-compliance event in the future.
21. **Technical Advisory Committee (TAC).** A TAC shall be organized and convened through a public process by the Discharger and shall, at a minimum, invite representatives from the Regional Water Board, the Bay Conservation and Development Commission, Coastal Conservancy, Corps, USFWS, and NMFS. The purpose of the TAC shall be to assess progress of the Project's ecosystem restoration by reviewing monitoring data and to suggest adaptive management strategies. Results of the data analysis shall be presented to the TAC at least biennially, for discussion and comment.
22. **California EcoAtlas.** The Discharger shall use the standard California Wetlands Form to provide Project information describing impacts and restoration measures not later than 14 days from the date of completion of Project construction activities. An electronic copy of the form can be downloaded from: <http://www.waterboards.ca.gov/sanfranciscobay/certs.shtml>. The completed form shall be submitted electronically to habitatdata@waterboards.ca.gov or shall be submitted as a hard copy to both (1) the Regional Water Board, to the attention of

EcoAtlas, and (2) the San Francisco Estuary Institute, 4911 Central Avenue, Richmond, CA 94804, to the attention of EcoAtlas.

Project: Future Phase I activities and Phases II and III

23. **Photo-Documentation Report.** To document levee and Pond conditions immediately at the Project site, the Discharger shall establish a minimum of four photo-documentation points at the Phase I Reach I location, eight photo-documentation points at locations for future Phase I construction events that include ecotone creation, and eight photo-documentation points at locations for each Project construction event for which berms are lowered and tidal action is restored, including the last Phase I construction event. These photo-documentation points should be selected to depict the pre- and immediate post-Project conditions where impacts to waters of the U.S. occur, including the FRM levee, Ponds A9 to A15, ecotone areas, stockpiling areas, and the adjacent areas. The Discharger shall prepare site maps with the photo-documentation points clearly marked. Prior to implementing each phase, the Discharger shall photographically document the condition of each site. These photo-documentation points shall be clearly marked and identified on a map that shall be included in the as-built reports.
24. **As-Built Plans.** The Discharger shall prepare an as-built report acceptable to the Executive Officer. The as-built report shall be submitted to the Executive Officer not later than 180 days after each Project phase, or construction event, is completed. The report shall describe the areas of actual disturbance during Project construction. The report shall clearly identify and illustrate the Project site and the locations of permanent and temporary impacts. Any deviations from the submitted 100 percent design plans, including impact quantities, shall be depicted in the as-built report. These deviations shall be displayed with reference to the 100 percent design drawings, and any installed structures or alterations to waters of the State shall be shown as the actual elevations in the as-built report. If the as-built report indicates that impacts were greater than those authorized in this Order, the Executive Officer may require enforcement and additional action by the Discharger, including but not limited to compensatory mitigation. The as-built report shall be submitted in both digital format and hard copy of at least 11-inches by 17-inches to the Regional Water Board. The as-built report shall be submitted either by electronic mail to staff or by uploading it to the Regional Water Board's FTP internet site. Instructions for uploading documents to the FTP internet site are available at http://www.waterboards.ca.gov/sanfranciscobay/publications_forms/documents/FTP_Discharger_Guide-12-2010.pdf. If the as-built report is submitted by uploading it to the FTP internet site, the Discharger shall notify the Regional Water Board case manager via electronic mail. For purposes of this Order, the definition for construction completion shall be the final date when construction contractors (excluding contractors for revegetation activities) are in the Project site.
25. **Notice of Mitigation Completion.** When the Discharger has determined that a mitigation area achieved the performance standards and final success criteria specified in the MAMP, a notice of mitigation completion shall be submitted to the Executive Officer. After acceptance of the notice of mitigation completion in writing by the Executive Officer, the Discharger's submittal of mitigation monitoring reports for that mitigation component is no longer required.

26. **Project Completion Report.** The Discharger shall notify the Regional Water Board by electronic mail or by hard copy of Project completion upon transfer of the Project, including the FRM levee and ecosystem restoration components, to the Non-Federal Sponsors. This notification, known as a Project Completion Report, shall consist of the following information: (a) the CIWQS Place ID for this Project (i.e., CWIQS Place ID 813084); (b) the date Project construction activities were completed; and (c) the completion date of mitigation plantings. Project construction activities for the purpose of this condition are defined as activities associated with construction of the Project, establishing native grass vegetation on the banks, and any plug plantings as per the Planting Plan. The Project Completion Report shall be submitted to Tahsa Sturgis at tahsa.sturgis@waterboards.ca.gov, Christina Toms at christina.toms@waterboards.ca.gov, and Brian Wines at brian.wines@waterboards.ca.gov or the current Regional Water Board staff members assigned to the Project.

Reach 1

27. **Reach 1 100 Percent Design.** The Discharger shall prepare 100 percent design plans for Phase I, Reach 1 acceptable to the Executive Officer. The 100 percent design plans for Phase I, Reach 1 shall be submitted to the Executive Officer for review and acceptance not later than 90 days prior to construction of Phase I, Reach 1. The plans shall describe the areas of anticipated disturbance during Project construction. The plans shall clearly identify and illustrate the Project site and the locations of permanent and temporary impacts. Any deviations from the submitted 90 percent design plans, including impact quantities, shall be depicted.
28. **Reach 1 Completion Report.** The Discharger shall notify the Regional Water Board by electronic mail or by hard copy when construction of Reach I is completed. This notification, known as the Reach I Completion Report, shall consist of the following information: (a) the CIWQS Place ID for this Project (i.e., CWIQS Place ID 813084); and (b) the date Project construction activities were completed. Project construction activities for the purpose of this provision are defined as activities associated with construction of Reach I. The Reach I Completion Report shall be submitted to Tahsa Sturgis at tahsa.sturgis@waterboards.ca.gov, Christina Toms at christina.toms@waterboards.ca.gov, and Brian Wines at brian.wines@waterboards.ca.gov or the current Regional Water Board staff members assigned to the Project.
29. **Final Operations and Maintenance Manual.** The Discharger shall prepare a workplan for the Project's Operation, Maintenance, Repair, Replacement, and Rehabilitation (O&M) Plan acceptable to the Executive Officer. The workplan shall be submitted to the Executive Officer for review and acceptance prior to the beginning of development of the O&M Plan. The workplan shall include collaborative review of a draft O&M Plan by a workgroup including the TAC members listed above. The Discharger shall submit the final O&M Plan to the Executive Officer for review and acceptance upon transfer of the Project to the local non-federal sponsor.

Deliverables for Future Project Phases

30. **Annual Status Updates.** The Discharger shall prepare and submit a status update report to the Executive Officer not later than January 31 of each year until the Project is completed. Once

monitoring activities begin, the status update report shall be submitted with the annual reports (see Provision 16). Each report shall describe the Project's progress, the status of each Project component, the status or anticipated change to Project funding for each component, and all other information, as appropriate.

31. **Project component 30 Percent Designs.** The Discharger shall prepare 30 percent design plans for subsequent Project work, including future Phase I construction activities, acceptable to the Executive Officer. The 30 percent design plans shall be submitted to the Executive Officer for review and acceptance not later than 12 months prior to the anticipated construction initiation date.
32. **Project component 60 Percent Designs.** The Discharger shall prepare 60 percent design plans for subsequent Project work, including future Phase I construction activities, acceptable to the Executive Officer. The 60 percent design plans shall be submitted to the Executive Officer for review and acceptance not later than 8 months prior to the anticipated construction initiation date. At a minimum, the 60 percent design plans shall include all components that were deemed acceptable in the Phase I, Reach I 60 percent design submittal.
33. **Project component 90 Percent Designs.** The Discharger shall prepare 90 percent design plans for subsequent Project work, including future Phase I construction activities, acceptable to the Executive Officer. The 90 percent design plans shall be submitted to the Executive Officer for review and acceptance not later than 6 months prior to the anticipated construction initiation date. The plans shall describe the areas of anticipated disturbance during Project construction. The plans shall clearly identify and illustrate the Project site and the locations of permanent and temporary impacts.
34. **Project component 100 Percent Designs.** The Discharger shall prepare 100 percent design plans for subsequent Project work, including future Phase I construction activities, acceptable to the Executive Officer. The 100 percent design plans shall be submitted to the Executive Officer for review and acceptance not later than December 15 in the year prior to the anticipated construction initiation date. The plans shall describe the areas of anticipated disturbance during Project construction. The plans shall clearly identify and illustrate the Project site and the locations of permanent and temporary impacts.
35. **Mechanism for approval of subsequent Project work.** The Discharger shall prepare supplemental applications for subsequent Project work, including the remaining Phase I construction events, Phase II, and Phase III, acceptable to the Executive Officer. The supplemental applications shall be submitted to the Executive Officer for review and acceptance not later than 12 months prior to the anticipated construction initiation date. The supplemental application shall consist of the following:
 - A complete CWA section 401 Water Quality Certification Application and Report of Waste Discharge.
 - A revised CMMP that reflects the current net loss of waters of the U.S. and corresponding compensatory mitigation options.
 - Engineering design plans (see Provisions 31 to 34).

- A supplemental analysis that demonstrates the impacts have been reduced to the maximum extent practicable and ecosystem restoration has been optimized (see Provision 36).
- Prior to Phase I's second construction event, an Ecotone and Pond Monitoring Plan (EPMP) shall be submitted, along with the supplemental application, to the Executive Officer for review and acceptance. The EPMP document shall contain information that details how the Project's ecosystem restoration will be monitored, including monitoring targets, metrics, and methods, to ensure there is not a loss in existing functions, values, or habitat. The supplemental document may contain and reference the MAMP but shall also provide additional information, including monitoring activities for mitigation identified in this Order for the Project's fill impacts (see Findings 20 to 22) and an ecotone module. This additional information regarding monitoring is consistent with the anticipated development specified in MAMP Sections 3.1 and 3.3. The EPMP may be submitted with, and coordinated with, the South Bay Salt Pond Phase 2 Project ecotone addendum monitoring plan. The following are the minimum requirements for additional information that shall be included in the supplemental document:
 - i. A complete pond and ecotone module that provides detailed methods, protocols, timing, performance and final success criteria, and Non-Federal Sponsors' roles for all pond and ecotone monitoring activities, including baseline monitoring, that will be implemented after each pond breach occurs. Since the pond monitoring in Phases II and III will reflect lessons learned from monitoring previously breached ponds, the pond and ecotone module shall undergo future revisions. All future revisions to the monitoring plan shall be submitted to the Executive Officer for review and acceptance by January 31 in the year that pond breaches or adaptive management actions are proposed.
 - ii. Clearly defined monitoring roles and responsibilities for the Non-Federal Sponsors, including updated monitoring cost estimates and contributions by the Non-Federal Sponsors during each pond's monitoring period.
 - iii. Consistent with Section 3.1 and 3.3 of the MAMP, a summary of the updated MAMP methods, triggers, and actions. The summary shall provide a technical justification for each trigger and action. The summary shall be updated as needed prior to each future pond-breaching event. Updated summaries shall be submitted to the Executive Officer by January 31 in the year that pond breaches or adaptive management actions are proposed. Updated MAMP methods, triggers, and actions shall address:
 - The timing and duration of pressure transducer deployment to monitor water levels in the ponds
 - The locations of transects or Surface Elevation Tables to monitor sedimentation rates in ponds
 - Methods for monitoring suspended sediment concentrations within tidal source waters and restoring ponds

- Additional detail re: the timing of aerial photography flights and the types of products that will be collected (e.g., natural color, infrared, normalized vegetation difference index)
 - Methods for assessing the acreage and geographic distribution of high tide refugia within and along the ponds
 - Methods, triggers, and actions for addressing the percent cover and species richness of native plants on FRM levee side slopes, ecotone side slopes, restored marsh areas, and lowered pond levees, as well as for minimizing the establishment and spread of invasive species¹⁵ throughout the site. Please note that the Regional Water Board typically requires corrective action when invasive species make up 20% of the relative cover or 5% of the absolute cover in a given area.
- iv. The Regional Water Board is a lead agency in the development and implementation of a San Francisco Bay Regional Wetland Monitoring Program (Wetlands RMP), a proposed coordinated and comprehensive long-term monitoring program with the goal of monitoring bayland wetlands to ensure their on-going management, restoration, and protection. Development and implementation of a Wetlands RMP is also called for in the CCMP, also called the Estuary Blueprint. It is expected that the Discharger may choose to comply with any requirement of this Provision through a collaborative effort (i.e., Wetlands RMP) to conduct or cause to be conducted the required monitoring.
- v. A mechanism to verify that SLR is occurring at the rate assumed in the application materials.
- Appropriate CEQA documentation for any impacts not previously considered in the Joint EIS/EIR.
36. **Impact Reduction and Environmental Benefit Optimization.** The Discharger shall prepare supplemental analysis for subsequent Project work acceptable to the Executive Officer. The supplemental analysis shall be submitted to the Executive Officer not later than 12 months prior to the anticipated initiation date for that activity. When the Regional Water Board reviews project alternatives to determine the least environmentally damaging practicable alternative (LEDPA), all State water quality standards must be met. Supplemental analysis shall demonstrate that impacts to waters of the U.S. have been reduced to the maximum extent practicable and the Project's environmental benefit has been optimized. The supplemental analysis shall be submitted to the Executive Officer for review and approval with the corresponding supplemental application (see Finding 35). If the Executive Officer finds that the supplemental analysis may cause a significant alteration to the Project, as defined in Finding 15, then the supplemental analysis may be presented before the Regional Water Board for review and approval prior to implementation. Each supplemental analysis shall contain relevant technical documents that demonstrate each phase results in the optimized alignment that reduces impacts and increases restoration acreage.

¹⁵ Invasive species include those listed by the California Invasive Plant Council at <http://www.cal-ipc.org/ip/inventory/>

The following are technical documents that shall be included in the supplemental analysis, as appropriate:

- Comparison of how alternate FRM levee alignments along Reaches 4 and 5, east of Artesian Slough, including the alignment proposed by the Regional Water Board (see Att. C), would affect long-term water management, water quality, and habitat functions/values of the City and landfill mitigation marshes, given projected SLR and the need for these marshes to continue to provide suitable habitat for State and federally-listed tidal wetland species (Att. C, Figures 1 and 3);
- Comparison of projected short-term (0 to 10 years post-breach) and long-term (10+ years post-breach) establishment of vegetated tidal marsh plain bayward of the FRM levee under alternate levee alignments east of Artesian Slough;
- Profiles for Artesian Slough and Coyote Creek option;
- Cross-sections representing existing and future conditions by reach;
- Soil suitability reports for the landward levee alignment east of Artesian Slough;
- Demonstration of land acquisition for alternative levee alignments; and
- Demonstration that the Artesian Slough crossing design will not affect mixing rates and dilution for the RWF's discharges.

37. **Public Notice.** The Regional Water Board will public notice supplemental applications. If public commenters request a public hearing, or if there are other issues meriting a hearing before the Regional Water Board, the Board will consider approval of the supplemental application at its regular meeting. In the absence of a request or other issues, the Executive Officer may approve the supplemental application administratively.

Other Requirements

38. The Discharger shall immediately notify the Regional Water Board by telephone whenever an adverse condition occurs as a result of this discharge. Such a condition includes, but is not limited to, a violation of the provisions of this Order, a significant spill of petroleum products or toxic chemicals, or damage to control facilities that would cause noncompliance. A written notification of the adverse condition shall be submitted to the Regional Water Board within two weeks of occurrence. The written notification shall identify the adverse condition, describe the actions necessary to remedy the condition, and specify a timetable, subject to the modifications of the Executive Officer, for the remedial actions.
39. The Discharger shall notify the Regional Water Board, in writing or via electronic mail, at least 30 days prior to actual start dates for each Project component (i.e., prior to the start of grading or other construction activity for any Project component, including the compensatory mitigation components).
40. The Discharger shall at all times fully comply with the prohibitions, specifications, mitigation and monitoring requirements, engineering plans, specifications, and technical reports

submitted with the Corps' application and the plans and reports required by this Order (e.g., Provisions 7 to 13, 16 to 18, 19, 20, and 22 to 36), which, together, serve as the basis for the Project description this Order covers.

41. The Discharger shall be responsible for work conducted by its consultants, contractors, and subcontractors on the Project.
42. The Discharger is considered to have full responsibility for correcting any and all problems that arise in the event of a failure that results in an unauthorized release of waste or wastewater. The discharge of any hazardous, designated, or non-hazardous waste as defined in Title 23, Division 3, Chapter 15 of the California Administrative Code, shall be disposed of in accordance with applicable State and federal regulations.
43. The Discharger shall remove and relocate any wastes that are discharged at any sites in violation of this Order.
44. The Discharger shall maintain a copy of this Order at the Project site at all times during construction of the Project and be made available to Regional Water Board staff upon request. All foremen and other employees responsible for overseeing that construction of the Project complies with permitting requirements shall have access to and be familiar with the Order requirements.
45. The Discharger shall permit the Regional Water Board or its authorized representatives at all times, upon presentation of credentials:
 - a. Entry onto Project premises, including all areas on which fill of wetlands or other waters will occur or on which fill is located or mitigation is occurring or in which records are kept.
 - b. Access to copy any records required to be kept under the terms and provisions of this Order.
 - c. Inspection of any treatment equipment, monitoring equipment, or monitoring method required by this Order.
 - d. Sampling of any discharge or surface water covered by this Order.
46. This Order does not authorize commission of any act causing injury to the property of another or of the public; does not convey any property rights; does not remove liability under federal, State, or local laws, regulations or rules of other programs and agencies; nor does this Order authorize the discharge of wastes without appropriate permits from other agencies or organizations.
47. The Discharger shall timely pay all fees associated with this Order. The fee amount for this Order shall be in accordance with the current fee schedule, per California Code of Regulations, Division 3, Chapter 9, Article 1, section 2200(a)(3). The fee payment shall indicate the Order

number, the CIWQS Place ID no. 813084, the Regulatory Measure ID no. 413855, and the applicable season.

48. This Order is subject to modification or revocation upon administrative or judicial review, including review and amendment pursuant to CWC section 13330 and 23 CCR section 3867.
49. The Regional Water Board may add to or modify the conditions of this Order, as appropriate, to implement any new or revised water quality standards and implementation plans adopted and approved pursuant to the CWC or CWA section 303 or in response to new information concerning the conditions of the Project. Additionally, the Regional Water Board reserves the right to suspend, cancel, or modify and reissue this Order, after providing notice to the Discharger, if the Regional Water Board determines that the Project fails to comply with any of the conditions of this Order, or when necessary to implement any new or revised water quality standards and implementation plans adopted or approved pursuant to the CWC or CWA section 303 (33 U.S.C. § 1313).
50. This Order is not intended and shall not be construed to apply to any discharge from any activity involving a hydroelectric facility requiring a Federal Energy Regulatory Commission (FERC) license or an amendment to a FERC license unless the pertinent Project materials for the Order were filed pursuant to 23 CCR subsection 3855(b) and those Project materials specifically identified that a FERC license or amendment to a FERC license for a hydroelectric facility was being sought.
51. The Regional Water Board may consider rescission of this Order upon Project completion and the Executive Officer's acceptance of notices of completion of mitigation for all mitigation, creation, and enhancement projects required or otherwise permitted now or subsequently under this Order.

I, Bruce H. Wolfe, Executive Officer, do hereby certify that the foregoing is a full, complete and correct copy of an Order adopted by the California Regional Water Quality Control Board, San Francisco Bay Region on December 13, 2017.

Bruce H. Wolfe
Executive Officer

Attachments

- Attachment A: Project Figures
- Attachment B: Monitoring and Adaptive Management Plan (MAMP)
- Attachment C: Landward Levee Alignment East of Artesian Slough Memo
- Attachment D: Phase I, Reach I 60 Percent Design Plans


Attachment A: Project Maps

Project Maps are from the
401 Water Quality Certification Application
Materials received from June 16, 2017,
through September 2017

**South San Francisco Bay
Shoreline Project**


**City of San Jose
Santa Clara County**

December 2017



N:\Projects\2606-03 Shoreline Study\03\Reports\USACE Shoreline Project\Fig 1 Vicinity Map.mxd mlg/and

Figure 1. Vicinity Map
 USACE Shoreline Project - Section 401 Permit Application (2606-03)
 June 2017



N:\Projects\2606-03 Shoreline Study\03\Reports\USACE Shoreline Project\Fig 2 USGS Map.mxd; miagarde

Figure 2. USGS Topographic Map
USACE Shoreline Project - Section 401 Permit Application (2606-03)
June 2017



N:\Projects\2606-03 Shoreline Study\03\Reports\USACE Shoreline Project\Fig 3 Project Site and Aerial Photograph.mxd mlr/garde

Figure 3. Project Site and Aerial Photograph
 USACE Shoreline Project - Section 401 Permit Application (2606-03)
 June 2017



N:\Projects\2606-03 Shoreline Study\03\Reports\USACE Shoreline Project\Fig 4 Project Phases2.mxd





FIGURE 5



M:\Projects\2606-03 Shoreline Study\03\Reports\USACE Shoreline Project\Fig 5 Existing Habitats at Phase I Levee Sites.mxd



N:\Projects\2606-01 Shoreline Study\03 Reports\RWQCB Application\Fig 7a Reach I Levee Impact Analysis.mxd




Figure 7a. Reach I Levee Impact Analysis
USACE Shoreline Project - RWQCB Application (2606-03)
August 2017



N:\Projects\2606-03 Shoreline Study\03 Reports\RWQCB Application\Fig 7b Reach 5 Levee Impact Analysis.mxd




Figure 7b. Reach 5 Levee Impact Analysis
USACE Shoreline Project - RWQCB Application (2606-03)
August 2017



M:\Projects\2606-03 Shoreline Study\03\Reports\USACE Shoreline Project\Fig 7 Low-High SLR Scenarios.mxd

Figure 8. Levee Impact Analysis - Low, Medium and High SLR Scenarios



N:\Projects\2606-03_Shoreline_Study\03\Reports\RWQCB_Application\Fig 9 Project Jurisdiction Changes and Net Loss.mxd

Figure 9 Project Jurisdiction Changes and Net Loss
USACE Shoreline Project - RWQCB Application (2606-03)
August 2017



N:\Projects\2606-01 Shoreline Study\03 Reports\RWQCB Application\Fig 10 Reach 2&3 Levee Impact Analysis.mxd

Figure 10. Reaches 2-3 Levee Impact Analysis


USACE Shoreline Project - RWQCB Application (2606-03)
August 2017



Diagram 2. In-Pond Preparation for Breaching of Pond A12.



Diagram 3. In-Pond Preparation for Ponds A9, A10, A11, and A18



**Attachment B:
Monitoring and Adaptive Management Plan
(MAMP)**

MAMP is from the
401 Water Quality Certification Application Materials
received from June 16, 2017,
through September 2017

**South San Francisco Bay
Shoreline Project**

**City of San Jose
Santa Clara County**

December 2017

SOUTH SAN FRANCISCO BAY SHORELINE STUDY

Monitoring and Adaptive Management Plan for Ecosystem Restoration

TABLE OF CONTENTS

	<u>Page</u>
1. Introduction	5
1.1 Authorization for Monitoring and Adaptive Management	5
1.2 Relation to South Bay Salt Pond Restoration Project Adaptive Management and Monitoring.....	5
1.3 Procedure for Drafting the Monitoring and Adaptive Management Plan	6
1.4 Rationale for Adaptive Management.....	6
2. Adaptive Management Planning	10
2.1 Project Objectives, Constraints and Considerations.....	10
2.2 Proposed Ecosystem Restoration Actions	11
2.3 Conceptual Models.....	12
2.4 Sources of Uncertainty	15
3. Monitoring.....	17
3.1 Targets.....	21
3.2 Monitoring Metrics.....	21
3.3 Monitoring Methods.....	21
3.4 Database Management.....	22
4. Regular Assessments	23
4.1 Assessment Process	23
4.2 Frequency of Assessments	23
4.3 Documentation and Reporting.....	23
5. Decision Making	24
5.1 Triggers	25
5.2 Potential Adaptive Management Actions.....	25
5.3 Project Close Out.....	28
6. Costs for Implementation of Monitoring and Adaptive Management.....	29
6.1 Costs for Implementation of Monitoring.....	29
6.2 Costs for Implementation of Adaptive Management	29

TABLES

Table 1. Project Objectives, Constraints, and Uncertainties

Table 2. Monitoring Topics, Targets, and Metrics Associated with Ecosystem Restoration Objectives

Table 3. Monitoring Cost Estimate

Table 4. Adaptive Management Decision Matrix

Table 5. As-Needed Assessments

Table 6. Adaptive Management Construction Activities

Table 7. Invasive and Nuisance Plants

Table 8. Monitoring and Adaptive Management Cost Summary Table

FIGURES

Figure 1. SBSPP Restoration Project Organizational Structure and Functions

Figure 2. Adaptive Management Process

Figure 3. Project Implementation Schedule

Figure 4. Tidal Habitat Conceptual Model

Figure 5. Managed Pond Conceptual Model

Figure 6. Landscape Conceptual Model

Figure 7. Adaptive Management Assessment and Decision Making: Sediment Dynamics Example

GLOSSARY

Adaptive management action. Actions undertaken to improve performance if restoration targets are not met. Actions may consist of assessments, construction, phasing, and operations and maintenance.

Conceptual Model. A simple, qualitative model that describes general functional relationships among essential components of a system.

Consideration. A statement of conditions the alternative plans should avoid, minimize, or mitigate, as possible. Considerations are less restrictive than constraints.

Constraint. A restriction that limits the extent of the planning process. It is a statement of things the plan should avoid.

Monitoring metric. A measure for assessing change with respect to a specific restoration target. Each restoration target has at least one metric that would be measured during monitoring and is expected to provide insight into the project's progress towards that target.

Objective. Statement of project purpose.

“Staircase.” Terminology adopted from the SBSP Restoration Project. The SBSP Restoration Project uses a “staircase” analogy to describe the proposed project, with each step on the staircase representing one phase of tidal restoration implementation. Adaptive management determines how far up the “staircase” the project proceeds. The “staircase” issues are those that determine whether the Shoreline Study proceeds through the later phases, or halts before all phases are completed.

Target. A performance measure that provides quantifiable restoration metrics used to assess project performance with respect to project objectives, constraints, and considerations.

Trigger. Management triggers identify the point at which the system may not be performing or progressing as expected.

Uncertainty. Disagreement or lack of knowledge about how a system functions, specifically, how a restoration action may or may not result in the desired outcome.

1. Introduction

This document provides the feasibility-level monitoring and adaptive management plan for the South San Francisco Bay Shoreline Study (Shoreline Study). The Shoreline Study is a flood risk management and ecosystem restoration effort that is recommending a project to reduce tidal flood risk and restore tidal marsh habitat along southern San Francisco Bay.

This plan identifies potential monitoring activities, outlines how results from the monitoring would be used to assess project success and, if needed, adaptively manage the project to achieve the desired ecosystem restoration objectives. The plan specifies who would be responsible for monitoring and adaptive management activities and provides estimated costs.

1.1 Authorization for Monitoring and Adaptive Management

Section 2039 of WRDA 2007 directs the Secretary of the Army to ensure that, when conducting a feasibility study for a project (or component of a project) for ecosystem restoration, the recommended project includes a plan for monitoring the success of the ecosystem restoration. The implementation guidance for Section 2039 (USACE 2009) specifies that ecosystem restoration projects include plans to track and improve restoration success through monitoring and adaptive management.

1.2 Relation to South Bay Salt Pond Restoration Project Adaptive Management and Monitoring

The non-Federal sponsors for the Shoreline Study are currently collaborating to implement the South Bay Salt Pond (SBSP) Restoration Project, which encompasses 15,100 acres in the South Bay and includes the USFWS-owned parts of the Shoreline Study area. In 2009, the SBSP Restoration Project completed program-level planning, program-level NEPA compliance, and program-level permitting for the entire 15,100 acres, including the Shoreline Study project area. The USFWS was the lead agency for NEPA; the USACE was a cooperating/responsible agency.

Adaptive management is an integral component of the SBSP Restoration Project (EDAW et al 2007). The SBSP Restoration Project identifies a range of potential implementation and habitat outcomes, with the endpoint to be determined through phased implementation guided by adaptive management. One of the fundamental project trade-offs is the conversion of existing waterfowl and shorebird habitat in the former salt ponds to tidal wetland habitat for a range of native marsh-dependent species. The two defined project endpoints are a 50:50 ratio of tidal and managed pond habitats or a 90:10 ratio, depending on how successfully the restored and enhanced ponds are able to maintain existing populations of waterfowl and shorebirds. The final habitat mix may be at either endpoint, or somewhere between the two.

The SBSP Restoration Project uses a “staircase” analogy to describe the proposed project, with each step on the staircase representing one phase of tidal restoration implementation. Adaptive implementation determines how far “up the staircase” the project proceeds. Before proceeding with each subsequent phase, the SBSP Restoration Project decision makers would consider the staircase issues. If the restoration is not transpiring as expected and no other solutions (through construction, operations, maintenance, or phasing) are feasible, the decision could be made to halt the project before continuing to subsequent phases.

The SBSP Restoration Project Management Team includes members of the Shoreline Study project delivery team (PDT), who represent the specific needs of the Shoreline Study and its project area. The goals and objectives for the Shoreline Study and the SBSP Restoration Project are very similar; however the geographic footprint of the two efforts is not identical. The Shoreline Study is being conducted as a series of interim feasibility studies, the first of which focuses on Ponds A9-A15 (owned by USFWS) and Pond A18 (currently

owned by the City of San Jose and not within the SBSP Restoration Project footprint). Because the current interim feasibility study includes a subset of ponds within the SBSP Restoration Project, this report draws from the monitoring and applied studies being conducted by the larger SBSP Restoration Project.

1.3 Procedure for Drafting the Monitoring and Adaptive Management Plan

This Monitoring and Adaptive Management and Monitoring Plan (MAMP) was prepared by members of the Shoreline Study PDT and SBSP Restoration Project – including staff from the U.S. Army Corps of Engineers (USACE) San Francisco District, staff from the California State Coastal Conservancy, the SBSP Restoration Project Executive Project Manager, and the SBSP Restoration Project Lead Scientist – and staff from the consulting firms ESA PWA and HT Harvey & Associates, under contract to the California State Coastal Conservancy.

The Shoreline Study MAMP is consistent with the plan developed for the SBSP Restoration Project (2007), but reflects Shoreline Study-specific goals, objectives, and geography. The Shoreline Study MAMP was developed to be consistent with the framework for adaptive management in the previously mentioned USACE implementation guidance (USACE 2009).

1.4 Rationale for Adaptive Management

The primary incentive for implementing an adaptive management program is to increase the likelihood of achieving desired project outcomes given project uncertainties. All ecosystem restoration projects face uncertainty due to incomplete understanding of relevant ecosystem structure and function, resulting in imprecise relationships between project actions and corresponding outcomes. Flood protection projects, too, face engineering uncertainties. Given these uncertainties, adaptive management provides an organized and coherent process that suggests management actions in relation to measured project performance compared to desired project outcomes. Adaptive management establishes the critical feedback among project monitoring, and informed project management, and learning through reduced uncertainty.

In the case of the Shoreline Study, cost-shared monitoring and adaptive management will focus on the constructed ecosystem restoration elements of the project to ensure their success. However, the Shoreline Study also fits within the larger context of the SBSP Restoration Project, which examines larger-scale (regional) effects that set the context for site-specific analysis of implemented restoration projects. These include:

- Determining species presence and landscape/ecosystem evolution in response to restoration activities,
- Signaling that the phased restoration can proceed or determine that additional actions are necessary before moving forward, and
- Determining if and when tidal marsh restoration should halt due to undesired consequences on the natural system.

The future project recommended by the Shoreline Study would implement tidal restoration of existing managed ponds in phases. While the expectation is that all phases will be constructed, there are landscape-scale uncertainties that could cause implementation of future restoration features to halt because of undesired changes to ecosystems and populations outside of the project area. In addition, the presence of mercury in the sediments and risk of increasing bioaccumulation of mercury in the food web within the study area is a key project constraint that may delay or halt the restoration of certain ponds. The significance of this risk will be unknown until project implementation is begun. Monitoring for the “phased implementation” and mercury-related aspects of the project are not included as part of the cost-shared Shoreline Study monitoring and adaptive management program, but rather will be conducted by the SBSP Restoration Project.

For flood risk management and public access components of the project, cost-shared monitoring and adaptive management activities are not recommended. Minor adjustments to these features will be covered as routine operation and maintenance performed by the non-Federal sponsors. Major adjustments to such features to adjust to changed conditions after project implementation would require a post-authorization-change process.

Adaptive Management Team

Under the SBSP Restoration Project’s organizational structure, the Adaptive Management Team (AMT) is the group responsible for making decisions about adaptive management. The AMT consists of a subset of the SBSP Restoration’s Project Management Team (PMT) members. Figure 1 (SBSP Restoration Project Organizational Structure and Functions) shows the participants in the adaptive management process for the SBSP Restoration Project, who would also make adaptive management decisions for the future project recommended by the Shoreline Study.




Figure 1. SBSP Restoration Project Organizational Structure and Functions

The AMT considers input from the Science Team (through the Lead Scientist), Stakeholder Forum, and Local Work Groups, as necessary, when making decisions. The Executive Leadership Group provides decisions on overall direction of the future project and on issues involving competing interests between agencies. Information Management Staff provide data management services for the AMT.

Participants in each group are listed below for the SBSP Restoration Project. The SBSP Restoration Project AMMP (2007) provides a detailed description of each group. For the Shoreline Study specifically, the landowners are USFWS and the San Jose/Santa Clara Water Pollution Control Plant, the local flood control district is the Santa Clara Valley Water District, and the Stakeholder Forum and Local Work Groups include only participants relevant to the Shoreline Study project area.

Executive Leadership Group = heads of the Project Management Team agencies, consisting of the California State Coastal Conservancy (SCC), the landowning and management agencies, local flood control districts, the Army Corps of Engineers, and Project funders.

AMT = U.S. Fish & Wildlife Service, California Department of Fish & Wildlife, SCC, local flood control districts, USACE, Lead Scientist, some regulatory staff, and other involved organizations.

Science Program = science directors and contractors, with a Lead Scientist responsible for coordination with the PMT.

Information Management = San Francisco Estuary Institute (or equivalent entity) as a contractor to the SCC.

Stakeholder Forum = core stakeholders with demonstrated, ongoing interest in South San Francisco Bay ecosystem restoration (local business and land owners, environmental orgs, public access/recreation, infrastructure, advocates and institutions, flood management, public works/health), local government staff and elected officials.

Local Work Groups = associated with each pond complex

Overview of Adaptive Management

Adaptive management is an iterative process that uses regular monitoring and assessments to determine whether follow-up actions are necessary to keep the project on track towards its objectives. For the purposes of this plan, monitoring and adaptive management are presented in four steps. These steps are shown graphically in Figure 2 (Adaptive Management Process) and discussed in the following sections.

- Adaptive management planning (Section 4)
- Monitoring (Section 5)
- Regular assessments (Section 6)
- Decision making (Section 7)




Figure 2. Adaptive Management Process

Adaptive management planning consists of identifying project objectives, constraints, and considerations; describing conceptual models; and identifying key uncertainties. Adaptive management planning sets the stage for determining what monitoring is required to assess whether the project is progressing toward the desired outcome. Regular assessments check monitoring results against restoration targets (desired outcomes) and management triggers (negative outcomes). The decision-making process determines if and when adaptive management actions should be implemented.

The adaptive management steps described in the sections below will be flexible to accommodate lessons learned from the monitoring results. For example, as new information becomes available, the Adaptive Management Team will update the conceptual models and may revise the monitoring metrics and methods to better address the remaining uncertainties. In the event that unanticipated uncertainties are identified, the adaptive management process will be adjusted as needed to support decision-making, so the Adaptive Management Team can continue to steer the project towards the desired outcome.

2. Adaptive Management Planning

This section: (1) identifies objectives, constraints, and considerations identified for the Shoreline Study, (2) outlines ecosystem restoration actions included in the recommended plan, (3) presents conceptual models that relate project actions (and potential adaptive management actions) to desired project outcomes, and (4) lists sources of uncertainty.

2.1 Project Objectives, Constraints and Considerations

During the initial problem identification phase of the feasibility study, the PDT, with stakeholder input, identified planning objectives, constraints, and considerations that would guide the development of ecosystem restoration, flood risk management, and recreation aspects of the future project (Table 1. Planning Objectives, Constraints, Considerations, and Uncertainties).

For these objectives, constraints, and considerations, the team also identified related uncertainties in future conditions, which are described in Section 4.4 below.

Table 1. Planning Objectives, Constraints, Considerations, and Uncertainties

Objectives		Uncertainties
1.	Reduce potential economic damages due to tidal flooding in areas near the South Bay shoreline in Santa Clara County.	• Flood and infrastructure performance □ • Climate change
2.	Reduce the risk to public health, human safety and the environment due to flooding from tidal sources along the South Bay shoreline in Santa Clara County.	• Flood and infrastructure performance □ • Climate change
3.	Increase contiguous marsh to restore ecological function and habitat quantity, quality, and connectivity (including transition zones) in the study area for native, resident plant and animal species including special-status species such as steelhead trout, Ridgway's rail, and salt marsh harvest mouse.	• Sediment dynamics □ • Effects on non-avian species □ • Ecotones □ • Climate change
4.	Provide opportunities for public access, education, and recreation in the study area.	• Public access & wildlife
Constraints		Uncertainties
1.	Do not jeopardize any listed species.	• Bird use of changing habitats □ • Sediment dynamics
2.	Do not significantly increase the potential for bioaccumulation of mercury in the food web within the study area.	• Mercury
3.	Recreational features must be compatible with ecosystem restoration objectives and flood risk management objectives.	• Public access and wildlife
4.	Comply with applicable regulatory requirements.	• No major uncertainties
5.	Do not negatively impact groundwater quality.	• No major uncertainties
6.	No negative permanent impacts on function of existing major infrastructure (wastewater treatment plant, PG&E, railroad, stormwater pump station, landfill, recycling facilities).	• Flood and infrastructure performance
Considerations (Avoid, minimize, or mitigate)		Uncertainties

1.	Loss of existing outboard marshes and mudflats in the study area.	• Sediment dynamics
2.	Reduction in the quality of existing tidal marsh, including fragmentation and increased edge effects.	• Sediment dynamics
3.	Creation of new tidal areas without transition zones.	• No major uncertainties
4.	Negative impacts to threatened and endangered species.	• Bird use of changing habitats □ • Effects on non-avian species □ • Sediment dynamics
5.	Net reduction of total habitat value for major categories of water birds, including shorebirds, waterfowl, and miscellaneous species that use these habitats within the larger SBSP Project area.	• Bird use of changing habitats
6.	Proliferation of nonnative and/or undesirable species in the study area.	• Invasive and nuisance species
7.	Access by predators to special-status species habitat in the study area.	• Invasive and nuisance species
8.	Negative impacts to cultural resources.	• No major uncertainties
9.	Negative impacts to existing recreational infrastructure function within the study area.	• Public access and wildlife
10.	Increases in vector populations in the study area.	• Invasive and nuisance species
11.	Negative impacts to existing water quality and sediment quality in the study area.	• Mercury □ • Sediment dynamics

2.2 Proposed Ecosystem Restoration Actions

The Shoreline Study proposes to restore approximately 2,900 acres of former commercial salt production ponds to tidal marsh and associated habitats. Tidal habitat restoration will be phased and achieved mainly through restoration of natural physical and ecological processes rather than through constructed physical features or plantings. In addition, the project proposes to construct 3.5 miles of levees to provide coastal flood protection.

The proposed project includes construction of outboard levee breaches and internal berm breaches to introduce tidal flows to the ponds. Some of the outboard levees and internal berms would be lowered to reconnect marsh to mudflat, improving water, sediment, and organism exchange. Pilot channels, starter channels, ditch blocks and side cast natural berms will be used to accelerate evolution of the ponds and enhance habitat.

The ecosystem restoration component of the proposed project would occur as three phases of pond breaches to establish tidal connection, with five years between each set of breaches (Figure 3. Project Implementation Schedule). The first phase would breach Ponds A12 and A18 (in 2020), the second would breach Ponds A9, A10, and A11 (in 2025), and the third would breach Ponds A13, A14, and A15 (in 2030). Under the adaptive implementation concept, design and construction of the later phases may be modified based on what is learned in monitoring of earlier phases. In the unlikely event that the results of the earlier phase(s) indicate undesirable outcomes that cannot be avoided by adaptive management actions, project implementation would be halted prior to construction of the later phase(s).

Through its phased implementation approach, it is possible that the Shoreline Study may cease tidal restoration actions after either the first or second phase. This would only take place if the USACE and the Adaptive Management Team decided, based on the latest monitoring and science available on issues such as

bird use and mercury contamination, that the highest ecological value of those particular ponds were for them to remain as pond habitat for specific guilds of birds. The proposed phases were selected specifically because they could be implemented as separable elements, although with cumulative synergistic benefits. However, regardless of the ultimate endpoint, the Shoreline Study will have implemented a cost effective restoration project and achieve significant ecological benefits as part of a nationally significant restoration effort.




Figure 3 – Project Implementation Schedule

2.3 Conceptual Models

The purpose of the conceptual model is to provide the linkage between project actions and expected system response. Planning for the Shoreline Study used the conceptual ecological model developed for the SBSP Restoration Project (Trulio et al 2007) to represent current understanding of ecosystem structure and function in the project area, identify performance measures, and help select parameters for monitoring. The model illustrates the effects of important natural and anthropogenic activities that result in different ecological stressors on the system. Figures 4, 5, and 6 present the conceptual models for tidal habitat, managed pond habitat, and overall landscape habitat interactions.




Figure 4. Tidal habitat conceptual model




Figure 5. Managed pond conceptual model




Figure 6. Landscape conceptual model

The tidal habitat conceptual model is directly relevant to the desired habitat type and ecosystem restoration objectives for the Shoreline Study. The managed pond and landscape conceptual models are relevant in that they describe the “staircase” issues (associated with phased implementation), issues that determine whether the project recommended by the Shoreline Study proceeds beyond the first phase of tidal marsh restoration, or halts before all phases are completed (see Section 9).

2.4 Sources of Uncertainty

Gaps in our knowledge about South San Francisco Bay ecosystem function and the landscape-scale effects of restoration actions can influence how we achieve the project objectives over the course of implementation. Key uncertainties associated with ecosystem restoration, flood risk management, and public access were identified so that monitoring could be targeted to reduce these uncertainties and guide future actions, including cost-shared adaptive management.

Sediment dynamics, including the extent to which estuarine sedimentation is sufficient to convert mudflats to vegetated marsh and extent to which tidal habitat restoration might result in the loss of slough and bay tidal mudflat habitat regionally.

Bird use of changing habitats, including the extent to which tidal habitat species can be recovered while maintaining the diversity and abundance of nesting and migratory waterbirds observed during pre-project conditions.

Effects on non-avian species, including the extent to which restoration will affect fish, mammals, and other critical species in the South Bay ecosystem.

Mercury, including the extent to which the future project’s ecosystem restoration and other actions might result in an increase in bioavailable mercury in the food chain.

Invasive and nuisance species, including the invasive *Spartina* hybrids, red foxes, California gulls, and mosquitoes.

Public access and wildlife, including the extent to which various forms of public access and recreation can be integrated into the future project without significantly affecting wildlife.

Ecotones, including the extent to which the ecotones (transitional habitat located between tidal marsh and upland habitats) will support desirable vegetation and not support invasive vegetation.

Flood and infrastructure performance, including the extent to which the new infrastructure will perform as designed.

Climate change, including whether sea level rise will be greater than assumed in the design.

Table 1 (Planning Objectives, Constraints, Considerations, and Uncertainties) lists the uncertainties as they relate to each of the project objectives, constraints, and considerations. Some of these uncertainties relate directly to the efficacy of actions being proposed (e.g., ability to meet ecosystem restoration objectives), while others take into account the landscape-scale effects of multiple restoration actions in South San Francisco Bay (thus relating to adaptive implementation).

3. Monitoring

The purposes of monitoring are to assess progress towards project objectives, detect early signs of potential problems, and reduce uncertainties. For each key uncertainty, restoration targets (success criteria) were developed to identify the desirable outcome, and then monitoring metrics defined for measuring each restoration target (Table 2. Monitoring topics, targets, and metrics associated with ecosystem restoration objectives). The monitoring elements included in this table have been limited to activities associated with ecosystem restoration project objectives. The restoration targets and success criteria define how the project will know when ecosystem restoration success has been achieved and monitoring activities can cease.

Table 2. Monitoring topics, targets, and metrics associated with ecosystem restoration objectives

Primary Monitoring Topics		Category	Restoration Targets/Success Criteria	Monitoring Metrics
1.	Sediment dynamics	Sedimentation Inside the Ponds	<p>Water levels inside the ponds are similar to just outside the ponds, allowing full exchange of water and sediments (Years 1-3 of breaching phase only).</p> <p>Accretion rate of the breached ponds is sufficient to reach marsh vegetation colonization elevations within the planning time frame (Years 1-5 of breaching phase only).</p> <p>Initial modeling projects that the ponds will reach marsh plain elevation within 15-20 years after breaching. Since this is beyond the monitoring period for the project, the restoration target for the first 10 years will be that the accretion rates are on a trajectory toward meeting that criterion. Specific elevation targets for each pond will be refined based on the ponds' initial bottom elevation, and the sediment accretion curves developed from the previous restoration of adjacent Ponds A6, A19, A20 and A21.</p>	<ul style="list-style-type: none"> • Water levels in ponds • Sedimentation rates in ponds • Suspended sediment concentrations in ponds

		Restored Tidal Marsh Habitat (Inside the Ponds)	<p>Tidal marsh vegetation is on a trajectory toward other successful marsh restoration sites in South San Francisco Bay.</p> <p>Native tidal marsh species, including pickleweed (both annual and perennial species) and cordgrass, are expected to begin naturally colonizing the marsh plain within 2 years of pond bottom reaching the appropriate elevations through natural sedimentation (typically an elevation between Mean Tide Level and Mean Higher High Water).</p>	<ul style="list-style-type: none"> • Tidal marsh habitat acreage in ponds
2.	Bird use of changing habitats	Ridgway's Rail	<ul style="list-style-type: none"> • Contribute to the recovery of the Ridgway's rail by providing new tidal marsh habitat and ensuring restored marshes are on a trajectory toward vegetated marsh. 	<ul style="list-style-type: none"> • Tidal marsh habitat acreage in ponds (see Item 1 above)
3.	Non-avian species	Salt Marsh Harvest Mouse	<ul style="list-style-type: none"> • Contribute to the recovery of the salt marsh harvest mouse by providing new tidal marsh habitat by providing new tidal marsh habitat and ensuring restored marshes are on a trajectory toward vegetated marsh. 	<ul style="list-style-type: none"> • Tidal marsh habitat acreage in ponds (see Item 1 above)
4.	Invasive and nuisance species	Invasive and Nuisance Plants	<ul style="list-style-type: none"> • Habitat trajectory toward native/non-native composition of a reference marsh and other restoration sites. Qualitative inspections for invasive species (especially <i>Spartina hybrids</i> and <i>Lepidium latifolia</i>) will occur annually, quadrant or transect sampling once marsh has 20% vegetation cover. Any hybrid <i>Spartina</i> presence will be reported to the regional control effort, and any marsh containing over 30% <i>Lepidium</i> will trigger control activities. 	<ul style="list-style-type: none"> • Abundance of non-native species

5.	Ecotones	Transition zones	<ul style="list-style-type: none"> • Transition zone habitat comprising wide, gently-sloped vegetated terrain with a diverse habitat mosaic dominated by (>50% relative cover) perennial native grassland and for species interspersed with salt panne and seasonal wetland habitats transitioning along a salinity gradient to native salt marsh community representative of historic transition zone habitats. 	<ul style="list-style-type: none"> • Plant species composition in transition zones
----	----------	------------------	--	---

Monitoring activities associated with flood risk management, adaptive implementation, or permit compliance for the recommended project will not be cost shared by the USACE, but will be funded and implemented by the non-Federal sponsor through the SBSP Restoration Project. However, information collected through these types of monitoring activities may result in future cost-shared activities (e.g., changes to the authorized project).

Monitoring and activities that address regional changes from the combined effects of Shoreline Study and SBSP Restoration Project will not be cost shared by the USACE unless they are also linked directly to the Shoreline Study’s ecosystem restoration objectives and are conducted within the Shoreline project footprint. These activities related to regional changes will be conducted as the continuation of ongoing activities currently performed under the SBSP Restoration Project. Coordination of the future Shoreline Project with the SBSP Restoration Project will allow for more complete and consistent information to guide decision-making as bay-wide effects are considered. Regional monitoring includes monitoring of changes to mudflat and tidal marsh acreages, changes to bird populations and abundance, and mercury bioavailability.

Each monitoring metric was detailed in terms of monitoring methods, locations, frequency and duration in order to develop a cost estimate (See Table 3. Monitoring Cost Estimate). The monitoring cost estimate is \$968,000 (First Cost October 2014 price level).

Although the monitoring cost estimates presented in this document display activities during the proposed ten years of cost-shared monitoring after construction, monitoring will continue beyond the initial ten years, funded by the non-Federal sponsor, if the criteria for ecosystem success have not yet been met (see Table 2. Monitoring topics, targets, and metrics associated with ecosystem restoration objectives).

Table 3. Monitoring Cost Estimate

Restoration Target Category	Monitoring Metric (Brief)	Monitoring Metric & Method	Which Years?	# Years	Cost/Unit (before SS adjustment)	Cost/Unit *	Unit	# Units	Total Cost*	Notes
Sedimentation Inside the Ponds	Water levels in ponds	* Water levels inside the ponds collected using pressure transducers in the ponds and adjacent sloughs. Monitor until no damping observed.	0+, 1, 2 after each phase	9	\$ 50,000	\$ 50,000	1 phase (3 yrs/phase, 2 wks/yr)	3	\$ 150,000	Approximately \$16,700 per year for three years per phase (2-3 tide gages). Note: SBSBP is not monitoring water levels currently.
Sedimentation Inside the Ponds	Sedimentation rates in ponds	* Sedimentation rates inside ponds: Transects or SETs in breached ponds, annually at first and then less frequently as rates of accretion slow. Consider using Regional Sediment Dynamics monitoring data, such as LIDAR surveys if sufficiently detailed for use inside ponds.	0+, 2, 5, 10 after each phase	12	\$ 25,000	\$ 25,000	1 event	12	\$ 300,000	Assume same methods as at Island Ponds and Pond A6. Investigate using bathymetry or LIDAR inside the breached ponds.
Sedimentation Inside the Ponds	Suspended sediment concentrations in ponds	* Suspended sediment concentration monitoring * See related monitoring in Regional Mudflat Habitat and Sediment Dynamics	10	1	\$ 150,000	\$150,000	1 event	1	\$ 150,000	Estimate is cost for conducting sampling for input variables to model, and running marsh sustainability model. Assume model is run at Year 10, though timing may vary.
Restored Tidal Marsh Habitat (Inside the Ponds)	Tidal marsh habitat acreage in ponds	* Tidal marsh habitat acreage inside the ponds. Collect acreages via remote imagery with limited ground-truthing.	5, 10	2	\$ 300,000	\$ 54,000	2	1	\$ 108,000	Included in Regional Tidal Marsh Habitat. No costs for vegetation community surveys since these will not be conducted within 10 years of breaching.
Ridgway's Rail	Presence of tidal marsh habitat	* Tidal marsh habitat acreage inside the ponds. Collect acreages via remote imagery with limited ground-truthing (as above).							\$ -	cost already covered by tidal marsh acreage monitoring
Salt Marsh Harvest Mouse	Presence of tidal marsh habitat	* Tidal marsh habitat acreage inside the ponds. Collect acreages via remote imagery with limited ground-truthing (as above).							\$ -	cost already covered by tidal marsh acreage monitoring
Invasive and Nuisance Plants	Abundance of non-native species	* Abundance of non-natives such as non-native Spartina spp. (Qualitative assessments for invasive species will occur annually.)						N/A (see note)	\$ -	Covered by SBSBP and transition zone monitoring.
Transition zones	Plant species composition in transition zones	* Plant species composition including abundance of native species. * Annual habitat monitoring during a 3-year plant establishment period to ensure establishment of native plant species. * Annual qualitative assessments for invasive species.	0, 1, 2, 5, 7, 10	6	No Fill - \$8,000 - \$10,000/yr; 30:1 Fill - \$25,000 - \$30,000/yr; 100:1 Fill \$66,000.	\$8,000 - \$10,000/yr \$25,000 - \$30,000/yr \$66,000	1 event	6	\$ 54,000	6 Years Monitoring (Total) includes habitat monitoring, species composition, and qualitative assessments; Estimate based on total transition zone acreage.
SUBTOTAL									\$ 762,000	
27% Contingency									\$ 205,740	
TOTAL (First cost Oct 2014 price levels)									\$ 967,740	
AVERAGE ANNUAL COST (APPROX)									\$ 48,387	
* Assumes Shoreline Study cost is 18% of entire cost estimate for SBSBP Restoration Project, based on relative acreages to be monitored.										
Assume project constructed in three phases from 2017 to 2031, with monitoring and adaptive management 2021 to 2041 (10 years following each phase for a total of 20 years).										
Note: Year 0+ means immediately after breaching.										
Any monitoring that occurs after 10 years post construction will be a 100% non-Federal responsibility										

3.1 Targets

Table 2 (Monitoring topics, targets, and metrics associated with ecosystem restoration objectives) lists the restoration targets as related to the project uncertainties, which are directly linked to the project objectives, constraints, and considerations (Table 1. Planning Objectives, Constraints, Considerations, and Uncertainties) and indicate how the project will know when ecological success has been achieved and monitoring activities can cease. Typical data sources for developing these targets are the published academic literature, quantitative baseline data, or requirements set by a regulatory agency. Targets include both long-term goals and intermediate conditions as the ecosystem changes. Quantitative targets, such as minimum numbers or ranges of variability, do not yet exist for all restoration targets. These targets will be developed using existing data or regulations and many are expected to evolve as monitoring and assessments are conducted. References to “significant impacts” in the target descriptions are related to National Environmental Policy Act and California Environmental Quality Act significance, which will be identified in the Environmental Impact Statement/Report.

Restoration targets are intended to hold the Shoreline Study to levels of performance that are under the Shoreline Study’s control, and not to levels controlled by external factors.

The monitoring is organized by “Restoration Target Categories,” which are specific sub-categories within each of the key uncertainties. Categories are the basic elements of the ecosystem that must be monitored to determine whether the project objectives are being met, or are likely to be met in the future. Use of the Restoration Target Categories helps in cross-referencing the monitoring to later assessment and decisions-making steps by allowing cross-referencing between tables.

3.2 Monitoring Metrics

Specific, measureable monitoring metrics, or parameters, to assess change with respect to the restoration targets are presented in Table 2 (Monitoring topics, targets, and metrics associated with ecosystem restoration objectives). Note that while habitat creation for the Federally protected Ridgway’s rail (formerly the California clapper rail, *Rallus longirostris obsoletus*) and the salt marsh harvest mouse (*Reithrodontomys raviventris*) is a project objective, the monitoring metrics for these species within this MAMP only includes the establishment of the target habitat. The timing of adequate habitat development to support these species varies greatly between the individual ponds, depending on their initial bottom elevations. For example, in the nearby Pond A21 (restored in 2006), rails were detected using the restored marsh habitat in Year 8 post-restoration.

3.3 Monitoring Methods

Table 3 (Monitoring Cost Estimate) describes the monitoring metrics and methods in additional detail, such as timing relative to restoration phases, spatial extent, and frequency. Each of the three pond breaching phases will have its own timeframe for baseline monitoring, construction, post-construction monitoring and adaptive management, and turnover to the non-Federal sponsor for operation and maintenance. For each phase of pond breaching, baseline monitoring would begin three years prior to breaching and post-construction monitoring would continue until ecological success criteria are met. Extensive monitoring that has already occurred in these areas indicates that bird use has a high degree of inter-annual variability. Therefore, to understand the immediate, as well as cumulative, effects of

the restoration actions, continued baseline monitoring is essential. Although previous and ongoing monitoring results are available and will inform the proposed project, this information provides a general understanding of what will happen within the restored ponds, but the bigger picture of cumulative effects across multiple ponds, is unknown. The period of cost-shared monitoring will not exceed ten years (Figure 3. Project Implementation Schedule). Section 7.3 provides additional discussion of monitoring duration as related to project close out.

The monitoring method summaries in Table 3 (Monitoring Cost Estimate) are described in enough detail to make the approach clear, but do not fully describe the monitoring regime. A monitoring plan with detailed methods, protocols, timing, and responsible parties will be developed prior to start of monitoring, as each monitoring study is contracted.

3.4 Database Management

Database management will be provided by the SCC, who will likely contract with the San Francisco Estuary Institute (SFEI) or other similar entity for this role. The database manager will be responsible for storing final monitoring reports and other Shoreline Study documentation (decisions, agendas, reports) and making them available on the SBSP Restoration Project website. Monitoring reports will be searchable by topic and principle author.

The database will be designed to store and archive the Shoreline Study monitoring data. The format of each monitoring data set will vary as appropriate to the type of monitoring. Therefore, data are expected to be archived separately by study, rather than collated in one master database. Each dataset will include:

- Data and metadata transfer and input policies and standards
- Data validation procedures
- Mechanisms to ensure data security and integrity

Monitoring data sets will be available to the public upon request.

4. Regular Assessments

The assessment phase compares the results of the monitoring efforts to the desired project performance targets. The SBSP Restoration Project Science Program has been the primary group responsible for these assessments, for the regional monitoring and adaptive management effort. The Lead Scientist for the SBSP Restoration Project will facilitate regular communication of assessment results from the Science Program to the AMT, who will make recommendations to the USACE. The USACE will be the decision maker for any adaptive management actions undertaken on projects that it is responsible for constructing.

This section defines the assessment process, acceptable variances between monitoring results and targets, the frequency and timing for comparison of monitoring results to the selected targets, and assessment documentation.

4.1 Assessment Process

The SBSP Restoration Project Science Program will identify methods for comparing the restoration targets/ triggers with monitoring data. These methods will include appropriate statistical comparisons (e.g., hypothesis testing, ANOVA, multivariate methods). The results of these assessments will be documented and stored in the data management system.

The SBSP Restoration Project Science Program members will collaborate with the AMT to define magnitudes of difference (statistical differences, significance levels) between measured and desired values that will constitute variances. These variances will be used to recommend adaptive management actions to the USACE.

Note that, while there are no assessments specific to sea level rise, any predictions of tidal habitat evolution will incorporate the most up-to-date sea level rise information and guidance at the time of assessments.

4.2 Frequency of Assessments

An annual meeting will be held between the AMT and the SBSP Restoration Project Science Team to discuss monitoring and research findings, management triggers, and implications for adaptive management. Assessments may be more frequent, depending on the relevant physical or ecological scale of each restoration target. Table 3 (Monitoring Cost Estimate) includes two columns describing the frequency and timing of monitoring. The temporal scale of the system responses was one of the main considerations in determining frequency and timing of monitoring. For example, inspections for levee erosion should be conducted monthly at first, then annually and after major rainfall and tidal events. In this case the frequency of assessments will be greatest during the first year, with decreasing frequency after the first year.

4.3 Documentation and Reporting

Project assessment documentation will be prepared following each annual meeting in the form of detailed meeting notes. The meeting notes will describe progress towards project objectives as

characterized by the restoration targets. The database manager will be responsible for storing the meeting notes and making them available on the SBSP Restoration Project website.

5. Decision Making

The AMT will receive input from the SBSP Restoration Project Science Team in an annual meeting that will focus on relevant monitoring findings, management triggers, and implications for future project phases. If the AMT believes that small management actions need to happen, they would recommend to the USACE that those actions be implemented immediately. If a larger change to the project approach or a substantial action is necessary, the AMT would vet this change or action publicly through the SBSP Restoration Project’s PMT and its working groups such as the Stakeholder Forum, Alviso Regional Working Group, and/or the Regulatory Work Group, depending on the scale and type of issue. The AMT would report the results of the vetting process to the USACE, who will decide whether to take action.

For each management trigger there is a list of potential adaptive management actions the AMT and Science Team might recommend that the USACE take if a management trigger is reached. Table 4 (Adaptive Management Decision Matrix) describes the assessments and potential management actions associated with each restoration target category.

Table 4. Adaptive Management Decision Matrix

Restoration Target Category	Monitoring Metrics	Management Triggers/ Conditions Requiring Assessment	Assessments Prompted by Management Trigger	Potential Management Action
Sedimentation Inside the Ponds	<ul style="list-style-type: none"> Water levels in ponds Sedimentation rates in ponds Suspended sediment concentrations in ponds 	<ul style="list-style-type: none"> Projections based on the rate of mudflat accretion suggest vegetation colonization elevations are not likely to be achieved within the planning time frame. 	<ul style="list-style-type: none"> Convene study session to review findings and assess whether colonization is compromised. [A] If tidal marsh is not meeting projections, assess biological significance of slower tidal flat evolution. [A] 	<ul style="list-style-type: none"> If vegetation colonization is compromised and deemed biologically detrimental, widen breaches to encourage better tidal exchange [C] Adjust to increase pond mudflat accretion. Potential management actions include adding wave breaks, placing fill, or in-bay material placement to “feed” the restored ponds. [C] Implement management or adjust design (e.g., remove more levees to increase connectivity between ponds and adjacent sloughs) based on study results [C] Reconsider movement up staircase. [P]
Restored Tidal Marsh Habitat (Inside the Ponds)	<ul style="list-style-type: none"> Tidal marsh habitat acreage in ponds 	<ul style="list-style-type: none"> No vegetation within 10 years of monitoring 	<ul style="list-style-type: none"> Identify causes of slow vegetation establishment [A] Review sediment dynamics [A] 	<ul style="list-style-type: none"> Remove impediment to vegetation establishment. [C] See Potential Management Actions for Sedimentation Inside the Ponds.
Invasive and Nuisance Plants	<ul style="list-style-type: none"> Abundance of non-native species 	<ul style="list-style-type: none"> Presence of other non-native plant species that is greater than 5% of vegetation cover. Presence of new invasive plants with high potential to spread. Presence of non-native <i>Spartina</i> or hybrids 	<ul style="list-style-type: none"> Continue to re-evaluate what is meant by “control” of invasive species and adjust monitoring and management triggers based on the latest scientific consensus [A] If invasive species cannot be controlled, study biotic response to non-native vegetation [A] 	<ul style="list-style-type: none"> No construction actions proposed. Control invasive <i>Spartina</i> in future restored tidal marsh [I]
Transition zones	<ul style="list-style-type: none"> Plant species composition in upland transition zones 	<ul style="list-style-type: none"> Dominant native plant species cover does not establish Invasive species constitute >10% of habitat 	<ul style="list-style-type: none"> No additional assessments proposed. 	<ul style="list-style-type: none"> Active seeding/planting to revegetated bare areas [C] Control invasive <i>Lepidium</i> in transition zone [I] Weed control [M]

* A = Assessment; C = Construction; I = Invasive and Nuisance Plants; P = Phasing (not cost shared); M = Operations & Maintenance (not cost shared)

Figure 7 (Adaptive Management Assessment and Decision Making: Sediment Dynamics Example) steps through the decision-making process for one of the Shoreline Study uncertainties: Sediment Dynamics. This example is used to illustrate adaptive management decision making throughout Section 7.




Figure 7. Adaptive Management Assessment and Decision Making: Sediment Dynamics Example

5.1 Triggers

Each restoration target has a management trigger for action if the system is not performing well. A trigger (also known as “Conditions Requiring Assessment”) is a threshold that, when reached, indicates that the Shoreline Study may be diverging from a restoration target. The intent of the triggers is to anticipate problems before they cause significant impacts to the system. This advance notice would provide project managers with time to investigate the causes and take action, as necessary, to put the system back on track.

Each management trigger has a corresponding list of potential actions the project team may take if a trigger is reached (discussed in Section 7.2 Potential Adaptive Management Actions). Like the restoration targets, the triggers will be reviewed and updated regularly as additional information becomes available.

5.2 Potential Adaptive Management Actions

Potential management actions are taken when the project is not progressing towards restoration targets as planned and a management trigger has been reached. Typically, the first action would be to conduct an assessment of available monitoring data and consult with external and internal experts to inform subsequent management actions. For this plan, potential management actions are categorized as either (1) as-needed assessments, (2) construction (adjustments to design), or (3) changes to operations, and maintenance. Changes to restoration phasing (adaptive implementation) are also a potential outcome, but those actions are not included as cost-shared activities under the Shoreline Study MAMP.

5.2.1 As-Needed Assessments Triggered by Monitoring

When the cause for tripping a management trigger or the appropriate response is not immediately apparent, these additional assessments use available data (monitoring or other) to better understand what is causing the system to respond differently from target. These assessments typically occur prior to other adaptive management actions and involve convening an assessment team of experts and decision makers to advise the USACE on how to proceed (Table 5. As-needed assessments).

For example, if regular monitoring finds that there is no vegetation establishment within 10 years of monitoring the assessment team would assess whether vegetation establishment is, in fact, caused by sediment dynamics (lack of sedimentation) (Figure 7. Adaptive Management Assessment and Decision Making: Sediment Dynamics Example). If this is the case, the team would assess the biological significance of slower tidal flat evolution. If sediment dynamics is not the cause, the team would examine other potential reasons for slow vegetation establishment.

Table 5. As-needed assessments

Restoration Target Category	Potential Management Action	Type*	Shoreline Study Cost Estimate (unadjusted**)	Cost Estimate *	Notes
Sedimentation Inside the Ponds	• Convene study session to review findings and assess whether colonization is compromised.	A	\$ 25,000	\$ 4,500	All reviews @\$25,000, adjusted by 18%*.
Sedimentation Inside the Ponds	• If tidal marsh is not meeting projections, assess biological significance of slower tidal flat evolution.	A		\$ -	Already covered in applied studies
Restored Tidal Marsh Habitat (Inside the Ponds)	• Identify causes of slow vegetation establishment	A	\$ 50,000	\$ 9,000	
Restored Tidal Marsh Habitat (Inside the Ponds)	• Review sediment dynamics	A		\$ -	Already covered in monitoring
California Clapper Rail	• Assess habitat suitability	A		\$ -	Already covered in monitoring
Salt Marsh Harvest Mouse	• Assess habitat suitability	A		\$ -	Already covered in monitoring
Invasive and Nuisance Plants	• Continue to re-evaluate what is meant by "control" of invasive species and adjust monitoring and management triggers based on the latest scientific consensus	A		\$ -	Already covered in monitoring
Invasive and Nuisance Plants	• If invasive species cannot be controlled, study biotic response to non-native vegetation	A	\$ 25,000	\$ 4,500	All reviews @\$25,000, adjusted by 18%*.
SUBTOTAL				\$ 18,000	
27% Contingency				\$ 4,860	
TOTAL (First Cost Oct 2014)				\$ 22,860	

5.2.2 Construction (Adjustments to Design)

Most construction actions involve adjusting the tidal restoration design (e.g. widening breaches or placing fill) when the project is not progressing towards the objectives as planned (Table 6. Adaptive Management Construction Activities). Design adjustments would be tailored to the specific problem as identified through the assessment. The majority of the proposed actions have been implemented elsewhere in San Francisco Bay for similar marsh habitat restoration projects.

For example, if the sediment dynamics study session (described above) finds that slower tidal flat evolution is biologically significant, the design could be adjusted to encourage faster tidal evolution. This might involve widening breaches, placing wave breaks or additional fill, or preserving bayfront levees (Figure 7. Adaptive Management Assessment and Decision Making: Sediment Dynamics Example).

Table 6. Adaptive Management Construction Activities

Restoration Target Category	Potential Management Action	Type*	Cost Est.	Basis for Cost Estimate
Sedimentation Inside the Ponds	* If vegetation colonization is compromised and deemed biologically detrimental, widen breaches to encourage better tidal exchange	C	\$ 230,000	Assume 25% widening
Sedimentation Inside the Ponds	* Adjust to increase pond mudflat accretion. Potential management actions include adding wave breaks, placing fill, or in-bay material placement to "feed" the restored ponds.	C	\$ 2,610,000	Assume sidecasts are 50% of 36,000 ft of starter channel at \$145/LF
Sedimentation Inside the Ponds	* Implement management or adjust design (e.g., remove more levees to increase connectivity between ponds and adjacent sloughs) based on study results	C	\$ 840,000	Assume lowering 7,500 ft of levee at \$112/ft
Restored Tidal Marsh Habitat (Inside the Ponds)	* Remove impediment to vegetation establishment.	C		
California Clapper Rails	No construction actions proposed.			
Salt Marsh Harvest Mouse	No construction actions proposed.			
Invasive and Nuisance Plants	No construction actions proposed.			
Transition zones	* Active seeding/planting to revegetated bare areas	C	\$ 25,000	Assume 20% replating @ \$7,000/acre (no irrigation; grassland seeding; plug planting @ 400-500 plants/acre). Estimate does not include any soil amendments, maintenance, or irrigation costs.
SUBTOTAL			\$ 3,705,000	
27% Contingency			\$ 1,000,350	
TOTAL (First Cost Oct 2014)			\$ 4,705,350	

5.2.3 Invasive and Nuisance Plant Control

These adaptive management activities are for the removal of invasive species that may accidentally enter the future restored tidal marsh and transition zones and are beyond the normal operation and maintenance activities that will be performed by the USFWS or non-Federal sponsor. These activities will ensure the establishment of native species, which is a key component of the project’s ecosystem restoration objectives.

Monitoring for invasive species will not be cost shared by the USACE, but will be performed by existing efforts related to invasive plants and routine operation and maintenance activities.

Within the future tidal marsh areas, this category of proposed cost-shared adaptive management would involve spot control for *Spartina* hybrids whose propagules may enter the project area from the bay through the natural sedimentation that will establish this type of habitat. These spot-control activities will address the possibility that the proposed project will contribute to potential area of infestation of a bay-wide eradication effort (Invasive *Spartina* Project).

Within the future transition zones, the cost-shared adaptive management would address invasive *Lepidium*. The transition areas are more prone to invasion because *Lepidium* thrives in areas of physical disturbance. The transition areas would be a physically disturbed area because they would be constructed by moving large volumes of soil.

Table 7. Invasive and Nuisance Plants

Restoration Target Category	Potential Management Action	Type*	Cost Estimate
Invasive and Nuisance Plants	• Control invasive <i>Spartina</i> in future restored tidal marsh	M	\$ 250,000
Invasive and Nuisance Plants	• Control invasive <i>Lepidium</i> in transition zone	M	\$ 900,000
	SUBTOTAL Option		\$ 1,150,000
	27% Contingency		\$ 310,500
	TOTAL (First Cost Oct 2014)		\$ 1,460,500

5.3 Project Close Out

Closeout of the project would occur after the period of cost-shared monitoring and adaptive management. Additional monitoring and adaptive management needed to determine when the project has successfully met its objectives will be conducted by the non-Federal sponsor as part of the operation and maintenance project phase. The project will be determined a success if the restoration targets (Table 2. Monitoring topics, targets, and metrics associated with ecosystem restoration objectives) have been met to the satisfaction of the USACE South Pacific Division Commander. The Division Commander will take into account the recommendations of the San Francisco District Commander and AMT, who will consult with the Executive Leadership Group, South Bay Salt Pond Restoration Project Stakeholder Forum and Science Program, Federal and State resource agencies, and others as appropriate.

Cost-shared monitoring is proposed for a period ten years following each phase of pond breaching. Monitoring beyond this ten-year period will be funded solely by the non-Federal sponsor. Conversely, if the restoration targets are met before the end of the ten-year period, monitoring may be discontinued.

6. Costs for Implementation of Monitoring and Adaptive Management

Cost-shared monitoring and adaptive management actions by the USACE will be limited to actions conducted within the project footprint that are associated with meeting the project's ecosystem restoration objectives, and will not extend beyond 10 years after construction.

The costs for cost-shared monitoring and adaptive management are summarized in Table 8 (Monitoring and Adaptive Management Cost Summary Table). Detailed cost estimates are described in the following sections. The total estimated cost for monitoring and adaptive management for the Shoreline Study, including a 27% contingency, is \$8.7 million (First Cost October 2014 price level).

The individual cost elements are approximate and are intended to provide a reasonable basis for budgeting potential costs. Because uncertainties remain in the project elements, monitoring, and adaptive management actions, the cost estimates provided in this report will need to be refined before these actions are implemented.

6.1 Costs for Implementation of Monitoring

Table 3 reports the cost estimates for Shoreline Study monitoring. The costs are based on the frequency of monitoring and the amount of monitoring. All costs assume the monitoring plan is executed in full. The total estimated cost for Shoreline Study monitoring, including a 27% contingency, is \$968,000 (First Cost October 2014 price level).

Many of the monitoring and assessment costs are estimated based on previously-estimated costs for the SBSP Restoration Project AMMP (Trulio et al 2007). The SBSP Restoration Project costs are scaled based on relative project areas. This assumes that costs can be estimated on a per-acre basis and reapplied for different regions in the South Bay.

The Shoreline Study's estimated share of monitoring and adaptive management costs is 18% of the combined Shoreline Study and SBSP Restoration Project costs. This calculation is based on the ratio of the Shoreline Study area to the combined Shoreline Study and South Bay Salt Pond area (2,891 acres/15,926 acres). Monitoring costs for the Shoreline Study would likely be higher if monitoring and adaptive management for the Shoreline Study were not coordinated with the SBSP Restoration Project.

6.2 Costs for Implementation of Adaptive Management

The costs for adaptive management are organized into the three adaptive management action categories. The costs of as-needed assessments, construction, and phasing, operations, and maintenance are reported in Table 5, Table 6, and Table 8, respectively. The construction cost estimates were provided in part by USACE. Many of the cost estimates were derived from other South Bay pond restoration projects. The total estimated cost for Shoreline Study adaptive management, including a 27% contingency, is \$6,189,000 (First Cost October 2014 price level) for Ponds A9 - A15 and A18, with the potential construction actions contributing approximately three fourths of the costs. This total cost assumes that all adaptive management actions are implemented and likely overestimates total

costs. The relatively significant cost of adaptive management compared to initial construction of ecosystem restoration features is associated with the potential need to mobilize and demobilize for additional construction.

For management triggers where multiple adaptive management actions may be considered and only one implemented, we estimated costs for one representative action. The actual action selected during decision-making may not be the one assumed in the cost estimate and costs may differ. Total costs, however, are expected to be equal to or lower than the costs estimated here.

Table 8. Monitoring and Adaptive Management Cost Summary Table

Restoration Target Category	Monitoring	Adaptive Management			Adaptive Management Total	Total Cost
		Assessment	Construction	Invasive and Nuisance Plants		
Sedimentation Inside the Ponds	\$600,000	\$4,500	\$3,680,000		\$3,684,500	\$4,284,500
Restored Tidal Marsh Habitat (Inside the Ponds)	\$108,000	\$9,000			\$9,000	\$117,000
CA Clapper Rail	\$0				\$0	\$0
Salt Marsh Harvest Mouse	\$0				\$0	\$0
Invasive and Nuisance Plants		\$4,500		\$1,150,000	\$1,154,500	\$1,154,500
Upland transition zones	\$54,000		\$25,000		\$25,000	\$79,000
Subtotal for Monitoring & Adaptive Management	\$762,000	\$18,000	\$3,705,000	\$1,150,000	\$4,873,000	\$5,635,000
Overhead for regular assessments, meetings, data management (\$75K/year)						\$1,500,000
TOTAL (Including 27% contingency) (First Cost Oct 2014)	\$967,740	\$22,860	\$4,705,350	\$1,460,500	\$6,188,710	\$8,656,450

Note: Adaptive Management column includes assessments triggered by monitoring results, construction, and invasive and nuisance plant costs.

References

- EDAW, Philip Williams and Associates, Ltd., H.T. Harvey and Associates, Brown and Caldwell, and Geomatrix (2007). South Bay Salt Pond Restoration Project Final Environmental Impact Statement/Report. Prepared for U.S. Fish and Wildlife Service and California Department of Fish and Game.
- Trulio, L., D. Clark, S. Ritchie, A. Hutzal, and the Science Team (2007). South Bay Salt Pond Restoration Project Administrative Draft Adaptive Management Plan. November 14, 2007.
- U.S. Army Corps of Engineers (USACE) (2009). Implementation Guidance for Section 2039 of the Water Resources Development Act of 2007(WRDA 2007) – Monitoring Ecosystem Restoration, CECW-PB. Washington D.C., August 31, 2009.

**Attachment C:
Landward Levee Alignment
East of Artesian Slough Memo**

**South San Francisco Bay
Shoreline Project**

**City of San Jose
Santa Clara County**

December 2017

San Francisco Bay Regional Water Quality Control Board

TO: South Bay Shoreline Protection Project Team (internal)

FROM: Christina Toms
Senior Environmental Scientist (Specialist)
PLANNING DIVISION

DATE: June 8, 2017

SUBJECT: South Bay Shoreline Protection Project: Justification for landward levee alignment

The South Bay Shoreline Protection Project (Project) is a joint Flood Risk Management (FRM)/Ecosystem Restoration (ER) effort between the US Army Corps of Engineers (Corps), California Coastal Conservancy (Conservancy), and Santa Clara Valley Water District (District). The purpose of this memo is to briefly memorialize the Water Board's reasons for preferring a landward levee alignment (Figure 1) east of Artesian Slough to the Locally Preferred Plan (Figure 2) proposed in the US Army Corps of Engineers' 2015 Final Interim Feasibility Study/EIS/EIR.

1. Smaller Earthwork Volumes

The LPP proposes to build the FRM levee east of Artesian Slough along the centerline of the present Pond A18 levee. The precise bathymetry of Pond A18 is not known, but bottom elevations appear to range between +2 and +3 ft NAVD. The Pond A18 levee is un-engineered, has crest elevations largely below +12 ft NAVD (Figures 3 and 4), and is located in an area with Bay Mud depths of up to 18 ft (see geotechnical appendix to the USACE report). To compensate for the likely settlement that would occur along much of the FRM levee in this area, the Corps proposes to build Reach 4 to an as-built elevation of +19.7 ft NAVD (Reach 5 would be built to +15.2 ft NAVD – the design levee crest – due to negligible local depths of Bay Mud). Figure 5 displays a cross-section of the FRM levee design on top of a cross-section of the existing Pond A18 berm. The Corps report describes a fill volume of approximately **1.55M cy** to construct Reaches 4 and 5; of this volume, approximately 1.2M cy would have to be imported from off-site (Table 1). The levee fill volume calculation assumes a base elevation of 0 ft NAVD, meaning below-grade foundation soils would have to be excavated and treated/compacted to be compatible with FRM levee specs.

The landward levee alignment moves the FRM levee centerline inland where it can capture existing high ground around the Zanker Landfill, the un-engineered berms that separate the San Jose-Santa Clara WWTP's inactive biosolids ponds, and the engineered levee along the active sludge ponds' western boundary (Figures 3 and 4). Of the levee alignment's four segments east of Artesian Slough (Zanker Landfill, Inactive Sludge Ponds, Active Biosolid Ponds Segment 1, and Active Biosolid Ponds Segment 3), only the Inactive Biosolid Ponds segment would require a full core FRM levee (3H:1V side slopes, 16 ft crest width). The Zanker and Active Biosolid Pond segments would likely only require "veneer" treatments to augment existing side slopes, which would ultimately be buried under the 30H:1V ecotone (for example, Figure 6 shows just

such a treatment for the Zanker Landfill). In addition, the negligible depth of Bay Mud deposits beneath most of the landward alignment means that only the portion near the Zanker Landfill would likely have to overbuild, and then only to approximately +16.7 ft NAVD. As a result, the landward levee alignment would likely require less fill volume to construct. Using the Corps' assumption of a levee/ecotone base at 0 ft NAVD, we estimate the landward levee would require roughly **1.45M cy** of material, only 110K cy less than the LPP (Table A-1). However, the alignment's location farther inland likely means that such deep excavation is likely not necessary. Applying conservative assumptions about local topography (City mitigation marsh at +2 ft NAVD, inactive biosolid ponds graded down to +5 ft NAVD, and the interior of Pond A18 at +3 ft NAVD) to the levee fill volume calculation results in an estimate of **895K cy** for the entire levee/ecotone. The ultimate volume necessary for levee construction will likely fall somewhere between these two estimates, and be considerably less than the LPP volume. The landward levee alignment's smaller volumes will likely result in a project that is cheaper and easier to build.

2. Volume, Availability, and Proximity of Inactive Sludge Pond Material

As mentioned previously, construction of the LPP levee and ecotone would require the import of over a million cy of material from off-site locations. This material would have to be trucked to the site, likely stockpiled, and managed until it could be used for construction. The volumes and timing of available material are uncertain due to the variety of projects in the SF Bay Area that require clean fill, particularly other upcoming FRM/ER projects such as Phase 2 of the South Bay Salt Ponds and the SAFER Bay project.

The footprint of inactive biosolid ponds that would be underneath and bayward of the landward levee alignment is approximately 95 acres. This area has an average elevation of +7.7 ft NAVD, slightly above local MHHW of +7.6 ft NAVD; low cordgrass marsh in the area begins to establish at roughly +4.3 ft NAVD (ESA PWA 2012). There is therefore considerable "elevation capitol" within the 95-acre pond footprint to provide material for construction of the ecotone, while still being able to rapidly develop tidal wetland habitats post-restoration. Table A-1 displays the volume of soil available in the inactive biosolid ponds and biosolid piles above a range of elevations.¹ For example, if the ponds and piles were excavated down to an elevation of +5 ft NAVD, they would provide over half a million cy of material for ecotone construction. A likely similar amount of material would be available landward of the levee, in the inactive sludge ponds between Zanker Landfill and the active sludge ponds. Since the inactive ponds are immediately adjacent to the levee/ecotone footprint, material from them would not require extensive trucking or handling to get into place, lowering potential GHG emissions from construction.

Use of inactive sludge pond material provides a "win-win" for the project: it provides a nearby source of construction material (likely making construction quicker and cheaper), and gives the City of San Jose (City) a mechanism to efficiently close its legacy biosolid ponds. The Water Board's practice for other similar properties is to require remedial actions to permanently close sites with contaminants, such as the inactive biosolid ponds, in a manner that will be protective

¹ Table A-1 separates the volumes of the sludge piles from the pond beds/berms because the pile material has slightly elevated levels of cadmium, and should be buried beneath the surface of the ecotone. Preliminary review of inactive sludge pond geotechnical data by Groundwater Protection Division chief Terry Seward indicates that the bed/berm material is largely suitable for ecotone construction. Note that the physical and chemical properties of the legacy biosolids are considerably different from fresher biosolids due to extensive exposure to time and sunlight; this proposal is not meant to address the feasibility of utilizing younger biosolids as a wetland construction medium.

of human health and the environment. This would potentially make it easier for the City to utilize this land consistent with its proposed Master Plan.

3. Elimination of “No Net Loss” as an Obstacle to Permitting

A June 2015 submittal from the Corps to the Water Board indicated that construction of the Project overall (not just Reaches 4 and 5) would require filling of 137.6 acres of wetlands and waters of the State, and would restore 54.7 acres of wetlands along the ecotones of Ponds A12 and A18 as well as the lowered levees around Pond A18. This results in a net loss of 82.9 acres of wetlands and waters. In 2016, the Corps updated this assessment, and calculated a net loss of 101.4 ac from construction of the overall Project. With high rates of sea level rise (estuarine transgression over the ecotone), the Corps estimated that this net loss would shrink to 74.1 acres. In the long term, of course, the Project also facilitates the tidal restoration of 2,900 acres of salt ponds (A9-A15, A18).

Most of the wetlands and waters that would be filled are isolated, non-tidal wetlands, while the restored wetlands would be tidal wetlands within a recovering regional tidal wetland complex. The Corps has argued that the restored wetlands would have comparatively greater habitat values than most of the existing wetlands that would be filled, and they are correct. Nonetheless, the Water Board’s historic interpretation and application of the “no net loss” policy makes it difficult to reconcile the certain short-term loss of wetlands and waters with the uncertain long-term recovery of tidal wetland habitats. This is particularly challenging given (1) short-term (Phase 1, A12 and A18) wetland restoration would largely be limited to narrow strips along ecotones and lowered levees, not broad expanses of dendritic tidal marsh plains (Figure 2)², and (2) the long-term development of tidal wetland habitats within salt ponds subsided below tidal vegetation elevation thresholds is largely dependent on local sediment supply, sediment accretion rates, and SLR rates, all of which are temporally/spatially variable and challenging to predict (see ESA PWA 2012).

The landward levee alignment effectively eliminates this obstacle by facilitating the short-term restoration of over 70 acres of vegetated marsh within the footprint of the bayward former inactive sludge ponds. These areas could be graded to an appropriate elevation such that as soon as Pond A18 was breached, they would have sufficient “elevation capitol” to rapidly establish and develop vegetated marsh habitats much sooner than lower, subsided areas within the Pond A18 interior. The landward levee alignment also facilitates the enhancement of approximately 66 acres of existing mitigation marshes (managed wetlands) north and west of the Zanker landfill. These mitigation wetlands were developed in the 1980s, when the field of tidal wetland restoration was in its infancy, and are not providing the types of fully functional tidal habitats they were meant to provide. The LPP isolates these wetlands between the FRM levee and the Zanker landfill, further degrading their habitat values; in the long term SLR would gradually reduce opportunities for the mitigation marshes (which sit low in the tidal frame at about +2 to +4 ft NAVD) to drain at low tide. The landward alignment would instead allow these marshes to be directly breached to Pond A18 so that they may develop as fully functional tidal wetlands.³

² Broad, dendritic marsh plains are much more effective than narrow fringing wetlands at supporting the beneficial uses targeted by tidal wetland restoration, particularly the provision of habitat for rare and endangered species.

³ This transitional period would likely result in a temporary shift from pickleweed-dominated to cordgrass-dominated habitats; the transition could be executed gradually to minimize impacts to listed species.

The ecological functions and values of the newly restored (in the inactive sludge ponds) and enhanced (in the mitigation marshes) wetlands would be further improved by lowering the Pond A18 “stairstep” levee to marsh elevations between MHHW and EHW (Figure 1). This way, the levee can provide critical high tide refugia that is *internal* to the Pond A18/former inactive sludge pond complex, as opposed to the high tide refugia along the outer fringes of the marsh on the ecotone. Internal high tide refugia is critical for listed species such as Ridgway rail and salt marsh harvest mouse that have small home ranges that may be far from terrestrial ecotones. The lowering of this levee (and the rest of the Pond A18 levee) would provide additional upland-to-wetland acreage for the Project’s accounting.

Finally, construction of the landward FRM levee and ecotone would require the placement of fill in jurisdictional wetlands within inactive biosolid ponds and the mitigation marshes. The footprint of impact from these fill activities has not yet been calculated, but it would likely be offset by the restoration and enhancement activities described above. Table 1 below presents the approximate differences in post-project habitat types between the landward levee alignment and the LPP. Note how the landward levee alignment restores significantly more vegetated wetland areas (highlighted in green) than the LPP.

Table 1. Estimated Post-Project Habitats for the Landward Levee Alignment and the LPP.


Habitat Type	Acreages – Landward	Acreages – LPP
Upland	84	85
High Marsh – Pickleweed	24	4
High Marsh – Cordgrass	77	13
Low Marsh – Cordgrass	83	17
High Intertidal Mudflat	386	355
Mid-High Intertidal Mudflat	337	321
Mid-Low Intertidal Mudflat	30	31
Low Intertidal Mudflat	25	16
Shallow Subtidal B	27	19
Shallow Subtidal A	>1	>1
Managed Wetlands	N/A	90

4. Police Bomb Disposal Range

One of the legacy sludge ponds south of the proposed landward levee alignment is used on a non-continual basis (a few times a month) by local police departments for bomb disposal, target practice, and other related uses. The Project proposes constructing a new portion of the Bay Trail on top of the levee. In the case of the landward alignment, a short (~300 ft) portion of the new trail would therefore be located adjacent to this pond. To avoid conflicts with police activities, the trail in this area could be subject to temporary closures (requiring gates, and someone to open/close them), or routed instead farther out (bayward) along the ecotone levee, possibly with a boardwalk. The proximity of the disposal range to the levee needs to be evaluated further but should not preclude the use of this alignment.

5. Conclusion

The landward levee alignment eliminates a major obstacle to South Bay Shoreline Protection Project permitting, would likely require less dirt to build and be cheaper and easier to construct, and provides an alternative mechanism for the City of San Jose to address their legacy biosolid ponds.




0 750 1,500
Feet

1:18,000; 1 in = 1,500 ft at letter size

Figure 1
South Bay Shoreline Protection Project
Landward Levee Alignment:
Projected Post-Restoration Habitats





0 750 1,500
Feet

1:18,000; 1 in = 1,500 ft at letter size

Figure 2
South Bay Shoreline Protection Project
LPP Levee Alignment:
Projected Post-Restoration Habitats







Figure 3
South Bay Shoreline Protection Project
Local Topography + Levee Alignments:
East of Artesian Slough



Figure 4: Levee Alignments: Profile Elevations




Figure 5: Representative Cross-Section + LPP: Pond A18 Levee




Figure 6: Representative Cross-Section +LPP: Zanker 2




Figure 7: Representative Cross-Section + LPP: Inactive Sludge Ponds




Figure 8: Representative Cross-Section+ LPP: Active Sludge Ponds - Segment 1




Figure 9: Representative Cross-Section + LPP: Active Sludge Ponds - Segment 3




Table A-1: Levee Cut and Fill Volumes

Levee Fill Volumes (LPP, USACE 2015)

LPP Levee Reach	Project Station		Distance (ft)	Fill (cy)			Subtotal Fill (cy)
	Begin	End		Levee Core	50-ft Bench	Ecotone	
4	94+75	150+00	5,525	312,566	92,083	477,102	881,751
5	150+00	197+75	4,775	174,079	79,583	412,337	665,999
							1,547,750 TOTAL

Levee Fill Volumes (Landward Alignment, Water Board 2017)

Assumptions re: existing topography (mitigation marsh edge at +2 ft NAVD, inactive sludge ponds at +5 ft NAVD, Pond A18 at +3 ft NAVD)

Levee Reach	Distance (ft)	Design Elevations (ft NAVD)		Fill (cy/lf)		Subtotal Fill (cy)		
		Levee Crest	Bayward Ground Surface	Levee Core	Ecotone	Levee Core	Ecotone	
Zanker	4,099	16.7	2	9	108	35,707	442,876	
Inactive Sludge	2,802	15.2	5	18	52	49,328	145,760	
Active Sludge - 1	2,419	15.2	5	0	48	0	116,515	
Active Sludge - 3	1,509	15.2	3	0	69	0	103,981	
							85,034	809,133
								894,167 TOTAL

Assumptions consistent w/ USACE approach (base elevation of 0 ft NAVD)

Levee Reach	Distance (ft)	Design Elevations (ft NAVD)		Fill (cy/lf)		Subtotal Fill (cy)		
		Levee Crest	Bayward Ground Surface	Levee Core	Ecotone	Levee Core	Ecotone	
Zanker	4,099	16.7	0	10	139	40,565	571,585	
Inactive Sludge	2,802	15.2	0	35	116	97,169	323,687	
Active Sludge - 1	2,419	15.2	0	0	107	0	258,743	
Active Sludge - 3	1,509	15.2	0	0	107	0	161,407	
							137,734	1,315,423
								1,453,157 TOTAL

Available Cut Volumes from Pond A18 Levee (LPP, USACE 2015)

LPP Levee Reach	Project Station		Distance (ft)	Cut (cy)		Subtotal Cut (cy)
	Begin	End		Degrade	Inspection Trench	
4	94+75	150+00	5,525	154,817	9,822	164,639
5	150+00	197+75	4,775	164,712	8,489	173,201
						337,840 TOTAL

Available Cut Volumes from Inactive Sludge Ponds (Landward Alignment, Water Board 2017)

Location	Volume (cy) Above Elevation (ft NAVD)							
	0	1	2	3	4	5	6	7
Inactive Sludge Ponds	942,511	818,961	696,174	582,069	489,277	410,450	340,530	283,819
Old Sludge Piles	209,011	185,596	162,182	138,830	115,876	94,366	75,040	58,134
TOTALS	1,151,521	1,004,557	858,355	720,899	605,153	504,816	415,570	341,953

Note: This is only for the ponds underneath and bayward of the proposed levee/ecotone. Additional material could be made available from inactive ponds landward of the levee.

**Attachment D:
Phase I, Reach 1 60 Percent Design Plans**

Phase I, Reach I 60 Percent Design Plans can be found at the following link:

https://www.waterboards.ca.gov/sanfranciscobay/board_info/agendas/2017/December/SouthBayShoreline/TO_Attachment_D_SSFBSPP_813084.pdf

**South San Francisco Bay
Shoreline Project**

**City of San Jose
Santa Clara County**

December 2017

**Appendix B:
Comments on Tentative Order**

**401 Water Quality Certification and
Waste Discharge Requirements**

**South San Francisco Bay
Shoreline Project**

**City of San Jose
Santa Clara County**

December 2017



November 15, 2017

Mr. Bruce H. Wolfe
Executive Officer
San Francisco Bay Regional Water Quality Control Board
1550 Clay St, 15th Floor
Oakland CA 94612

Dear Mr. Wolfe:

Thank you for this opportunity to comment on the draft Tentative Order for the South San Francisco Bay Shoreline Project. We appreciate the extensive amount of time that RWQCB staff have devoted to the Shoreline Project and that they have accommodated the construction schedule of the Corps process by drafting the Order within a very short timeframe.

This is a large and complex project has multiple phases and the RWQCB staff have sought to streamline the permitting process by providing a means to approve subsequent phases in the Tentative Order. The Conservancy appreciates this efficiency. However, the Conservancy also has concerns about the ramifications of some of the provisions of Tentative Order and how it will impact future project implementation. The key concerns are discussed more fully below. Specific comments on language in the Tentative Order are in the attached table of comments.

Voluntary Ecosystem Restoration vs. Mitigation

Most of our comments have to do with a misunderstanding of the purpose of the project. The Tentative Order initially correctly describes the project (pp. 2-3) as a multi-benefit project that seeks to restore former salt evaporation ponds, protect adjacent communities from flooding, and provide recreational opportunities. However, on p. 4, there is a different interpretation of the project purposes: "Phase I is expect to result in Project impacts and the ecosystem restoration work in Phases I, II, and III is intended to provide mitigation for those impacts." This description sets the stage for requirements that are extremely problematic.

The Conservancy would like to restate that the restoration options were selected for their own value in order to meet the project's ecosystem restoration goals. The Conservancy is involved in the Shoreline Project because it will implement the goals of the South Bay Salt Pond Restoration Project in an area where restoration is impossible without flood protection infrastructure.

1515 Clay Street, 10th Floor
Oakland, California 94612-1401
510-286-1015 Fax: 510-286-0470

CONSERVANCY
CL-1

CONSERVANCY
CL-1
(CONT.)

This project is not an infrastructure project with some mitigation elements – as is demonstrated by the vast amount of restoration proposed, much more than would be required to offset impacts. Furthermore, since the fill impacts from the flood protection measures (132.2 acres permanent fill or 8.76 acres net fill) are relatively minor when compared to the tremendous benefits from just the first phase of proposed restoration (restoring 1120 acres of existing ponds to tidal action), the Conservancy would expect that this project is self-mitigating by the end of Phase I. However, the Conservancy proposes to continue to restore ponds in Phases II and III, adding up to an additional 1780 acres of tidal restoration (pursuant to the adaptive management framework), because that is the goal of the project and the purpose of our agency, not to secure unnecessary, additional mitigation.

CONSERVANCY
CL-2

Infeasibility of Mitigation

The Tentative Order currently states that if the restoration proposed in Phase II (900 acres) and Phase III (880 acres) is not implemented, then the project must provide compensatory mitigation elsewhere.

This requirement could adversely impact the ability of the Project to implement its Monitoring and Adaptive Management Plan (MAMP). The MAMP outlines project risks, a method for evaluating results, and a decision-making process to address or correct problems that arise while implementing the project. As described on p. 18 of the Tentative Order, the MAMP states that one of the potential ways to respond to adverse results to is to delay or halt pond breaching. (Indeed, having this ability to delay or stop the project is a primary reason that the restoration will be phased.)

The grounds upon which the Adaptive Management team might recommend that restoration be delayed or stopped are the same reasons that would make mitigation impossible elsewhere in San Francisco Bay. For example, if lack of sediment causes newly breached ponds to erode a significant amount of mudflat habitat, which millions of migratory shorebirds depend on, then pond breaching would likely need to stop in all of San Francisco Bay. Alternatively, if there is a Bay wide decline in pond-specialist species (e.g. grebes and phalaropes), then pond conversion in all of San Francisco Bay would need to be slowed or halted.

Obviously, the Shoreline Project expects to be successful; not implementing the wetland restoration proposed in Phase II and III is an extreme scenario. However, we are entering an era of greater uncertainty. The Conservancy and the other Project proponents have created a process through the MAMP to address uncertainty as much as possible. However, if the Project proponents are not able to implement all of the proposed restoration, there are not going to be alternatives at this scale available elsewhere.

Since mitigation is infeasible, the current language in the Tentative Order could create a scenario where the project will have no choice but to restore all the ponds, regardless of the

Mr. Bruce H. Wolfe
November 15, 2017
Page 3

input from the Adaptive Management monitoring and applied studies, undermining this carefully crafted program. For these reasons, the Conservancy requests changes to the Tentative Order language in the attached comments.

RWQCB and Adaptive Management Decision-Making


The project fully intends to communicate adaptive management decisions to our stakeholders and including the RWQCB. However, requiring the RWQCB's Executive Director approval for not implementing the restoration in Phase II and III essentially gives Executive Director "veto power" over the decision-making process outlined in the MAMP. The Adaptive Management decision-makers have to consider a broad suite of issues that include, but are not limited to, enhancing the resources overseen by the RWQCB. Making an adaptive management action subject to RWQCB approval (except to the extent that a proposed action requires a permit) would give the RWQCB a role not shared by any other stakeholder.

The Conservancy suggests an alternative approach in comment number nine. We propose that the Order should describe a process (e.g. the Technical Advisory Committee) for involving and informing RWQCB staff in the Adaptive Management decision-making process. The Order should clarify that the RWQCB shares the understanding of the Shoreline Project that there may be valid reasons that the Adaptive Management decision-makers recommend halting or delaying pond restoration and that the Project would not be held responsible for natural processes beyond anyone's control.

— There are also additional concerns discussed in the attached table of comments.

We appreciate that the RWQCB's flexible approach in crafting an Order for a lengthy, complex project with different agencies and future phases. We hope that some of the requirements can be modified to better accommodate the realities of implementing an ambitious ecosystem restoration and flood protection project in a new era of uncertainty with rising seas and climate change.

Sincerely,



Amy Hutzel
Deputy Executive Officer

Amy Hutzel
Deputy Executive Officer

CONSERVANCY
CL-2
(CONT.)

CONSERVANCY
CL-3

COMMENTS
1-20



United States Department of the Interior



FISH AND WILDLIFE SERVICE

San Francisco Bay National Wildlife Refuge Complex
1 Marshlands Road
Fremont, California 94555

November 15, 2017

Mr. Bruce H. Wolfe
Executive Officer
San Francisco Bay Regional Water Quality Control Board
1550 Clay St, 15th Floor
Oakland CA 94612

Dear Mr. Wolfe:

Thank you for this opportunity to provide comments on the draft Tentative Order for the South San Francisco Bay Shoreline Project (Project). A portion of the Project will be constructed on lands owned by the U.S. Fish and Wildlife Service and managed as part of the Don Edwards San Francisco Bay National Wildlife Refuge (Refuge). As a project team member, I want to express our appreciation for the work of the Regional Water Quality Control Board (RWQCB) staff. Your staff have contributed a considerable amount of time and effort working collaboratively and proactively with our project team in meeting RWQCB requirements while accommodating the federal processes and schedules that U.S. Army Corp of Engineers (USACE) must follow for their Congressionally approved projects.

We all share the common goal and sense of urgency for achieving flood risk reduction for a highly vulnerable section of shoreline in South San Francisco Bay through the construction of a flood risk management levee integrated with ecosystem restoration and public recreation improvements. The draft Order allows for Phase I of the Project to be initiated in the near term while charting a framework for future project phases to be implemented in sequence based upon adaptive management. The Refuge shares many of the same comments as the USACE and non-federal sponsors provided on the draft Order. As the federal landowner for the portion of the levee to be constructed along Refuge Ponds A12-13 and A16 and the restoration of Refuge Ponds A9-15, I want to reiterate the following comments for your consideration.

COMMENT 21 [The draft Order initially correctly describes the Project (pp. 2-3) as a multi-benefit project that seeks to restore former salt evaporation ponds, protect adjacent communities from flooding, and provide recreational opportunities. However, on p. 4, there is a different interpretation of the project purpose: "Phase I is expected to result in Project impacts and the ecosystem restoration work in Phases I, II, and III is intended to provide mitigation for those impacts." The restoration components of the project were not presented under NEPA/CEQA or the federal Clean Water Act as being mitigation for project impacts; therefore that interpretation is incorrect and should be revised appropriately. It is our position that the Project as described in the NEPA/CEQA document does not need nor require mitigation.

COMMENT 22 [The Refuge is involved in this Project because it will implement a portion of the South Bay Salt Pond Restoration Project, consistent with the Refuge's Comprehensive Conservation Plan that fulfills the purposes for which the Refuge was established for the protection and restoration of habitat for fish and wildlife, including federally listed species such as the California Ridgway's rail and salt marsh harvest mouse. The wetland restoration would be impossible without the construction of flood risk management infrastructure, and in turn, the flood risk management levee as integrated with the proposed wetland restoration features will be more resilient and sustainable in the face of climate change. The project description fully describes the considerable amount of restoration proposed, an amount in our opinion much higher than would be required as mitigation to offset impacts. For example, during Phase I the net fill impacts from the flood protection measures (8.67 acres) are minor when compared to the tremendous benefits from just Phase I of proposed restoration (restoring 1120 acres of existing ponds to tidal action).

COMMENT
22
(CONT.)

In addition, as the Project continues to restore additional ponds in Phases II and III, it will be adding up to an additional 1780 acres of tidal restoration, as described in the project description.

COMMENT
23

The draft Order further states that if the restoration proposed in Phase II (900 acres) and Phase III (880 acres) is not implemented, then the Project must provide compensatory mitigation (CNMP) elsewhere. This requirement as stated in an order could adversely impact the ability of the Project to implement the USACE's approved Monitoring and Adaptive Management Plan (MAMP). The MAMP outlines project risks, a method for evaluating results, and a decision-making process to address or correct problems that arise while implementing the Project. As described on p. 18 of the draft Order, the MAMP states that one of the potential ways to respond to adverse results is to delay or halt pond breaching so that we can apply the best available science, address uncertainty, and inform future phases in an adaptive management framework. We respectfully request and concur with the USACE that references to CMMP be removed from the draft Order accordingly.

COMMENT
24

We all certainly expect the Shoreline Project to be successful in achieving the multi-benefits of flood risk reduction, ecosystem restoration, and recreation opportunities. The MAMP was prepared to address uncertainty as much as possible, and indeed the South Bay Salt Pond Restoration Project has a proven track record of using adaptive management as described in the MAMP and provides a mechanism through technical working groups and stakeholder forums to keep RWQCB staff updated and part of the decision-making process should uncertainties arise throughout the project. We recommend that the Order describe a process for how RWQCB staff wish to be engaged and informed through the USACE's adaptive management decision-making process. The Order should clarify that the RWQCB shares a similar concern of the Shoreline Project that there may be valid reasons that the project team may recommend halting or delaying pond restoration elements due to natural processes beyond anyone's control in furtherance of the Project as described.

Again, thank you for your staff's willingness and flexibility in working with the project team to craft the Tentative Order for this project. We recognize that such a lengthy and complex project with multiple phases means that there are additional details to be provided on future reaches and project phases. We appreciate the opportunity to seek the Board's approval of an order that allows Phase I to move forward with construction and restoration as soon as feasible as we continue to plan together for the other reaches with RWQCB staff.

Sincerely,



Anne Morkill
Refuge Complex Manager
San Francisco Bay National Wildlife Refuge Complex

CC: LTC David A. Kaulfers, U.S. Army Corp of Engineers
Rechelle Blank, Santa Clara Valley Water District
Brenda Buxton, California Coastal Conservancy
John Bourgeois, South Bay Salt Pond Restoration Project

November 15, 2017

Tahsa Sturgis
San Francisco Regional Water Quality Control Board
1515 Clay Street, Suite 1400
Oakland, CA 94612

Subject: Comment Letter – South Bay Shoreline Project Order Comments

Dear Ms. Sturgis:

The Santa Clara Valley Water District (District) appreciates the opportunity to comment on the tentative "Water Quality Certification and Waste Discharge Requirements for: U.S. Army Corps of Engineers, South San Francisco Bay Shoreline Project, Santa Clara County" (Tentative Order) from the San Francisco Bay Regional Water Quality Control Board (Regional Board). The South San Francisco Bay Shoreline Project (Project) is an important multi-purpose project whose primary purposes are to restore up to 2,900 acres of diked, former salt ponds to tidal marsh, and to provide protection from tidal flooding and sea-level rise to homes, businesses, and infrastructure in Santa Clara County. Restoring tidal action to these former salt ponds, while providing long-term flood-protection, is good for the environment and people, and it fulfills an important policy of the San Francisco Bay Plan.

The District is partnering on this \$177 million Project with the U.S. Army Corps of Engineers (USACE), the California Coastal Conservancy (Coastal Conservancy), and the U.S. Fish and Wildlife Service. USACE is contributing \$71 million in federal dollars to the Project.

*DISTRICT
CL-1* While the District appreciates that the Tentative Order would approve the Project, the District shares the concerns of USACE and the Coastal Conservancy that the Tentative Order, if adopted, would impose unprecedented, onerous, and unwarranted conditions on a Project the Regional Board should be unreservedly supporting. The fundamental problem with the Tentative Order is that it treats the up-to 2,900 acres of tidal marsh restoration as mere mitigation for 8.76 acres of net fill needed for the flood protection, rather than as a key element of the Project. The tidal marsh restoration is key to the Project, as the Regional Board previously recognized for the South Bay Salt Pond Restoration Project: the main reason why the new flood protection system needs to be built is because the Project will be breaching the salt-pond dikes to create new tidal marsh. Nor is the Tentative Order's proposed mitigation ratio of approximately 330:1 reasonable. The District requests that the Regional Board revise the Tentative Order to incorporate the comments below.

*COMMENTS
25-42* **I. Restoring Tidal Marsh Is Not Proposed as Mitigation and Should Not be Characterized as Mitigation for the Project, As The Regional Board Has Previously Recognized**

The tentative order, in finding 22, treats the 2,900 acres of restored tidal marsh proposed by the Project as mitigation for the project's net fill of 8.76 acres of waters. The Project's tidal marsh restoration is not proposed to be mitigation for the fill; rather, the fill is necessary in large part *because* of the tidal marsh restoration. The fill is being placed on the landside of the restored tidal marsh to construct new flood protection that becomes necessary in large part because the dikes

that currently provide an incidental measure of flood protection have to be breached in order to restore the tidal marsh.

COMMENTS
25-42

The Regional Board has previously—and correctly—recognized, for the South Bay Salt Pond Restoration Project (SBSRP), that tidal marsh restoration is not mitigation for the fill that may be necessary for the restoration. The Regional Board's findings for that project (R2-2008-0078) recognized that restoring tidal marsh should not be viewed as mitigation: finding 96 of the SBSRP order found that "[n]o penalties will be imposed for a failure to achieve the interim and final habitat goals, since this is a restoration (not a mitigation) project", and finding 16 found that "[n]o compensatory mitigation is required for impacts to existing wetlands and waters of the State, since this restoration project will result in many more acres of restored and enhanced habitats than the acres of habitat that are impacted."

Although the Tentative Order, in finding 9, states that it is modeled after SBSRP, it treats the restoration component of this Project very differently than restoration was treated in SBSRP. The Regional Board should be consistent: the Tentative Order should not treat the restoration component of the Project as mitigation for fill, just as the Regional Board treated the fill necessary for the restoration component of SBSRP. No compensatory mitigation should be required here.

II. The Tentative Order Misapplies The No-Net-Loss Policy

The Tentative Order, in findings 32 and 33, cites the California Wetlands Conservation Policy (Executive Order W-59-93), often called the "no-net-loss policy", and the Basin Plan (which incorporates the no-net-loss policy), as the principal basis for requiring 2,900 acres of mitigation for 8.76 acres of net fill here. As described below, the Tentative Order misapplies the no-net-loss policy.

The policy focuses on a programmatic approach to preserving and enhancing wetlands: it requires State agencies to "encourage partnerships to make restoration, landowner incentive programs, and cooperative planning efforts the primary focus of wetlands conservation."¹ The Project is developed through a cooperative partnership between agencies and landowners to restore wetlands and waters. The policy "is not meant to be achieved on a permit-by-permit basis". Yet the Tentative Order tries to apply the policy to this individual permit, without regard to the broader partnership represented by this Project, contrary to the policy's direction that it is to be implemented on a programmatic, rather than permit-by-permit, basis.

The Regional Board should read the no-net-loss policy as encouraging approval of the Project as-is, rather than as requiring conditioning the Project on thousands of acres of mitigation.

III. No Mitigation Should be Required Because The Project Provides Significant Benefits To Beneficial Uses, As The Regional Board Previously Recognized

Water Code section 13263(a) requires waste discharge requirements to implement relevant water quality control plans, and to take into consideration the beneficial uses to be protected. The water quality control plan here—the Basin Plan—incorporates the no-net-loss policy, but, as just discussed, that policy supports approval of the Project as is, rather than with thousands of acres

¹ https://www.waterboards.ca.gov/water_issues/programs/cwa401/docs/wrapp2008/executive_order_w59_93.pdf

of mitigation. Nor does the Tentative Order justify its conditions as necessary to promote beneficial uses: in fact, the Tentative Order recognizes that the Project as-is will provide significant benefits to beneficial uses. No additional mitigation is necessary.

The Tentative Order, in finding 31, lists a number of beneficial uses in the Project area, but the Tentative Order identifies no beneficial uses that will be adversely impacted by the Project. Finding 16 goes on at length, and in great detail, about how the Project as-is is expected to "result in a significant contribution to tidal wetland restoration", providing water quality and associated habitat and vegetation benefits "on a spatially significant scale".

In the SBSRP, the Regional Board recognized that salt pond restoration projects promote beneficial uses and require no compensatory mitigation: in Finding 16 in its order for that project (R2-2008-0078), the Regional Board found that "[n]o compensatory mitigation is required for impacts to existing wetlands and waters of the State, since this restoration project will result in many more acres of restored and enhanced habitats than the acres of habitat that are impacted." Similar benefits would be generated by the Project, and thus the same approach should be used here.

Because the Project as-is significantly promotes beneficial uses, no additional mitigation is required.

IV. A Mitigation Ratio Of 330:1 Is Excessive And Unjustified

Even if mitigation were required for the 8.76 acres of net fill, the Tentative Order would require 2,900 acres of mitigation—a ratio of nearly 330:1. That kind of ratio is unprecedented and unjustified.

Compensatory mitigation requirements must be roughly proportionate to a project's impacts. (*Dolan v. City of Tigard* (1994) 512 U.S. 374, 391.) A 330:1 mitigation ratio, for a project that is largely a restoration project, is also not roughly proportionate to any impacts this project may have.

Requiring a mitigation ration of 330:1, or anything close to that, would set an unfortunate precedent. It would signal that the Regional Board wants to stand in the way of restoration projects by imposing onerous conditions, rather than promoting such projects by blessing them with streamlined approvals. The Regional Board should rethink the Tentative Order's excessive and unjustified mitigation for this Project.

V. If Phases II And III Restoration Are Not Built, No Additional Mitigation Should Be Required

The ecosystem restoration component of the Project will occur in three phases (Phases I, II, and III) of pond breaches to establish tidal connection. The Tentative Order requires all phases of the restoration to be completed, and requires additional mitigation to be proposed for approval if not all phases are implemented (Findings 8, 22). Phase 1 of the restoration is scheduled to be constructed in 2022, and completion of this phase would result in restoration of up to over 1,000 acres of tidal marsh habitat. The design and construction of Phases 2 and 3 restoration will be guided by the Project's Monitoring and Adaptive Management Plan. Phases II and III of the Project are likely to be built, adding many hundreds of acres of restored tidal marsh to the Project. Only

COMMENTS
25-42

in the unlikely event that Phase I causes unavoidable but undesirable outcomes would Phases II and III be reconsidered.

Even if Phase I does not result in all of the restoration benefits predicted, no additional mitigation should be required. Finding 96 of SBSRP (Order No. R2-2008-0078) stated that "No penalties will be imposed for a failure to achieve the interim and final habitat goals, since this is a restoration (not a mitigation) project"; that order instead envisioned a collaborative process to achieve the desired results. A similar approach should be used here.

VI. The District Should Not be Named as A Discharger in the Water Quality Certification or Waste Discharge Requirements

If the Regional Board revises the Tentative Order's current approach of treating the restoration component of this Project as mitigation for the fill necessary for the Project, then the following discussion becomes less important from a practical perspective. Nevertheless, the District is compelled to raise these issues until the Tentative Order is revised to drop its objectionable mitigation conditions.

As the District and USACE have explained to the Regional Board in other contexts, the Regional Board's authority to impose waste discharge requirements is limited to discharges of "waste". (Water Code section 13260(a)(1); see *Lake Madrone Water District* (1989) 209 Cal.App.3d 163 (flushing unwanted sediment accumulated behind dam was a discharge of waste).) The term "waste" is commonly understood as meaning "something discarded 'as worthless or useless.'" (*Waste Management of the Desert v. Palm Springs Recycling Center, Inc.* (1994) 7 Cal.4th 478, 485.) But constructing a beneficial project is not a discharge of something worthless or useless. (See *Tahoe-Sierra Preservation Council, Inc. v. Tahoe Reg'l Planning Agency* (D.NV 1999) 34 F.Supp.2d 1226, 1254 (distinguishing *Lake Madrone* to hold that "building a house" is not a discharge of waste under Porter-Cologne), *rev'd in part on other grounds*, 216 F.3d 764, *aff'd*, 535 U.S. 302.) This Project—restoring tidal marsh and constructing flood protection—is beneficial; it is not a discharge of waste subject to waste discharge requirements.

Nor would Water Code section 13376 authorize the Regional Board to issue a permit to the District for dredge-and-fill discharges. Water Code section 13372(b) unambiguously makes Water Code section 13376 operative "only to discharges for which the state has an approved permit program" under Section 404 of the Clean Water Act. California does not have an approved permit program under Section 404, and thus section 13376 cannot give the Regional Board authority.

Even if this Project were a discharge of waste, the Tentative Order, in finding 4, recognizes that this project will be built on the District's property. Water Code section 13270 precludes issuing waste discharge requirements to one public agency for discharges of waste on that agency's property by another public agency. Because this Project will be constructed by USACE on the District's property, and both are public agencies, Water Code section 13270 prohibits issuing waste discharge requirements for the construction of the Project to the District.

Nor may the Regional Board issue a Section 401 certification to the District. Section 401 applies only to persons who apply for a federal license or permit. (33 U.S.C. 1341(a).) The District has not applied for a federal license or permit, and thus Section 401 does not apply to the District.

COMMENTS
25-42

VII. Feasibility Constraints Of Alternative Levee Alignments Should Be More Clearly Acknowledged

Finding 13 discusses an alternative, more landward, levee alignment east of Artesian Slough for Reaches 4 and 5 that the Tentative Order describes, in finding 21 and elsewhere, as having greater environmental benefits with fewer impacts. The District and its Project partners considered suggestions for alternative alignments in the EIR/EIS process, including the Regional Board's suggestion of the alternative alignment raised in the Tentative Order. The District has considered, and will consider, alternative alignments, though the District is mindful that alternative alignments need to be feasible. Different alternative alignments raise various feasibility constraints, including enduring that any alternative is within the scope of the Project authorized for the USACE by Congress, avoiding interference with the City of San Jose's current plan for the San Jose-Santa Clara Regional Wastewater Facility, maintaining adequate buffers against a nearby San Jose Police Department bomb facility, and achieving consensus among stakeholders for the inclusion of legacy biosolid lagoons on the bayside of the proposed levee.

The District and its Project partners expect to continue assessing whether these constraints can be overcome by the alternative alignment discussed in the Tentative Order, or by some variation of that alternative alignment. While Attachment C to the Tentative Order acknowledges some of these constraints, that appendix and those constraints are not clearly acknowledged in, or incorporated into, the Tentative Order itself. The Tentative Order should more clearly acknowledge that alternative alignments may not be achievable, and the Regional Board should not be linking possible future mitigation requirements to alternatives that may not be achievable.

VIII. Impacts Mitigated To Less-Than-Significant Levels Are Not Under The Regional Board's Jurisdiction

The main impact identified in the Tentative Order—filling of waters of the United States—was analyzed in Section 4.6.5 of the EIR/EIS. The EIR/EIS concluded, in Section 4.6.6, that the fill of waters associated with the Project would have only less-than-significant impacts. Because impacts from fill would be less-than-significant, CEQA does not allow the Regional Board to impose additional mitigation for fill-related impacts.

As for other impacts identified in the EIR/EIS, the Tentative Order, in finding 30, correctly notes that the EIR/EIS found that the mitigation measures proposed in the EIR/EIS “would mitigate all of these impacts to less than significant levels”. The Regional Board does not have authority to second-guess the conclusion of the EIR/EIS that no additional mitigation is necessary for these impacts that will already be mitigated to less-than-significant levels. (See *Ogden Env'tl Serv. v. City of San Diego* (S.D. Cal. 1988) 687 F.Supp. 1436, 1450-1452 (responsible agency does not have authority over impacts mitigated to less-than-significant levels).)

IX. The Technical Advisory Committee (TAC) Is Advisory

Provision B.20 requires the formation of a technical advisory committee (TAC) to assess, review, and suggest adaptive management strategies. The Mitigation and Adaptive Management Plan (MAMP), included as Attachment B to the Tentative Order, in Section 5, already prescribes a process for how decision-making will occur as part of the adaptive management process. While the District does not object to receiving suggestions and advice from the TAC, the ecosystem restoration activities would be undertaken through the MAMP's adaptive management process,

COMMENTS
25-42

and the Tentative Order should make clear that the TAC has no actual decision-making authority in the adaptive management process.

X. No Fees Are Applicable

Finding 50 prescribes fees that the District would be responsible for. But Government Code section 6103(a) exempts the District from having to pay any fees.

XI. Other Technical Comments

Finding 5 states that, after 10 years, the Non-Federal Sponsors will assume the costs of the ponds' operation, maintenance, and management. This finding should be changed to make clear that responsibilities for costs, which will also include costs of operating and maintaining the new flood protection structures, will be allocated pursuant to the Project Partnership Agreement, which has not yet been completed.

Finding 7 states that Alviso has over 2,000 residents and 500 structures. It would be more accurate to state that Alviso has over 2,500 residents and 1,100 structures.

Finding 8 could be read to suggest that the Project is intended to allow the Union Pacific railroad tracks to continue functioning over Artesian Slough. Keeping the railroad functioning has nothing to do with Artesian Slough. The reference to Artesian Slough should be deleted as it relates to the railroad.

Finding 10, among other findings, refers to Reaches 4 and 5 of the FRM levee as being a "proposed conceptual" alignment. That alignment is not conceptual; it is the Congress-authorized alignment. All references to the "proposed conceptual" alignment for Reaches 4 and 5 should be changed to "authorized" alignment.

Finding 10 states that "Where the levee crosses an existing water feature, such as a slough, structures will be installed to allow flow during normal conditions and during flood conditions." As described in the Project EIR, a tide gate closure structure is being designed to be placed across the Artesian Slough to prevent water from overtopping existing levees along the slough during future high-tide events. The tide gate structure will be designed in coordination with the City of San Jose to allow for the city's wastewater treatment plant's discharge during storms. It is expected that the tide gate structure would remain open during normal and flood conditions, but that the opening would be regulated depending on flow conditions. The District suggests that the word "allow" be revised to "regulate".

Finding 10 discusses planting or seeding of marsh vegetation at the toe of the levee following construction. Generally, in the San Francisco Bay it is not necessary to seed marsh plain species because tidal waters have sufficient seed source. Active planting and seeding of marsh vegetation will be done as an adaptive management measure only as necessary.

Finding 10 (in the section on "Ponds A12 and A18 Tidal Restoration") gets the descriptions of Ponds A12 and A18 reversed. The finding currently suggests that the bottom elevation of Pond A18 is lower than the bottom elevation of Pond A12. In fact, as noted in Section 3.8.3.2 of the

25-42
COMMENTS

Tahsa Sturgis
Page 7
November 15, 2017

EIR/EIS, Pond A12 has the lowest bottom elevation of all the ponds. The Tentative Order should reverse the descriptions of Ponds A12 and A18.

Finding 30 incorrectly identifies the CEQA lead agency as the California State Coastal Conservancy. The Tentative Order should indicate the Santa Clara Valley Water District as the lead agency under CEQA. The Tentative Order also incorrectly identifies the Environmental Impact Report (EIR) certification date as September 24, 2015. The District certified the EIR for the project on March 22, 2016.

Sincerely,



Melanie Richardson, P.E.
Interim Chief Operating Officer
Watersheds

cc: N. Camacho, R. Callender, N. Nguyen, R. Gibson, R. Blank, B. Wolfe, K. Lichten

COMMENTS
25-42



DEPARTMENT OF THE ARMY
SAN FRANCISCO DISTRICT, US ARMY CORPS OF ENGINEERS
1455 MARKET STREET,
SAN FRANCISCO CALIFORNIA 94103-1398

November 15, 2017

Mr. Bruce H. Wolfe
Executive Officer
San Francisco Bay Regional Water Quality Control Board
1515 Clay St, Suite 1400
Oakland CA 94612

Dear Mr. Wolfe:

COMMENTS
43-56

Thank you for this opportunity to comment on the draft Tentative Order for the South San Francisco Bay Shoreline Project. We appreciate the large amount of time and effort that your staff has devoted to working with the project sponsors to resolve a number of issues. In addition, your staff have worked hard to accommodate the federal processes and schedules that the U.S. Army Corps of Engineers (USACE) must follow for its projects. USACE has a number of concerns which are presented in the attached table of comments. We would like to highlight a few of these concerns in this letter.

CORPS
CL-1

First, the project's flood risk management and ecosystem restoration features are interdependent; the latter were not formulated by assessing mitigation needs. The ecosystem restoration components of the project were formulated to take advantage of restoration opportunities resulting from construction of flood risk management features. Without construction of these features, tidal habitat restoration would not be feasible in the project area due to the resulting increased flood risk. In addition, the restoration components of the project were not presented under NEPA, CEQA, or the federal Clean Water Act as being mitigation for project impacts. The entire project was evaluated as an integrated whole and was determined to have an overall positive effect on habitat, fish and wildlife, and water quality. It is our position that the project as described in the NEPA/CEQA document does not need mitigation.

CORPS
CL-2

Second, the adaptive management process proposed for the project has been a vital element in alleviating concerns and securing support for the project from a wide variety of stakeholders, as well as in addressing potential impacts of breaching ponds that were discussed in the NEPA/CEQA document. This process, to be administered by a broad-based adaptive management team, is intended to be science-based and responsive to the results of the project's proposed monitoring program. However, the draft Tentative Order would effectively mandate tidal restoration of all the managed ponds on the project site, voiding this collaborative process and negating the scientific foundation of the proposed adaptive management process. To avoid this outcome, in the event that tidal restoration needs to

CORPS
CL-2
(CONT.)

slow or stop, the project sponsors would need to assume onerous off-site restoration burdens that likely would not be technically feasible.

CORPS
CL-3

Finally, the draft Tentative Order's proposed Contingency Mitigation and Monitoring Plan (CMMP) would be problematic for several reasons. As explained earlier, USACE restoration projects cannot have habitat mitigation as a component and the project as described should not require mitigation. Also, the conditions that would result in a delay or cessation of pond breaching, such as excessive impacts to water birds or a shortage of sediment in the Bay, would also apply to tidal restoration in alternate locations. In addition, the required offsite habitat restoration plan is not a part of the Congressionally-authorized project and USACE cannot spend federal funds on developing such a plan. For all these reasons, we request that the CMMP be removed from the draft Tentative Order.

USACE has reviewed the comment letter and comments from the State Coastal Conservancy and concurs with their comments as well.

Again, USACE appreciates the flexibility shown by RWQCB staff and your interest in working with the project sponsors towards the goals of managing flood risk and restoring valuable tidal habitats on a timely basis in the face of rising sea levels. We look forward to receiving the Water Quality Certification in December, as this will support our schedule to compete for federal funding that will be finalized in January and announced in February, thereby enabling a late spring construction contract award for Reach 1.

Please direct all questions or requests for more information concerning this matter to Bill DeJager at (415) 503-6866 or at William.R.DeJager@usace.army.mil.

Sincerely,

**KENDALL.THOM
AS.R.1231850356**

Digitally signed by
KENDALL.THOMAS.R.1231850356
DN: c=US, o=U.S. Government,
ou=DoD, ou=PKI, ou=USA,
cn=KENDALL.THOMAS.R.1231850356
Date: 2017.11.15 15:49:55 -08'00'

Thomas R. Kendall, P.E.
Chief, Planning Branch

Enclosure

STATE CAPITOL
P.O. BOX 942849
SACRAMENTO, CA 94249-0025
(916) 319-2025
FAX (916) 319-2125

DISTRICT OFFICE
1313 N. MILPITAS BOULEVARD, SUITE 255
MILPITAS, CA 95035
(408) 262-2501
FAX (408) 262-2512

Assembly California Legislature

KANSEN CHU

朱感生

CHAIR: ASSEMBLY COMMITTEE ON ARTS, ENTERTAINMENT,
SPORTS, TOURISM, AND INTERNET MEDIA
ASSEMBLYMEMBER, TWENTY-FIFTH DISTRICT



COMMITTEES
INSURANCE
TRANSPORTATION-
WATER, PARKS, AND WILDLIFE

SELECT COMMITTEES
CHAIR: HATE CRIMES
ASIA/CALIFORNIA TRADE AND
INVESTMENT PROMOTION
FOSTER CARE
IMPROVING BAY AREA
TRANSPORTATION SYSTEMS

APPOINTMENTS
COMMISSION ON ECONOMIC
DEVELOPMENT

October 2, 2017

Larry Goldzband
Executive Director
San Francisco Bay Conservation and Development Commission
455 Golden Gate Ave., Suite 10600
San Francisco, CA 94103

Bruce Wolfe
Executive Officer
San Francisco Bay Regional Water Quality Control Board
1515 Clay St., Suite 1400
Oakland, CA 94612

Dear Mr. Goldzband and Mr. Wolfe:

I am writing to ask your agencies to give full consideration to the permit applications submitted by the U.S. Army Corps of Engineers for construction of the South San Francisco Bay Shoreline Project.

Authorized by Congress in the Water Infrastructure Improvements for the Nation Act in 2016, the Shoreline Project will restore close to 3,000 acres of former salt ponds to tidal wetlands and provide coastal flood risk management for northern San Jose. The Shoreline Project is a critical part of the South Bay Salt Pond Restoration Project, the largest wetland restoration effort on the west coast of the United States. Over 15,000 acres of former commercial salt ponds were acquired in 2003 by state and federal resource agencies, followed by an extensive public planning process, and the start of restoration actions and monitoring in 2009. The Shoreline Project will double the acres of wetlands restored to date as part of South Bay Salt Ponds Project, while providing flood management for: 650 housing units and 2500 residents and infrastructure in the community of Alviso; the San José-Santa Clara Regional Wastewater Facility, which cleans the wastewater of over 1.5 million people in the South Bay; and State Route 237, a major Silicon Valley artery.

I thank you for your work to protect San Francisco Bay and I urge your agencies to approve permits for the construction of the South San Francisco Bay Shoreline Project.

Sincerely,

A handwritten signature in black ink that reads "Kansen Chu".

KANSEN CHU
State Assemblymember, 25th AD



**Appendix C:
Response to Comments**

**401 Water Quality Certification and
Waste Discharge Requirements**

**South San Francisco Bay
Shoreline Project**

**City of San Jose
Santa Clara County**

December 2017

**Response to Comments on the Tentative Order
for the
South San Francisco Bay Shoreline Protection Project**

On October 2, 2017, we received a comment letter supportive of the Project from State Assembly member Kansen Chu, 25th AD. Although that letter was not commenting on the Tentative Order, we have included it in this package.

Comment Number	Commenter	Topic	Comment	Response
1	Coastal Conservancy (Conservancy)	Discharger Roles and Responsibilities	<p>Finding 5. Discharger</p> <p>All clarifying language explaining roles and application of state vs. federal requirement. Suggested additional language is <u>underlined</u>:</p> <p>The Discharger will implement the Project as described in the application materials and herein. As described in the agreement among the Corps and Non-Federal Sponsors, <u>the Corps will be responsible for construction of flood protection, ecosystem restoration, and some recreational elements. Although the Corps works cooperatively with the Non-Federal Sponsors, the Corps is the party directly responsible for project implementation and will follow the provisions of this Order that are applicable to federal agencies. This remains in effect until the Corps deems a project element complete, at which time it will be turned over to the US Fish and Wildlife Service or the Non-Federal Sponsors for operation and maintenance. The USFWS will follow the provisions of this Order that are applicable to a federal agency for operations and maintenance activities on their property. Any construction activities, operations, and maintenance undertaken directly by the Non-Federal Sponsor will follow the provisions of this Order applicable to state and local governments. For example, once the flood risk management (FRM) levee is constructed and fully functional, the Corps will transfer the levee’s operation, maintenance, and management responsibility to the District.</u></p>	<p>Comment noted. The Tentative Order findings are intended to describe the anticipated roles of the Corps, Conservancy, and District, as well as the U.S. Fish and Wildlife Service (USFWS), which would be anticipated to complete future operation and maintenance actions under a different order.</p> <p>Finding 5, paragraph 2, has been revised as follows:</p> <p>5. The Discharger will implement the Project as described in the application materials and herein. As described in the agreement among the Corps and Non-Federal Sponsors, <u>the Corps will be responsible for construction of flood protection, ecosystem restoration, and some recreational elements.</u> Once the flood risk management (FRM) levee is constructed and fully functional, the Corps will transfer the levee’s operation, maintenance, and management responsibility to the District. The Corps and the Non-Federal Sponsors will share financial responsibility for the ecosystem restoration monitoring and adaptive management. However, the Corps’ ecosystem restoration cost sharing obligation is restricted to ten years following each pond-breaching event. Once the Discharger’s cost-sharing obligation ends, the Non-Federal Sponsors will assume the total cost for each pond’s long-term operation, maintenance, and management. <u>Responsibilities for costs, which will also include operation and maintenance costs, will be allocated pursuant to the PPA, when it is finalized.</u> Currently, the Non-Federal Sponsors</p>

Comment Number	Commenter	Topic	Comment	Response
1 (cont.)	Coastal Conservancy (Conservancy)	Discharger Roles and Responsibilities		are negotiating how their respective roles and responsibilities, <u>including cost sharing</u> , will be divided during the ecosystem restoration’s long-term operation, maintenance, and management.
2(a)	Conservancy	Mitigation	<p>Finding 8. Project Construction Phasing</p> <p>For reasons discussed in cover letter and throughout comments, we request that this Order delete “is intended to provide mitigation for those impacts” in Section 8 and describe the purpose of the project in a manner consistent with project description in Section 6. In other words, the purpose of the wetland restoration in all phases is improve ecosystem habitat and function, not to provide mitigation.</p>	See general response regarding mitigation.
2(b)	Conservancy	Mitigation	<p>Finding 8. Project Construction Phasing</p> <p>Please delete (strikeout) as follows: “If Phase I is successfully implemented and the Discharger does not move forward with Phases II and III, the Discharger will submit supplemental information on Project impacts and propose alternative mitigation, as appropriate and as described in the Provisions.” For reasons discussed in cover letter and throughout comments, we suggest that the submittal required if Phase II and III do not go forward is consistent with language proposed in comment number 9.</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
2(b) (cont.)	Conservancy	Mitigation	<p>Please also note that since success is not defined in this Order, this could potential [<i>sic</i>] create problems in the future over different interpretations. Since the adaptive management process is considering dynamics in the broader landscape of San Francisco Bay, successful restoration of Phase I ponds does not necessarily mean Phase II and III can be implemented. Although highly unlikely, the Project needs to preserve its ability to consider issues outside of the project area that could warrant slowing or halting breaching of additional ponds. This is an additional reason for changing this requirement.</p>	
3	Conservancy	Marsh Planting	<p>Finding 10. Phase I (2018-2022), FRM Levee</p> <p>Please delete “will” and substitute “may” in the following sentence: “Marsh vegetation will<u>may</u> be seeded or planted...” and “pickleweed...will<u>may</u> be planted”.</p> <p>This is generally not done in SF Bay restoration projects as the tidal waters bring in sufficient seed source for marsh species. However, the project will likely plant higher marsh and upland species above marsh plain.</p>	<p>The requested revision has been made. We concur that tidal waters should bring in sufficient seed sources for marsh species, and also that higher marsh and upland species should be planted. We note the Project application submitted to the Water Board stated marsh vegetation “will” be seeded or planted.</p> <p>The vegetation is anticipated to be continuous and serve as erosion protection. Marsh vegetation will<u>may</u> be seeded or planted at the toe of the levee following construction. Peripheral halophytes such as 12- to 18-inch tall pickleweed (<i>Salicornia pacifica</i>) will<u>may</u> be planted at the toe of the levee, <u>if necessary</u>.</p>

Comment Number	Commenter	Topic	Comment	Response
4	Conservancy	Ecotone	<p>Finding 10. Phase I (2018-2022), Ecotone Creation</p> <p>Please edit this sentence “The ecotones will be constructed with a 30:1 horizontal to vertical slope...” to reflect the discussion at the Sept. 2016 ecotone charrette that acknowledges that there may be variation in the final design of the ecotone and the quantities estimated in this Order are expected to be the maximum amount.</p>	<p>The requested revision to Finding 10 regarding the ecotone slope has been made.</p> <p>The ecotones will be constructed with <u>an average</u> 30:1 horizontal to vertical slope.</p>
5	Conservancy	Monitoring (EPMP)	<p>Finding 11. Phase II (2027)</p> <p>The Order refers to both a MAMP and an Ecotone and Pond Monitoring Plan (EPMP). This is confusing since the MAMP already includes a description of pond monitoring. It seems likely that the EPMP is a placeholder for the ecotone monitoring addendum that the Conservancy has already submitted to the RWQCB as part of the Phase 2 permitting for the South Bay Salt Pond Restoration Project. If that is the intent, we request that the language in this paragraph to refer to that ecotone addendum specifically instead of an additional plan which seems to overlap with the MAMP. See comment 20 as well for further discussion of ecotone monitoring requirements.</p>	<p>Comment noted. We are not proposing to make the requested change. We are supportive of the Project’s ecotone and pond components and expect the results of the proposed EPMP would both characterize the performance of the implemented Project and significantly inform future implementation of these restoration and adaptive management measures elsewhere in the Bay.</p> <p>If the Conservancy would prefer to include the specific updated restoration targets and monitoring plan, including an ecotone monitoring plan, with future South Bay Salt Pond Restoration Project monitoring plan submissions, or in reference to these submissions, then Water Board staff would find that approach acceptable.</p> <p>The Tentative Order has been revised to allow the use of the South Bay Salt Pond Phase 2 Project ecotone addendum monitoring plan as a model for the EPMP, to the extent the addendum meets the</p>

Comment Number	Commenter	Topic	Comment	Response
5 (cont.)	Conservancy	Monitoring (EPMP)		requirements set forth in the Tentative Order. The Discharger may also incorporate South Bay Shoreline ecotone monitoring into the addendum and complete the required work.
6	Conservancy	Landward Levee Alignment East of Artesian Slough	<p>Finding 13. Future Project Design Decisions, Landward Levee Alignment East of Artesian Slough</p> <p>The discussion of the Pond A18 Alternative does not note that there are constraints to pursuing this alternative. For the Shoreline proponents to pursue levee alignment alternatives 1) the lands must be provided in a condition suitable for restoration or construction, 2) the project costs cannot increase more than 20% over authorized costs, and 3) the alternative cannot require new NEPA/CEQA analysis or feasibility analysis. Otherwise, the Corps will be required to re-open project planning which [may] delay project implementation and jeopardize Congressional appropriations.</p>	<p>Comment noted. Water Board staff understands the constraints regarding implementing potential changes to the proposed alignment, and we appreciate the extensive discussions we have had on this issue with Project stakeholders. The Tentative Order, including its appendices, appropriately recognizes potential constraints and sets forth specific steps for considering alternative alignments, which we understand Corps staff is now completing.</p> <p>The Tentative Order’s language regarding alternative landward levee alignments between Artesian Slough and Coyote Creek reflects the productive discussion between Water Board staff and Project stakeholders including the Dischargers, USFWS, and BCDC. That discussion is already expected to result in the use of a modified San Jose Regional Wastewater Facility levee, rather than construction of what would have been a duplicate new levee immediately adjacent to it, for part of the alignment. This is expected to reduce anticipated Project costs and impacts, including the volume of fill material required to construct the levee. The Landward Levee Alignment Memo described the anticipated benefits of an alternative alignment between Artesian Slough and Coyote Creek, including reduced Project costs. The Tentative Order requires updates regarding work that Corps staff is already doing to reduce Project costs and increase</p>

Comment Number	Commenter	Topic	Comment	Response
6 (cont.)	Conservancy	Landward Levee Alignment East of Artesian Slough		<p>ecosystem restoration opportunities, including evaluating the landward levee alignment alternatives. In addition, future mitigation requirements are not linked to the landward levee alignment in the Tentative Order as the District describes.</p> <p>The Tentative Order authorizes the Project authorized by Congress, but recognizes that an alternative landward levee alignment east of Artesian Slough may be beneficial to the Federal and Non-Federal Sponsors from a cost standpoint as well as reduce the anticipated amount of net loss of waters of the U.S. to zero, or better. Finding 13 discusses the benefits that may result from an alternative alignment. Those include, but are not limited to, reduced Project costs, reduced volume of fill needed to build the Project, reduced fill in jurisdictional waters and opportunities to create new jurisdictional waters, avoidance of future water management issues that would result from building the levee between the Bay and existing wetlands, and opportunities to address cleanup of legacy biosolids ponds at the San Jose Regional Wastewater Facility in coordination with the Project, potentially resulting in reduced cleanup costs for the City of San Jose. Prior discussion with the Conservancy, Corps, and District indicated that they potentially preferred a landward levee alignment east of Artesian Slough for these reasons. The Tentative Order discussion regarding an alternative alignment does not discount the challenges that must be overcome before the design is finalized. Rather, the Tentative Order sets forth a mechanism that would eliminate or reduce obstacles by identifying and authorizing a range of</p>

Comment Number	Commenter	Topic	Comment	Response
6 (cont.)	Conservancy	Landward Levee Alignment East of Artesian Slough		landward levee alignments. Finding 30 notes that any potential significant environmental impacts associated with a landward levee alignment east of Artesian Slough have already been identified in the Joint EIS/EIR. Thus, the Tentative Order facilitates potential landward levee alignments and does not present, or attempt to minimize, obstacles that those alignments may face as designs become finalized.
7	Conservancy	Mitigation	<p>Finding 15. Authorization Process for Future Project Phases</p> <p>Please delete this sentence: “In addition, depending on overall Project impacts and tidal restoration success, this Order may be modified to require compensatory mitigation beyond that now required herein.”</p> <p>While we appreciate that the Order is deferring some decision-making in order to provide the project with flexibility, the Project proponents will not be able to fulfill this requirement for reasons discussed in cover letter.</p>	Comment noted. See general response regarding mitigation. In addition, the Tentative Order has been revised to clarify that the restoration of Ponds A12 and A18 as part of Project Phase I addresses the Project’s temporal impacts associated with fill in jurisdictional waters.
8	Conservancy	Additional Analysis for Levee Alternatives	<p>Finding 15. Authorization Process for Future Project Phases</p> <p>We request that the supplemental analysis for Reach 4 and 5 requested on p. 15 be deleted or modified. The differences in environmental benefits between the levee alternatives are primarily in the amount of acreage restored to tidal action. The impacts of the levee alignments to long-term water management, water quality,</p>	<p>Comment noted. The Tentative Order has been revised to delete the requirement for new detailed sediment modeling:</p> <p>This Order requires that the supplemental analysis for Reaches 4 and 5 <u>quantitatively</u> address the impacts of alternative levee alignments on (a) anticipated rates and extent of post-breach establishment of vegetated tidal</p>

Comment Number	Commenter	Topic	Comment	Response
8 (cont.)	Conservancy	Additional Analysis for Levee Alternatives	<p>habitat functions, wave energy, and establishment of tidal marsh plain are likely to be fairly similar or would be difficult to quantify with any precision given the relatively small amount of topographical changes or increased tidal influence (compared to the pond size).</p> <p>This analysis described in the Order are not necessary for the Corps to justify an alternative levee alignment. Rather, the factors that most influence the feasibility of the any levee alignment are: 1) lands provided in a condition suitable for restoration or construction, 2) alternative levee alignment does not increase project costs more than 20% over authorized costs, and 3) the alternative does not require new NEPA/CEQA analysis or feasibility analysis. Since the Shoreline proponents agree that increasing the amount of tidal restoration and decreasing impacts to waters of the U.S. is a desirable goal, we suggest that requiring information or analysis that focuses on addressing the constraints listed above will be more helpful in assessing levee alignment feasibility. Additional modeling or other quantitative analysis (beyond estimating acreage of additional tidal wetlands) is less critical for decision-making in this instance.</p>	<p>marsh; (b) long-term water management operations, water quality, and habitat functions/values in the City and landfill mitigation marshes given anticipated sea level rise (Att. C, Figures 1 and 3); and (c) anticipated attenuation of wave energy by vegetated tidal marsh seaward of the ecotone.</p> <p>However, a basic qualitative assessment that provides sufficient documentation to compare the likely spatial and temporal development of restored tidal marsh is still required for any alternative levee alignment in Provision 37:</p> <ul style="list-style-type: none"> • Comparison of projected short-term (0 to 10 years post-breach) and long-term (10+ years post-breach) establishment of vegetated tidal marsh plain seaward of the FRM levee under alternate levee alignments east of Artesian Slough and suspended sediment concentrations of 100 mg/L and 200 mg/L (consistent with the modeling work performed by ESA PWA in 2012 and cited in the September 2015 South Bay Shoreline Phase 1 Study); <p>The constraints regarding alternative levee alignments have been well documented and communicated. As detailed in Tentative Order Attachment C, the alternative alignment likely will reduce overall Project costs because it utilizes land that has advantages over the land conditions along the currently proposed alignment along Reaches 4 and 5. These advantages include better construction access, reduced need for construction dewatering, and the availability of soil for construction.</p>

Comment Number	Commenter	Topic	Comment	Response
				<p>Furthermore, any alignment would not only have to be justified economically, but also environmentally. Therefore, the requirements for the supplemental analysis, which reflect Water Board staff's discussions with Corps staff, and which we understand Corps staff is already completing, are intended to aid the Discharger in justifying the design. See also response to Comment 6.</p>
9a	Conservancy	EO Approval of Adaptive Management Decisions	<p>Finding 15. Authorization Process for Future Project Phases.</p> <p>We request modification or deletion of this language: “In addition to supplemental applications, any changes to the Project that reduce the ecosystem restoration amount, thereby reducing the Project’s compensatory mitigation amount, must be approved by the Water Board’s Executive Officer before those changes can be implemented (see Findings 21 and 22).”</p> <p>The first sentence conflates all ecosystem restoration proposed by the project with compensatory mitigation, which is problematic for numerous reasons discussed in the cover letter and in the comments.</p> <p>The second sentence requires the EO’s approval to implement the recommendations of the Adaptive Management program, which is problematic for reasons discussed in the cover letter.</p>	<p>Tentative Order Findings 21 and 22 have been revised for clarity regarding the Project’s fill-based and non-fill based impacts and the related mitigation requirements. Specifically, they have been revised to clarify (1) that the proposed restoration of Ponds A12 and A18 as part of Phase I will address the Project’s anticipated temporal impacts to jurisdictional waters; (2) that the restoration work in Phases II and III is anticipated to be self-mitigating; and (3) that proposed creation of jurisdictional waters in Phases II and III is a component of the Project’s compensatory mitigation for proposed permanent fill associated with construction during Phase I (See general response regarding mitigation). See also response to Comment 7.</p> <p>We are not proposing to modify the “acceptable to the Executive Officer” language. The Water Board, with the Tentative Order, is approving a proposed Project design. To the extent there are future changes to the design, and they are appropriately framed in the Tentative Order, Executive Officer approval is a relatively efficient mechanism for allowing changes to an approved project. The alternative, review by the Water Board at a regularly scheduled meeting, is more time-consuming and</p>

Comment Number	Commenter	Topic	Comment	Response
9a (cont.)	Conservancy	EO Approval of Adaptive Management Decisions	<p>We would like to propose that the Order focus on process for involving and informing RWQCB staff of Adaptive Management decisions by suggesting the following language (if not in this section of the Order, in another appropriate place). Suggested language is below:</p> <p>The Adaptive Management Plan outlines project risks, a method for evaluating results, and a decision-making process to address or correct problems. One of the potential ways to address problems is to delay or halt the conversion of ponds to tidal wetlands. For example, if a lack of sediment causes newly breached ponds to erode a significant amount of mudflat habitat, which millions of migratory shorebirds depend on, then pond breaching would likely cease. Alternatively, if there is a significant Bay wide decline in pond-specialist bird species (e.g. grebes and phalaropes), then pond conversion would need to be slowed or halted. Scenarios such as these would reduce the Project’s ultimate ecosystem restoration acreage, but this would [be] because of regional natural processes beyond the control of the Project.</p> <p>If the Project anticipates that the Phase II and/or III ecosystem restoration is delayed or halted beyond the schedule proposed in the Order, the Project’s Adaptive Management Team will present findings and recommendations for delaying or stopping restoration to key stakeholders, including regulatory agencies and a representative appointed by the Executive Director [<i>sic</i>] of the RWQCB [or perhaps this is</p>	<p>unnecessary because the Tentative Order specifies the parameters that revisions must meet in order to be “acceptable to the Executive Officer” in Finding 15 and Provisions 1 and 35.</p> <p>Water Board staff intends to continue to be involved in the collaborative adaptive management processes associated with Bay margin tidal restoration. If data is collected during the monitoring period or other sound scientific information developed that justifies implementing adaptive management approaches, including delaying future pond breaches, the Water Board’s Executive Officer will review it and any supporting documentation. The Tentative Order includes language intended to allow Executive Officer review of the likely Project outcomes. However, should the information presented to the Water Board propose Project changes that fall outside what the Tentative Order authorizes, then review by and approval from the Water Board may be required.</p> <p>This language is not intended to require tidal restoration that is not supported by data collection and monitoring. Rather, the Executive Officer approval requirement recognizes that a while range of adaptive management techniques could be implemented at the Project site, any significant changes to the Project require Executive Officer or Water Board approval.</p>

Comment Number	Commenter	Topic	Comment	Response
9a (cont.)	Conservancy	EO Approval of Adaptive Management Decisions	<p>the TAC process referred to in the Order]. It is anticipated that delaying or stopping Phase II or III restoration would be a “worst case scenario” after other measures and alternatives had been considered and documented as insufficient to address concerns.</p> <p>If the Project experiences delays in implementation of Phase II and/or III ecosystem restoration due to lack of funding, the Project proponents shall document the funding short fall and prepare a funding strategy for submittal to the Executive Director that shall consider using local and state sources of funding in order to complete implementation.</p>	
9(b)	Conservancy	EO Approval of Adaptive Management Decisions.	<p>Finding 16. Ecosystem Restoration and Benefits of Tidal Marsh Restoration and Ecotones</p> <p>As discussed in cover letter and in comments, please either modify as suggested above in comment nine or delete (strikeout) as follows: “This Order requires any modifications to Phase II and III implementation to be submitted to the Water Board Executive Officer for review and approval (see Finding 15 and Provision 1).”</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
10	Conservancy	Mitigation	<p>Finding 21. Project’s Net Loss of Waters of the U.S.</p> <p>This section notes that the net loss is only 8.76 acres. This section should also point out that the proposed 1,120 acres of wetland restoration proposed in Phase I is outside of any Adaptive Management “risk”.</p> <p>We would also appreciate if this Order could reframe the ecosystem restoration as not the same as compensatory mitigation.</p>	See general response regarding mitigation.
11	Conservancy	Mitigation	<p>Finding 21. Project’s Net Loss of Waters of the U.S.</p> <p>We request that the last two paragraphs on this page requiring “compensatory mitigation” be deleted for reasons discussed in cover letter and throughout comments.</p> <p>As noted above, Phase I alone includes 1,120 acres of wetland restoration (regardless of levee alignments) which should be evaluated against the fill impacts (132 acres permanent fill).</p>	See general response regarding mitigation.
12	Conservancy	Mitigation	<p>Finding 22. Project Mitigation</p> <p>Please delete this sentence: “However, the habitat conversion’s success and consistency with these policies is contingent upon the completion of all three Project phases, including</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
12 (cont.)	Conservancy	Mitigation	<p>the Project’s ecosystem restoration components.”</p> <p>It seems unlikely that 8.76 acres of impacts requires 2,900 acres of mitigation.</p>	
13	Conservancy	CEQA	<p>Finding 30. California Environmental Quality Act (CEQA)</p> <p>Please note the CEQA lead was the SCVWD, not the Conservancy.</p>	<p>Finding 30 of the Tentative Order has been revised as requested to reflect the correct lead agency.</p> <p>The Conservancy<u>District</u>, as the lead agency, certified a combined Interim Feasibility Study and Environmental Impact Statement (EIS)/Environmental Impact Report (EIR) (Joint EIS/EIR) (HDR, July 2015) for the Project on September<u>March 24</u>22, 2015<u>2016</u>.</p>
14	Conservancy	Monitoring	<p>Provision 15. Pond and Ecotone Monitoring</p> <p>This is monitoring is consistent with what the Project has proposed in the MAMP. We request that the requirement for the EPMP be modified or deleted since we believe it is already covered in the MAMP. If there is concern that the MAMP does not sufficiently include ecotone monitoring, then we suggest this condition include a reference to the SBSP Restoration Project’s Adaptive Management’s addendum which includes ecotone monitoring parameters and triggers for management.</p>	<p>See response to Comment 5.</p>

Comment Number	Commenter	Topic	Comment	Response
15	Conservancy	Mitigation	<p>Provision 17. Contingency Mitigation and Monitoring Plan (CMMP)</p> <p>Please delete the requirement for a preparation of a Contingency Mitigation and Monitoring Plan. This Plan would be impossible to implement for reasons discussed in cover letter and throughout comments.</p>	<p>See mitigation response. Further, Water Board permits for projects that require mitigation for impacts to waters of the State include performance standards that are to be used in assessing the success of the mitigation project, as well as provisions for contingency measures to be implemented in the event that a mitigation project does not attain its performance standards.</p> <p>The requirement for a CMMP was included in the Order because of the significant uncertainties associated with full implementation of tidal marsh restoration (e.g., long time lag between fill and the first breaching of outer levees, uncertainties with respect to sediment availability, uncertainties associated with the relative rates of sediment accretion and sea level rise, the possibility that the AMT may recommend that some salt ponds be maintained as open water ponds, and the uncertainties related to federal funding for future project phases). The CCMP is initially, and potentially primarily, an accounting mechanism that tracks Project fill impacts and allows the gradual resolution of what are now areas of uncertainty. Requirements for contingency measures are a standard component of Water Board permits that require mitigation. The MAMP is not sufficiently flexible to address contingency measures, which is inconsistent with standard Water Board permit development procedures.</p> <p>Dischargers usually submit draft MAMPs to the Water Board, and those draft MAMPs are revised in consultation with the Water Board to provide a high</p>

Comment Number	Commenter	Topic	Comment	Response
				level of certainty that sufficient mitigation will be provided for unavoidable impacts that are authorized by Water Board permits. Since the Corps did not incorporate Water Board input into the MAMP, it is necessary to address unresolved issues in the CMMP.
16	Conservancy	Monitoring	<p>Provision 24. Photo-Documentation Report</p> <p>The requirement for a minimum of 20 photo-documentation sites may be excessive for some phases of the project such as Phase I, Reach I, which involves less than a mile of levee. Is there a way to add language to decrease the number, if appropriate?</p>	<p>Comment noted. The photo-documentation provision has been revised as follows:</p> <p>To document levee and Pond conditions immediately at the Project site, the Discharger shall establish a minimum of 204 photo-documentation points <u>at the Phase I Reach I location, 8 photo-documentation points at locations for future Phase I construction events that include ecotone creation, and 8 photo-documentation points at locations for each Project construction event for which berms are lowered and tidal action is restored, including the last Phase I construction event. Each Project component, including all Phase I construction events, Phase II, and Phase III.</u></p>
17	Conservancy	Mitigation	<p>Provision 26. Notice of Mitigation Completion</p> <p>Since the project has not proposed any compensatory mitigation, we would interpret this condition as not applicable and ask that the Order please delete this paragraph. We expect to provide results of ecosystem restoration monitoring consistent with the MAMP as required elsewhere in the Order.</p>	<p>See general response regarding mitigation. The Notice of Mitigation Completion is appropriate.</p>

Comment Number	Commenter	Topic	Comment	Response
18	Conservancy	Monitoring Requirements	<p>Provision 36. Mechanism for approval of subsequent Project work</p> <p>The conditions outlined under “mechanism for approval of subsequent Project work” conflates all the proposed ecosystem restoration with compensatory mitigation requiring a more detailed level of monitoring to demonstrate that “the Project’s compensatory mitigation” is avoiding “a loss in existing functions, values, or habitat”. Since this is an ecosystem restoration project, not a mitigation project, we request that the second and fifth bullets be deleted in order to not characterize the ecosystem restoration as mitigation.</p> <p>To address the RWQCB’s concern about ecotone monitoring, we would then suggest under that, consistent with comment 6, section iii (p. 47) add the ecotone addendum proposed as part of the SBSP Restoration Project’s Phase 2 instead of a separate EPMP plan.</p>	See general response regarding mitigation and response to Comment 5.
19	Conservancy	MAMP	<p>Provision 36. Mechanism for approval of subsequent Project work</p> <p>[“]Consistent with Section 3.1 and 3.3 of the MAMP[...”]</p> <p>Please delete reference to updating the MAMP since the MAMP has been adopted by the Corps’ Civil Works Review Board and it is not feasible to update this document. The additional information listed in bullets under iii could still</p>	The request for update is specific to ecotone monitoring and to the referenced MAMP sections, which themselves call for more-detailed work. Water Board staff communicated to the Conservancy and other Project stakeholders in our collaborative meetings that ecotone monitoring needed further development because it was not fully addressed in the MAMP. We understand that with the MAMP reviewed and approved by the Corps, the ability to make changes to the MAMP may not be

Comment Number	Commenter	Topic	Comment	Response
19 (cont.)	Conservancy	MAMP	be provided as we develop the details of implementation of the MAMP, but not as part of a formal modification of the MAMP.	<p>possible without delaying Project construction. As such, in part to facilitate the Project’s construction and internal Corps processes, that work has been specified as a separately-named plan. Therefore, the EPMP is a supplemental document that eliminates the need to revise the MAMP and serves to complete the MAMP’s recognition that a more detailed monitoring plan should be developed prior to the start of monitoring.</p> <p>For instance, the EPMP requirement is intended to fulfill the need for additional quantitative restoration targets, as referenced in MAMP Section 3.1¹:</p> <p>“Targets include both long-term goals and intermediate conditions as the ecosystem changes. Quantitative targets, such as minimum numbers or ranges of variability, do not yet exist for all restoration targets. These targets will be developed using existing data or regulations and many are expected to evolve as monitoring and assessments are conducted.”</p> <p>The EPMP requirement is also consistent with the recognition in the MAMP that more detailed monitoring methods would be needed outside the general approach that was used in the MAMP, as stated in Section 3.3:</p> <p>“The monitoring method summaries in Table 3 (Monitoring Cost Estimate) are described in enough detail to make the approach clear, but do not fully describe the monitoring regime. A monitoring plan</p>

¹ South San Francisco Bay Shoreline Study, Monitoring and Adaptive Management Plan for Ecosystem Restoration (September 2015)

Comment Number	Commenter	Topic	Comment	Response
19 (cont.)	Conservancy	MAMP		<p>with detailed methods, protocols, timing, and responsible parties will be developed prior to the start of monitoring as each monitoring study is contracted.”</p> <p>These sections in the MAMP acknowledge the necessity of a more detailed monitoring plan and assume the plan will be developed prior to the start of monitoring. Therefore, the requirements and reference to these MAMP sections in Provision 36 are necessary.</p>
20	Conservancy	Additional Analysis for Levee Alternatives	<p>Provision 37. Impact Reduction and Environmental Benefit Optimization</p> <p>As stated in comment 9, we [request] the first and second bullets requiring additional analysis for Reach 4 and 5 in Provision 35 be deleted or modified.</p> <p>We would also like to clarify that requiring extensive additional modeling or other quantitative analysis could jeopardize the project’s eligibility for Congressional appropriations (because this extent of additional technical analysis would trigger a new feasibility analysis, making the project ineligible for construction funding).</p>	<p>See Response to Comment 8.</p>

Comment Number	Commenter	Topic	Comment	Response
Conservancy Cover Letter (CL)-1	Conservancy	Voluntary Ecosystem Restoration vs. Mitigation	<p>Most of our comments have to do with a misunderstanding of the purpose of the project. The Tentative Order initially correctly describes the project (pp. 2-3) as a multi-benefit project that seeks to restore former salt evaporation ponds, protect adjacent communities from flooding, and provide recreational opportunities. However, on p. 4, there is a different interpretation of the project purposes: "Phase I is expect to result in Project impacts and the ecosystem restoration work in Phases I, II, and III is intended to provide mitigation for those impacts." This description sets the stage for requirements that are extremely problematic.</p> <p>The Conservancy would like to restate that the restoration options were selected for their own value in order to meet the project's ecosystem restoration goals. The Conservancy is involved in the Shoreline Project because it will implement the goals of the South Bay Salt Pond Project in an area where restoration is impossible without flood protection infrastructure.</p> <p>This project is not an infrastructure project with some mitigation elements - as is demonstrated by the vast amount of restoration proposed, much more than would be required to offset impacts. Furthermore, since the fill impacts from the flood protection measures (132.2 acres permanent fill or 8.76 acres net fill) are relatively minor when compared to the tremendous benefits from just the first phase of proposed restoration (restoring 1120 acres of existing ponds to tidal action), the Conservancy</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
Conservancy Cover Letter (CL)-1	Conservancy	Voluntary Ecosystem Restoration vs. Mitigation	<p>would expect that this project is self-mitigating by the end of Phase I. However, the Conservancy proposes to continue to restore ponds in Phases II and III, adding up to an additional 1780 acres of tidal restoration (pursuant to the adaptive management framework), because that is the goal of the project and the purpose of our agency, not to secure unnecessary, additional mitigation.</p>	
Conservancy CL-2	Conservancy	Infeasibility of Mitigation	<p>The Tentative Order currently states that if the restoration proposed in Phase II (900 acres) and Phase III (880 acres) is not implemented, then the project must provide compensatory mitigation elsewhere.</p> <p>This requirement could adversely impact the ability of the Project to implement its Monitoring and Adaptive Management Plan (MAMP). The MAMP outlines project risks, a method for evaluating results, and a decision-making process to address or correct problems that arise while implementing the project. As described on p. 18 of the Tentative Order, the MAMP states that one of the potential ways to respond to adverse results to is to delay or halt pond breaching. (Indeed, having this ability to delay or stop the project is a primary reason that the restoration will be phased.)</p> <p>The grounds upon which the Adaptive Management team might recommend that restoration be delayed or stopped are the same reasons that would make mitigation impossible elsewhere in San Francisco Bay. For example, if</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
Conservancy CL-2 (cont.)	Conservancy	Infeasibility of Mitigation	<p>lack of sediment causes newly breached ponds to erode a significant amount of mudflat habitat, which millions of migratory shorebirds depend on, then pond breaching would likely need to stop in all of San Francisco Bay. Alternatively, if there is a Bay wide decline in pond-specialist species (e.g. grebes and phalaropes), then pond conversion in all of San Francisco Bay would need to be slowed or halted.</p> <p>Obviously, the Shoreline Project expects to be successful; not implementing the wetland restoration proposed in Phase II and III is an extreme scenario. However, we are entering an era of greater uncertainty. The Conservancy and the other Project proponents have created a process through the MAMP to address uncertainty as much as possible. However, if the Project proponents are not able to implement all of the proposed restoration, there are not going to be alternatives at this scale available elsewhere.</p> <p>Since mitigation is infeasible, the current language in the Tentative Order could create a scenario where the project will have no choice but to restore all the ponds, regardless of the input from the Adaptive Management monitoring and applied studies, undermining this carefully crafted program. For these reasons, the Conservancy requests changes to the Tentative Order language in the attached comments.</p>	

Comment Number	Commenter	Topic	Comment	Response
Conservancy CL-3	Conservancy	RWQCB and Adaptive Management Decision-Making	<p>The project fully intends to communicate adaptive management decisions to our stakeholders and including the RWQCB. However, requiring the RWQCB's Executive Director approval for not implementing the restoration in Phase II and III essentially gives Executive Director "veto power" over the decision-making process outlined in the MAMP. The Adaptive Management decision-makers have to consider a broad suite of issues that include, but are not limited to, enhancing the resources overseen by the RWQCB. Making an adaptive management action subject to RWQCB approval (except to the extent that a proposed action requires a permit) would give the RWQCB a role not shared by any other stakeholder.</p> <p>The Conservancy suggests an alternative approach in comment number nine. We propose that the Order should describe a process (e.g. the Technical Advisory Committee) for involving and informing RWQCB staff in the Adaptive Management decision-making process. The Order should clarify that the RWQCB shares the understanding of the Shoreline Project that there may be valid reasons that the Adaptive Management decision-makers recommend halting or delaying pond restoration and that the Project would not be held responsible for natural processes beyond anyone's control.</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
21	USFWS	Mitigation	<p>Finding 8. Project Construction Phasing</p> <p>p. 2-3 "The draft Order initially correctly describes the Project (pp. 2-3) as a multi-benefit project that seeks to restore former salt evaporation ponds, protect adjacent communities from flooding, and provide recreational opportunities. However, on p. 4, there is a different interpretation of the project purpose: "Phase I is expected to result in Project impacts and the ecosystem restoration work in Phases I, II, and III is intended to provide mitigation for those impacts." The restoration components of the project were not presented under NEPA/CEQA or the federal Clean Water Act as being mitigation for project impacts; therefore that interpretation is incorrect and should be revised appropriately. It is our position that the Project as described in the NEPA/CEQA document does not need nor require mitigation."</p>	See general response regarding mitigation.
22	USFWS	Mitigation	<p>The Refuge is involved in this Project because it will implement a portion of the South Bay Salt Pond Restoration Project, consistent with the Refuge's Comprehensive Conservation Plan that fulfills the purposes for which the Refuge was established for the protection and restoration of habitat for fish and wildlife, including federally listed species such as the California Ridgway's rail and salt marsh harvest mouse. The wetland restoration would be impossible without the construction of flood risk management infrastructure, and in turn, the flood risk</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
			<p>management levee as integrated with the proposed wetland restoration features will be more resilient and sustainable in the face of climate change. The project description fully describes the considerable amount of restoration proposed, an amount in our opinion much higher than would be required as mitigation to offset impacts. For example, during Phase I the net fill impacts from the flood protection measures (8.67 acres) are minor when compared to the tremendous benefits from just Phase I of proposed restoration (restoring 1120 acres of existing ponds to tidal action). In addition, as the Project continues to restore additional ponds in Phases II and III, it will be adding up to an additional 1780 acres of tidal restoration, as described in the project description.</p>	
23	USFWS	Mitigation	<p>The draft Order further states that if the restoration proposed in Phase II (900 acres) and Phase III (880 acres) is not implemented, then the Project must provide compensatory mitigation (CNMP) elsewhere. This requirement as stated in an order could adversely impact the ability of the Project to implement the USACE's approved Monitoring and Adaptive Management Plan (MAMP). The MAMP outlines project risks, a method for evaluating results, and a decision-making process to address or correct problems that arise while implementing the Project. As described on p. 18 of the draft Order, the MAMP states that one of the potential ways to respond to adverse results is to delay or halt pond breaching so that we can apply the best</p>	<p>See general response regarding mitigation.</p>

Comment Number	Commenter	Topic	Comment	Response
			<p>available science, address uncertainty, and inform future phases in an adaptive management framework. We respectfully request and concur with the USACE that references to CMMP be removed from the draft Order accordingly.</p>	
24	USFWS	Monitoring	<p>We all certainly expect the Shoreline Project to be successful in achieving the multi-benefits of flood risk reduction, ecosystem restoration, and recreation opportunities. The MAMP was prepared to address uncertainty as much as possible, and indeed the South Bay Salt Pond Restoration Project has a proven track record of using adaptive management as described in the MAMP and provides a mechanism through technical working groups and stakeholder forums to keep RWQCB staff updated and part of the decision-making process should uncertainties arise throughout the project. We recommend that the Order describe a process for how RWQCB staff wish to be engaged and informed through the USACE’s adaptive management decision-making process. The Order should clarify that the RWQCB shares a similar concern of the Shoreline Project that there may be valid reasons that the project team may recommend halting or delaying pond restoration elements due to natural processes beyond anyone’s control in furtherance of the Project as described.</p>	<p>See responses to Comments 5 and 9a.</p>

Comment Number	Commenter	Topic	Comment	Response
25	Santa Clara Valley Water District (District)	Mitigation	<p>Finding 22. Project Mitigation</p> <p>The tentative order, in finding 22, treats the 2,900 acres of restored tidal marsh proposed by the Project as mitigation for the project's net fill of 8.76 acres of waters. The Project's tidal marsh restoration is not proposed to be mitigation for the fill; rather, the fill is necessary in large part because of the tidal marsh restoration. The fill is being placed on the landside of the restored tidal marsh to construct new flood protection that becomes necessary in large part because the dikes that currently provide an incidental measure of flood protection have to be breached in order to restore the tidal marsh.</p> <p>The Regional Board has previously-and correctly-recognized, for the South Bay Salt Pond Restoration Project (SBSRP), that tidal marsh restoration is not mitigation for the fill that may be necessary for the restoration. The Regional Board's findings for that project (R2-2008-0078) recognized that restoring tidal marsh should not be viewed as mitigation: finding 96 of the SBSRP order found that "[n]o penalties will be imposed for a failure to achieve the interim and final habitat goals; since this is a restoration (not a mitigation) project", and finding 16 found that "[n]o compensatory mitigation is required for impacts to existing wetlands and waters of the State, since this restoration project will result in many more acres of restored and enhanced habitats than the acres of habitat that are impacted."</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
25	Santa Clara Valley Water District (District)	Mitigation	<p>Although the Tentative Order, in finding 9, states that it is modeled after SBSPRP, it treats the restoration component of this Project very differently than restoration was treated in SBSPRP. The Regional Board should be consistent: the Tentative Order should not treat the restoration component of the Project as mitigation for fill, just as the Regional Board treated the fill necessary for the restoration component of SBSPRP. No compensatory mitigation should be required here.</p>	
26	District	No Net Loss Policy	<p>Finding 32. Basin Plan Wetland Fill Policy Finding 33. California Wetlands Conservancy Policy</p> <p>The Tentative Order, in findings 32 and 33, cites the California Wetlands Conservation Policy (Executive Order W-59-93), often called the "no-net-loss policy", and the Basin Plan (which incorporates the no-net-loss policy), as the principal basis for requiring 2,900 acres of mitigation for 8.76 acres of net fill here. As described below, the Tentative Oder misapplies the no-net-loss policy.</p> <p>The policy focuses on a programmatic approach to preserving and enhancing wetlands: it requires State agencies to "encourage partnerships to make restoration, landowner incentive programs, and cooperative planning efforts the primary focus of wetlands conservation." The Project is developed through a cooperative partnership between agencies and landowners to restore</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
26 (cont.)	District	No Net Loss Policy	<p>wetlands and waters. The policy "is not meant to be achieved on a permit-by-permit basis". Yet the Tentative Order tries to apply the policy to this individual permit, without regard to the broader partnership represented by this Project, contrary to the policy's direction that it is to be implemented on a programmatic, rather than permit-by-permit, basis.</p> <p>The Regional Board should read the no-net-loss policy as encouraging approval of the Project as-is, rather than as requiring conditioning the Project on thousands of acres of mitigation.</p>	
27	District	Mitigation	<p>Finding 31. Water Quality Control Plans.</p> <p>Water Code section 13263(a) requires waste discharge requirements to implement relevant water quality control plans, and to take into consideration the beneficial uses to be protected. The water quality control plan here-the Basin Plan-incorporates the no-net-loss policy, but, as just discussed, that policy supports approval of the Project as is, rather than with thousands of acres of mitigation. Nor does the Tentative Order justify its conditions as necessary to promote beneficial uses: in fact, the Tentative Order recognizes that the Project as-is will provide significant benefits to beneficial uses. No additional mitigation is necessary.</p> <p>The Tentative Order, in finding 31, lists a number of beneficial uses in the Project area, but the Tentative Order identifies no beneficial uses that will be adversely impacted by the Project.</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
27 (cont.)	District	Mitigation	<p>Finding 16 goes on at length, and in great detail, about how the Project as-is is expected to "result in a significant contribution to tidal wetland restoration", providing water quality and associated habitat and vegetation benefits "on a spatially significant scale".</p> <p>In the SBSPRP, the Regional Board recognized that salt pond restoration projects promote beneficial uses and require no compensatory mitigation: in Finding 16 in its order for that project (R2-2008-0078), the Regional Board found that "[n]o compensatory mitigation is required for impacts to existing wetlands and waters of the State, since this restoration project will result in many more acres of restored and enhanced habitats than the acres of habitat that are impacted." Similar benefits would be generated by the Project, and thus the same approach should be used here.</p> <p>Because the Project as-is significantly promotes beneficial uses, no additional mitigation is required.</p>	
28	District	Mitigation (Ratio)	<p>Even if mitigation were required for the 8.76 acres of net fill, the Tentative Order would require 2,900 acres of mitigation—a ratio of nearly 330:1. That kind of ratio is unprecedented and unjustified.</p> <p>Compensatory mitigation requirements must be roughly proportionate to a project's impacts. (<i>Dolan v. City of Tigard</i> (1994) 512 U.S. 374, 391.) A 330:1 mitigation ratio, for a project that</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
28 (cont.)	District	Mitigation (Ratio)	<p>is largely a restoration project, is also not roughly proportionate to any impacts this project may have.</p> <p>Requiring a mitigation ration of 330:1, or anything close to that, would set an unfortunate precedent. It would signal that the Regional Board wants to stand in the way of restoration projects by imposing onerous conditions, rather than promoting such projects by blessing them with streamlined approvals. The Regional Board should rethink the Tentative Order's excessive and unjustified mitigation for this Project.</p>	
29	District	Mitigation (CCMP)	<p>Finding 8. Project Construction Phasing Finding 22. Project Mitigation</p> <p>The ecosystem restoration component of the Project will occur in three phases (Phases I, II, and III) of pond breaches to establish tidal connection. The Tentative Order requires all phases of the restoration to be completed, and requires additional mitigation to be proposed for approval if not all phases are implemented (Findings 8, 22). Phase [I] of the restoration is scheduled to be constructed in 2022, and completion of this phase would result in restoration of up to over 1,000 acres of tidal marsh habitat. The design and construction of Phases 2 and 3 restoration will be guided by the Project's Monitoring and Adaptive Management Plan. Phases II and III of the Project are likely to be built, adding many hundreds of acres of restored tidal marsh to the Project. Only in the</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
29 (cont.)	District	Mitigation (CCMP)	<p>unlikely event that Phase I causes unavoidable but undesirable outcomes would Phases II and III be reconsidered.</p> <p>Even if Phase I does not result in all of the restoration benefits predicted, no additional mitigation should be required. Finding 96 of SBSPRP (Order No. R2-2008-0078) stated that "No penalties will be imposed for a failure to achieve the interim and final habitat goals, since this is a restoration (not a mitigation) project"; that order instead envisioned a collaborative process to achieve the desired results. A similar approach should be used here.</p>	
30(a)	District	Whether Discharge is a "Waste"	<p>If the Regional Board revises the Tentative Order's current approach of treating the restoration component of this Project as mitigation for the fill necessary for the Project, then the following discussion becomes less important from a practical perspective. Nevertheless, the District is compelled to raise these issues until the Tentative Order is revised to drop its objectionable mitigation conditions.</p> <p>As the District and USACE have explained to the Regional Board in other contexts, the Regional Board's authority to impose waste discharge requirements is limited to discharges of "waste". (Water Code section 13260(a)(1); see <i>Lake Madrone Water District</i> (1989) 209 Cal.App.3d 163 (flushing unwanted sediment</p>	<p>Dredge and fill discharges causing discharges of sediment involve discharges of "waste": "There is no doubt that concentrated silt or sediment associated with human habitation and harmful to the aquatic environment is 'waste' under the statute." (<i>Lake Madrone Water District v. State Water Resources Control Board</i> (1989) 209 Cal.App.3d 163, 169. See also, State Water Board Resolution No. 2004-0030 [favorably citing the <i>Lake Madrone</i> finding that accumulated sediment was a discharge of waste and noting the impact of sediment on steelhead habitat].) The State Board has determined that discharges "produced by dredging or filling operations" involving "the discharge of earth, rock, or similar solid materials" are properly regulated by WQCs and WDRs.² The State Board reasoned that such regulation is necessary because:</p>

² State Board Order 2004-0004 (*Statewide General WDRs for Dredge and Fill Activities in Waters of the State*), p. 2.

Comment Number	Commenter	Topic	Comment	Response
30a (cont.)	District (cont.)	Whether Discharge is a "Waste" (cont.)	<p>accumulated behind dam was a discharge of waste.) The term "waste" is commonly understood as meaning "something discarded 'as worthless or useless.'" (<i>Waste Management of the Desert v. Palm Springs Recycling Center, Inc.</i> (1994) 7 Cal.4th 478, 485.) But constructing a beneficial project is not a discharge of something worthless or useless. (See <i>Tahoe-Sierra Preservation Council, Inc. v. Tahoe Reg'/ Planning Agency</i> (D.NV 1999) 34 F.Supp.2d 1226, 1254 (distinguishing Lake Madrone to hold that "building a house" is not a discharge of waste under Porter Cologne), rev'd in part on other grounds, 216 F.3d 764, aff'd, 535 U.S. 302.) This Project—restoring tidal marsh and constructing flood protection—is beneficial; it is not a discharge of waste subject to waste discharge requirements.</p>	<p>Discharges of fill can directly or indirectly destabilize the channel or bed of a receiving water by changing geomorphic parameters, including hydrologic characteristics, sediment characteristics, or stream grade. Such destabilization diminishes the ability of the water body to support designated beneficial uses.³</p> <p>Dischargers cite <i>Tahoe-Sierra Preservation Council, Inc. v. Tahoe Reg'/ Planning Agency</i> (D.NV 1999) 34 F.Supp.2d 1226 (note subsequent negative treatment omitted in Dischargers' comment). The court in that case noted facts that distinguished the case from <i>Lake Madrone</i>, specifically, that the activity in question – building a house – was not expected to result in discharges of concentrated silt or sediment. (<i>Id.</i> at pp. 1253-1254.) In this case, all parties anticipate that there will be discharges of sediment to the receiving waters, as demonstrated in the Joint EIS/EIR that states:</p> <p>“Construction activity would be conducted consistent with waste discharge requirements (WDRs) prescribed for compliance with the State’s Porter-Cologne Act and BMPs outlined in the required Stormwater Pollution Prevention Plan (SWPPP) for the Shoreline Phase I Project (AMM-GEO: Prepare SWPPP)...Applying these measures would reduce any potential impacts to a less-than-significant level.”⁴</p>

³ *Id.* at pp. 3-4.

⁴ Joint EIS/EIR at pg. 4-47.

Comment Number	Commenter	Topic	Comment	Response
30a (cont.)	District	Whether Discharge is a "Waste"		<p>“Construction of the FRM levee would involve soil disturbance along the levee alignment, adjacent areas, and staging areas, thereby temporarily exposing the soil in these areas to erosion. The Project’s WDRs and SWPPP would include measures to control erosion during construction (AMM-GEO-6: Prepare SWPPP). In addition, as work in areas is completed, disturbed areas would be stabilized consistent with the SWPPP...”⁵</p> <p>“Operation and Maintenance actions that result in soil disturbance are likely to temporarily increase turbidity and suspended sediment; these activities include placement of dredge material on levee tops, dredging of ponds and stockpiling of dredge materials, and gaining access to excavation sites...However, avoidance and minimization measures would be implemented to minimize temporary increases in turbidity and suspended sediment (AMM-ABR-1, AMM-ABR-2, AMM-ABR-4, AMM-ABR-6, AMM-ABR-10), as well as spills or other chemical contamination from construction equipment.”⁶</p> <p>“Table 1.5-1, Regulation Summary: Authority to regulate discharges of waste into waters of the State, which are defined as “any surface or groundwater, including saline water, within the boundaries of the State” (California Water Code, Section 13050). This definition includes, but is broader than, waters of the United States.</p>

⁵ Joint EIS/EIR at pg. 4-47.

⁶ Joint EIS/EIR at pg. 4-227 and 4-228

Comment Number	Commenter	Topic	Comment	Response
30a (cont.)	District	Whether Discharge is a "Waste"		<p>Primarily implemented through waste discharge requirements (WDRs).</p> <p>Table 1.5-1, Applicability to Shoreline Phase I Project: WDR Order No. R2-2008-0078 established limitations on the discharge of waste associated with the SBSPRP activity for restoration of 3,069 acres of former salt ponds and ongoing maintenance. Either this WDR would be amended to apply to the Shoreline Phase I Project or the Shoreline Phase I Project would have a similar WDR order."</p> <p>Therefore, the Tentative Order is consistent with the Project's Joint EIS/EIR in that it implements the requirements in its provisions that were anticipated therein as related to discharges of waste (i.e., sediment). Provisions 4, 5, 6, 7, 8, 9, 10, 12, and 13 all facilitate waste disturbance management by requiring construction BMPs that limited waste disturbance and discharge, or plans that outline methods to limit waste disturbance and discharge.</p> <p>The San Francisco Bay Water Board's Basin Plan designates beneficial uses, establishes water quality objectives, and contains implementation programs and policies to achieve those objectives for all waters addressed through the plan. Sediment is regulated by Basin Plan Discharge Prohibition 9, which prohibits the discharge of "[silt, sand, clay, or other earthen materials from any activity in quantities sufficient to cause deleterious bottom deposits, turbidity or discoloration in surface waters or to unreasonably affect or threaten to affect</p>

Comment Number	Commenter	Topic	Comment	Response
30a (cont.)	District	Whether Discharge is a "Waste"		<p>beneficial uses."⁷ The intent of prohibiting such discharges "is to prevent damage to the aquatic biota by bottom deposits which can smother non-motile life forms, destroy spawning areas, and, if putrescible, can locally deplete dissolved oxygen and cause odors."⁸</p> <p>In this case, the discharge will be entirely associated with human activities as opposed to natural deposition. The harmful effects of the fill on the aquatic environment are described extensively in the Joint EIS/EIR. The Impacts section of the Order (See Findings 20 to 22 and Finding 31) have been revised to discuss the impact fill has on beneficial uses. Water Code section 13263 authorizes the regional water boards to regulate discharges of dredge and fill materials with WDRs to protect the beneficial uses of waters of the State.</p>
30(b)	District	Application of Water Code Section 13376	<p>Nor would Water Code section 13376 authorize the Regional Board to issue a permit to the District for dredge-and-fill discharges. Water Code section 13372(b) unambiguously makes Water Code section 13376 operative "only to discharges for which the state has an approved permit program" under Section 404 of the Clean Water Act. California does not have an approved permit program under Section 404, and thus section 13376 cannot give the Regional Board authority.</p>	<p>The operation of the Water Code is not contingent upon the State having an approved program to issue 404 dredge and fill permits under the Clean Water Act. The District provides no authority to support such an assertion.</p> <p>The Legislature added Chapter 5.5 to the Water Code in 1972 to provide the State Board with adequate statutory authority to implement the federal Clean Water Act National Pollutant Discharge Elimination System (NPDES) permit program.⁹ In 1978, Chapter 5.5 was amended to authorize a state</p>

⁷ Basin Plan, Table 4-1.

⁸ *Ibid.*

⁹ Stats. 1972, ch. 1256.

Comment Number	Commenter	Topic	Comment	Response
30(b) (cont.)	District	Application of Water Code Section 13376		<p>permit program to permit discharges of dredged or fill material.¹⁰ Nothing in the 1978 amendments or subsequent changes to Chapter 5.5 should be construed as preventing the State from protecting water resources against unpermitted discharges, regardless of whether it has obtained approval to issue dredge or fill material permits implementing the Clean Water Act section 404 permit program. A careful reading of the provisions in Chapter 5.5, particularly sections 13372 and 13376, supports this conclusion.</p> <p>Water Code section 13372 establishes that Chapter 5.5. shall be construed to ensure consistency with the implementation of the Clean Water Act.¹¹ Section 13376 requires a person discharging or proposing to discharge dredge and fill material to waters of the United States to file a report of waste discharge with the State. Water Code section 13377 requires the State Board or regional boards to, as required or authorized by the Clean Water Act, issue dredge and fill materials. Read together, these Water Code provisions establish the framework for state authority to assume the federal permitting program under Clean Water Act section 404. Nothing in the express language of these provisions operates to prevent the San Francisco Bay Water Board from issuing WDRs for discharges to waters of the State. Moreover, as explained below, the practical effect of sections 13376 and 13377 is limited because California has not taken over the 404 permitting program.</p>

¹⁰ Stats. 1978, ch. 746.

¹¹ Wat. Code § 13372, subd. (a).

Comment Number	Commenter	Topic	Comment	Response
30(b) (cont.)	District	Application of Water Code Section 13376		<p>Subdivision (b) of Water Code section 13372 limits the authority of the State to issue section 404 permits and to require reports of waste discharge until the State actually takes over the program. It states, in part, that “[t]he provisions of Section 13376 requiring the filing of a report for the discharge of dredged or fill material and the provisions of this chapter relating to the issuance of dredged or fill material permits by the State Board or a regional water board shall be applicable only to discharges for which the state has an approved permit program.”¹² This provision only seeks to eliminate the confusion and inconsistency that would arise from a scenario in which the Corps and the State concurrently issued 404 permits; it does not bar the implementation of all other provisions in Chapter 5.5 related to dredge or fill activities, or any other section of Porter-Cologne. This interpretation is supported by the plain language of section 13376, which states “[t]he discharge of [...] dredged or fill material [...] <i>except as authorized by [...] dredged or fill material permits, is prohibited.</i>”¹³ Section 13376 explicitly notes the potential circumstance where a regional water board may require a report of waste discharge for discharges in waters of the State:</p> <p style="padding-left: 40px;"><i>Unless required by ... a regional board, a report need not be filed under this section for discharges that are not subject to the permit application requirements of the</i></p>

¹² Wat. Code § 13372, subd. (b) (emphases added).

¹³ Wat. Code § 13376 (emphases added).

Comment Number	Commenter	Topic	Comment	Response
30(b) (cont.)	District	Application of Water Code Section 13376		<p>Federal Water Pollution Control Act, as amended.¹⁴</p> <p>Section 13372 is silent on the provision of section 13376 that prohibits the unauthorized discharge of dredged and fill material, and is otherwise silent on other sections of Porter-Cologne, requiring the San Francisco Bay Water Board to issue WDRs for discharges of waste to waters of the State. Had the Legislature intended to limit the State’s authority to regulate dredge and fill discharges in State waters until such time that the State has an approved permit program, the Legislature would have also done so explicitly in section 13376.</p>
30(c)	District	Application of Water Code Section 13270	<p>Finding 4. Local-Federal Partnership</p> <p>Even if this Project were a discharge of waste, the Tentative Order, in finding 4, recognizes that this project will be built on the District's property. Water Code section 13270 precludes issuing waste discharge requirements to one public agency for discharges of waste on that agency's property by another public agency. Because this Project will be constructed by USACE on the District's property, and both are public agencies, Water Code section 13270 prohibits issuing waste discharge requirements for the construction of the Project to the District.</p>	<p>Water Code 13270 states:</p> <p>Where a public agency as defined in subdivision (b) of Section 13400 leases land for waste disposal purposes to any other public agency ..., the provisions of Sections 13260, 13263, and 13264 shall not require the lessor public agency to file any waste discharge report for the subject waste disposal, and the regional board ... shall not prescribe waste discharge requirements for the lessor public agency as to such land....</p> <p>To the extent section 13270 has any application, the State Board construed section 13270 in State Water</p>

¹⁴ *Ibid.*

Comment Number	Commenter	Topic	Comment	Response
30(c)	District	Application of Water Code Section 13270		<p>Board Order WQ 90-3 (<i>San Diego Unified Port District</i>). In that order, the State Board considered whether it was appropriate to name the Port District as a discharger on National Pollutant Discharge Elimination System (NPDES) permits held by various ports and boatyards. The State Board first noted that Water Code section 13270 “supports the conclusion that it is appropriate to name non-operating landowners in waste discharge requirements.”¹⁵ The State Board ultimately remanded the NPDES permits to the San Diego Water Board with instructions to specify more clearly that the Port District was not responsible for monitoring or day-to-day operations, “or at most it should be held only secondarily liable for permit obligations.”¹⁶ <i>San Diego Unified Port District</i> states: “The Regional Board has the discretion to name non-operating landowners in waste discharge requirements/NPDES permits because landowners may properly be considered “dischargers” under the Clean Water Act and the Water Code.”¹⁷</p> <p>This is not a situation like the <i>San Diego Unified Port District</i>, where there was an entity who only held title to the land, but was not actively involved in the discharge. District staff has completed Project actions including identifying potential sources of sediment for the Project’s levee and sites where that sediment could be stored, negotiating with site landowners regarding that storage, and coordinating with City of San Jose staff on aspects of Project design, including Pond A18 acquisition. In addition,</p>

¹⁵ *San Diego Unified Port District* at p. 4.

¹⁶ *Id.* at pp. 4 and 5.

¹⁷ *Id.* at p. 15.

Comment Number	Commenter	Topic	Comment	Response
30(c)	District	Application of Water Code Section 13270		<p>the District’s responsibilities include Project monitoring and oversight, as evidenced in the approval of the Joint EIS/EIR (see response to Comment 30(d)). The District and the Conservancy are partners with the Corps in the Project, as further evidenced in the Design Agreement between these parties that outlines the partnership’s design roles and responsibilities, including a 35/65 percent Non-Federal Sponsor to Federal Sponsor cost-sharing ratio, and the eventual Project Partnership Agreement (PPA) that will provide similar details regarding Project construction and O&M responsibilities and cost-sharing percentages. The Joint EIS/EIR further details the District’s specific responsibilities in overseeing the construction contractor and other duties with respect to protecting water quality, including monitoring/oversight. When the Joint EIS/EIR was approved by the District, each Project partner’s responsibility and duties, as it pertains to Project implementation, were detailed in the Mitigation Monitoring and Reporting Program (MMRP). The MMRP stated the following:</p> <p>“...The USACE is responsible project design, construction, and initial maintenance of the improvements. The District is responsible for partially funding the Project, acquiring real property interests needed for the project, and operating and maintaining the Project’s flood risk management elements after construction is complete.</p> <p>“...The table below provides a summary of the AMMs and mitigation measures proposed for the Project and for each measure identifies the timeframe for implementation, the entity/entities</p>

Comment Number	Commenter	Topic	Comment	Response
30(c)	District	Application of Water Code Section 13270		<p>responsible for implementation, and the entity/entities responsible for monitoring oversight.”</p> <p>The table referenced in the MMRP goes on to list the District as the party responsible for monitoring/oversight on nearly every AMM and mitigation measure. The following AMMs had shared implementation responsibility for all Project partners, including the District: GEO-5, HYD-1A, HYD-1B, HYD-1C, WAT-17, ABR-11, TBR-2C, and REC-2.</p> <p>In this case, there is a discharge that could affect water quality. The District’s Board Agenda Memoranda (March 22, 2016) acknowledges that “the Project would result in significant impacts on hydrology, water quality, biological resources....” Impact Wat-01 (violate any water quality standard or waste discharge) lists 24 mitigation measures the District deemed necessary. A person discharging waste that could affect the quality of waters of the State must file a report of waste discharge.¹⁸ In cases where a discharger proposes a discharge that will impact waters of the State, Water Code section 13263 states that the regional board “<i>shall</i> prescribe requirements as to the nature” of the proposed discharge.¹⁹ The Order appropriately identifies the District as a discharger.</p>

¹⁸ Wat. Code § 13260.

¹⁹ Wat. Code § 13263 (emphasis added).

Comment Number	Commenter	Topic	Comment	Response
30(d)	District	Application of CWA Section 401	Nor may the Regional Board issue a Section 401 certification to the District. Section 401 applies only to persons who apply for a federal license or permit. (33 U.S.C. 1341(a).) The District has not applied for a federal license or permit, and thus Section 401 does not apply to the District.	<p>The Water Board may regulate the District’s dredge and fill activities in the absence of an application.</p> <p>As U.S. EPA explains in the “Clean Water Act Section 401 Water Quality Certification: A Water Quality Protection Tool For States and Tribes” (401 Handbook), however, the Corps (the applicant in this case) does not permit its own dredge and fill activities pursuant to Clean Water Act section 404, but will still apply for section 401 water quality certification.²⁰ This is codified in the Code of Federal Regulations:</p> <p style="padding-left: 40px;">Although the Corps does not process and issue permits for its own activities, the Corps authorizes its own discharges of dredged or fill material by applying all applicable substantive legal requirements, including public notice, opportunity for public hearing, and application of the section 404(b)(1) guidelines. The CWA requires the Corps to seek state water quality certification for discharges of dredged or fill material into waters of the U.S.²¹</p> <p>The State Water Board is authorized to administer water quality certification in California²² and has promulgated Title 23 of the California Code of Regulations, section</p>

²⁰ 401 Handbook, https://www.epa.gov/sites/production/files/201611/documents/cwa_401_handbook_2010.pdf, at p. 4.

²¹ 40 C.F.R. § 336, subd. (a)(1).

²² Wat. Code § 13160.

Comment Number	Commenter	Topic	Comment	Response
30(d) (cont.)	District	Application of CWA Section 401		<p>3855, which requires that an “application for water quality certification shall be filed with the regional board executive officer in whose region a discharge may occur.” The requirement to apply for certification under is inherent in Clean Water Act section 301, prohibiting discharge without a permit, and explicitly required by section 3855, requiring submission of an application for certification before discharging.</p> <p>There is no question that certification is required for the Project, which the District and Corps agree involves dredge and fill activities that impact waters of the United States.²³ There is also no question that the District is appropriately named as a discharger in a certification for this Project, given the District’s involvement in key aspects of the project, as described in the response to Comment 30(c). Staff construed the Corps’ application for certification and the District’s Joint EIS/EIR to be an application that covered both the District’s and the Corps’ activities. The only alternative interpretation is that the Corps and District failed to comply with requirements that parties apply for water quality certification for dredge and fill activities. Moreover, proceeding without certification would violate the Clean Water Act, leaving both the Corps and the District vulnerable to the Clean Water Act’s citizen suit provisions, so it is to the District’s benefit that the Water Board has acted to issue a WDR/WQC.</p>

²³ Clean Water Action Section 404(b)(1) Determination (July 1, 2015), Section 8.0 Waters of the United States Impact Estimates.

Comment Number	Commenter	Topic	Comment	Response
30(d) (cont.)	District	Application of CWA Section 401		<p>Finally, the State’s authority to protect waters focuses on the protection of beneficial uses and is broader than the Corps’ authority under Clean Water Act section 404. The Water Board has independent authority under the Water Code to regulate discharges of waste to waters of the State, including wetlands, that would adversely affect the beneficial uses of those waters, through waste discharge requirements or other orders.²⁴ Water Code section 13263(a) requires the Water Board to “implement any relevant water quality control plans that have been adopted, and shall take into consideration the beneficial uses to be protected, the water quality objectives reasonably required for that purpose, other waste discharges, the need to prevent nuisance, and the provisions of Section 13241.” The Water Board has statutory authority under Porter-Cologne to adopt WDRs requiring mitigation, independent of Clean Water Act section 401.</p>

²⁴ Basin Plan § 4.23.4.

Comment Number	Commenter	Topic	Comment	Response
31	District	Landward Levee Alignment East of Artesian Slough	<p>Finding 13. Future Project Design Decisions.</p> <p>Finding 13 discusses an alternative, more landward, levee alignment east of Artesian Slough for Reaches 4 and 5 that the Tentative Order describes, in finding 21 and elsewhere, as having greater environmental benefits with fewer impacts. The District and its Project partners considered suggestions for alternative alignments in the EIR/EIS process, including the Regional Board's suggestion of the alternative alignment raised in the Tentative Order. The District has considered, and will consider, alternative alignments, though the District is mindful that alternative alignments need to be feasible.</p> <p>Different alternative alignments raise various feasibility constraints, including enduring that any alternative is within the scope of the Project authorized for the USACE by Congress, avoiding interference with the City of San Jose's current plan for the San Jose-Santa Clara Regional Wastewater Facility, maintaining adequate buffers against a nearby San Jose Police Department bomb facility, and achieving consensus among stakeholders for the inclusion of legacy biosolid lagoons on the bayside of the proposed levee.</p> <p>The District and its Project partners expect to continue assessing whether these constraints can be overcome by the alternative alignment discussed in the Tentative Order, or by some</p>	See response to Comment 6.

Comment Number	Commenter	Topic	Comment	Response
31 (cont.)	District	Landward Levee Alignment East of Artesian Slough	variation of that alternative alignment. While Attachment C to the Tentative Order acknowledges some of these constraints, that appendix and those constraints are not clearly acknowledged in, or incorporated into, the Tentative Order itself. The Tentative Order should more clearly acknowledge that alternative alignments may not be achievable, and the Regional Board should not be linking possible future mitigation requirements to alternatives that may not be achievable.	
32	District	Mitigation	<p>Finding 30. California Environmental Quality Act (CEQA)</p> <p>The main impact identified in the Tentative Order-filling of waters of the United States-was analyzed in Section 4.6.5 of the EIR/EIS. The EIR/EIS concluded, in Section 4.6.6, that the fill of waters associated with the Project would have only less-than-significant impacts. Because impacts from fill would be less-than-significant, CEQA does not allow the Regional Board to impose additional mitigation for fill-related impacts.</p> <p>As for other impacts identified in the EIR/EIS, the Tentative Order, in finding 30, correctly notes that the EIR/EIS found that the mitigation measures proposed in the EIR/EIS "would mitigate all of these impacts to less than significant levels". The Regional Board does not have authority to second-guess the conclusion of the EIR/EIS that no additional mitigation is</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
32 (cont.)	District	Mitigation	necessary for these impacts that will already be mitigated to less-than-significant levels. (See <i>Ogden Env'tl Serv. v. City of San Diego</i> (S.D. Cal. 1988) 687 F.Supp. 1436, 1450-1452 (responsible agency does not have authority over impacts mitigated to less-than-significant levels).)	
33	District	TAC	<p>Provision 22. Technical Advisory Committee (TAC)</p> <p>Provision B.20 [22] requires the formation of a technical advisory committee (TAC) to assess, review, and suggest adaptive management strategies. The Mitigation and Adaptive Management Plan (MAMP), included as Attachment B to the tentative Order, in Section 5, already prescribes a process for how decision-making will occur as part of the adaptive management process. While the District does not object to receiving suggestions and advice from the TAC, the ecosystem restoration activities would be undertaken through the MAMP's adaptive management process, and the Tentative Order should make clear that the TAC has no actual decision-making authority in the adaptive management process.</p>	<p>Comment noted. The use of technical advisory groups is a common and appropriate practice and means by which project proponents can take advantage of significant expertise in an efficient way, to a project's benefit. The Water Board's involvement in the TAC would be focused on providing our staff expertise to assist in the collaborative scientific discussion, rather than a regulatory oversight involvement. The TAC would be organized and convened through a public process by the Discharger. TAC members would include the Water Board, BCDC, Conservancy, Corps, USFWS, and the NMFS. The TAC's purpose is to assess the Project's ecosystem restoration success. The goal of the TAC is facilitate discussions about the most recent monitoring data. While the TAC may not have decision-making authority, the TAC would still provide input regarding adaptive management decisions. The TAC would have the same decision making authority as the MAMP's adaptive management team (AMT), as evidenced in MAMP Section 5.0, "The AMT would report the results of the vetting process to the USCE, who will decide whether to take action."</p>

Comment Number	Commenter	Topic	Comment	Response
34	District	Fees	<p>Finding 41 and Provision 48</p> <p>Finding 50 [41 and Provision 48] prescribes fees that the District would be responsible for. But Government Code section 6103(a) exempts the District from having to pay any fees.</p>	<p>We disagree. The Board has required named sponsors who are partnering with the Corps to pay fees that would otherwise be due</p> <p>Section 6103.4, subdivision (g), specifically notes that section 6103, subdivision (a) does not apply to any fees required by Division 7 of the Water Code. Issuance of WDRs falls within the services described in Division 7.</p>
35	District	Maintenance	<p>Finding 5. Discharger</p> <p>Finding 5 states that, after 10 years, the Non-Federal Sponsors will assume the costs of the ponds' operation, maintenance, and management. This finding should be changed to make clear that responsibilities for costs, which will also include costs of operating and maintaining the new flood protection structures, will be allocated pursuant to the Project Partnership Agreement, which has not yet been completed.</p>	<p>The requested change has been made to the Tentative Order. See response to Comment 1.</p>
36	District	Project Site Description	<p>Finding 7. Site Description and Background</p> <p>Finding 7 states that Alviso has over 2,000 residents and 500 structures. It would be more accurate to state that Alviso has over 2,500 residents and 1,100 structures.</p>	<p>Comment noted. The language regarding Alviso was taken from the application materials. The Tentative Order has been revised as follows:</p> <p>The community of Alviso has over <u>2,500</u> residents, <u>1,100</u> structures, and 3,000 commuters who work and travel through the area each day.</p>

Comment Number	Commenter	Topic	Comment	Response
37	District	Union Pacific Railroad	<p>Finding 8. Project Construction Phasing</p> <p>Finding 8 could be read to suggest that the Project is intended to allow the Union Pacific railroad tracks to continue functioning over Artesian Slough. Keeping the railroad functioning has nothing to do with Artesian Slough. The reference to Artesian Slough should be deleted as it relates to the railroad.</p>	<p>Comment noted. The Tentative Order has been revised to clarify that Finding 8 addresses the railroad’s continued operation.</p> <p>“Appropriate infrastructure construction where the Project crosses the Union Pacific railroad tracks and Artesian Slough to ensure the Project can provide effective flood protection while still allowing the railroad to function effectively. This Order does not authorize a separate project to modify the railroad line to address the effects of anticipated sea level rise.”</p>
38	District	Landward Levee Alignment East of Artesian Slough	<p>Finding 10. Phase I (2018-2022)</p> <p>Finding 10, among other findings, refers to Reaches 4 and 5 of the FRM levee as being a "proposed conceptual" alignment. That alignment is not conceptual; it is the Congress-authorized alignment. All references to the "proposed conceptual" alignment for Reaches 4 and 5 should be changed to "authorized" alignment.</p>	<p>Comment noted. Since the currently-proposed alignment along Reaches 4 and 5 is only at a 30 percent design stage and may change, in order to minimize costs and maximize ecosystem restoration opportunities, prior to its construction, then the current "proposed conceptual" description is accurate.</p>
39	District	Artesian Slough Crossing	<p>Finding 10. Phase I (2018-2022)</p> <p>Finding 10 states that "Where the levee crosses an existing water feature, such as a slough, structures will be installed to allow flow during normal conditions and during flood conditions."</p> <p>As described in the Project EIR, a tide gate closure structure is being designed to be placed</p>	<p>Comment noted. The Tentative Order’s existing language appropriately reflects expectations regarding discharges and flows at Artesian Slough. The requested edit would not significantly modify its meaning.</p>

Comment Number	Commenter	Topic	Comment	Response
39 (cont.)	District	Artesian Slough Crossing	<p>across the Artesian Slough to prevent water from overtopping existing levees along the slough during future high-tide events. The tide gate structure will be designed in coordination with the City of San Jose to allow for the city's wastewater treatment plant's discharge during storms. It is expected that the tide gate structure would remain open during normal and flood conditions, but that the opening would be regulated depending on flow conditions.</p> <p>The District suggests that the word "allow" be revised to "regulate".</p>	
40	District	Other	<p>Finding 10. Phase I (2018-2022)</p> <p>Finding 10 discusses planting or seeding of marsh vegetation at the toe of the levee following construction. Generally, in the San Francisco Bay it is not necessary to seed marsh plain species because tidal waters have sufficient seed source. Active planting and seeding of marsh vegetation will be done as an adaptive management measure only as necessary.</p>	The requested change has been made in the Tentative Order. See response to Comment 3.
41	District	Other	<p>Finding 10. Phase I (2018-2022)</p> <p>Finding 10 (in the section on "Ponds A12 and A18 Tidal Restoration") gets the descriptions of Ponds A 12 and A 18 reversed. The finding currently suggests that the bottom elevation of Pond A 18 is lower than the bottom elevation of Pond A 12. In fact, as noted in Section 3.8.3.2 of</p>	<p>The descriptions of Pond A12 and A18 were taken directly from the application materials. The revisions requested in this comment have been made in the Tentative Order.</p> <p><i>Ponds A12 and A18 Tidal Restoration:</i> Ponds A12 and A18 are proposed for the first phase of</p>

Comment Number	Commenter	Topic	Comment	Response
41 (cont.)	District	Other	the EIR/EIS, Pond A12 has the lowest bottom elevation of all the ponds. The Tentative Order should reverse the descriptions of Ponds A 12 and A 18.	<p>restoration because they have experienced the greatest degree of subsidence, and their <u>Pond A12's</u> bottom elevation is too low to support intertidal marsh vegetation. Restoring tidal action to Ponds A12 and A18 maximizes the potential for the sites to accrete sediment transported from the Bay on flood tides. After Pond A12 is breached, the anticipated sediment deposition is expected to raise its bottom elevation sufficiently to support colonization by intertidal marsh vegetation. Pond A18<u>12's</u> bottom elevation is so low that, after it is restored to tidal action, several feet of sediment deposition from sediment transported on flood tides will be needed before the pond bottom reaches a sufficient elevation to support colonization by marsh vegetation. The sedimentation process is expected to proceed at rates determined in part by suspended solids concentrations in the South Bay as well as factors causing re-suspension of sediment, such as wave action and tidal currents, in the South Bay and breached pond (ESA PWA 2012; HTH 2012). <u>After Pond A12 is breached, the anticipated sediment deposition is expected to raise its bottom elevation sufficiently to support colonization by intertidal marsh vegetation.</u> Internal pond dike breaches will be conducted to reconnect historical channels and restore hydrologic connections to the innermost ponds in the Project footprint.</p>

Comment Number	Commenter	Topic	Comment	Response
42	District	CEQA	<p>Finding 30. California Environmental Quality Act (CEQA)</p> <p>Finding 30 incorrectly identifies the CEQA lead agency as the California State Coastal Conservancy. The Tentative Order should indicate the Santa Clara Valley Water District as the lead agency under CEQA. The Tentative Order also incorrectly identifies the Environmental Impact Report (EIR) certification date as September 24, 2015. The District certified the EIR for the project on March 22, 2016.</p>	See response to Comment 13.
District CL-1	District	Mitigation	<p>While the District appreciates that the Tentative Order would approve the Project, the District shares the concerns of USACE and the Coastal Conservancy that the Tentative Order, if adopted, would impose unprecedented, onerous, and unwarranted conditions on a Project the Regional Board should be unreservedly supporting. The fundamental problem with the Tentative Order is that it treats the up-to 2,900 acres of tidal marsh restoration as mere mitigation for 8.76 acres of net fill needed for the flood protection, rather than as a key element of the Project. The tidal marsh restoration is key to the Project, as the Region Board previously recognized for the South Bay Salt Pond Restoration Project; The main reason why the new flood protection system needs to be built is because the Project will be breaching the salt-pond dikes to create new tidal marsh. Nor is the</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
District CL-1 (cont.)	District	Mitigation	Tentative Order’s proposed mitigation ratio of approximately 330:1 reasonable. The District request that the Regional Board revise the Tentative Order to incorporate the comments below.	
43	Corps	Project Purpose and Mitigation Requests	<p>Finding 22. Project Mitigation.</p> <p>The Shoreline Project is a multipurpose project that includes substantial ecosystem restoration in addition to flood risk management and recreation. The ecosystem restoration components of the project were formulated to take advantage of restoration opportunities resulting from construction of flood risk management features to protect adjacent floodplains. They were not formulated by assessing mitigation needs.</p> <p>In addition, the restoration components of the project were not presented under NEPA, CEQA, or the federal Clean Water Act as being mitigation for project impacts. Including habitat mitigation in a restoration project is contrary to national USACE policy and jeopardizes the project.</p> <p>REQUEST: The restoration components of the project should not be treated as mitigation.</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
44	Corps	Project Phases	<p>Due to concerns over potential side effects of breaching ponds, such as effects on water birds and erosion of mudflats, the project includes an adaptive management plan to govern breaching of the second (A9, A10, A11) and third (A13, A14, A15) sets of ponds. The RWQCB and other agencies will have members on the Adaptive Management Team (AMT) and will have input into AMT decisions. If breaching of these additional ponds is effectively required by the Order, this would negate the science basis</p> <p>This plan will use a science-based approach, informed by monitoring data, to decide whether and when to breach ponds beyond the initial breaches at ponds A12 and A18. The plan balances trade-offs between aquatic habitat types and their respective benefits as the restoration progresses. The project sponsors expect that all the ponds will be breached over time, but safeguards are needed to ensure that impacts of breaching are acceptable and to respond to unexpected events should they occur. This adaptive management process will help implement the restoration program for the South Bay adopted by the South Bay Salt Pond Restoration Project.</p> <p>Finding #15 implies that Executive Officer approval is indicated to implement the recommendations of the Adaptive Management Team. Since the additional acreage in Phases II and III are not necessary to offset FRM levee impacts (see Comment #1), the Order should</p>	<p>The Tentative Order recognizes and supports the use of a science-based approach to inform future actions at the second and third sets of ponds. This is consistent with the Water Board’s long history of support of such approaches. This is shown, for example, in our work to participate in the Regional Monitoring Program, the Long-Term Management Strategy for the management of dredged sediment, and the Habitat Goals project, among other efforts. As such, and as recognized in the Tentative Order, we intend to participate in and significantly rely on the work of the adaptive management team to inform Project decisions. At the same time, the Water Board is a regulatory agency responsible for ensuring the Project meets applicable State water quality standards. As such, the Tentative Order appropriately sets forth a discussion of Project impacts and necessary mitigation for those impacts. Significant changes to an authorized project will require appropriate review, and the Tentative Order sets for efficient mechanisms for such review, delegating more-minor reviews to the Executive Officer.</p> <p>It is standard practice in Water Board permitting for the Water Board to approve acceptable impacts to waters of the State and to determine the sufficiency of mitigation for those impacts. Since we are responsible for ensuring that sufficient mitigation is provided for impacts authorized by Water Board permits, it is inappropriate for us to delegate oversight of that mitigation to other agencies. Although other agencies, such as the Corps and the California Department of Fish and Wildlife (CDFW)</p>

Comment Number	Commenter	Topic	Comment	Response
44 (cont.)	Corps	Project Phases	<p>focus on process for involving and informing Water Board staff in the Adaptive Management process rather than having these decisions be subject to Executive Officer approval. The Adaptive Management Team, which will include the Water Board, will make the decision to breach or not breach ponds in Phases II and III based on available science. of the Monitoring and Adaptive Management Plan as well as its intended role in mitigating potential impacts under NEPA and CEQA.</p> <p>REQUEST: Revise text to indicate that the base project includes the FRM actions plus tidal restoration of ponds A12 and A18. Additional tidal restoration (ponds A9-A11, A13-A15) is likely but the timing is not certain. Tidal restoration of these ponds should not be required by the Order (directly or indirectly) as these restoration decisions will be governed by the Monitoring and Adaptive Management Plan. The decision on whether and when to breach should not be subject to Executive Officer approval.</p>	<p>also require mitigation for impacts, it is very rare for the Water Board, or its Executive Officer, to require mitigation that is contrary to the requirements of the Corps Regulatory Division or the CDFW. The Water Board is committed to making decisions that are consistent with the best available science, and to considering the recommendations of the AMT with respect to any necessary modifications to project mitigation.</p> <p>If data obtained in the future supports not breaching some Phase II or Phase III ponds, the Water Board is committed to working with all parties to revise the project in a manner that is consistent with good science, as well as conformance with Water Board regulations and policies. If significant revisions are necessary to allow for less conversion of salt ponds to tidal marsh, the permittees will have a full opportunity to present alternative project designs to the Water Board for consideration. See response to Comment 9a.</p> <p>In addition, Water Board policies allow for more flexibility in using the best available science than is possible for Corps projects. The Basin Plan incorporates references to acting in conformance with the most recent versions of the Habitat Goals Reports (<i>Baylands Ecosystem Habitat Goals</i> (1999) (<i>Habitat Goals</i>), and the <i>Baylands Ecosystem Species and Community Profiles</i> (2000)). The Corps is constrained by the need to use federally-approved habitat assessment protocols. For example, in the <i>Final Integrated Document for the South San Francisco Bay Shoreline Phase I Study</i> (See pages ES-16 through ES-23), the Corps determined that it</p>

Comment Number	Commenter	Topic	Comment	Response
44 (cont.)	Corps	Project Phases		<p>could not fund the creation of ecotones along the new FRM levee because the only federally approved habitat assessment method, the Combined Habitat Assessment Protocol (CHAP), could not demonstrate a net habitat benefit associated with creating ecotones. Text on page ES-22 of the <i>Final Integrated Document</i> acknowledges that the results from the CHAP model “contradicts the current scientific understanding of the value of upper marsh transitional habitats in tidal marshes.” The Water Board is committed to making decisions that are consistent with the current scientific understanding of marsh habitats.</p> <p>We do not agree that there is complete certainty at this time that the additional acreage of tidal marsh restoration proposed in Phases II and III will not be necessary to offset FRM levee impacts. As is noted in Sections S.3.11.1 through S.3.12.4 of the <i>Final Integrated Document</i>, there is a delay of many years between the first impacts associated with the FRM levee and the initiation of tidal marsh restoration, there is uncertainty with respect to the availability of sufficient sediment in the South Bay to support the restoration of tidal marshes when the levees are eventually breached, and the rate of sediment accretion in tidal marshes may not occur at a rate that is sufficient to sustain tidal marshes as sea level rises.</p> <p>As noted in the general response regarding mitigation, the comment’s stated net fill of less than 8.76 acres described for the Shoreline Project is based in part on giving the Project credit for all tidal marsh creation that will be associated with lowering</p>

Comment Number	Commenter	Topic	Comment	Response
44 (cont.)	Corps	Project Phases		<p>internal levees to marsh elevations in Phases II and III of the Project. If Phases II and III, and their associated lowering of internal levees, are not implemented, then the net fill for the Shoreline Project will increase to approximately 50 to 77 acres. In addition, when we determined that the complete Shoreline Project would have net fill of less than 8.76 acres, we gave the project credit for 28 acres on levees and ecotones that would be uplands at the time of project construction, but would become wetlands after 50 years of sea level rise. Without this allowance for sea level rise, the project’s net fill would have been on the order of 35 acres.</p> <p>We believe that the commenter’s concerns can be sufficiently addressed in the context of the wording in the Tentative Order, and have assured the Corps of this in several meetings.</p>
45	Corps	Mitigation Requests	<p>Finding 22. Project Mitigation Provision 17. Contingency Mitigation and Monitoring Plan (CMMP)</p> <p>Finding #22 and Provision #15 describe portions of the project as constituting “mitigation” for project impacts.</p> <p>The ecosystem restoration components of the Shoreline Project can only occur with the provision of flood risk management. To comply with both national USACE policy and the Bay Conservation and Development Commission Bay Plan, the flood risk management provided</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
45 (cont.)	Corps	Mitigation Requests	<p>must go beyond merely current levels of flood protection and must provide for future sea level rise. This inherently involves placing more fill than if we were merely maintaining current levels of flood protection. that the Bay is facing a future of accelerating sea level rise and declining sediment concentrations. The Water Board should reconsider imposing mitigation requests on projects like this one, as this may discourage these kinds of projects in the future.</p> <p>REQUEST: We ask that that the word mitigation be replaced with restoration throughout the document. Phase I alone (FRM features, ecotone, plus breaching of ponds A12 and A18) makes the entire project self-mitigating.</p> <p>The approach of requesting mitigation in multipurpose projects like the Shoreline project sets a poor precedent for tidal marsh restoration projects and integrated FRM/tidal marsh projects around the Bay. As been noted by various stakeholders in the region, including the Water Board, these types of projects are urgently needed given</p>	
46	Corps	CMMP	<p>Provision 17. Contingency Mitigation and Monitoring Plan (CMMP)</p> <p>Provision #15 states that "The CMMP shall provide for a minimum mitigation amount sufficient to ensure no net loss of area and function, including temporal loss, of waters of the U.S. resulting from the Project."</p>	See response to Comment 15.

Comment Number	Commenter	Topic	Comment	Response
46 (cont.)	Corps	CMMP	<p>This backup mitigation plan is beyond the scope of the authorized project. The Monitoring and Adaptive Management Plan should not require any contingency or compensatory mitigation. The studies requested would also be outside of the scope of the authorized project. If for any reason Congress ceases to appropriate construction funds after only the FRM portion of the project has been completed, this would constitute a major project change and would cause the project team would apply for an amendment to the Order.</p> <p>REQUEST: Delete the CMMP in Provision 15.</p>	
47	Corps	Northern Legacy Ponds (Stairstep)	<p>Provision 37. Impact Reduction and Environmental Benefit Optimization</p> <p>Provision 35 [37] and Attachment C address potential levee alignment changes along the southern edge of Pond A18.</p> <p>The project team is committed to fully evaluating and implementing an optimized FRM levee alignment at the location of the northernmost set of legacy lagoons, located within the easternmost stairstep of the south berm of pond A18. This is subject to three practical conditions:</p> <ol style="list-style-type: none"> 1. The lands are made available to the project in a condition suitable for project use. 2. The alignment change can be supported via value engineering. 	<p>Comment noted. We appreciate and recognize Corps staff's commitment to complete an evaluation of the alternative levee alignments identified in the Tentative Order. The Tentative Order's language reflects extensive discussions with the Corps and other Project stakeholders to identify the work needed to consider alternative alignments. The current language addresses expectations regarding the completion of that work. As a result, we are not proposing changes to the Tentative Order's current language. See responses to Comments 6 and 31 for further clarification regarding the Tentative Order's inclusion of alternative levee alignments.</p>

Comment Number	Commenter	Topic	Comment	Response
47 (cont.)	Corps	Northern Legacy Ponds (Stairstep)	<p>3. No significant new environmental compliance work will be required by the project sponsors.</p> <p>REQUEST: USACE wishes to work out language that would facilitate future inclusion of this area in the project.</p>	
48	Corps	Landward Levee Alignment East of Artesian Slough	<p>Finding 15. Authorization Process for Future Project Phases Provision 37. Impact Reduction and Environmental Benefit Optimization</p> <p>Provision #35 [37] and Finding #15 are intended to memorialize the process that has been established between the Water Board and the project team for refining the designs and optimizing the benefits in Reaches 4 and 5. Pursuant to USACE policy, any alignment changes would take place through the USACE Value Engineering Process. This means that any change needs to save cost or increase environmental benefits for the same cost. To make these decisions, the team is first looking at the real estate and engineering feasibility, and environmental benefits for each alignment change. If the alignment changes are found to be infeasible for reasons in any of the above categories, USACE will be unable to make them and will proceed with the authorized alignment.</p> <p>Some of the submittals that the Water Board requires in Provision 35 are out of step with USACE policy and beyond what is required to</p>	See response to Comment 8. As noted, the requirement for submittal of sedimentation modeling has been removed.

Comment Number	Commenter	Topic	Comment	Response
48 (cont.)	Corps	Landward Levee Alignment East of Artesian Slough	<p>make the alignment change decision. This includes the sedimentation modeling requested in Provision #35, which would be a major undertaking and would delay FRM and subsequent tidal restoration due to the time required.</p> <p>REQUEST: This Provision should be revised so that the list of technical documents to be submitted is not as prescriptive we will provide sufficient documentation to prove that any decision to change or not change the alignment is justified).</p>	
49	Corps	Roles and Responsibilities	<p>Finding 5. Discharger</p> <p>Finding #5 describes the Applicant/"Discharger," as USACE and the 2 Non-Federal Sponsors, despite the fact that USACE was the only entity to apply for a Water Quality Certification. USACE has not waived sovereign immunity relative to state law. Therefore characterizing USACE as a discharger is not appropriate.</p> <p>REQUEST: If the Water Board insists on naming multiple "Dischargers," we ask that you please add clarifying language explaining roles and application of state vs. federal tasks stated in the Order. Suggested additional language is underlined.</p> <p>"The Discharger will implement the Project as described in the application materials and herein.</p>	<p>See response to Comment 1, further describing the responsibilities of the various dischargers, as represented by the dischargers. See response to Comments 1 and 32(d) regarding why naming the Corps, District, and Conservancy as dischargers is appropriate. Also, the Corps applied for Water Quality Certification. As such, it has requested to be named as a Discharger under the Certification.</p>

Comment Number	Commenter	Topic	Comment	Response
49 (cont.)	Corps	Roles and Responsibilities	<p>As described in the project partnership agreement between the USACE and Non-Federal Sponsors, USACE will be responsible for construction of flood protection, ecosystem restoration, and some recreational elements. Although USACE works cooperatively with the Non-Federal Sponsors, USACE is responsible for project implementation and will follow the provisions of this Order that are applicable to federal agencies. Pursuant to the project partnership agreement, this remains in effect until USACE deems a project element complete, at which time it will be turned over to the US Fish and Wildlife Service or non-federal sponsors for operation and maintenance. The USFWS will follow the provisions of this Order that are applicable to a federal agency for operations and maintenance activities on their property. Any construction activities, operations, and maintenance undertaken directly by the non-federal sponsor will follow the provisions of this Order applicable to state and local governments. For example, once the flood risk management (FRM) levee is constructed and fully functional, USACE will transfer the levee’s operation, maintenance, and management responsibility to the District....”</p>	

Comment Number	Commenter	Topic	Comment	Response
50	Corps	Revegetation	<p>Finding 10. Phase I (2018-2022)</p> <p>Finding #10 describes the revegetation of the project area.</p> <p>REQUEST: We ask that you rephrase this so it says that vegetation may be seeded or planted. This is because tidal waters in the Bay have a sufficient amount of seed for vegetation to be established below MHHW without necessitating active planting, as documented by successful tidal marsh establishment without planting at a number of projects.</p>	See response to Comment 3.
51	Corps	Ecotone	<p>Finding 10. Phase I (2018-2022)</p> <p>Finding #10 describes the ecotone slope as 30:1.</p> <p>REQUEST: We ask that you change this to be “an average 30:1 horizontal to vertical slope” to allow for undulation and topographic variation.</p>	See response to Comment 4.
52	Corps	Pond Description	<p>Finding 10. Phase I (2018-2022)</p> <p>Finding #10 switches the descriptions of Ponds A12 and A18. A12 is the deepest and most-subsided pond.</p> <p>REQUEST: Correct pond description.</p>	See response to Comment 41.

Comment Number	Commenter	Topic	Comment	Response
53	Corps	Approvals and Submittals	<p>Some approvals and submittals are described under the findings.</p> <p>REQUEST: We ask that you make sure that any requested approval and submittals are listed in the Provisions section of the Order.</p>	<p>Comment noted. We were unable to identify instances where submittals were inadvertently required in the Findings, but not in the Provisions. Based on further discussion with Corps staff regarding this comment, we understand it was intended as a request to create a “punch list” of required submittals. We will work with Corps staff to create that list leading up to or following the Board meeting at which the Tentative Order is heard.</p>
54	Corps	Earthen Materials	<p>Prohibition 3.</p> <p>Prohibition #3 says that the discharge of earthen materials is prohibited.</p> <p>REQUEST: We ask that you revise this to say “except where authorized by this Order.”</p>	<p>Comment noted. Prohibition 3 has been revised as follows:</p> <p>3. The discharge of silt, sand, clay, or other earthen materials from any activity in quantities sufficient to cause deleterious bottom deposits, turbidity, or discoloration in surface waters is prohibited, <u>except as otherwise described herein.</u></p>
55	Corps	Directional Drilling	<p>Prohibition 7.</p> <p>Prohibition #7 disallows the use of directional drilling.</p> <p>REQUEST: We ask that you move this to the Provisions and state that directional drilling is allowed with the condition of a directional drilling plan approved by the Water Board’s Executive Officer.</p>	<p>Comment noted. The directional drilling prohibition has been removed. The following provision that conditionally allows directional drilling after acceptance of a plan by the Water Board's Executive Offer, has been added to the Tentative Order:</p> <p>12. Directional Drilling Plan. <u>If directional drilling is necessary at the Project site, the Discharger shall prepare a Directional Drilling Plan acceptable to the Water Board’s Executive Officer. The plan shall be submitted</u></p>

Comment Number	Commenter	Topic	Comment	Response
55 (cont.)	Corps	Directional Drilling		<p><u>to the Water Board’s Executive Officer at least 30 days prior to each Project phase in which directional drilling is proposed or may be needed. The Directional Drilling Plan shall contain boring plans that include the following items: a sketch of the approximate locations of drill entry and exit points; the proposed depth of bore and a statement of waterbody conditions that supports the proposed depth of the bore; approximate length of the proposed bores; type and size of boring equipment to be used; estimated time to complete the bore; list of lubricants and muds to be used; name(s) of contractor and cell phone numbers of the construction supervisor(s) and monitor(s); name(s) of the environmental and biological monitor(s); site-specific monitoring conditions; monitoring protocols; and a containment and clean-up plan. The drill mud pressure and volume shall be monitored at all times during drilling to ensure that hydrofracture or other loss of drill muds has not occurred. In the event of a sudden loss in pressure or volume, the Discharger shall take appropriate steps, including immediately halting the drilling operation to ensure that drilling muds are not discharged to waters of the U.S. All drilling muds, slurries, oils, oil-contaminated water, and other waste materials removed from the bore hole or otherwise used during the Project shall be disposed of at a permitted landfill, other appropriately permitted site, or at an upland site approved in advance by the Water Board’s Executive Officer.</u></p>

Comment Number	Commenter	Topic	Comment	Response
56	Corps	Fueling and Equipment	<p>Prohibition 9.</p> <p>It will not be possible to refuel construction equipment only on sites that cannot drain to State waters.</p> <p>REQUEST: Change text to allow refueling in areas that may drain to State waters only under an approved refueling plan.</p>	<p>Comment noted. Prohibition 9, formerly 10, has been revised accordingly. The following provision that requires submittal of a refueling plan has been added to the Tentative Order:</p> <p>11. <u>Spill Prevention and Containment Plan.</u> <u>The Discharger shall prepare a Spill Prevention and Containment Plan (SPCP) acceptable to the Water Board’s Executive Officer. The SPCP shall be submitted to the Water Board’s Executive Officer no later than 90 days prior to start of any construction event in which construction equipment is planned or needed. The plan shall describe the preventative spill measures that shall be implemented, including equipment leak prevention, and what actions shall be taken in the event of a spill. In the event of a containment spill, the Discharger shall take appropriate steps, including immediately halting the construction work, containing and mitigating the spill, and immediately notifying appropriate authorities, including Water Board staff. Containers for storage, transportation, and disposal of containment absorbent materials shall be provided on-site.</u></p>

Comment Number	Commenter	Topic	Comment	Response
Corps CL-1	Corps	Project Purpose	<p>First, the project’s flood risk management and ecosystem restoration features are interdependent; the latter were not formulated by assessing mitigation needs. The ecosystem restoration components of the project were formulated to take advantage of restoration opportunities resulting from construction of flood risk management features. Without construction of these features, tidal habitat restoration would not be feasible in the project area due to the resulting increased flood risk. In addition, the restoration components of the project were not presented under NEPA, CEQA, or the federal Clean Water Act as being mitigation for project impacts. The entire project was evaluated as an integrated whole and was determined to have an overall positive effect on habitat, fish and wildlife, and water quality. It is our position that the project as described in the NEPA/CEQA document does not need mitigation.</p>	See general response regarding mitigation.
Corps CL-2	Corps	Project Purpose	<p>Second, the adaptive management process proposed for the project has been a vital element in alleviating concerns and securing support for the project from a wide variety of stakeholders, as well as in addressing potential impacts of breaching ponds that were discussed in the NEPA/CEQA document. This process, to be administered by a broad-based adaptive management team, is intended to be science-based and responsive to the results of the project’s proposed monitoring program.</p>	See general response regarding mitigation.

Comment Number	Commenter	Topic	Comment	Response
Corps CL-2 (cont.)	Corps	Project Purpose	<p>However, the draft Tentative Order would effectively mandate tidal restoration of all the managed ponds on the project site, voiding this collaborative process and negating the scientific foundation of the proposed adaptive management process. To avoid this outcome, in the event that tidal restoration needs to slow or stop, the project sponsors would need to assume onerous off-site restoration burdens that likely would not be technically feasible.</p>	
Corps CL-3	Corps	Mitigation (CMMP)	<p>Finally, the draft Tentative Order’s proposed Contingency Mitigation and Monitoring Plan (CMMP) would be problematic for several reasons. As explained earlier, USACE restoration projects cannot have habitat mitigation as a component and the project as described should not require mitigation. Also, the conditions that would result in a delay or cessation of pond breaching, such as excessive impacts to water birds or a shortage of sediment in the Bay, would also apply to tidal restoration in alternate locations. In addition, the required offsite habitat restoration plan is not a part of the Congressionally-authorized project and USACE cannot spend federal funds on developing such a plan. For all these reasons, we request that the CMMP be removed from the draft Tentative Order.</p> <p>USACE has reviewed the comment letter and comments from the State Coastal Conservancy and concurs with their comments as well.</p>	<p>See general response regarding mitigation and Comment 15.</p>

General Response Regarding Mitigation

This general response is intended to address Comments 2(a), 2(b), 7, 9, 10, 11, 12, 15, 17, 18, CL-1, CL-2, CL-3, 21, 22, 23, 25, 26, 27, 28, 29, 32, SCVWD CL-1, 43, 45, and Corps CL-1, all of which address mitigation, and many of which have overlapping issues.

Water Board staff views the Project as an important one that will both improve flood protection for Alviso and the nearby area of San Jose, and implement a key part of the larger South Bay Salt Pond Restoration. In part as a result, staff has worked diligently to support Project permitting, including submitting comments on the Project CEQA/NEPA document in early 2015, providing a letter of support to the Corps in 2016 to assist the Corps' internal approval process, meeting regularly over the past year with the SCVWD, Corps, and Conservancy, and providing them and other interested stakeholder with two administrative draft orders to review prior to circulating the Tentative Order for formal public comment. The Tentative Order would authorize the entire Project and sets forth mechanisms facilitate its timely construction, taking into account numerous uncertainties. That work reflects the Water Board's commitment to promoting and facilitating both this Project and projects with large-scale restoration components.

Revisions to the Tentative Order

The Tentative Order has been revised to clarify that the restoration of Ponds A12 and A18 as part of Project Phase I addresses the Project's temporal impacts associated with fill in jurisdictional waters. The Tentative Order has been revised to clarify that while it allows the construction of Project Phases II and III, there are circumstances, relating to the need to avoid to-be-identified adverse impacts to water quality and beneficial uses, where such construction may not be completed.

In response to comments, the Tentative Order has been revised as follows:

Finding 20. Project's Fill of Waters of the U.S.

"...The Project work will also ~~cause permanent non-fill based impacts to modify~~ waters of the U.S., without permanent placement of fill, including berm excavation, outboard dike breaches and lowering, ~~and anticipated habitat conversion from former salt ponds to tidal marsh after tidal action is restored to the ponds, and establishment of~~ a permanent FRM levee maintenance area (see Table 6)."

Table 1: Summary of the Project’s Non-Fill-Based Impacts, Including Restoration Actions.

Permanent Non-Fill Impacts			
Feature	Area	Length	Fill
	(Acres)	(Linear Feet)	(Cubic Yards)
Phase I: Pond A12 southeastern berm excavation	0.740	19,607	
Phase I: Pilot Channel	7.8	4,373	-62,920
Phase I: Pond A12 and A18 outboard dike breaches and internal berm lowering	18.5	16,050	-89,105
<u>Phase I: Restoration of tidal action to Ponds A12 and A18</u>	<u>1,120</u>	==	==
Phase II: Ponds A9-A11 outboard dike breaches and internal berm lowering	20.0	==	0
<u>Phase II: Restoration of tidal action to Ponds A9-A11</u>	<u>900</u>	==	==
Phase III: Ponds A13-A15 outboard dike breaches and internal berm lowering	20.0	==	0
<u>Phase III: Restoration of tidal action to Ponds A13-A15</u>	<u>880</u>	==	==
Phases I to III: Permanent FRM Maintenance Easement	5.32	19,451	0
Total	<u>722,972.36¹</u>	35,657²	-152,025

¹ This amount includes overlapping areas.

² Since the ecotone will run parallel to the FRM levee, the stockpile impact length overlaps with the FRM levee impact length.

Finding 21. Project’s Net Loss of Waters of the U.S.

“...The phasing will result in a net loss of waters ~~during~~starting in Phase I due to the lag time between the initiation of construction activities and the eventual return of tidal action to the ponds, ecotone creation, and anticipated tidal marsh restoration. ~~There~~After Phase I is completed, including Ponds A12 and A18 breaching, there will be an approximate 76.96-acre net loss of waters of the U.S., not including sea level rise mitigation credit. After the 14-year Project is completed, there will be an approximate 8.76-acre net loss of waters of the U.S.,” with the currently proposed FRM levee alignment, although the currently projected loss could turn into a net gain of waters of the U.S. with an alternative landward alignment along Reaches 4 and 5 (see Att. C) (see Table 7).”

Table 2: Summary of the Total Net Loss of Waters of the U.S. by Project Phase.

Created waters of the U.S.		Total Net Loss of waters of the U.S. after creation (acres) ³
Description	Area (Acres)	
Pond A12 southeastern berm excavation	0.740	131.5
Ecotones -below high tide line ⁴	36.0	95.46
Phase I Pond A12 and A18 outboard dike breaches and berm lowering	18.5	76.96
Phase II Ponds A9-A11 outboard dike breaches and berm lowering	20.0	56.96
Phase III Ponds A13-A15 outboard dike breaches and berm lowering	20.0	36.96

This Order specifies minimum required mitigation the Discharger is required to complete to compensate for Project impacts, and deadlines for completing the mitigation (see Finding **Error! Reference source not found.**). Due to the need to phase construction activities and the uncertainty in the final levee alignment and associated impacts, final mitigation amounts may be greater or less than the minimum specified. ~~The~~ herein. To facilitate Project construction, the Order sets forth a process to determine final mitigation requirements as plans for future Project phases are further developed.

³ The values in this column reflect the running net-loss total starting with 132.2 acres of fill-based impacts.

⁴ This area is being counted as new created waters because it has not historically existed in this area.

If there is a minimal net loss of waters of the U.S. from the final FRM levee alignment, then the tidal restoration and ecotone creation, if fully implemented consistent with the deadlines in this Order, will serve as sufficient compensatory mitigation for the impacts from Project construction activities. If there is a net loss of waters of the U.S. from the final FRM levee alignment that is greater than the amount described above in Table 7, the Order requires the Discharger to update the Project’s impact quantities, and propose and implement additional compensatory mitigation as described in the Provisions- (see Provisions 17, 35, and 36). Pursuant to an agreement between the Corps, District, and Conservancy, the Coastal Conservancy is responsible for complying for the requirements of Provision 17, regarding preparation and implementation of a Contingency Mitigation and Monitoring Plan.

When the Discharger submits supplemental applications for future Project work, total Project impacts will be taken into account to calculate the impacts to waters of the U.S., including temporary and permanent losses.”

Finding 22: Project Mitigation

~~“In total, the Project will restore up to 2,900 acres of tidal marsh by 2032 and create approximately 91.52 acres of ecotone by Year 2022, if the proposed restoration is successfully implemented. The Discharger will mitigate the Project’s fill-based impacts by restoration actions that include creating jurisdictional waters of the U.S. and restoring tidal action to existing jurisdictional waters. As detailed in Finding 21 and summarized below, the Project will create approximately 59 acres of new jurisdictional waters from lowering and removing berms, and 36 acres of created ecotone habitat will be immediately below the high tide line, while another 28 acres of created ecotone will become jurisdictional by 2067 from sea level rise. The anticipated restoration of tidal action to the Project’s ponds is expected to provide water quality improvements, habitat for rare and endangered species and resident and migratory shorebirds and waterfowl, more and higher-quality estuarine-upland transitional habitat (ecotone) along the proposed levees in Ponds A12, A13, and A18 than is currently available, protect beneficial uses, and increase the shoreline resiliency to sea level rise. In addition, restoring tidal marsh and creating estuarine-upland transitional habitat is consistent with the Goals Report and CCMP. However, the mitigation requirement may change as designs for the FRM levee alignment east of Artesian Slough are further developed, which may reduce the Project’s fill-based impacts. As discussed in Findings 13 to 15, the Discharger is evaluating an alternative FRM levee alignment east of Artesian Slough that would reduce the Project cost and maximize ecosystem restoration opportunities. The other uncertainty in the final mitigation requirement is the ecosystem restoration’s degree of success. The anticipated tidal marsh habitat acreage may not be successful if observed sediment accretion rates in the South Bay are significantly less than anticipated rates, or mitigation and monitoring results from the first set of breached ponds do not lead to a recommendation to breach Ponds A9-A15. Thus~~ Since berm lowering and removal in Phases II and III are expected to create jurisdictional features that will reduce the Project’s net fill

amount to the currently projected 8.76 acres, there is uncertainty associated with future tidal marsh restoration and its sufficiency as mitigation for Project impacts. Therefore, the mitigation for the Project’s total impacts will become more certain as the designs for future Phases are further developed and the monitoring results provide more information about the likelihood of success for the restoration activities. To account for the uncertainty in the Project’s ecosystem restoration success and FRM levee alignment east of Artesian Slough, the Order sets forth a mechanism to account for, and, as needed, adjust the Project’s impacts and compensatory mitigation amounts authorized by this Order (see Provisions 17, 31, 35, and 36).

... ~~The remaining 8.76~~In addition, the Project will restore up to 2,900 acres of net fill will be mitigated by conversion of existing pond habitat to restored tidal marsh by 2032 and created create approximately 91.52 acres of ecotone, by 2022, if the proposed restoration is successfully implemented. The anticipated tidal marsh and ecotone habitat are regionally scarce and their restoration and creation, respectively, are recommended in the Habitat Goals report (see Finding 16). The ecotone area will convert approximately ~~95.4~~91.52 acres of current salt pond habitat to wetland-upland transitional habitat. The conversion will facilitate a tidal wetlands restoration that mimics historical San Francisco Bay landforms. The net benefit is an increase in tidal marsh habitat and its associated beneficial uses and functions, and a corresponding decrease in salt ponds. This habitat conversion is consistent with the Water Board’s Basin Plan Wetland Fill Policy and California Wetlands Conservation Policy (see Findings ~~32 and 33~~). **Error! Reference source not found. and Error! Reference source not found.** However, the habitat conversion’s success and consistency with these policies is contingent upon the completion of all three Project phases, including the Project’s ecosystem restoration components. The remaining temporal loss of waters of the U.S. from fill-based impacts will be mitigated by the anticipated 1,120 acres of converted habitat (i.e., tidal marsh and ecotone) in Ponds A12 and A18 at the end of Phase I (see Table 8).

Table 8: Summary of Restored Tidal Marsh and Ecotone Creation by Project Phase.

<u>Phase</u>	<u>Maximum Anticipated Tidal Marsh Habitat Restored</u>	<u>Ecotone Created (Acres)</u>	<u>Anticipated Construction (Year)</u>
--------------	---	--------------------------------	--

	<u>(Acres)⁵</u>		
<u>I</u>	<u>1,120⁶</u>	<u>91.52⁷</u>	<u>2022</u>
<u>II</u>	<u>900</u>	<u>0</u>	<u>2027</u>
<u>III</u>	<u>880</u>	<u>0</u>	<u>2032</u>
<u>Total</u>	<u>2,900</u>	<u>91.52</u>	<u>--</u>

Mitigation for Non-Fill-Based Impacts: The Project’s non-fill-based impacts will be mitigated by the corresponding conversion of pond habitat to restored tidal marsh and created ecotone, similar to the mitigation for the remaining ~~net-fill-based temporal impacts~~ (see above). The restored tidal marsh and created ecotones will mitigate the Project’s non-fill based impacts because the ~~size of the habitat conversion is~~ habitat’s expected quality and associated benefits are sufficient to offset ~~the net-fill amount,~~ non-fill based impacts ~~that may result from loss of managed pond habitat,~~ and any temporal loss of functions and values that will occur from the time fill-based impacts occur to when the restoration is implemented- ~~and becomes fully established.~~ Similar to the fill-based impact mitigation, the non-fill-based mitigation ~~is~~ in each phase is associated with and contingent upon completion of ~~all three~~ the respective Project ~~phases~~ phase, including the proposed tidal and wetland restoration- ~~(i.e., Phase I pond conversion impacts are mitigated by the anticipated tidal and wetland restoration in the Phase I ponds, and similarly, impacts associated with the restoration in Phases II and III are mitigated by the restoration in Phases II and III).~~”

The Tentative Order requirement for a Contingency Mitigation and Monitoring Plan (CMMP) has been revised to include submittal of an analysis of the Project’s consistency with the Basin Plan Wetland Fill Policy.

Provision 17. Contingency Mitigation and Monitoring Plan (CMMP).

“The Discharger shall prepare a Contingency Mitigation and Monitoring Plan (CMMP) acceptable to the Water Board’s Executive Officer. The CMMP shall be submitted not later

⁵ These amounts are for the converted habitat on-site, not created jurisdictional waters. Mitigation credit for this conversion is only being given for the temporal loss of waters of the U.S. and functions and values of existing beneficial uses that result from the Project’s fill-based impacts.

⁶ Under the FRM levee landward alignment for Reaches 4 and 5, this amount would be increased by a maximum of 70 acres to approximately 1,190 acres, which would bring the total anticipated tidal marsh restoration amount to 2,970 acres.

⁷ Approximately 55.52 acres of the created ecotone will initially be above the high tide line after construction. After 50 years of the sea level rise, about 27.32 acres will be above the high tide line. The ecotone above the high tide line will enhance beneficial uses associated with tidal marshes by providing high tide refugia for special-status species.

than January 31, 2020 (the year that construction along Reaches 4 and 5 is anticipated). If the Project is delayed and construction along Reaches 4 and 5 does not occur in 2020, the CMMP shall be submitted in the same year that construction along Reaches 4 and 5 is rescheduled to occur. The CMMP shall provide for a minimum mitigation amount sufficient to ~~ensure~~demonstrate consistency with the Basin Plan Wetland Fill Policy and the California Wetlands Conservation Policy (Findings 32 and 33). This shall include an analysis of issues such as ensuring no net loss of area and function, including temporal loss, of waters of the U.S. resulting from the Project. Updates to the CMMP shall be submitted if all or a portion of the Project's ecosystem restoration components is not implemented. Any updates to the CMMP shall be submitted to the Water Board's Executive Officer no later than January 31 in each year that changes to the Project described in the Order are proposed. ~~The~~If the Project's impacts described herein are reduced or increased, a description of the impacts and the difference in acreage from the quantities described herein shall be submitted to the Water Board's Executive Officer. If the updated impacts reflect a net loss of zero acres of jurisdictional waters, then the CMMP shall consist of the Project described herein. Otherwise, the CMMP shall include the following:

- a. AAn analysis of the Project's consistency with the Basin Plan Wetland Fill Policy and the California Wetlands Conservation Policy, as described above, and including a description of any changes to Project components or impacts as compared to the Project description in this Order.
- ~~a.b.~~Consistent with the analysis, a mitigation proposal, workplan, monitoring plan, performance standards, and other information, as appropriate, sufficient to ~~ensure providing~~provide appropriate mitigation of permanent and temporal losses of functions and values of waters of the U.S. resulting from Project implementation, ~~and to ensure that the Project results in no net loss, and a long-term net gain, in wetland and waters area, functions, and values.~~

At a minimum, the CMMP shall propose ~~the creation of an area of waters equivalent to the net loss of area resulting from the Project. In addition, the CMMP shall propose~~ additional mitigation to address delays of greater than 5 years between the timing of impacts and construction of restoration from the schedules listed in the Findings in implementation of the Project's tidal restoration.”

Project Impacts

Several commenters suggest that the project is a multipurpose project, self-mitigating, and requires no additional mitigation.

We recognize that the proposed Project is both a flood management and an ecosystem restoration project. The Tentative Order would conditionally authorize construction of all Project phases – both construction of the levee and the ecosystem restoration. The Tentative Order would

conditionally authorize, but does not require, restoration of tidal action to 2,900 acres of diked Baylands. The mitigation provisions of the Tentative Order are therefore drafted to recognize expected adaptive management actions and account for uncertainties associated with the Project.

As Water Board staff stated in our written comments on the *Draft Interim Feasibility Report and Environmental Impact Statement/Report for the South San Francisco Bay Shoreline Phase I Project, Santa Clara County, CA, SCH No. 2006012020* (Water Board, February 23, 2015) (Joint EIS/EIR), the Project will result in a large amount of fill of waters of the U.S. The large fill amount is due to the FRM levee, which has independent utility, and its associated ecotones, which are aspects of levee design that reduce the levee's expected long-term impacts and provide a restoration benefit with respect to anticipated sea level rise, while also reducing anticipated costs for levee operation and maintenance.

The FRM levee has impacts to waters of the State of up to 58 acres. Even if the restoration elements of the Shoreline Project were not being proposed, the FRM levee would be necessary because: the Alviso area has experienced subsidence in response to historic over drafting of groundwater aquifers; the existing salt pond levees were not designed or constructed to provide FEMA-approved flood protection, and are in a state of poor repair; and sea level rise is likely to result in Bay waters overtopping the existing salt pond levees. If the FRM levee were proposed as a stand-alone project, then compensatory mitigation would be required.

The ecosystem restoration component could not move forward without sufficient flood risk management, which the levee is intended to provide. The restoration is an efficient means to provide necessary compensatory mitigation for the permanent and temporary impacts of fill placement associated with the levee. As the Conservancy and other Project stakeholders have noted in meetings, finding alternate mitigation is likely to be difficult and expensive.

The Order considers, generally, two types of fill-based impacts to jurisdictional waters: first, potential net loss of waters associated with the permanent fill of jurisdictional waters, including wetlands; and, second, temporal losses associated with a delay of 10 to 25 years between initial impacts and the completion of the restoration (i.e., the anticipated establishment of the associated mitigation). For the latter (temporal impacts), the Order has been revised to clarify that they would be fully addressed by completion of the restoration of tidal action to Ponds A12 and A18 during Project Phase I, and that the Phase II and III restoration work, by itself, is considered a self-mitigating restoration project (see above discussion of revisions).

For the former (permanent fill), current Basin Plan Wetland Fill Policy, while flexible, requires, in essence, no net loss and a long-term net gain in the quality, permanence, and area of jurisdictional wetlands. In part as a result, the Revised Tentative Order identifies proposed work in Phases I, II, and III that would mitigate for fill impacts in Phase I, with the goal of achieving no net loss of areal extent. Phase I includes an estimated 132 acres of permanent fill-based impacts that would be mitigated, by a combination of: being placed below the high tide line as ecotones (36 ac); anticipated sea level rise over the next fifty years (28.2 ac); creation of new jurisdictional area in Phase I through a combination of dike breaches, berm lowering, and excavation (19.24 ac); and by approximately 40 acres of new jurisdictional habitat created from berm breaching and lowering during the Phase II and Phase III restoration. If Phases II and III are not completed, there would be a net loss of waters of the U.S. of up to 77 acres immediately following Phase I completion in 2022 and approximately 50 acres in 2067, after subtracting out

the credit given for expected new jurisdictional area that will be created by anticipated sea level rise.

The Tentative Order includes a requirement for a Contingency Mitigation and Monitoring Plan (CMMP)—a key part of the mechanism that allows the Project as a whole to be authorized while still addressing areas of uncertainty about Project design, timing, and impacts. That requirement has also been revised to incorporate an analysis of the developing Project’s consistency with the Basin Plan Wetland Fill Policy. As such, the revision both requires and allows the Discharger to use the analysis to provide the then-most-up-to-date information about Project impacts and benefits to address any potential inconsistencies with the Policy. In addition, as we noted in our response to Comment 1, the Corps’ description of the Project as a multipurpose project does not establish a minimum threshold for tidal marsh restoration that would be necessary to demonstrate that the project is self-mitigating. That approach, however, could be developed in the CMMP’s consistency analysis.

The Interim Feasibility Study and Environmental Impact Statement (EIS)/Environmental Impact Report (EIR) (Joint EIS/EIR) (HDR, July 2015) presents the Shoreline Project as a self-mitigating project because of the tidal marsh restoration component. However, this document does not establish how much restoration is necessary, at a minimum, to provide adequate mitigation for the project impacts to waters of the State associated with the FRM levee. The Order has been written to support the full implementation of the restoration activities. The Order also provides flexibility for modifying mitigation requirements in response to changing circumstances within the project area (e.g., insufficient sediment for tidal marsh restoration, recommendations to delay levee breaching to prevent excessive loss of tidal mudflats, recommendations to retain more managed ponds for water fowl).

In addition, there is no guarantee that the breached ponds will actually accumulate sufficient sediment to support tidal marsh vegetation. As is noted in Sections S.3.11.1 through S.3.12.4 of the Joint EIS/EIR: there is a delay of many years between the first impacts associated with the FRM levee and the initiation of tidal marsh restoration; there is uncertainty with respect to the availability of sufficient sediment in the South Bay to support the restoration of tidal marshes when the levees are eventually breached; and the rate of sediment accretion in tidal marshes may not occur at a rate that is sufficient to sustain tidal marshes as sea level rises. The U.S. Environmental Protection Agency (EPA) also expressed concern in their comment letter ⁸on the Joint EIS/EIR about the time delay between the Project’s first impacts and the tidal marsh restoration:

“...it can take many decades for tidal marsh habitat to develop and the DEIS identifies a time lag between the anticipated project impacts and successful habitat restoration. While this impact is identified as less than significant because the project will result in a net increase in wetlands in the long term, the discussion in the DEIS is not adequate to demonstrate that mitigation is not needed for the loss of wetlands in the near-term.”

⁸ *Draft Environmental Impact Statement for the South San Francisco Bay Shoreline Study: Alviso Ponds and Santa Clara County Interim Feasibility Study Project, Santa Clara and Alameda Counties, California (CEQ # 20140371)* (U.S. EPA, February 23, 2015).

“The FEIS should include additional discussion of likely short-term wetland impacts and further justification for the conclusion that compensatory mitigation is not required. Specifically, the FEIS should identify the acres of wetlands likely to develop within 3-5 years after predicted construction-related impacts. This can be done by estimating the acreage that will fall within the tidal range known to support marsh vegetation. If this acreage of expected short-term wetland development is less than the acreage of wetlands fill, then the FEIS should estimate how long it will take to achieve no net loss of wetlands.”

The Tentative Order Contains a Flexible Mechanism for Determining If Any Additional Mitigation Is Necessary.

Several commenters assert that the Tentative Order requires a 330:1 mitigation ratio. That is incorrect. That ratio assumes the Project will be constructed, as proposed, in its entirety, that the only Project component requiring mitigation will be about 9 acres of permanent fill, and it equates the benefits from the conversion of existing jurisdictional waters to tidal action with the impacts from the permanent fill of jurisdictional waters. It is a simplified analysis that does not consider the range of potential impacts associated with the Project, the Water Board’s Wetland Fill Policy and associated Basin Plan policies, or suggest how potential shortcomings in those policies might be addressed in the face of climate change and anticipated sea level rise. The Tentative Order, including the revisions discussed here, is intended to provide a more-nuanced approach that allows the Discharger to play a significant role in describing Project benefits and, in a more thoughtful way, balance issues like the benefits of conversion with the impacts of fill.

The restoration activities will likely provide sufficient mitigation for impacts to waters of the State associated with constructing the Project. The 2,900 acres of anticipated tidal restoration proposed in Phases I, II, and III would mitigate the loss, through conversion, of 2,900 acres of former salt ponds, which is a permanent non-fill based impact. The Tentative Order recognizes that 2,900 acres of tidal marsh restoration, if successful, are consistent with Bay-wide collaborative science-based guidance including the Baylands Habitat Ecosystem Goals Project, and will provide enhanced beneficial uses over the existing beneficial uses on-site and provide further shoreline resiliency. The use of an ecotone levee design adds to the resilience over time of the proposed restoration design, while improving the range of habitat types present and the beneficial uses those types support. The anticipated enhanced beneficial uses are being counted towards mitigation for the temporal loss of functions and values of beneficial uses and waters of the U.S. that is associated with the time lapse between fill and pond breaching until a fully functional tidal marsh becomes established.

Changes to the required compensatory mitigation may be necessary, however, should there be significant changes to the anticipated Project design or implementation. The Tentative Order recognizes there is uncertainty around both the area of impacts and the area of proposed mitigation. As described in the Order, the Discharger is evaluating alternative landward levee alignments that may reduce the Project’s total net fill. Furthermore, the area of waters to be gained by berm breaching and lowering is a rough estimate that will be informed by design work and adaptive management review that are yet to be completed. Water Board staff expects a portion of the levee alignment to move at least somewhat landward. This, in combination with the restoration project’s beneficial impacts, would result in a Project that is at least roughly fully

self-mitigating. Finally, as noted by the commenter, adaptive management review may determine it is inadvisable to complete all or part of the proposed Phase II and III tidal action restoration.

To address the uncertainty associated with aspects of the Project, including the amount of fill associated with the levee alignment between Artesian Slough and Coyote Creek, the amount of creation that will be accomplished as part of all Project phases, including whether Phases II and III are constructed, the Tentative Order incorporates the CMMP. The CMMP is, in part, an accounting mechanism, describing impacts and proposing, as necessary, changes to mitigation. The CMMP is necessary to account for the potential loss of compensatory mitigation credit that may result if Phases II and III are not completed and, as noted above, to take into account the more-certain information about the Project that will be available the design has been finalized and then once it has been built. The CCMP also provides a means for reporting on progress and modifying the Project's compensatory mitigation, as appropriate. Order Provisions 18, 36, and 37 establish a mechanism by which the Discharger may present all relevant technical information to determine how much, if any, compensatory mitigation is necessary. Any modifications to the compensatory mitigation requirement and relevant technical information will require review and acceptance either by the Executive Officer or the Water Board, with appropriate public review and input.

The CMMP allows the Water Board to revisit the Project's consistency with the Basin Plan Wetland Fill Policy in the future, based on the ongoing performance of restoration elements and on evolving State policies with respect to climate change and sea level rise adaptation. The text of the Order allows the Discharger to implement the Shoreline Project in conformance with Corps policy, while ensuring consistency with Water Board policies.

The Tentative Order defines success in reference to the Discharger's submitted Mitigation and Adaptive Management Plan (MAMP). Monitoring reports and a continued agency collaboration through implementation of a Technical Advisory Committee (TAC) will further define ecosystem restoration success. This approach is taken because the Water Board recognizes that large-scale ecosystem restoration includes uncertainties that require an adaptive management approach. Water Board staff supports and intends to continue participating collaboratively in adaptive management efforts to identify the progress of and appropriate future changes to tidal restoration efforts in the Bay. As such, we support adaptive management efforts as an effective approach to ensure the success of Bay restoration efforts. Based on our ongoing collaborative meetings with the Discharger and other Project stakeholders, we understand that an adaptive management approach was preferred for the reasons stated in the Conservancy's comment. We concur that it is a better, more flexible approach than specifying prescriptive success measurements in the Tentative Order.

Legal Bases for Requiring Mitigation

The Tentative Order identifies the uncertainty around anticipated Project impacts, restoration actions, and expected creation of jurisdictional waters, including wetlands. Given the uncertainty, the Project's expected net fill may best be described as a range running from net creation of waters (should the FRM levee alignment be shifted to the landward-most alternative between Artesian Slough and Coyote Creek and all three Project phases be constructed) to 50-

77⁹ acres of net fill, should Phases II and III not be completed and should there be no changes to the levee alignment.

Compensatory mitigation is required pursuant to the California Wetlands Conservation Policy (“No Net Loss Policy”) and the State’s Anti-Degradation Policy (all part of the San Francisco Bay Water Quality Control Plan). In addition, mitigation is necessary to comply with the California Environmental Quality Act, Clean Water Act and the Porter-Cologne Water Quality Control Act.

The Basin Plan

The Basin Plan incorporates by reference the No Net Loss Policy,¹⁰ the Antidegradation Policy¹¹ and the Corps’ 404(b)(1) Guidelines. These require compensatory mitigation for the fill-based and non-fill based impacts to waters of the U.S. and beneficial uses. The Tentative Order’s compensatory mitigation requirement for the Project’s fill-based impacts and associated temporal impact is consistent with the findings in the Joint EIS/EIR and applicable State regulations.

The commenters correctly note that there are significant uncertainties with respect to the availability of sufficient sediment to support the predicted amount of tidal marsh restoration, in addition to uncertainties with respect to the ability of restored tidal marshes to survive as marshes as sea level rises. These comments support our concern that the project may not actually be self-mitigating over the long implementation period of the complete project, especially if the proposed levee lowering to tidal marsh elevations in Phases II and III does not occur, and net fill of waters of the state increases to approximately 50 to 77 acres.

As such, the Tentative Order appropriately applies the No Net Loss Policy. Findings 32 and 33 cite the No Net Loss Policy and Basin Plan, respectively, and Findings 21 and 22 discuss the Project impacts and the required compensatory mitigation. The comment describes the Project as having 8.76 acres of net fill. However, the Project’s total fill amount, without compensatory mitigation, is more than 132 acres. The difference between those two numbers results from the Water Board staff’s evaluation of the Project as a whole under the No Net Loss policy, as reflected in the Tentative Order. Aspects of that evaluation are summarized in Tentative Order Table 7 and include identifying compensatory mitigation opportunities such as the areas of ecotone-related fill that will provide habitat and remain below the high tide line (36 ac), planned outboard dike breaches and berm lowering associated with Phases I, II, and III (18.5 to 58.5 ac in total), and the areas of fill that will immediately be above the high tide line following fill placement, but will be below the high tide line after 50 years of anticipated sea level rise in 2067 (28.2 ac).

Executive Order W-59-93 is the California Wetlands Policy, more commonly known as the "No Net Loss" Policy. The first objective of the Policy is “[t]o ensure no overall net loss and long-term gain in the quantity, quality, and permanence of wetlands acreage and values in

⁹ As referenced earlier herein, the low end of this range takes into account mitigation credit for anticipated sea level rise over the next 50 years, while the high end is the net fill amount immediately following Phase I construction.

¹⁰ Basin Plan, section 4.23.1 (citing Calif Wetland Conservation Policy Exec Order 59_93).

¹¹ Basin Plan, at 2.1.7 (incorporating Res. 68-16, Statement of Policy with Respect to Maintaining High Quality of Waters in California).

California....”¹² The No Net Loss Policy has been incorporated into Basin Plan chapter 5, Plans and Policies, and also appears in Chapter 4, Implementation Plans (section 4.23), which states: “The Water Board will refer to [the Policy] for guidance when permitting or otherwise acting on wetland issues.” The Basin Plan states that the “Water Board will evaluate both the project and the proposed mitigation together to ensure that there will be no net loss of wetland acreage and no net loss of wetland functions.”¹³ Mitigation is appropriate to ensure compliance with the No Net Loss Policy.

As a part of considering Project compliance with the No Net Loss Policy, the Tentative Order appropriately takes into account programmatic efforts to maintain, restore, and enhance wetlands. These include the 1999 Baylands Habitat Goals project and its associated Habitat Goals Update, as well as the Comprehensive Conservation and Management Plan for the Bay, recently updated by the San Francisco Estuary Partnership. Those planning documents, referenced in the Basin Plan, set forth the reasoning for why restoration of tidal action to historically diked Baylands is desirable, as well as limits to that restoration (e.g., the need to maintain former salt ponds in order to support the bird populations and associated species that have developed there over time). The existing diked former salt ponds are jurisdictional waters of the U.S., and converting the salt ponds to tidal marsh is a permanent impact that will affect the ponds’ existing beneficial uses. The planning documents above help explain why the Project’s proposed conversion is an appropriate and desirable step.

The Antidegradation Policy commits to maintaining higher quality waters of the state to the maximum extent possible.¹⁴ These policies apply to waters of the State, including wetlands, like those at issue here.¹⁵

The Basin Plan also incorporates by reference the Corps’ own regulations,¹⁶ which similarly require mitigation for impacts:

[N]o discharge shall be permitted unless appropriate and practicable steps have been taken which will minimize potential adverse impacts of the discharge on the aquatic ecosystem.¹⁷

[T]he district engineer will issue an individual section 404 permit only upon a determination that the proposed discharge complies with applicable provisions of 40 CFR part 230, including those which require the permit applicant to take all appropriate and practicable steps to avoid and minimize adverse impacts to waters of the U.S. Practicable means available and capable of being done after taking into consideration cost, existing technology, and logistics in light of overall project purposes. Compensatory mitigation for unavoidable impacts may be required to ensure that an activity requiring a section 404 permit complies with the Section 404(b)(1) Guidelines.¹⁸

¹² Executive Order W-59-93 (Aug. 23, 1993), at p. 1.

¹³ Basin Plan, § 4.34.4.

¹⁴ *Ibid.*

¹⁵ Classification of Wetlands, USGS (2013).

¹⁶ Basin Plan, § 4.34.4.

¹⁷ 40 C.F.R. § 230.10, subd. (d).

¹⁸ 40 C.F.R. § 230.91.

CEQA, Clean Water Act and Porter-Cologne

When adopting the Joint EIS/EIR, the District identified three environmental impacts that would remain significant after implementation of feasible mitigation measures, including the following:

“2) The Project will result in the loss of a substantial amount of human-created managed pond habitat that is used by managed-pond-specialist waterbirds (such as eared grebe, Wilson’s phalarope, red-necked phalarope, and Bonaparte’s gull) for foraging and roosting. Over time all the ponds in the study area would be converted. The South Bay Salt Ponds Restoration project and other tidal restoration projects in south bay have been restoring other managed ponds to tidal influence. Cumulatively there would be substantial loss of managed ponds in the Alviso pond complex. Due to the scale of the Project relative to other projects, the incremental impact of the Project would be considered cumulatively considerable. This impact could only be mitigated by replacing pond habitat being converted to tidal marsh. The conversion of other habitat to pond would be inconsistent with the objectives of the project, so no measure are available to lessen this impact. Adaptive management plans are designed to minimize significant impacts to pond-specialist birds, but given the long-term uncertainty of population trends the impact is still considered significant.”

The District’s Board Agenda Memorandum (March 22, 2016) concedes that "the Project would result in significant impacts on hydrology, water quality, biological resources...." Impact Wat-01 (violate any water quality standard or waste discharge) lists 24 mitigation measures, further establishing the numerous Project impacts. Similarly, the Joint EIS/EIR notes the following significant impacts requiring mitigation that are within the Water Board’s jurisdiction: hydrology and water quality, aquatic biological resources, terrestrial biological resources, geology and soils, and hazardous materials. The compensatory mitigation required in the Tentative Order mitigates the significant impact that was identified by the SCVWD that would "...remain significant despite implementation of feasible mitigation measures."¹⁹

The 404(b)(1) Analysis recognized that the increase in jurisdictional waters may be classified as mitigation from a regulatory standpoint:

“The USACE does not consider the increase in jurisdictional waters mitigation, but does recognize that, from a regulatory standpoint, they may be classified as mitigation.”

Consistent with the Discharger’s own findings regarding the Project’s significant impacts to waters of the U.S. and their existing beneficial uses, and the need for mitigation, the Tentative Order recognizes the conversion of pond habitat to tidal marsh (anticipated) will result in permanent, significant impacts to waters of the United States, which are also waters of the State, and their existing beneficial uses. The Tentative Order simply clarifies that the habitat conversion, while still a non-fill based permanent impact, is considered, by the Water Board, to be mitigated by the eventual success of significant tidal marsh restoration. This approach is consistent with the SCVWD’s own CEQA findings and SBSRP’s Order Water Board policy

¹⁹ Board Agenda Memorandum, South San Francisco Bay Shoreline Phase I Study – Resolution Certifying the Final Environmental Impact Report and Adopting Findings of Fact, Statement of Overriding Considerations, and Mitigation Monitoring and Reporting Program; and Approving the Project (March 22, 2016) (File No. 16-0113).

requires mitigation for impacts to waters of the State. For this reason, Water Board staff commented on the Joint EIS/EIR's findings regarding fill of waters of the U.S. and stated compensatory mitigation would be required. Water Board staff commented on the mitigation issue in the Water Board's EIR comment letter. The letter noted that the mitigation proposed for the Project's significant impacts to waters of the State consists of restoring open waters (former salt production ponds) to tidal marsh and outlined the issues with that approach, including uncertainty with respect to restoration success:

“The Project presents permitting challenges, in that it would place fill into up to about 137.6 acres of waters of the State, consisting of 16.8 acres of wetlands and 120.8 acres of other waters. This is a significant amount of Bay fill. The Project would facilitate salt marsh restoration and would be part of a long-term adaptive management strategy to address the potential impacts of sea level rise in the Bay. However, the current proposal could have a significant delay between the placement of levee fill (i.e., the impacts) and the salt marsh restoration work (i.e., the mitigation), and other factors lead to uncertainty regarding the timing and potential success of the restoration.”

One comment suggests that converting the existing pond habitat to tidal marsh habitat should serve as mitigation for the Project's fill-based impacts. This conversion is considered out-of-kind mitigation for permanent fill-based impacts because it does not create habitat (i.e., it results in a net loss of jurisdictional area), as the existing jurisdictional habitat is being converted into a different type of jurisdictional habitat. Therefore, as Water Board staff has noted on several occasions, and documented in the Project's CEQA record, the conversion of habitat in Ponds A9 to 16 and A18 may not serve to fully mitigate for the Project's significant fill impacts to waters of the State. However, the anticipated tidal marsh and areas of restored tidal action will serve as mitigation for the lost former salt pond habitat, the ponds' existing beneficial uses, and the temporal loss of function and values related to the time lapse between the beginning of Project construction and full tidal marsh establishment.

The Water Board has a duty as a responsible agency to require mitigation where necessary, pursuant to CEQA Guidelines 15096, subdivision (g), and 15126.4, subdivision (a)(1)(B). Once the Discharger identified potential impacts within the San Francisco Bay Water Board's jurisdiction, it triggered the Board's duty to evaluate the project and add any necessary mitigation. *Riverwatch v. Olivenhain Mun. Water Dist.* (2009) 170 Cal.App.4th 1186, 1207 holds that a responsible agency has an independent duty to review the EIR and “issue its own findings regarding the feasibility of relevant mitigation measures or project alternatives that can substantially lessen or avoid significant environmental effects.”²⁰

The CEQA Guidelines, the California Code of Regulations, the Clean Water Act, and Porter-Cologne affirm that a responsible agency may require additional mitigation and, in fact, imposes a *duty* to do so upon the responsible agency to do so if there are significant effects. The CEQA Guidelines provide:

²⁰ Citing Remy et al., Guide to the Cal. Environmental Quality Act (CEQA) (11th ed.2007) ch. III, subd. (B)(2), p. 53; Pub. Res. Code § 21081; and 1 Kostka & Zischke, Practice Under the Cal. Environmental Quality Act (Cont.Ed.Bar 2d ed.2008), § 3.22, p. 126.

- “When considering alternatives and mitigation measures, a responsible agency has responsibility for mitigating or avoiding the direct or indirect environmental effects of those parts of the project which it decides to approve.”²¹
- “When an EIR has been prepared for a project, the Responsible Agency *shall not* approve the project as proposed if the agency finds any feasible alternative or feasible mitigation measures within its powers that would substantially lessen or avoid any significant effect the project would have on the environment.”²²

In addition to the CEQA Guidelines, Title 23 of the California Code of Regulations, Section 3742, provides additional regulations specific to regional water boards when acting as responsible agencies:

The Board, when acting as a responsible agency may ... condition the discharge of waste ... for any project subject to CEQA to protect against environmental damage to water resources, to minimize adverse environmental impacts on water resources, or to ensure long-term protection of water resources....²³

Clean Water Act section 401(d) similarly requires that the regional water boards “*shall set forth*” limitations to ensure the permit will comply with “any other appropriate requirement of State law” in the certification. The Corps’ section 401(b)(1) guidelines similarly require mitigation where the Project will have adverse effects, or will degrade the existing aquatic ecosystem including fish.²⁴

Finally, Water Code section 13263(a) requires that regional water boards “(i)mplement any relevant water quality control plans that have been adopted.” As discussed below, the Basin Plan requires mitigation for impacts to beneficial uses to ensure no net loss of wetlands.²⁵

These above authorities consistently require the San Francisco Bay Water Board to act affirmatively to ensure mitigation measures are included in the Order.

The District suggests that once it had adopted mitigation measures in its EIR, there was no role for the Water Board to play, citing *Ogden Environmental Service v. City of San Diego* (S.D. Cal. 1988) 687 F.Supp. 1436, 1450-1452 (*Ogden*). In *Ogden*, the issue was more fundamental: whether an EIR was required at all. The lead agency made the determination that an EIR was not required; a responsible agency (the City) believed that an EIR was necessary and denied approval of the project because there was no EIR.²⁶ The court held that the City had not properly challenged the lead agency’s CEQA determination.²⁷ In doing so, the court construed sections 15096, subdivision (e) and 15162 of the CEQA Guidelines, pertaining to the steps a responsible agency must take to challenge the lead agency’s determination where the responsible agency

²¹ Cal. Code Regs., tit. 14, § 15096, subd. (g) (1).

²² *Id.* at § 15096, subd. (g)(2) [emphasis added].

²³ Cal. Code Regs., tit. 23, § 3742.

²⁴ 40 C.F.R. § 230.12, subd. (a).

²⁵ Emphasis added.

²⁶ *Ogden, supra*, 687 F.Supp. at p. 1441.

²⁷ *Id.* at pp. 1451-52.

believes the final EIR or negative declaration is not adequate for use by the responsible agency.²⁸ *Ogden* does not squarely address the situation here, however, where the District has prepared an EIR, identified significant impacts, and a responsible agency is identifying mitigation measures to address those impacts. Here, where the findings in the EIR determine that mitigation is necessary to reduce impacts, the Water Board “shall not” approve the project where, as here, there are feasible alternatives or mitigation measures within its powers that will substantially lessen or avoid significant effects.²⁹

Consistency With Prior Orders

As noted above, the FRM levee is necessary to protect Alviso against current flooding risks and against the additional flooding risks associated with sea level rise. The FRM levee and ecotone creation will result in net fill of a minimum of 8.67 acres of waters of the State if the Project is constructed, as proposed, in its entirety. They may result in net fill of about 50 to 77 acres of waters of the State if levee lowering associated with tidal marsh restoration is not implemented in Phases II and III. The precedent of the Water Board requiring mitigation for such fill is well established. Not requiring mitigation for fill would be contradictory to long-established Water Board precedent.

Some of the comments suggest that the Tentative Order is inconsistent with Order No. R2-2008-0078 and R2-2005-0034. We disagree. Findings 16 and 74 of Order R2-2008-0078 noted, in essence, that the authorized restoration project was self-mitigating. Finding 96 reflected that order’s requirements to timely complete adaptive management actions necessary to achieve restoration goals. The lack of a penalty refers to the absence of a typical time-based penalty (e.g., a 10 percent increase in mitigation for a specified amount of delay), imposed for failure to timely complete required compensatory mitigation. However, that order did set forth deadlines and related requirements to implement restoration actions, including adaptive management actions, necessary to maximize the restoration’s success and ensure the project’s self-mitigating nature. Additionally, fill associated with the portions of the SBSPRP authorized by Order No. R2-2008-0078 did not include significant amounts of fill associated with providing flood protection for developed areas inland of the former salt ponds. Such fill likely would have been referenced separately in that order, similar to the approach in the Tentative Order.

Separately, Order No. R2-2005-0034, adopted for the Hamilton/Bel Marin Keys wetland restoration project, evaluated the restoration project’s impacts and mitigation together, stating “[t]his project is consistent with the Basin Plan Wetland Fill Policy that establishes that there is to be no net loss of wetland acreage and no net loss of wetland value when the project and any proposed mitigation are evaluated together...” (Finding 37).

The Tentative Order’s compensatory mitigation requirements are consistent with Water Board practice at other sites and take into consideration anticipated sea level rise over the coming 50 years. There are significant differences between a typical mitigation site and the Project’s anticipated tidal marsh restoration. These differences are recognized in the Tentative Order, and the Tentative Order requires compensatory mitigation for the Project’s fill based impacts and associated temporal loss. Consistent with other projects that fill waters of the U.S., the new

²⁸ *Ibid.*

²⁹ Cal. Code Regs., tit. 14, § 15096, subd. (g)(2).

jurisdictional waters created in Phases I to III, which provide similar or increased habitat value, will serve as compensatory mitigation. At most tidal wetland mitigation sites, the elevation of the mitigation site is set at an elevation appropriate to the desired type of tidal marsh vegetation in the same year that authorized impacts to waters of the State are implemented. These mitigation sites usually attain final performance criteria for tidal marsh vegetation and hydrology within five years of authorized impacts to waters of the State. In the Project, however, there will be a significant lag between when the Project's impacts take place and when work is completed on the associated mitigation components. The former salt ponds will not be breached to tidal action until at least five years after the Project places fill in waters of the State. After levee breaching, 10 to 20 years (or more) of sediment accumulation will be necessary before the pond bottom elevations are high enough to support the growth of tidal marsh vegetation. In other words, it will take the restoration ponds at least 15 to 25 (or more) years after initial impacts to get to the physical condition that most tidal marsh mitigation sites attain in their first year. As noted in the Tentative Order, Project impacts are associated significantly with a beneficial public purpose: reducing flood impacts to Alviso and shoreline infrastructure.

As discussed above, there is some uncertainty as to the benefits to be gained by restoring tidal action. These include uncertainty in the time required for sediment to accrete to mud flat or tidal marsh levels in deep ponds (and uncertainty as to whether it will ever accrete to such levels), whether accretion will keep pace with anticipated sea level rise, potential water column chemistry impacts, and other issues. The MAMP speaks to this uncertainty in that it provides the framework for making adaptive management decisions, including discontinuing or delaying future pond breaches, which are based on not only sediment dynamics and wetland vegetation establishment, but also bird use of changing habitats, non-avian species, invasive and nuisance species, and ecotones.³⁰ In addition, although the anticipated tidal marsh restoration is expected to result in habitat that is regionally scarce, provides beneficial uses, and increases shoreline resiliency, the long-term success of tidal marsh restoration and funding mechanism to sustain long-term marsh restoration and monitoring are unclear at this point. Although there is uncertainty in the long-term success of tidal marsh restoration, the Tentative Order recognizes the increased habitat value from the anticipated tidal marsh habitat and allows it to serve as mitigation for the temporal loss of waters of the U.S beneficial uses from permanent fill-based impacts. This approach is consistent with the SBSPRP's Order requirements with respect to the restoration components. In addition, the Tentative Order allows the anticipated tidal marsh restoration enhancement to beneficial uses and shoreline resiliency to mitigate the substantial temporal impact associated with the time lapse between the fill-based impacts' implementation and the anticipated tidal anticipated tidal marsh establishment (see response to SCVWD Comment 28 and Corps Comments 43 and 44). Therefore, the Tentative Order is consistent with the requirements set forth in the SBSPRP's Order and with Basin Plan policy. It goes a step further in that it recognizes the anticipated potential range of Project benefits to offset the Project impacts to the maximum extent that can be allowed by Water Board's governing regulations and policies.

³⁰ *South San Francisco Bay Shoreline Study, Monitoring and Adaptive Management Plan for Ecosystem Restoration* (September 2015).