17

18

19

20

21

22

23

24

25

26

27

28

1	DOWNEY BRAND LLP
2	KEVIN M. O'BRIEN (Bar No. 122713)
2	DAVID R.E. ALADJEM (Bar No. 152203) MEREDITH E. NIKKEL (Bar No. 254818)
3	621 Capitol Mall, 18th Floor
	Sacramento, CA 95814-4731
4	Telephone: 916.444.1000
	Facsimile: 916.444.2100
5	kobrien@downeybrand.com
	daladjem@downeybrand.com
6	mnikkel@downeybrand.com
7	
,	Attorneys for Protestant
8	NORTH DELTA WATER AGENCY, BRANNAN
	ANDRUS LEVEE MAINTENANCE DISTRICT,
9	RECLAMATION DISTRICT 999,
10	RECLAMATION DISTRICT 2060,
10	RECLAMATION DISTRICT 2068,
11	RECLAMATION DISTRICT 407, RECLAMATION DISTRICT 317,
11	RECLAMATION DISTRICT 517, RECLAMATION DISTRICT 551,
12	RECLAMATION DISTRICT 105,
	RECLAMATION DISTRICT 563,
13	RECLAMATION DISTRICT 2067, and
	RECLAMATION DISTRICT 2098.
14	
1	
15	BEFORE THE CALIFORNIA STATE WAT

BEFORE THE CALIFORNIA STATE WATER RESOURCES CONTROL BOARD

In the matter of Hearing re California WaterFix Petition for Change

SURREBUTTAL TESTIMONY OF GILBERT COSIO, MBK ENGINEERS

PROFESSIONAL BACKGROUND AND QUALIFICATIONS

1. I am a registered civil engineer in the State of California. I specialize in the fields of flood control, hydrology, hydraulics, water resources planning, drainage, water supply, surveying, and levee maintenance. I am a principal at MBK Engineers, located at 455 University Avenue, Suite 100, Sacramento, CA 95825. MBK Engineers specializes in water resources engineering and performs these engineering services for local public agencies and private clients, principally in the Delta and the Sacramento Valley. Exhibit DFCG-2, which was previously admitted into testimony, is a true and correct copy of my professional qualifications.

ہم	
DOWNEY BRAND LLP	
Ω	
Z	
2	
<u>м</u>	
E	
Z	
> 0	
Ŏ	

- 2. Exhibit DFCG-1 is a true and correct copy of my written testimony in this proceeding, which was previously admitted into evidence. On October 28, 2016 I provided oral testimony in support of the case-in-chief of the Delta Flood Control Group ("DFCG"), which includes Brannan-Andrus Levee Maintenance District, Reclamation District No. 999, Reclamation District No. 2060, Reclamation District No. 2067, Reclamation District No. 2068, Reclamation District No. 2068, Reclamation District No. 407, Reclamation District No. 317, Reclamation District No. 551, Reclamation District No. 150, and Reclamation District No. 563.
- 3. I have reviewed the testimony submitted by Petitioners in support of the case-inchief in this proceeding and in the rebuttal phase of the proceeding, together with the supporting exhibits.
- 4. DWR's evaluation of the levees that will be affected directly or indirectly by the WaterFix Project will be based on an evaluation of those levees' current condition (April 25, 2017 Transcript, Vol. 36, p. 38, lines 1-8.). However, these levees were accepted into the flood control system without the kind of geotechnical work that is now typically performed on new levee structures. Our knowledge of these levees' structure and condition is limited by that fact. Mr. Bednarski admits that, to date, the necessary geotechnical work to evaluate the condition of these levees has not been performed, beyond the conceptual design phase. (April 25, 2017 Transcript, Vol. 36, p. 30, lines 16-25.) Thus, it is not proper for Mr. Bednarski to draw any conclusions about the stability or composition of the levees that could be affected by the WaterFix project.
- 5. Mr. Bednarski testified that no damage to levees and related structures were observed during pile driving at other Delta facilities, including the Alternative Intake at Victoria Canal, the Freeport Intake, and the Sankey Diversion Facility on the Sacramento River. (DWR-75, pp. 11-12, lines 27-4.) He went on to testify that "DWR will be implementing well-accepted engineering practices, similar to the approaches taken in the successful engineering projects identified above." (DWR-75, p. 13, lines 3-4.)
- 6. DWR has taken the position that, if slope stability criteria are properly developed, there would not be impacts in terms of slope stability or any other levee failures. (*See* April 25,

2017 Transcript, pp. 26-27).

7. DWR's witnesses have testified that levees will not be jeopardized by the construction or operation of the project because all work will be performed using accepted engineering practices. The conceptual design presented by the Project proponents provides no further detail on these practices. However, Mr. Bednarski offered up examples of other piledriving projects in the Delta as evidence that the current proposal should not present concerns (see April 25, 2017 Transcript, p. 14, lines 14-21: "My written testimony cites a number of relevant examples of recent successful pile-driving projects in the delta. Taken collectively, these projects have driven thousands of piles with a combination of vibratory and impact-driven piles near levees without any negative impact. Consequently, DWR does not foresee any issues with levee integrity due to pile-driving activities on the WaterFix."). Presumably, Mr. Bednarski believes that the types of potential impacts of the Project on levee stability, which were detailed in the Final EIR/S Appendix 6A at p. 6A-32 (copy attached as DFCG-21), will be fully addressed by such "well-accepted engineering practices." (DWR 75, p. 13, lines 3-4.)

- 8. In my experience, the projects offered up by DWR as examples of successful Delta projects included significant protections for flood control structures that are notably absent from DWR's conceptual design. Specifically the Victoria Alternative Intake Project and other similar projects incorporated a number of special features after consulting with engineers with extensive experience in designing and overseeing the construction of flood control projects in the Delta.
 - a. One of these features involved building an entirely new setback levee within the existing levee. As a result, much of the work, including pile driving, was performed on the original levee alignment, and not the new levee which was reconstructed landward of the original levee. The new levee functioned as a "fail-safe" protection against the possibility that pile driving on the existing levee could have resulted in failure of that levee.
 - b. In addition, the project incorporated peak particle velocity (motion) sensors in both the main levee and the setback levee that were intended to provide advance warning of any levee instability by detecting any acceleration of the materials in

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

the levee.

- Further, the project incorporated inclinometers that were installed to measure lateral deformation of the levees and piezometers that were installed to measure "pore pressure" that could indicate the liquefaction of the sandy soils that exists in many Delta levees.
- d. The project incorporated ground monuments that enabled the contractor and design engineers to determine whether there had been any lateral or vertical movement of the levees during the course of construction.
- Lastly, the project included extensive monitoring of neighboring levees to assure stresses to the levees did not exceed predetermined safe levels.
- 9. Mr. Bednarski offered rebuttal testimony that the Clean Water Act section 408 permitting process that is administered by the United States Army Corps of Engineers (USACE) would provide a backstop to protect area levees from WaterFix impacts. In particular, he testified that "in addition to the USACE's internal reviews, a safety assurance review by an independent panel of experts will be performed as part of the permitting process," and that to meet that requirement, DWR "will have to show in the permit application that proposed alterations to the levee sections and construction activities including encroachment into the river channel and pile driving will not compromise the existing levees." (DWR-75, p. 15, lines 14-19.)
- 10. The USACE section 408 permitting process does not provide for mandatory review by an independent panel, but allows the applicant to request such a review. (See USACE Engineer Circular (EC) No. 1165-2-216, Policy and Procedural Guidance for Processing Requests to Alter US Army Corps of Engineers Civil Works Projects Pursuant to 33 U.S.C. 408, at p. 12 (DFCG-22).
- 11. In my opinion, based on my experience as a professional engineer working in the Delta levee system, the imposition of an independent review panel is crucial in this case to assuring that the proposed project adequately protects existing levees. In my experience, project design, especially features to protect local structures, benefits by review of independent and local engineers. USACE, through the Independent External Peer Review process referenced in EC

17

18

19

20

21

22

23

24

25

26

27

28

1

2

3

4

5

6

7

8

9

10

11

1165-2-216 and elaborated on in detail in USACE Engineer Circular (EC) No. 1165-2-214, Civil Works Review (DFCG-23), Appendix D, has established a exactly such a process. That process is intended to ensure that the engineering used to design and construction major infrastructure meets the highest standards of public safety and reliability. Similarly, DWR has, in its investigations into the recent problems at the Oroville Dam spillway, convened an independent board of commissioners that is comprised of national experts to comment upon and oversee the design and reconstruction process. More generally, in the Urban Flood Risk Reduction Program Guidelines that have been prepared by DWR (DFCG-24), there is a provision for independent review of major projects. Independent reviewers "must be individuals who are distinguished experts in engineering, hydrology and other appropriate disciplines" and must be "free from any real or apparent conflict of interest." (DFCG-24, p. 8-1.) Moreover, an independent review "should also include review before, during, and after construction, and review on a regular schedule sufficient to inform the State of the adequacy, appropriateness, and acceptability of the design and construction activities for the purpose of ensuring public health, safety, and welfare." (DFCG-24, p. 8-2.) By requiring these standards through external oversight, the process of independent external review for major projects is a well-established technique to ensure that such projects are designed and constructed to the highest engineering standards.

- 12. DWR has acknowledged throughout these proceedings that the California WaterFix project would be one of the most important elements of California's water infrastructure. Accordingly, it is entirely appropriate for DWR to use the Department to invoke the Corps' independent review process described in EC 1165-2-214 and in EC 1165-2-216 and convene an independent core of commissioners to oversee the design and construction of the California WaterFix Project. That process should, in addition, incorporate the provisions of the Urban Flood Risk Reduction Program for independent review.
- 13. In requesting such an independent board of commissioners, DWR should insist not only on academic experts, but also on engineers with extensive experience in the construction of facilities in the Delta. *E.g.*, USACE Engineering Manual (EM) No. 1110-2-1913, *Design and Construction of Levees* (DFCG- 25), at p. 2-3 ("Local people or organizations having knowledge

of foundation conditions in the area should be interviewed."); Appendix p. F-2 ("Local			
contractors and local officials are the best source of information on available borrow areas.");			
Appendix, p. F-4 ("In standard levee design the configuration of the levee is generally dictated by			
the foundation soils and the materials available for construction. Therefore, even under			
emergency conditions, an attempt should be made to make the embankment compatible with the			
foundation. Information on foundation soils may be available from local officials or engineers,			
and it should be utilized."). Without such independent review and oversight that incorporates			
local knowledge, it is simply not possible to ensure that the project will be designed and			
constructed to the standards required for such a major project.			